


Manhole & Riser



Water Valve
(Monument Box similar)

Notes:

1. This detail shall be used where frame and covers are being adjusted to grade.
2. Class B Concrete shall be used. Finish shall be rough.
3. Concrete shall be placed against neatly edged excavation.
4. Frames shall match ex. finished grade within 1/8".
5. Tack the area to be paved, prior to placement of AC.
6. A.C. may be 1/2' max. agg. only with prior approval of City Engineer.

Dr. KT	No.	Date	Revision	Appr.	Approved By: <i>F. Wally Sandelin</i>	12/28/00 Date	STD PLAN 123
Ch. WS					F. Wally Sandelin City Engineer R.C.E. 39895		
Date 12/00							