



CITY OF LODI

PUBLIC WORKS DEPARTMENT

Tree Well Sprinkler System Installation

PVC Pipe Class Table

Size	Class
In turf/planter	
1/2"	Class 315 PVC
3/4"	Class 200 PVC
1"+	Class 160 PVC
Mainline (constant pressure)	
2"+	Class 200 PVC
Under concrete or paving	
All	Schedule 80

Sheet 2 of 2

Dr. KT	No.	Date	Revision	Appr.	Approved By: <i>F. Wally Sandelin</i>	12/28/00	STD PLAN 137
Ch. WS					F. Wally Sandelin City Engineer R.C.E. 39895	Date	
Date 12/00							