



# CITY OF LODI

PUBLIC WORKS DEPARTMENT

## Waste Interceptor

Peak flow into interceptor (GPM)	Inches			
	B	D	L1	L2
0-67	24	30	36	24
67-112	30	30	48	30
112-165	36	36	60	36

Over 165 GPM, See Note 4

Note:

Total rated discharge capacity of all fixtures, equipment or appliances discharging into interceptor in accordance with uniform plumbing code or actual flow rate.

Dr. KT	No.	Date	Revision	Appr.	Approved By:		STD PLAN
Ch. WS					<i>F. Wally Sandelin</i>	12/28/00	<b>204</b>
Date 12/00					F. Wally Sandelin City Engineer R.C.E. 39895	Date	