
El Paso Desalination Plant



Bill Hutchison, Ph.D., P.E., P.G.
Water Resources Manager
El Paso Water Utilities
August 9, 2007


Current El Paso Water Supply


- Hueco Bolson Groundwater
- Mesilla Bolson Groundwater
- Rio Grande Diversion





Hueco Bolson


~ 1.6 million acres ~ 2,500 sq. mi.

















Brackish Groundwater Intrusion




Groundwater Management Issues

- Declining groundwater levels
- Brackish water intrusion










Kay Bailey Hutchison Desalination Plant


- EPWU and Ft Bliss
- Desalination Plant and some wells located on Ft Bliss
- Concentrate disposal by injection well


















Major Components


- Production Wells and Collector Lines
- Plant and Near-Plant Piping
- Concentrate Disposal Wells and Pipelines
























Production Wells and Collectors

- 3 Well Drilling Contracts
- 3 Pump Furnish-and-Install Contracts
- 4 Well Equipping Contracts
- 2 Pipeline Contracts


Period of Work: March 2005 to June 2007

Plant and Near-Plant Pipes

- Reverse Osmosis Plant
- "4-Pipe" Project (41,800 ft)
 - Airport Well Collector (Final)
 - Loop 375 Collector (Final)
 - Concentrate Pipeline (Initial)
 - Finished Water Pipeline



ESPA-1 Membranes





Plant Overview

- 5 Skids
- Flow Rate: 1.70 to 3.64 mgd per skid
- Expected Recovery: 70% to 82.5%
- Expected Salt Rejection: up to 93%

Pretreatment

- Antiscalant
- Acid
 - pH adjustment to7.4



Finished Water Treatment

- pH Adjustment to 7.5
 - Caustic Soda
- Corrosion Inhibitor
 - − ~ 2 ppm
- Disinfection
 - Sodium Hypochlorite
 - 1 ppm Cl residual

Concentrate Treatment

 Ability to add acid as needed



Plant and Near-Plant Pipelines

- 2 Contracts
 - Plant
 - 4-pipe project


Period of Work: July 2005 to June 2007


Concentrate Disposal

- 3 Injection Wells
- Surface Injection Facilities
- Concentrate Pipeline (97,800 ft)


Cost Comparison (2002)

Disposal Method	Capital (million)	Annual O&M (million)	Present Value (million)
Passive Evaporation	\$41	\$1.0	\$71
Enhanced Evaporation	\$23	\$2.9	\$88
Deep Well Injection	\$7	\$0.8	\$25












Injection Well Construction

- Class I Standards
- Open Hole Injection Zone
- Well 1 (2004)
 - 3,777 ft deep
- Well 3 (2006)
 - 4,030 ft deep
- Well 2 (2007)
 - 3,720 ft deep









Injection Well Summary

- Depth to Water (Static)
- Injection Capacity
- Depth to Water (Injection)
- Formation Water TDS
- Bottom Hole Temperature

- ~ 500 ft
- 1,400 to 2,000 gpm
- > 350 ft
- $\sim 8,800 \text{ mg/l}$
- $\sim 160^{\circ} F$

Surface Injection Facilities

- Yard Piping
- Storage Tanks (~300,000 gal each site)
- Electrical System (solar w/ backup)
- Communications and Controls



Injection Well Issues

- Reservoir capacity
 - Ongoing evaluation during initial operation of wells
- Potential for mineral precipitation
 - Concentrate is supersaturated with respect to:
 - Calcite
 - Barite
 - Silica

Concentrate Disposal

- Test Hole Drilling Contract (USACE)
- 3 Injection Well Construction Contracts
- Surface Injection Facility Contract
- Downhole Equipping Contract
- Concentrate Pipeline Contract

Period of Work: April 2003 to June 2007

30-Day Commissioning Test

- Originally Scheduled for May and June 2007
- Scenarios:
 - 1. One Skid (low flow)
 - 2. Two Skids (low flow)
 - 3. Three Skids (low flow)
 - 4. Four Skids (low flow)
 - 5. Five Skids (low flow)
 - 6. Five Skids (max flow)
 - 7. Two Skids (high flow)





Start-up Issues


- Programming of Control System
- Communications with Wells
- Plant Equipment



Start-up Summary


- Began July 19, 2007
- Currently running Scenario 6

Finshed Water to Distribution and Flow to Injection Wells



Capital Costs

- Production Wells and Collectors \$ 30 Million
- Plant and Near-Plant Pipes \$ 40 Million
- Concentrate Disposal \$ 17 Million



Total Cost: \$87 Million (21 Contracts)

Sources of Funding

- Congressional Appropriations
- TWDB Interest Free Loan
- EPWU Bonds and Cash
- Army Contribution
- Total

\$26.0 Million

\$ 1.0 Million

\$56.7 Million

\$ 3.3 Million

\$87.0 Million

Annual Operating Costs Assumes \$0.07/kwh and 80% Operation

- Wells, Collectors
- Ft Bliss (water and land)
- Desalination Plant
- Disposal
- Finished Water Pipeline

- \$ 700,000
- \$ 1,300,000
- \$ 2,600,000
- \$ 200,000
- \$ 26,000

Total

\$ 4,826,000

Amortized Capital and O&M (\$/AF) Assumes 5% Discount Rate

•	Wells, Collectors	\$ 189
•	Ft Bliss (water and land)	\$ 42
•	Desalination Plant	\$ 232
•	Disposal	\$ 49
•	Finished Water Pipeline	\$ 22

Total

\$ 534

Cost Comparison

