

Idaho Cleanup Project

Introduction to the Remote – Handled Waste Disposition Project (RWDP)

Presentation to the National Academy of Sciences

***By Alan T. Jines, P.E.
Federal Project Director***

August 28, 2007

Remote-Handled Waste Disposition Project (RWDP)

- ***A project in the formative stages designed to accept remote handled wastes stored at the INL that currently lack a treatment and disposition plan.***
- ***Primary waste streams are 317 cubic meters of RH waste stored at the Materials and Fuels complex and the Radioactive Waste Management Complex.***
- ***NE funded, EM managed***



RWDP Scope

- **Transport**
 - **Accept waste for transport and move from Materials and Fuels Complex (MFC) and the Radioactive Waste Management Facility to the Idaho Nuclear Technologies and Engineering Complex (INTEC)**
 - **Utilize road closures and transport plan**
- **Open, segregate and characterize**
 - **Utilize existing, upgraded Fluorine Dissolution Process (FDP) hot cell located in building CPP-666**
- **Treat as necessary**
 - **Sodium bearing waste**
 - **Sodium treatment process has been proven lab-scale (Oak Ridge)**
- **Repackage and ship for final disposal.**
- **Approximately 1,000 canisters will be processed over a 10 year period; total project spans 16 years**



Radioactive Scrap and Waste Facility at MFC

- *Liners will be retrieved, staged and shipped to INTEC from the Radioactive Scrap Waste Facility (RSWF)*



Radioactive Waste Management Complex

- 30 Hot Fuel Examination Facility (HFEF-5) Cans will be removed from RWMC's Interim Long Term Storage Facility for shipment to INTEC



Waste to be processed

- *Remote-handled waste has been generated by MFC (Formerly ANL-W) since the 1960s*
 - *Mainly from fuel/reactor assembly examination in the Hot Fuel Examination Facility (HFEF)*
 - *Mainly EBR I and EBR II*
 - *Some other fuels through ANL-E*
- *Types of waste*
 - *TRU and Mixed TRU*
 - *GTCC*
 - *Low Level & Mixed Low Level*
 - *Spent Fuel*
 - *Un-irradiated Fuel*
- *Since the 1960s, MFC has stored this waste in an underground configuration*
 - *Referred to as “Liners”*



Waste to be processed (cont)

- **Quantities**

- *Materials and Fuels Complex (MFC) RH-TRU: ~14 m³ including HEPA filters and ALHC waste*
- *MFC 317 m³ RH waste (LLW, SNF) stored at Radioactive Scrap Waste Facility (RSWF). (need picture here)*
- *Incidental amounts of newly-generated RH-TRU at Reactor Technologies Complex and , Naval Reactors Facility.*





LINERS TO BE PROCESSED





- *Total Number of Liners = 983*
 - MFC = 953*
 - RWMC = 30*
- *538 (24") Liners Contain Over-packed 16" Liners*
- *367 (16") Liners Contain HFEF-5 Cans*



24" & 16" Diameter Liners at MFC



The Four Pack




ISOMETRIC VIEW
SCALE: NONE

NOTES



1. ALL FRAME CONSTRUCTION IS HSS EXCEPT FOR HSS 123X41/4 FOR TONGUES.




Four Pack Transport Trailer



Liner Cask



Liner Cask Transport Trailer



Shipment Receipt at INTEC

- 4 – Packs can be:
 - Off loaded directly to designated Lag Storage area.
 - Placed in Flourinel and Storage Facility (FAST) Highbay for individual HFEF-5
Can Transfer to:
 - CPP-749 Silos
 - The FDP Cell
- Liner Casks can be:
 - Off loaded directly to designated Lag Storage area.
 - Placed in FAST Highbay for individual Liner Transfer to:
 - CPP-749 Silos
 - The FDP Cell



View of FDP Cell at 0.0 Elev – North to South




Sorting Table


- *Accommodate all liner sizes*
- *Jib Crane*
- *Plasma torch cutting (outer liners)*
- *Mill cutting (inner liners)*
- *Tools*
 - *Chop Saw*
 - *Shears*
 - *Electromagnet*
 - *Miscellaneous sorting tools*




Sorting Table




Plasma Cutting of 24" Liner




Mill Cutting of 16" Liner



Extraction of Waste



RWDP Characterization System Provides for Required Waste Segregation



Sodium/NaK Contamination

- *RSWF Sodium Inventory (~ 1500 kg)*
 - *45% of RSWF containers have residual or larger quantities of sodium*
 - *74% of the sodium containers have less than 1 kg sodium*
- *Additional 5 cold traps*
 - *3,275 kg sodium and 197 kg NaK*
- *Total Inventory – 1300 gal Na, 63 gal NaK*
- *Treatment will be by MEDE process – Melt-Drain-Evaporate*



Waste Disposition Pathways

- *TRU and Mixed TRU → WIPP*
 - *Package into 55-gal drum, ship via RH72B*
- *Low Level Waste*
 - *Low activity waste - off site commercial disposal facility*
 - *Higher activity materials to Nevada Test Site or alternate*
 - *Package into 3x3x3 boxes for in-cell handling, loadout*
- *Mixed Low Level*
 - *Treat all sodium onsite (except sodium-bonded fuel)*
 - *Very small volume of other MLLW*
 - *RCRA Toxic Metals*
 - *Macro-encapsulation would be treatment standard*
 - *Would likely rely on commercial treatment to match eventual disposal facility requirement*



Waste Disposition Pathways

- *Sodium Bonded Spent Fuel and Scrap*
 - *Return to MFC*
 - *Packaged in HFEF-5 cans*
- *Other wastes with disposal paths yet to be determined*
 - *Spent Fuel (prior to YUCCA opening)*
 - *Un-irradiated Fuel*
 - *Greater Than Class C waste*
 - *Baseline assumption is to repackage into HFEF-5 Cans for return to MFC*



D&D To support Hot Cell Work


- ***Extensive D&D of the Hot Cell will be required to support RWDP use.s of D&D***
 - *Reduces radiation fields*
 - *Provides space for new processes.*
 - *Sampling required*



FDP Hot Cell – Top level



Hot Cell -13 ft Level Looking East



Preliminary Life Cycle Cost Estimate

- ***Facilities modification and equipment*** ***\$80M***
- ***Operations*** ***\$160M***
- ***Secondary Waste Disposition*** ***\$20M***
- ***Transportation*** ***\$10M***

- ***Total*** ***\$270M***



Schedule

- *Critical Decision 0 – Concept approval* 14 Dec 00
- *Critical Decision 1 – Approve preliminary baseline range* 21 Dec 04
- *Critical Decision 1a – Alternative concept approval* 1st QTR FY08
- *Critical Decision 2 – Approve performance baseline, complete preliminary design* 3rd QTR FY08
- *Critical Decision 3 – Approve start of construction* 2nd QTR FY 09
- *Critical Decision 4 – Approve start of operations* 1st QTR FY12
- *Complete processing MFC RH TRU Waste* 4th QTRFY18
- *Complete Waste processing operations* 4th QTR FY21

