NRC INSPECTION MANUAL

INSPECTION PROCEDURE 72582

POWER ASCENSION TEST PROCEDURE REVIEW: LOSS OF OFFSITE POWER (GROUP A)

PROGRAM APPLICABILITY:

72582-01 INSPECTION OBJECTIVE

Ascertain whether the tests are consistent with regulatory requirements, guidance, license commitments, and technical specifications.

72582-02 INSPECTION REQUIREMENTS

- 02.01 Review the FSAR, DL Safety Evaluation Report, and docketed letters from the licensee and verify that the testing commitments have been included.
- 02.02 Verify standard procedures review requirements are met as defined in Procedure 72300.
- 02.03 Verify that the procedure contains acceptance criteria as follows:
 - a. Automatic transfer of plant power loads.
 - b. Automatic start of diesel generators.
 - c. Automatic load of diesel generators in the specified sequence.
 - d. Turbine bypass system operates to maintain specified pressure value.
 - e. Steam system power actuated pressure relief valves open and close at specified value.
 - f. Pressurizer safety valves do not lift.
 - g. Pressurizer spray valves open and close at specified values.
 - h. Reactor coolant temperature/pressure relationship remains within prescribed values.

Issue Date: 07/01/80 - 1 - 72582

- i. Pressurizer level is maintained within prescribed limits.
- j. Steam generator level remains within prescribed limits.

72582 - 2 - Issue Date: 07/01/80

- 02.04 Verify that precautions require that crew assignments are provided to perform necessary manual functions if needed, to maintain safe plant conditions.
- 02.05 Confirm that test conditions require:
 - a. Steady state plant operations with greater than 10% generator output.
 - b. Trip of the plant with breakers in specified positions so that plant loads will be transferred directly to the diesel generators following loss of house power.
 - c. Assurance that acceptance criteria are met.
 - d. Examination of data for any unusual equipment performance.
 - e. Verification that plant loads are in the final expected conditions.
 - f. Restoration of the plant to normal operation using facility procedures.

72582-03 INSPECTION GUIDANCE

Testing requirements for this test should be compared with applicable provisions of Regulatory Guide 1.68, and with the test program description in the FSAR.

END

Issue Date: 07/01/80 - 3 - 72582