

**Duwamish/Diagonal CSO/SD Sediment Remediation Project
Closure Report**

Elliott Bay/Duwamish Restoration Program Panel

Prepared for:
King County Department of Natural Resources and Parks
Elliott Bay/Duwamish Restoration Program Panel

Prepared by:
The EcoChem Team

EcoChem, Inc.
Anchor Environmental, L.L.C.

Panel Publication 39

Elliot Bay/Duwamish Restoration Program
NOAA Damage Assessment and Restoration Center Northwest
7600 Sand Point Way NE
Seattle, WA 89115-0070

(206) 526-6029
FAX (206) 526-6665

July 2005

Individuals and organizations needing further information about the Elliot Bay/Duwamish Restoration Program should contact the Administrative Director at the following address and telephone number:

John Kern, Administrative Director
Elliot Bay/Duwamish Restoration Program
NOAA Damage Assessment and Restoration Center Northwest
7600 Sand Point Way NE
Seattle, WA 98115-0070
(206) 526-6029 FAX: (206) 526-6665

The Panel of Managers holds regularly scheduled meetings that are open to the public. Technical Working Group and committee meetings are scheduled on an as-needed basis, and are also open to the public. Meetings are generally held at the National Oceanic and Atmospheric Administration, National Marine Fisheries Service – Regional Directorate Conference Room, Building 1, 7600 Sand Point Way NE, Seattle. The Panel recommends that you contact the Administrative Director at the above phone number to confirm meeting schedules and locations. The panel also holds periodic special evening and weekend public information meetings and workshops.

General Schedule for Panel and Committee Meeting Dates

Panel: quarterly, first Thursday of January, April, July, October, 9:30 A.M. – 12:30 P.M.
Habitat Development Technical Working Group: third Thursday of every month, 9:30 A.M. – 12:30 P.M.
Sediment Remediation Technical Working Group: scheduled as needed.
Public Participation Committee: scheduled as needed.
Budget Committee: scheduled as needed.

Environmental Review of Specific Products

Formal hearings and comment periods on appropriate environmental documents for proposed sediment remediation and habitat development projects will be observed. Please contact the Administrative Director for more information.

<p>This information is available in accessible formats on request at (206) 296-0600 (voice) and 1-800-833-6388 (TTY/TDD users only).</p>
--

Duwamish/Diagonal CSO/SD Sediment Remediation Project Closure Report

TABLE OF CONTENTS

1.0	INTRODUCTION.....	1
1.1.	BACKGROUND	1
1.2.	OBJECTIVES	5
2.0	CONSTRUCTION ACTIVITIES.....	9
2.1.	TIMELINE.....	9
2.2.	CONTRACTOR SELECTION.....	9
2.3.	GENERAL CONSTRUCTION PROCEDURES	10
2.4.	DREDGING OPERATIONS.....	10
2.4.1	Equipment.....	10
2.4.2	Sequencing.....	12
2.5.	DISPOSAL ACTIVITIES	15
2.6.	DECONTAMINATION	18
2.7.	CAPPING OPERATIONS.....	18
3.0	COMPLIANCE MONITORING.....	22
3.1	PROTECTION MONITORING	22
3.1.1	Water Quality Monitoring During Dredging.....	22
3.1.2	Water Quality Monitoring During Capping.....	30
3.2	PERFORMANCE MONITORING	31
3.2.1	Post-Dredge and Post-Cap Surveys	31
3.2.2	Sampling and Analysis of Water From Dewatering Process.....	32
3.2.3	Sediment Sampling	34
3.3	CONFIRMATIONAL MONITORING.....	46
4.0	SURVEYS.....	47
4.1	PRE-CONSTRUCTION, POST-DREDGE, AND POST-CAP SURVEYS	47
4.2	CONTRACTOR DAILY PROGRESS SURVEYS	47
4.3	QUANTITIES	48
5.0	DEVIATIONS FROM PLANS	49
6.0	POST CONSTRUCTION MONITORING	50
6.1	SEDIMENT CHEMISTRY STATIONS ON CAP SURFACE IN CLEANUP AREAS A AND B.....	50
6.2	EIGHT ADDITIONAL SEDIMENT CHEMISTRY STATIONS BEYOND THE CAP SITE BOUNDARY ...	54
7.0	AFFIDAVIT	56
8.0	REFERENCES.....	57

Tables

Table 1	Water Sample Turbidity Results During Dredging
Table 2	Water Sample Chemistry Results During Dredging
Table 3	Water Sample Turbidity Results During Capping
Table 4	Treated Water Sample Results From Dewatered Sediments

Table 5	Chemicals That Exceed SMS at 12 Stations Beyond Site Boundary Before and After Construction
Table 6	Changes in PCB Dry Weight and SMS Values at 12 Stations Beyond Site Boundary After Construction
Table 7	PCB Distribution and Model Prediction (mg PCB/kg DW)
Table 8	Quantities of Capping Materials (in Tons)
Table 9	2004 Baseline Chemistry at Cap Stations
Table 10	Summary of Surface Monitoring Stations and Schedule

Figures

Figure 1	Duwamish/Diagonal Vicinity Map
Figure 2	Cleanup Areas A and B Dredged and Capped
Figure 3	Bis(2-ethylhexyl)phthalate Distribution in Surface Sediment
Figure 4	Total PCB Distribution in Surface Sediment
Figure 5	Dredge Cut Plan
Figure 6	Offloading/Rehandling Facility Layout at Terminal 25
Figure 7	Required Grain Sizes for Cap Erosion Layer
Figure 8	Post-Construction Changes in PCB Dry Weight Concentrations at Twelve Stations Beyond Site Boundary
Figure 9	Predicted vs. Observed Post-Construction PCB Concentrations at Twelve Stations Beyond Site Boundary
Figure 10	Post Construction PCB Concentrations in ppm at Stations Beyond Site Boundary Compared to Predicted Values
Figure 11	Cap Monitoring Stations in Areas A and B Plus Baseline Chemistry Values For Bis(2-ethylhexyl)phthalate and PCBs

Appendices

Appendix A	Photos
Appendix B	Contractor Daily Reports
Appendix C	Inspector Daily Reports
Appendix D	Lab Reports
Appendix E	Blue Water Engineering Surveys
Appendix F	Water Quality Monitoring Sampling and Analysis Plan
Appendix G	Sediment Monitoring Sampling and Analysis Plan