

Free Spanning Subsea Pipelines

Discussion Session:

Cook Inlet Area

presented by

Olav Fyrileiv
Principal Engineer
Det Norske Veritas




Content of presentation

- Subsea pipelines in Cook Inlet
- Current distribution
- XTO pipelines
- Osprey pipelines
- Remarks



Cook Inlet Area





Subsea Pipelines in Cook Inlet


- Aging pipelines (installed late 60ties)
- “Thick walled” (thicker than needed from pressure containment)
- Significant corrosion in some oil lines
- Strong tidal current
- Seabed conditions are very dynamic
- Scouring giving span gaps of less than a foot
- Annual inspection for free spans (side scan sonar?)
- Spans longer than 50’ and 1’ gap intervened to avoid VIV damage
- Spans of 100 ft may fail due to VIV
- 14 failures due to VIV 1965-1976??



Current distribution – West Foreland



Current distribution



XTO pipelines



- A line dry oil (Plt. A to East Forelands) 2 leaks in in 1966 (year 1) + one in 1976 due to VIV
- B line wet oil (Plt. A to East Forelands) 3 leaks in in 1966-68
- 8" lines, 1-2.5" concrete
- 160-280 psig operating pressure
- Long spans, sandbag supports



FATFREE COMPLETED <i>No Wave Case</i>	Project: XTO pipeline from plt A to East Foreland	Date: 21/05/2004	Calculations by
	References: XTO pipeline from plt A to East Foreland		Verified by


Calculation Options	Current Modelling	Free Span Scenario		Response Data		Damping		SN-Curves		Safety Factors	
Analysis Level 2	Uc Histogram	Pipe in trench		RP-F105 Span		Sand - Medium		F1 (air)		NORMAL	
Code		h [m]	20	f _o (in-line)	2.840	<input type="checkbox"/> _struc	0.005	m ₁	3	<input type="checkbox"/>	0.50
RP-F105		L [m]	14	f _o (cr-flow)	2.918	<input type="checkbox"/> _soil (in-line)	0.015	m ₂	5	<input type="checkbox"/> _k	1.30
Return Period Values	Directionality	e [m]	0.30	A _{in} (in-line)	438	<input type="checkbox"/> _soil (cr-flow)	0.012	Log(C ₁)	11.699	<input type="checkbox"/> _t	1.20
Automatic Generated	Discrete - C dir.	d [m]	0.3	A _{cr} (cr-flow)	459	<input type="checkbox"/> _h, RM	0.000	Log(C ₂)	14.832	<input type="checkbox"/> _s	1.05
UPDATE SHEET	Environmental Data	<input type="checkbox"/> _pipe	20.0	<input type="checkbox"/> _max	2010			logN _{sw}	7.00	<input type="checkbox"/> _on	1.10
CALCULATE	Current-template	D [m]	0.281	<input type="checkbox"/> _D	0.13	K _S (in-line)	0.67	S ₀ [MPa]	0.00		
		L/D	50	S _{eff} /P _E	-0.02	K _S (cr-flow)	0.56	SCF	1.00		
				L _{eff,vs} /L	1.45	Soil stiffness				<input type="checkbox"/> _R	1.00
				L _{eff,v} /L	1.17	Sand - Medium					
						K _V	2.24E+07			<input type="checkbox"/>	Well Defined Span
						K _L	1.685E+07				
						K _{V,S}	5.300E+05				

FATIGUE LIFE		cross-flow direction	DYNAMIC STRESS [MPa]				in-line direction		EXTREME CONDITIONS	
In-line (Response Model)	2.45E+02 yrs	Peak Stress	V. Mises Stress	Peak Stress	V. Mises Stress	Current				
-	-	<input type="checkbox"/> _x(1 year)	0.0	19.3	<input type="checkbox"/> _x(1 year)	9.3	18.1	U _C (1 year)	1.09	0.00
-	-	<input type="checkbox"/> _x(10 year)	0.0	19.3	<input type="checkbox"/> _x(10 year)	9.3	18.1	U _C (10 year)	1.09	0.00
Cross-Flow	1.00E+06 yrs	<input type="checkbox"/> _x(100 year)	0.0	19.3	<input type="checkbox"/> _x(100 year)	9.3	18.1	U _C (100 year)	1.09	0.00




STRUCTURAL MODELLING													
Static Stress [MPa]		Transfer values		Areas [m ²]		Functional Loads		Pipe Dimensions [m]		Constants		Densities [kg/m ³]	
<input type="checkbox"/> _h	8.8	EI _{steel}	1.04E+07	<input type="checkbox"/> _i	0.02806	H _{eff} [N]	0.00E+00	D _s	0.2190	<input type="checkbox"/>	0.30	<input type="checkbox"/> _steel	7850
<input type="checkbox"/> _N	1.3	m _e	216	<input type="checkbox"/> _steel	0.00961	p [bar]	15	t _{steel}	0.0150	<input type="checkbox"/> _#C ⁻¹	1.17E-05	<input type="checkbox"/> _concrete	2250
<input type="checkbox"/> _M,cr	14.6	q	868	<input type="checkbox"/> _coating	0.00424	<input type="checkbox"/> _T [°C]	0	t _{concrete}	0.0250	E [N/m ²]	2.07E+11	<input type="checkbox"/> _coating	1600
<input type="checkbox"/> _M,in (100y)	4.0	S _{eff}	-1.68E+04	<input type="checkbox"/> _concrete	0.02011	Coating data		t _{coating}	0.0060	C _D (current)	1.00	<input type="checkbox"/> _cont	880
		C _a	1.00	A _e	0.06202	k _c	0.00					<input type="checkbox"/> _water	1027
		CSF	0.00			f _{cn} (MPa)	45						

Example – 20deg current flow



Example – 90deg current flow



Osprey pipelines


- Surface current 13 ft/s, bottom 7 ft/s
- 3 x 8" lines, no concrete coating
- Wet oil, gas & water injection lines
- Design code for VIV – DNV (RP-F105 or CN30.5, DNV81?)



Remarks

- VIV dominated by strong current
- Pipeline heading important
- Frequency important – stiffness and mass
- Most pipelines 8”, some 10”
- Acceptable span length depends more on pipeline heading than other parameters





DIN V