
Preliminary Design of Injector Complex

NSLS-II Accelerator Systems Advisory Committee

October 8th, 2007

T. Shaftan for NSLS-II team

Outline


- Introduction
- NSLS-II injection requirements
- Top-off
- Injection system overview
- Linac
- Booster
- Transport lines
- Cost
- Schedule
- Summary

Introduction

- CD-1: in-tunnel booster → most economical solution
- Support from technical reviews
- Concerns expressed by Lehman review regarding booster-ring cross-talk and impact on installation schedule and troubleshooting
- Recommendation from Lehman review to develop injector with a “compact” booster
- Given short schedule: linac and booster are semi-turnkey procurements
- Transport lines and ring injection straight are by BNL
- Maximum energy for the injector is 3.1 GeV

Requirements for NSLS-II Injection

- High reliability
- Reasonable initial fill time
- Low losses
- Lifetime 3 hours (with 3rd HC)
- Top-off
 - Stability of current <1 %
 - Time between top-off injections >1 min
 - Bunch-to-bunch variations of charge <20%




Ring Parameters Related to Injection




Parameter	Value
Energy, GeV	3
Circulating current, A	0.5
Circumference, m	792
Revolution period, μs	2.6
RF frequency, MHz (wavelength, m)	500(0.6)
Circulating charge, μC	1.3
Total number of buckets	1320
Number of filled buckets	$1320 \cdot 4/5 \approx 1080$
Charge per bucket, nC	1.25
Lifetime, hours	3
Interval between top-up cycles, min	1
Current variation between top-up cycles, %	0.55%
Charge variation between top-up cycles, nC	7.3

Injection Scenario


- Many (~1000) bunches in the ring →
→ multi-bunch injection
 - N_M bunches in the injected train
 - Filling N_M consecutive buckets in the ring
 - Sequentially shift the injection timing
- 1 Hz repetition rate suffices with pulse train injection
- 1 minute between top-off cycles
- Kickers duration are 2 turns long (5.2 μ sec) or can be even longer
- Considered in ALS top-off (10 bunches)



Top-off formats and bunch patterns




NSLS-II Injector Complex



Linac


- NSLS-II: 200 MeV, 15 nC/train, ~0.5% energy spread
- 100 MeV linac from THALES is in operations for SOLEIL
- Achieved parameters:
 - 10 nC/pulse in LPM
 - 0.5nC/pulse in SPM
- Close to NSLS-II requirements

	LPM		SPM		
	Specified	Measured	Specified	Measured	
Pulses				1	4
Pulse length (ns)	300	286	<2	1.3	1.3
Energy (MeV)	>=100	108	>=100	110	110
Charge/Pulse (nC)	8	9.3	0.5 and 2	0.52	2.15
Emittance (mm.mrad)					
Horizontal ($4\beta\gamma\sigma'$)	200	47	200	64	67
Vertical ($4\beta\gamma\sigma'$)	200	52	200	67	78
Energy spread (%)	± 1.5	± 0.5	± 1.5	± 0.58	± 0.82




Booster Layout

- $C=158.4$ m (1/5 of SR)
- $E = 0.2 \rightarrow 3$ GeV
- $Q = 10$ nC
- $\epsilon_x = 125 \rightarrow 30$ nm rad
- $\sigma_\gamma/\gamma = 0.5 \rightarrow 0.1\%$
- $N_b = 40-150$ bunches
- $F_{\text{rep}} = 1$ Hz
- 4-quadrant lattice
- 60 combined-function magnets
- 1 straight \rightarrow injection
- 1 straight \rightarrow RF (Two 499.68 MHz PETRA-type cavities)
- 1 straight \rightarrow extraction
- Low magnet peak field of 1 T
- 200 MeV injection energy



Booster Lattice



- ASPb-like solution
- Cost-effective design
- Periodicity of 4
- Combined function FODO lattice
- B , K_1 , K_2 in dipoles
- Matching triplets (additional quad family for flexibility)
- Low dispersion in long straights
- Discrete sextupoles for eddy-current compensation (+0.5 x, -1.4 y max at 1Hz)
- Preliminary design



Booster parameters


Parameter	ASP booster	NSLS-II booster
Emittance, nm	34.4	26.6
Circumference, m	130.2	158.4
Revolution time, ns	434	528
RF frequency, MHz	499.654	499.68
RF voltage, MV	1.2	1.2
Harmonic number	217	264
X/Y tune	9.2/ 3.25	10.91/6.69
X/Y Chromaticity	-8.83/-11.5	-13.8/- 18.9
X/Y coupling	5%	
Corrected chromaticities	+0.83/+0.87	+1.7/+1.7
Momentum Compaction	0.0098	0.0072
Energy loss per turn, keV	743	625
X/Y/Z damping time, ms	2.7/3.5/2.0	5.4/5.1/2.5
Damped energy spread, %	0.094	0.078
Damped bunch length, mm	19	13.9

Flexibility of NSLS-II booster



Booster injection and extraction

- Considering booster injection system be able to allow stacking of the low-energy beam at the maximum linac repetition rate of 10 Hz.
- Calculations are in progress of attempting to stack two consecutive (separated by 0.1 seconds) bunch trains transversely in the booster by injecting them with $\frac{1}{2}$ of the nominal kicker strength.
- Combination of DC strong septum and pulsed weak kicker is preferable and will be explored for both injection and extraction





Part Count / Magnetic element properties

Parameter	ASP	NSLS-II
Number, BF/BD	28/32	28/32
Length, BF/BD	1.35/1.15 m	1.35/1.4 m
Angle, BF/BD	3.43/8.25°	3.43/8.25°
Injection energy	100 MeV	200 MeV
Field, BF/BD (inj)	0.015/0.042 T	0.030/0.069 T
Field, BF/BD (ext)	0.443/1.25 T	0.443/1.00 T
Quadrupole K1, BF/BD (ext)	0.82595/-0.66977 m ⁻²	0. 0.82800/-0.63831 m ⁻²
Sextupole K2, BF/BD (ext)	3.54/-4.925 m ⁻³	4.10/-5.65 m ⁻³

Parameter	ASP	NSLS-II
Number, QF/QD/QG	8/8	8/8/8
Length, QF/QD/QG	0.25/ 0.15 m	0.45/0.15/ 0.15 m
K1, QF/QD/QG (inj)	-0.0784/ 0.0133 m ⁻²	0.123/0.058 /-0.0869 m ⁻²
K1, QF/QD/QG (ext)	-2.351/ 0.400 m ⁻²	1.84/0.871 /-1.30 m ⁻²

Focusing and defocusing dipole pole tips




Parameter	ASP	NSLS-II
Number, SF/SD	8/8	8/8
Length, SF/SD	0.2/0.2 m	0.15/0.15 m
K2, SF/SD (ext)	50/-30 m ⁻³	40/-40 m ⁻³


Thanks to S. Mikhailov (Duke Univ.)

er 8th 2007

Orbit correction and tolerances



Uncorrected and corrected orbits
(red - X, blue - Y)



Corrector maximum angles <1mrad

• Tolerances

- Dipole length 0.1%
- Dipole field 0.1%
- Dipole \parallel displ. 1mm
- Dipole \perp displ. 0.1mm
- Dipole roll 0.5mrad
- Quad \perp displ. 0.2mm
- Quad gradient 0.02%

Diagnosics and Instrumentation for Booster



- Measured parameters

Value	Accuracy	
• Current	30 mA	0.1%
• Fill pattern	40-150 bun.	1%
• Closed orbit		0.01 mm
• Beta-functions	<30 m	
• Dispersion	<35 cm	
• X/Y Tunes	10.9/6.7	0.01
• X geom. emittance	~30 nm·rad	10%
• X/Y chromaticities	-13.8/-18.9	0.3
• Coupling	<10%	1%
• Bunch length	16 ps RMS	2 ps
• Synchrotron Frequency	~20 kHz	1 kHz

 - Continuously monitored beam parameters:
 - Current
 - X/Y Tunes
 - Orbit
 - Beam shape
 - Diagnostics:
 - 20 X-Y BPMs
 - 1 DCCT
 - 2 striplines
 - 6 Fluorescent Screens
 - Fast Current Transformer
 - Synchrotron Light Monitor
 - Tune Measurement System
 - Bunch cleaner
- **Comments:**
- Booster is a turnkey procurement; diagnostics to be supplied by vendor according to our requirement
 - Libera BPM receivers are functional at two revolution frequencies therefore the same modules suitable for both ring and booster

Layout of LB TL

- Diagnostics:
 - Gun: 3 Wall Current Monitors
 - Linac
 - 4 Fluorescent Screens
 - 2 Current Transformers
 - Linac to Booster Transfer Line
 - 5 Fluorescent Screens
 - Integrating Current Transformer
 - 3 Four-Button pick-ups
- E = 200 MeV
- Q = 15 nC
- $\epsilon_n = 50$ mm mrad
- $\sigma_\gamma/\gamma = 0.5\%$
- $N_b = 40-150$ bunches
- LB TL will allow fast linac commissioning





Layout of BSR TL


- $E = 3 \text{ GeV}$
- $Q = 10 \text{ nC}$
- $\epsilon_x = 30 \text{ nm rad}$
- $\sigma_\gamma/\gamma = 0.1\%$
- $N_b = 40\text{-}150 \text{ bunches}$

- **Diagnostics:**
 - 6 Fluorescent Screens
 - Integrating Current Transformer
 - 6 Four-Button Pick-ups with Libera receivers
 - Two Cameras with external trigger

$\beta_{x,y} \quad \eta_{x,y}$ vs. Dist
xtr3Q_AchFODO5Q_inj6Q



Storage ring injection straight




- Quad-to-quad distance increased from 7.6 m (CD-1) to 9.3 m (CD-2)
- Pulsed magnets for up to 3.1 GeV max
- Combination of strong DC pre-septum with pulsed septum
- Closed bump of 15 mm
- Kickers with 5.2 μ s long pulse powered separately
- Pulsed magnets are within vendors capabilities
- Proposal on development and optimization of pulsed magnets and PS (total of 13 magnets for NSLS-II) in-house: Pulsed Magnet Lab

Injector cost

Activity	Labor, hr	Bare Cost, M\$
Linac	4087	9.963
Booster	16139	17.23
L-B TL	7163	1.345
B-SR TL	9796	1.808
Injector utilities	5015	0.871
Injector installation	16644	1.107
Injector testing	9308	0.731
Injector commissioning	9659	0.743
Total:	44.62 FTE	33.754

- Large procurements: Linac (~9M\$) and Booster (~15M\$)

Schedule



Summary

- NSLS-II full energy injector will support top-off operations in presence of short beam lifetime
- Multi-bunch injection with high charge per bunch train
- Linac and booster are semi-turnkey procurements
- NSLS-II booster is based on existing ASP design with some modifications
- We choose low-emittance cost-effective solution for NSLS-II booster
- We developed design of injection straight and transport lines
- Injector cost and schedule are developed
- Preliminary level of design

Acknowledgements

J. Rose, I. Pinayev, R. Heese, S. Ozaki, F. Willeke,
W. Guo, B. Nash, J. Bengtsson, E. Johnson,
R. Meier, S. Sharma, D. Hseuh, N. Tsoupas,
G. Ganetis, H. Nishimura, D. Robin, T. Shaftan,
J. Skaritka, R. Grubb, J. O'Connor, C. Lavelle,
T. Mennona

Back-up

Previous ASAC comments




Injection System with a Booster in Separate Tunnel (T. Shaftan)

- The committee is pleased with the injection tracking studies and recommends their continuation, including all insertion device effects and lattice errors.
- From experience elsewhere, the committee is not fully convinced that the present high beta straight for injection is long enough to accommodate injection equipment, and in particular is fully compatible with state of the art top-up requirements. In order to assess the adequacy of available space, an engineering layout of the injection straight of the storage ring should be generated. It is the feeling of the committee that a longer straight for injection could easily be accommodated in the lattice (see comments above).
- A possible operation at a 3.6 GeV energy was mentioned several times and the committee recalls that if NSLS-II intends to run at this energy, it should be included in the specifications of all systems such as magnets, absorbers, RF, Booster, and injection/extraction systems.
- The committee recommends a horizontally movable septum magnet at the ring injection point in order to ease commissioning through a near on-axis injection configuration as well as to optimize the kicker currents in relation to the final horizontal aperture.
- The Australian Light Source booster lattice design which is used as a reference design for the proposed booster lattice presents the drawback of limited flexibility in the tunes. The committee recommends the investigation of solutions which increase the accessible tune range.
- The proposed lattice for the booster synchrotron is pretty tight and the committee ask for an engineering layout in order to check that there is enough space for the correctors, diagnostics, vacuum pumps, etc. The committee recommends that the space required and the positioning of injection and extraction magnets inside the booster lattice be investigated (in particular the impact of the high value of the dispersion function in the injection and extraction straights has to be evaluated as well as the low beta values).
- The committee notes that there is no definite requirement yet for hybrid filling modes, but nevertheless recommends including this capability from the outset, since a need is almost certain to arise in the future.
- Regarding the issue of whether or not to use a single power supply for all storage ring injection kicker magnets, the committee believes that there will inevitably be differences from kicker to kicker (due to mechanical tolerances, thickness of ceramic coating, etc.). So the committee recommends that individual power supplies be used in order to optimize the bump closure and hence minimize the disturbance of the stored beam, in view of top-up operation.

Multi-bunch Injection


- Short lifetime → multi-bunch mode
- SLS experience: feedback for enhancement of the bunch pattern purity
- "Hunt&Peck" mode: is it necessary for NSLS-II ?
- Studies at ALS on pattern evolution

Studies at NSLS and ALS (in progress)






“Hunt & Peck”: Adjusting Average Value

- Measure charge in the ring buckets
- Every top-off cycle adjust gun grid voltage → adjust charge per bunch
- Inject macropulse (N bunches) with average charge equal to missing charge in N-bunches in the ring
- Eliminates all bunch-bunch variations on $N_b > N_{\text{MICRO}}$ scale
- Can be done in “sequential” or “hunt & peck” modes
- Reducing harmonics of SR bunch pattern: requires R&D



"Hunt & Peck": Fast modulation of macropulse


- Measure charge in the ring buckets
- Modulate gun voltage (laser intensity) with inverse of the charge/bunch in the pattern or
- or
- Stack bunches in the booster via multiple injections
- Inject "premodulated" macropulse into the ring




Alternative version by H. Nishimura (ALS)

- Circumference = 158.40000 [m]
- Betatron Tunes X/Y = 9.26706/ 4.19942
- Momentum Compaction = 7.51991E-003
- Chromaticity H = -11.46993
V = -7.17248
- Radiation Loss = 8.33737E+002 [keV]
- Natural Energy Spread = 1.45518E-003
- Natural Emittance = 1.61981E-008
- Radiation Damping H = 1.67192 [msec]
V = 3.80238 [msec]
E = 5.23937 [msec]
- Periodicity of 2 (racetrack)
- Combined function FODO lattice
- B, K₁ in dipoles
- 2 s_x, 2 s_y sextupoles per cell
- Booster Dynamic Aperture gives about ±30 mm in both planes (in middle of straight)
- Needs more realistic chromaticity correction
- Preliminary design


A Half Cell




Arc



Transition + Straight



DA and Emittance scan



- Maximum of DA is ± 10 mm in both planes
- Emittance of 26 to 100 nm·rad within tune footprint
- Broad range of optics solutions

Diagnosics in Linac & Linac-to-Booster Transport Line

- | Measured parameters (at Linac exit): | Value | Accuracy |
|--------------------------------------|-------------|----------|
| • Charge | 15 nC | 0.2% |
| • Fill pattern | | |
| • Energy | <270 MeV | 0.5% |
| • Energy spread | <0.5% RMS | 0.05% |
| • Beam positions | | 0.1 mm |
| • Beam sizes | ~2 mm | 0.1 mm |
| • Norm. emittances | ~50 mm·mrad | 5% |
- Continuously monitored beam parameters:
 - Charge
 - Energy
 - Beam positions
 - Bunch train pattern
- Diagnostics:
 - Gun:
 - 3 Wall Current Monitors or Fast Current Transformers
 - Linac
 - 4 Fluorescent Screens
 - 2 Integrating Current Transformers
 - Linac to Booster Transfer Line
 - 5 Fluorescent Screens
 - Integrating Current Transformer
 - 3 Four-Button Pick-ups with Libera BPM receivers

■ Comments:

- Linac is a turnkey procurement; diagnostics to be supplied by vendor according to our requirement; transport line we are developing ourselves
- Diagnostics suite must enable early commissioning of Linac and demonstration beam parameters required for lossless injection into Booster
- Charge monitoring will be used for interlocks

Diagnositics in Booster-to-Storage Ring Transport Line


- | Measured parameters (at Booster exit): | Value | Accuracy |
|--|------------|----------|
| • Charge | 10 nC | 0.2% |
| • Fill pattern | | |
| • Energy | 3 GeV | 0.5% |
| • Energy spread | <0.1% RMS | 0.05% |
| • Beam positions | | 0.1 mm |
| • Beam sizes | <1 mm | 0.1 mm |
| • Geom. emittances | ~30 nm·rad | 5% |
- Continuously monitored beam parameters:
 - Charge
 - Energy
 - Beam profile and position
 - Bunch train pattern

- Diagnostics:
 - 6 Fluorescent Screens
 - Integrating Current Transformer
 - 6 Four-Button Pick-ups with Libera receivers
 - Two cameras with external trigger capability

- **Comments:**
- Transport Line we are developing ourselves
- Diagnostics suite must enable early commissioning of Booster and demonstration of beam parameters required for lossless injection into Storage Ring
- Charge monitoring will be used for interlocks

Injector Service Area

1. Booster Service Area (20 m x 8 m)	160 m ²
2. L-B TL Service Area (3 m x 10 m)	30 m ²
3. B-SR TL Service Area	57 m ²
4. AC power disconnects/ switch gear	24 m ²
5. 2 entry labyrinths 2· (3 m·3 m)	18 m ²
7. Bathroom	25 m ²
8. Local Injection System Control room	54 m ²
10. Equipment storage area (spare parts and test instruments) (9 m ·9 m)	81 m ²
11. Electronic/Mechanical Workshop	100 m ²
12. Water and air distribution area	36 m ²
Total square footage	585 m ²
Walkways and corridors:	80 m ²
Total for building:	665 m ²



Activity Name	Original Duration	Finish	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016
				FY08	FY09	FY10	FY11	FY12	FY13	FY14	FY15	
Built-In Days for Funding Profile - Booster	389	21-Apr-09	07-07									
Booster Ring - Preliminary Design/Specification	83	19-Aug-09		22-Apr-09								
Booster Ring - Prepare Solicitation	42	19-Oct-09		20-Aug-09								
Booster Ring - Vendor Selection	90	03-Mar-10		20-Oct-09								
Booster Ring - Award Contract	0	03-Mar-10		03-Mar-10								
Booster Ring - Detail Design Vendor	292	29-Apr-11		04-Mar-10								
Booster Ring - Detail Design Support	292	29-Apr-11		04-Mar-10								
Booster Ring - Design Finished	0	29-Apr-11			29-Apr-11							
Booster Ring - Vendor Manufacturing Leadtime	146	01-Dec-11			02-May-11							
Booster Ring - Manufacturing Support	146	01-Dec-11			02-May-11							
Booster Ring - 1st Design/Contract Review	5	24-Mar-10		18-Mar-10								
Booster Ring - 2nd Design/Contract Review	5	29-Jun-10		23-Jun-10								
Booster Ring - 3rd Design/Contract Review	5	03-Nov-10			28-Oct-10							
Booster Ring - 4th Design/Contract Review	5	13-May-11			09-May-11							
Booster Ring - Final Design/Contract Review	5	13-Sep-11			07-Sep-11							
Booster Ring - Vendor Delivery	83	17-Jan-12			14-Sep-11							
Booster Vendor Leadtime - Built-In Float	120	06-Jul-12				18-Jan-12						
Booster Ring - is Delivered to BNL	0	06-Jul-12				06-Jul-12						
Booster Installation - Start Milestone	0					09-Jul-12						
Booster - Installation	111	14-Dec-12				09-Jul-12						
Booster Installation - Built-In Float	21	17-Jan-13					17-Dec-12					
Booster - Integrated Testing	84	17-May-13					18-Jan-13					
Booster - Ready for Commissioning	0	17-May-13					17-May-13					
Booster Ring - Commissioning	88	24-Sep-13					20-May-13					
Booster Commissioning - Built-In Float	21	24-Oct-13						26-Sep-13				
Storage Ring Beam Commissioning - Start	0							25-Oct-13				
Storage Ring w/o ID - Commissioning	86	03-Mar-14						25-Oct-13				
IVU - Installation	20	31-Mar-14						04-Mar-14				
IVU - Integrated Test	10	14-Apr-14						01-Apr-14				
Storage Ring w/ ID IVU - Commissioning	50	24-Jun-14						15-Apr-14				
Storage Ring Commissioning - Complete	0	24-Jun-14						24-Jun-14				
Early Project Completion	0	24-Jun-14						24-Jun-14				
NSLS-II Project - Built-In Float	250	25-Jun-15						25-Jun-14				
CD-4b Approve Start of Operations	0	25-Jun-15*									25-Jun-15*	

Booster Schedule