

HIGH PERFORMANCE CONCRETE
2006-07 FOLLOW-UP SURVEY RESULTS

**NATIONAL HIGH PERFORMANCE CONCRETE
FOLLOW UP SURVEY RESULTS**

BY: Louis N. Triandafilou, P.E.
FHWA Resource Center – Baltimore
Senior Structural Engineer

CLAUDE S. NAPIER, Jr., P.E.
FHWA Virginia Division Bridge Engineer

Rodolfo F. Maruri, P.E.
FHWA Virginia Assistant Division Bridge Engineer

HIGH PERFORMANCE CONCRETE
2006-07 FOLLOW-UP SURVEY RESULTS

Outline

- HPC Introduction
- 2006 National HPC Survey
 - Alternative Reinforcement
 - Self-Consolidating Concrete
 - Lightweight HPC
- Conclusion

HIGH PERFORMANCE CONCRETE
2006-07 FOLLOW-UP SURVEY RESULTS


Introduction

Cost of Corrosion-“Deficient Bridges”



HIGH PERFORMANCE CONCRETE
2006-07 FOLLOW-UP SURVEY RESULTS

Introduction – Cost of Substructure Corrosion



HIGH PERFORMANCE CONCRETE
2006-07 FOLLOW-UP SURVEY RESULTS



Introduction – Accident Damage



HIGH PERFORMANCE CONCRETE
2006-07 FOLLOW-UP SURVEY RESULTS

Introduction – Act of God Damage





- HIGH PERFORMANCE CONCRETE**
2006-07 FOLLOW-UP SURVEY RESULTS
- PURPOSE**
- Quantify the number and application of high performance concrete (HPC) projects across the nation,
 - Obtain information on the use of high performance reinforcement.
 - Follow-up to earlier HPC Survey 2003

- HIGH PERFORMANCE CONCRETE**
2006-07 FOLLOW-UP SURVEY RESULTS
- QUESTIONNAIRE**
- Prepared by a task force of the FHWA High Performance Concrete Technology Delivery Team
 - Members of task force include
 - State DOT
 - Industry
 - FHWA

- HIGH PERFORMANCE CONCRETE**
2006-07 FOLLOW-UP SURVEY RESULTS
- SURVEY DISTRIBUTION**
- Survey sent to:
 - 50 States
 - Federal Lands Highway
 - Puerto Rico
 - District of Columbia (DC)

- HIGH PERFORMANCE CONCRETE**
2006-07 FOLLOW-UP SURVEY RESULTS
- Survey Topics**
- General Use of HPC
 - HPC for Permeability Benefit
 - HPC for Strength Benefit
 - Self-Consolidating Concrete
 - Lightweight HPC
 - Alternative Reinforcement

HIGH PERFORMANCE CONCRETE 2006-07 FOLLOW-UP SURVEY RESULTS

Survey Topics (cont.)

- Alternative Reinforcement
 - Stainless Steel Reinforcement
 - Stainless Steel Clad Reinforcement
 - Epoxy Coated Reinforcement
 - Galvanized Reinforcement
 - MMFX Microcomposite (MMFX-2) Reinforcement
 - FRP Reinforcement
 - GFRP
 - CFRP
 - AFRP




HIGH PERFORMANCE CONCRETE 2006-07 FOLLOW-UP SURVEY RESULTS







Survey Topics (cont.)







- General Section
 - Primary characteristics of HPC tested
 - Method for specifying HPC
 - Number of projects planned and constructed
 - HPC Specification
 - Percentage of HPC used in the last 3 years (check)







HIGH PERFORMANCE CONCRETE 2006-07 FOLLOW-UP SURVEY RESULTS







Structural Element	Deck	Deck Overlays	Substructure	Superstructure	Other
General Use of HPC					
For the structure which used HPC, indicate the range of counts which best reflects the project specified providing the quality of the data.					
Structural Element	Deck	Deck Overlays	Substructure	Superstructure	Other
Number of Responses	1-10	11-20	21-30	31-50	>50
Deck	1	1	1	1	1
Deck Overlays	1	1	1	1	1
Substructure	1	1	1	1	1
Superstructure	1	1	1	1	1
Other	1	1	1	1	1
HPC for Permeability					
For the structure which used HPC, indicate the range of counts which best reflects the project specified providing the quality of the data.					
Structural Element	Deck	Deck Overlays	Substructure	Superstructure	Other
Number of Responses	1-10	11-20	21-30	31-50	>50
Deck	1	1	1	1	1
Deck Overlays	1	1	1	1	1
Substructure	1	1	1	1	1
Superstructure	1	1	1	1	1
Other	1	1	1	1	1
HPC for Strength					
For the structure which used HPC, indicate the range of counts which best reflects the project specified providing the quality of the data.					
Structural Element	Deck	Deck Overlays	Substructure	Superstructure	Other
Number of Responses	1-10	11-20	21-30	31-50	>50
Deck	1	1	1	1	1
Deck Overlays	1	1	1	1	1
Substructure	1	1	1	1	1
Superstructure	1	1	1	1	1
Other	1	1	1	1	1
HPC for Durability					
For the structure which used HPC, indicate the range of counts which best reflects the project specified providing the quality of the data.					
Structural Element	Deck	Deck Overlays	Substructure	Superstructure	Other
Number of Responses	1-10	11-20	21-30	31-50	>50
Deck	1	1	1	1	1
Deck Overlays	1	1	1	1	1
Substructure	1	1	1	1	1
Superstructure	1	1	1	1	1
Other	1	1	1	1	1
Other Placed HPC					
For the structure which used HPC, indicate the range of counts which best reflects the project specified providing the quality of the data.					
Structural Element	Deck	Deck Overlays	Substructure	Superstructure	Other
Number of Responses	1-10	11-20	21-30	31-50	>50
Deck	1	1	1	1	1
Deck Overlays	1	1	1	1	1
Substructure	1	1	1	1	1
Superstructure	1	1	1	1	1
Other	1	1	1	1	1

















HIGH PERFORMANCE CONCRETE 2006-07 FOLLOW-UP SURVEY RESULTS


Conclusions

- **HPC Provides**
 - Extension of service life
 - Reduced Maintenance
 - Lower Life Cycle Cost
- **Significant progress in HPC Implementation in the past 15 years, however, more needs to be done**
- **State DOTs and Industry have taken advantage of strength and durability of HPC**

HIGH PERFORMANCE CONCRETE 2006-07 FOLLOW-UP SURVEY RESULTS

Conclusions (cont)

- **Researchers and academia have provided solutions to design and construction problems**
- **FHWA has supported the research, development, deployment and implementation of HPC through the many programs and initiatives described above**
- **FHWA will continue to ensure that public and private sector partnerships be strengthened for successful implementation of HPC**



Route 15/29 SBL Bridge Superstructure Replacement & Widening



NOVA District



We Keep Virginia Moving

AGENDA

- Existing Structure ■
- Scope ■
- Accelerated Construction Procedure ■
- Construction Staging (Superstructure) ■
- Preparatory Work (Substructure) ■
- Questions



We Keep Virginia Moving

EXISTING STRUCTURE

Location: Route 15/29 SB Bridge over Broad Run, Prince William County

Superstructure: 3-Span, Concrete T beam, Simply Supported


Substructure: Wall Type Piers & Abutments

Year Built: 1952

Condition in 2005: Severe Deterioration of Superstructure



We Keep Virginia Moving



Bridge Elevation



We Keep Virginia Moving

Bridge Views



Profile View

Approach Roadway View



AGENDA ■





We Keep Virginia Moving

SCOPE

- Replace & Widen Superstructure
- Minimize Traffic Disturbance
 - Construction at Night only
 - Maintain 1 Lane of Traffic at Night
 - Restore Traffic to Normal (2 Lanes) at Day
 - Complete Work in 12 Nights



We Keep Virginia Moving



ACCELERATED CONSTRUCTION PROCEDURE (MODULAR CONSTRUCTION)

1. Preparatory Work
 - Maintain all Traffic Lanes
 - Widen Approaches
 - Modify Substructure for Modular Superstructure
2. Superstructure Replacement
 - Maintain 1 Lane of Traffic at Night
 - Remove Designated Portions of Superstructure
 - Replace with Modular Segments
 - Restore traffic to Normal (2 Lanes) at Day
 - Accomplish Work in 12 Nights
3. Overlay the Bridge and Approaches

AGENDA

Virginia Department of Transportation

We Keep Virginia Moving

PROPOSED MODULAR STRUCTURE

Module Configuration:
 Each Module Consists of a Prefabricated Conc. Deck on Two Steel Beams
 Module Width Arrangement in Transverse Section: (12'- 11") (9'-0") (8'- 9") (7'-10")
 Module Length = Span Length (- 44")
 Max. Module Weight = ~35 tons w/ Lightweight Concrete

Longitudinal Joints between Modules:
 Grouted/Waterproofed Keyways



Diaphragms between Modules:
 Field Installed Steel Diaphragms







Deck Parapets:
 Plant Cast Concrete







AGENDA

Virginia Department of Transportation

We Keep Virginia Moving













- Nighttime Operations Include:**
- Install Middle Diaphragms
 - Apply Rapid Set Joint Mortar

- Concrete in Deck & Rail:**
- Light Weight
 - Low Permeability



AGENDA ■



UHPC or UHPFRC


Ultra High-Performance
Fiber-Reinforced Concrete

Celik Ozyildirim, Ph.D., P.E.
Research Council, VDOT

Virginia Concrete Conference, March 2008


UHPC HISTORY

- 1994: Development of Bouygues, Lafarge, and Rhodia, France
- 1997: Sherbrooke, Canada Footbridge
- 2001: Bourg lès Valence, France Highway Bridges
- 2002: Seoul, Korea Footbridge of Peace




UHPC

- Compressive strengths \geq 30,000 psi
- High ductility
- Very low permeability
- Lighter, thinner, and more durable structural sections
- High shear capacity in bending



UHPC

- Two of the primary sources for these enhancements:
 - Finely graded and tightly packed nature of concrete constituent materials (no coarse aggregate)
 - Steel or synthetic fibers





UHPC




UHPC

- Bus shelter in Tucson, AZ

UHPC

- Light rail transit station, Calgary, Canada
- Canopies 20 mm (0.8 in) thick



UHPC

- 6x10 ft panel, 1-inch thick carries 2,000 lb car.



UHPC AT TFHRC



Sherbrooke Bridge, Canada, 1997



Footbridge of Peace Seoul, Korea, 2002



Bourg lès Valence Bridges, France



Opened in 2001,
UHPC Beams



UHPC, Wapello County, Iowa

- Three 110-ft beams, 27'-2" ft wide deck
- Beams cast in Canada in 2005
- Opened to traffic in 2006



UHPC Beams

- Route 624 over Cat Point Creek, Richmond County, Virginia
- 10 spans: 81 ft 6 in each
- Five 45-in bulb-T beams per span
- One span with UHPFRC



UHPC




UHPC Compressive Strength

Test	psi (average of 3)
1	30,456
2	30,747
3	30,492
4	27,275



Flexural Strength Test



UHPC



UHPC



UHPC



UHPC



UHPC



UHPC



UHPC



UHPC



Thank You

VTRC
Virginia Transportation
Research Council

Corrosion Resistant Reinforcing Steel (12 Projects)

Michael Sprinkel, P.E.
Associate Director – VTRC
Julius Volgyi, P.E.
Structure and Bridge – VDOT
Richard Weyers, P.E PhD
Professor-VPI&SU

VTRC
Virginia Transportation
Research Council

Why Use CRR?

- Lab and field studies evaluated the performance of uncoated reinforcement (UR), epoxy coated reinforcement (ECR) and corrosion resistant reinforcement (CRR) in decks.

VTRC
Virginia Transportation
Research Council

Disadvantages of ECR in decks

- Cracks are 33 % wider when ECR is used.
- Epoxy loses adhesion to steel as it ages.
- The permeability of epoxy increases with age.
- Epoxy cracks with age.


VTRC
Virginia Transportation
Research Council

Epoxy Loses Adhesion With Age



VTRC
Virginia Transportation
Research Council

Epoxy Cracks With Age



VTRC
Virginia Transportation
Research Council

Why Use CRR?

- Time to corrosion of UR and ECR was estimated at 25 to 50 years for VDOT concretes (1977-1995).
- ECR was estimated to increase the time to corrosion-induced spalling by only 5 years.
- Time to corrosion for CRR is ≥ 4.5 times that of UR.
- Time to corrosion of CRR was estimated at more than 200 years.



Why Use CRR?

- Crack control is better than ECR.
- Corrosion protection in cracks is better than ECR.
- Initial cost is \geq ECR.
- Life cycle cost is $<$ ECR.



Section 223 Steel Reinforcement

CRR shall conform to the requirements of one of the following standards:

- ASTM A1035/A1035M – 05 Standard Specification for Deformed and Plain, Low-carbon, Chromium, Steel Bars for Concrete Reinforcement.
- ASTM A955/A955M - 06a Standard and Specification for Deformed and Plain Stainless Steel Bars for Concrete Reinforcement.
- AASHTO Designation: MP 13M/MP 13-04, Standard Specification for Stainless Steel Clad Deformed and Plain Round Steel Bars for Concrete Reinforcement.



Section 223 Steel Reinforcement

- Revisions being reviewed by VDOT Specifications committee and the FHWA.



ASTM A1035/A1035M

- Will have an upper limit on yield strength as ductility may still be an issue.
- Has been adopted into the AASHTO LRFD Construction Specifications.
- Has not yet been adopted into the design specifications.



Available Products

- MMFX-2 by Steel Corporation of America, Inc.
- EnduraMet 32 by the Carpenter Company
- 2101, 2201, 2205, 304, 316 Stainless Steels



VDOT Plan to Use CRR

- 2007: modify design standards to specify CRR in decks (one to one replacement for Grade 60 rebars).
- January – December 2008: Advertise 12 projects (approximately 10%).
- January – December 2009: Advertise 24 – 30 projects (approximately 30%).
- January 2010: Full implementation.

Thank you.

Questions?



VTTC
Virginia Transportation
Research Council

**Virginia Concrete Conference
March 7, 2008**

VDOT EXPERIENCE WITH GROUTED TENDONS IN
VARINA-ENON PRECAST SEGMENTAL
POST-TENSIONED BRIDGE

Michael Sprinkel, P.E.
Associate Director
VTTC

Claude S. Napier, P.E.
Division Bridge Engineer
FHWA – VA


VTTC

**Bridge Construction
and
Typical Segment**




VTTC

**Dedication Ceremony
July 18, 1990**



VTTC

**I- 295 Varina-Enon Bridge
28 spans**



VTTC

**2001 Varina-Enon Inspection:
hole in duct; rust on strand & void in duct;
rust was confined to vicinity of hole**







Concerns?

- Long Term Performance of Structure
- Preventive Maintenance Requirements to Extend Service Life
- Future Rehabilitation Costs
- In-Depth Inspection Requirements
 - What Techniques?
 - How Frequently?
- Health Monitoring Requirements
 - Short Term Monitoring
 - Long Term Monitoring





Why did tendon fail in 17 years?

- Original grout (water, cement, admixture)
- Vacuum grout (high performance)
- Original grout and vacuum grout
- Chloride ions (none found)
- Carbonation of grout (original grout at failure)
- Moisture (grout has high moisture content)
- Oxygen (voids in tendons, unsealed vent tubes and inspection holes)
- Combination of factors


Concerns About Grouts in Tendons

- Voids due to bleeding and segregation (Bleeding in grouts used prior to 2000 was approximately 4 percent. In a 150 ft long tendon, 4 percent bleeding can cause 6 ft of void at the high points in the tendon)
- Voids due to incomplete grouting and leaks

Wick Induced Bleed Test
cement and water, aluminum powder, high performance prepackaged grout



-
- Tendon Inspection and Repair**
- Inspected tendons for voids in grout, flaws in ducts, and corrosion of strands and anchors (visual, wire probes, sounding, and bore scope) (2001 and 2002)
 - Vacuum grouted some voids (2003 and 2004)
 - Sealed some tendons (2003 and 2004)
 - Replaced 2 tendons (1 failed, 1 with 3 broken wires) (2007)
 - Evaluated condition of tendons using Magnetic Flux (approximately 80 % of each duct) (2007)
 - Twenty tendons selected for detailed evaluation by removal of a 2-ft section of duct (18 because of corrosion in bore scope pictures, 1 because of Magnetic Flux measurements by Dr Al Ghorbanpoor and 1 because of his visual inspections) (2007)
 - Plan to monitor tendons representing 6 conditions (2008)











Grout Moisture Content					
Tendon	Broken wires	Section loss	color	Moisture content, %	Absorption, %
NP13T10	2	7 wires 5.3 %	Gray	32.8	35.5
SP12T9	1	4.8 wires 3.6 %	Gray (bottom)	36.6	39.5
SP12T9	1	4.8 wires 3.6 %	White (top)	21.6	36.5

VTBC

Monitoring 6 Tendon Conditions



1. Voids, no vacuum grout (45 per cent of tendons)
2. Voids, incomplete vacuum grout
3. Drying shrinkage cracks in grout
4. Small section with minor pitting corrosion
5. Pitting corrosion and several broken wires
6. Vacuum grouted tendon with broken wires





Tentative Conclusions

- Tendons have voids
- Approximately 55 % of tendons were vacuum grouted
- Grout typically has high pH and high moisture content
- Corrosion typically associated with access to oxygen and absence of grout

Recommendations

- Vacuum grout tendons with accessible voids
- Repair ducts and vacuum grout tendons subjected to detailed inspections
- Monitor tendons representing 6 tendon conditions using visual inspections through transparent duct repairs, half cell and rate of corrosion measurements and acoustic emission sensors.

Recommendations

- Consider Other Health Monitoring Technologies Based on Failure Analysis
- Determine Future In-Depth Inspection Requirements
- Perform Additional Repairs As Recommended from On-going Evaluation of Bridge




Acknowledgements

- Steve Sharp and staff, Research Scientist VTTC
- Gary Martin and staff, VDOT Bridge Engineer
- Claude Napier, FHWA
- Rudy Maruri, FHWA
- Denney Pate and staff, Figg Bridge
- VSL staff






Precast Prestressed Concrete Beams and Girders For Virginia Highway Bridges

Rodney T. Davis, PhD, PE
Virginia Transportation Research Council



Economical Bridge Designs Using Normal Weight Concrete

Virginia PCBT's set as simple spans, CIP deck

- Span to beam depth h ratio of 18 to 21, with 20 being about optimal
- Beam spacing up to about 10 feet
- Beam Concrete 8000psi
- Beam web width 7 inches
- Equivalent of 0.8 ½" dia. strands per inch of beam depth h
- Deck concrete 4000psi
- Continuity diaphragms and integral backwalls

Economical Bridge Designs

Virginia PCBT's set as simple spans, CIP deck

- Span to beam depth h ratio greater than 20
- Beam spacing of about 10 feet maintained with span to depth ratios up to 24 requires LW deck
- Beam Concrete 8000psi (normal weight unless reduced superstructure weight is needed, reduced modulus and reduced self-weight offset in pretensioned beams)
- Lightweight deck concrete up to 5000psi and down to 110 pcf
- Add beam lines only if necessary

Spliced Girder Superstructures

- Use typical spliced girder construction for spans from 170 feet to 380 feet
- Try span to girder depth h ratios of 21 at the pier and 29 near midspan
- Girder concrete strength 8000psi
- Use individual splices with moment capacity as reinforced concrete section
- Use conventional 4000psi CIP deck
- Use 4 or more tendons, spread them out in web
- Need P/T duct specification similar to Florida DOT, but we don't need nor want the plastic duct

Spliced Girder Superstructures

- Girder weight has important influence as span length increases
- Modify section
- Reduce beam and deck densities
- Add girder lines
- Increase girder strength last option
- Pier segments use custom form
- No massive elements in girders



Properties for Design Tensile Strength

- Lightweight concretes are exhibiting about 7/8th of the tensile strength of the equivalent normal weight concrete
- Slower cure results in higher tensile strength relative to the compressive strength

Tensile Strength of Typical 8000psi Beam Concretes		
Failure mode	NWC	LWC
Splitting Tensile	0.090 f_c'	0.080 f_c'
Beam Rupture	0.085 f_c'	0.075 f_c'
Tension Field	0.060 f_c'	0.055 f_c'

Properties for Design Modulus of Elasticity

- Modulus of elasticity of lightweight concrete is dependent on the volume of lightweight aggregate, and the paste density
- Modulus of elasticity of normal weight concrete is dependent on the type of aggregate, and the paste density

Modulus of Elasticity of Typical 8000psi Beam Concretes		
	NWC	LWC
At Transfer	4200-5600 ksi	3100-3300 ksi
In Service (VA)	5000-6500 ksi	3300-3500 ksi
Dried at 50% RH		3100 ksi

Properties for Design Creep Coefficient for P/S plus Self-weight

- Beam concretes using slag (and presumably fly ash) show a marked increase in early age creep as well as strength when cured at lower temperatures (less than 135 degF)
- Range of values in the table are for peak concrete temperatures during curing from 130 to 165 degF
- Creep from prestress transfer and self-weight is complete in 7 to 60 days depending on curing regimen

Creep Coefficient for Typical 8000psi Beam Concretes		
Interval	NWC	LWC
Transfer to day 7 - 60	0.25 -1.2	0.25 - 1.2

Properties for Design Autogenous Shrinkage of Beam Concrete

- Use of lightweight aggregates is known to reduce autogenous shrinkage and its associated stresses
- This is a difficult strain to measure as it is occurring during the accelerated curing of the beams
- Vertical cracking of beams during cooling and before prestress transfer indicates that the beam has shortened during the curing process
- Reduces camber at transfer

Autogenous Shrinkage Strain for Typical 8000psi Beam During Accelerated Cure		
	NWC	LWC
Microstrain	about 250	lower

Properties for Design Total Shrinkage of Beam Concrete

- Lightweight concrete exhibited more shrinkage than the normal weight concrete after leaving the form
- Beams cured at lower temperature showed more shrinkage after leaving the form than beams cured above 150 degF

Total Shrinkage Strain for Typical 8000psi Beams		
	NWC	LWC
Microstrain	about 350	about 350-450


Mix Design Beam Concretes

Typical 8000psi Beam Concrete Constituents		
	NWC	120 PCF LWC
Portland Cement	450 pcy	480 pcy
Slag	300 pcy	320 pcy
Water	232 pcy	248 pcy
w/cm ratio	0.31	0.31
Fine Aggregate	1050 pcy	1150 pcy
Coarse Aggregate	2100 pcy	1050 pcy

Problem Areas - Precast Prestressed Beams and Girders



- Beam end cracking at transfer of prestress
- Thermal stress induced web cracking and cold joints
- Creep and shrinkage, camber growth

Upper and Lower Strut-and-Tie Models for Beam End Design



Working Stress for Vertical Beam End Reinforcement

- 22ksi for normal weight concrete in non-aggressive environments
- 19ksi for lightweight concrete
- 16ksi for aggressive environments, spliced girder segment ends





Curing Method of Precast Prestressed Beams

- Higher temperature, shorter duration
 - Lower final tensile and compressive strength
 - Little creep and less shrinkage after prestress transfer
 - Improved production
- Lower temperature, longer duration
 - Higher final tensile and compressive strength
 - More creep and shrinkage after prestress transfer
 - Camber growth may be unacceptable for LW beams, and will not meet 50% camber growth spec

Fabrication of Beams

- Casting should proceed quickly and continuously
- Upon initial set enclosure temperature should be ramped at a rate such that the form temperature does not exceed the concrete temperature by more than a few degrees
- Beam temperature should be kept constant until transfer strength has been achieved
- Strands should be cut as quickly as possible after steam has been stopped
- Best results have been achieved when ramp rate is slower, and transfer strengths are above 6400psi

Rte. 33 over the Mattaponi River at West Point, Virginia



Count On Concrete for Long Life & Value

A Contractors Footprint in the Deck!

How Can Contractors Contribute to Long Life & Value in Full Depth Precast/Prestressed Deck Systems?


- Address Construction Means & Methods in the Shop Drawing Phase.
- Panel Production
- Handling, Transport, & Storage
- Field Engineering & Accuracy of Installation
- Erection
- Transverse & Longitudinal Joints

Means & Methods in the Shop Drawing Phase


- Will construction be top-down, or bottom-up? If top-down, will add'l reinforcing be required for setting operation? (live loading of installation equipment on partially completed deck)
- Will producers standard lifting and handling embeds be adequate for setting operation? If not, can producer install embeds that will also accommodate contractors setting operation?
- How will panels be supported in place prior to keyway grouting? Haunch Support Angles? Leveling Bolts?

Construction Loading For Top-Down Erection


CAT 950F wheel loader
(machine weight is 35,000 lbs)



Older Panel Elevation adjustment method.
Angle support system is preferred.




Size Panel Supports For Construction Loading



Panel Production

- Have a competent contractor employee interact with the panel supplier during initial casting operation and as necessary thereafter to verify embed location and overall conformity to dimensional requirements.
- Challenge the panel supplier to perform better than his specified tolerances require.



Handling, Transport, & Storage


- Develop a formal lifting, transport, and jobsite storage (if necessary) plan.
- Set panels from delivery truck into final position whenever possible. Avoid stockpiling panels on jobsite.
- If panels must be stored on site, improve storage area as necessary to insure its load bearing characteristics and stability under adverse weather conditions.
- If stacking is required, always use square blocking material. (4x4 or 6x6, not 4x6)
- Periodically check stockpiles for unexpected settlement and modify as required



Blocking Supports Panel in Crowned Position




Variable Height Blocking for Bottom Panel Preserves Crown.
Square Blocking For All Successive Panels.



Field Engineering & Accuracy of Installation

- Top of girder elevations should be shot twice, by different instrument men if possible.
- Set grade points to coincide with transverse panel joints, or multiples thereof.
- Install string-lines set at a constant vertical offset along centerline of girders above grade points for use in installation of panel support devices.
- Project management should inspect string-lines for common plane between girders, and smooth vertical transitions between spans or into abutments as applicable PRIOR to any panel erection or installation of panel supporting devices.



Panel Erection

- Inspect panels for dimensional irregularities and remediate prior to erection.
- Lay-out termination points on girders for each panel.
- Adjust rigging so that panels hang at roughly the same cross slope as the girders.
- If leveling bolts are used for panel support and elevation control, check and set elevation as each panel is installed, and once panel is on grade, use torque wrenches to compare torque values between the bolts of each panel. Actual torque values are insignificant, but adjust until all bolts for each panel fall within a range of 10%. This procedure will minimize the occurrence of hard point bearing areas in the panels prior to haunch grouting.



Panel Erection



Transverse & Longitudinal Joints


- Joints between precast panels have historically been a source for moisture intrusion and corrosion.
- Most joints are "wet cast" in that they are filled with a high performance cast-in-place concrete after erection.
- Research is currently under way that investigates the possibility of "match cast" transverse panel joints. Match casting would eliminate the need for CIP closures, and the waterproofing of the joint would be obtained by either an epoxy gel, or a thin compressed neoprene strip adhered to one side of the joint.

Wet Cast Joints

- Project specifications generally call for either water-blasting or sand-blasting to be performed in advance of joint filling operations under the wet cast method.
- The best condition would be for the precast supplier to sand-blast joint surfaces as soon as possible after form removal. The form finish paste would be removed from the surface, and both coarse and fine aggregate would be visible on the bonding plane. Immediately prior to the placement of the CIP joint fill material, the contractor would perform a high pressure water-blast of the bonding planes. The water-blasting removes any deleterious material deposited since sand blasting, and properly moisture impregnates the surfaces for the best bond with the chosen joint fill CIP concrete.

Wet Cast Joint

Note Exposed Aggregate Surface



Match Cast Joints

(Not currently utilized in full depth deck panels, but hopefully coming soon!)

- Closely inspect joints for any irregularities
- Grind off any form seam or joint marks that might interfere with tightness of joint.
- Sand or water-blast surface to obtain good bonding profile for chosen epoxy.
- Use epoxy gel with enough set time and in appropriate temperature conditions to allow for minute adjustments of panel as may be required without premature set.

Thank You

- Special Thanks to:
Dr. Maher Tadros P.E., Leslie D. Martin
Professor of Civil Engineering at University of
Nebraska for his Contribution of pictures used
in this presentation.

FULL DEPTH PRECAST DECK PANELS – A PRECASTER'S PERSPECTIVE



BAYSHORE CONCRETE PRODUCTS



GOAL / OBJECTIVE

- COLLECTIVELY, WE (OWNERS, DESIGNERS, PRECASTERS, & ENGINEERS) NEED TO DEVELOP FULL DEPTH DECK PANELS THAT ARE A COST EFFECTIVE ALTERNATIVE, CREATES EFFICIENT CONSTRUCTION METHODS, AND PROVIDES A LONG LASTING, MAINTENACE FREE BRIDGE DECK.



OVERVIEW

- CONCRETE CHARACTERISTICS
- TOLERANCES
- JOINT DETAILS
- SURFACE FINISH
- SHEAR POCKETS
- PANEL GEOMETRY
- FORMWORK



CONCRETE CHARACTERISTICS

- HIGH PERFORMANCE CONCRETE
 - PERMEABILITY – ASTM C1202 – 56 DAY DURATION
 - SCALING – ASTM C 672 – 80 DAY DURATION (50 CYCLES)
 - FREEZE-THAW – ASTM C 666 - 180 DAY DURATION
 - CREEP – ASTM C 512 - 120 DAYS TO 13 MONTH DURATION
 - STRENGTH – ASTM C 39 – 28 DAY DURATION
- CONCRETE MIX TESTING
 - ALLOW TIME PRIOR TO PRODUCTION
- STORAGE REQUIREMENTS
 - MINIMIZE STORAGE NEEDED PRIOR TO ERECTION
 - CALCULATE / ESTABLISH TIME FOR CREEP/SHRINKAGE TO OCCUR




TOLERANCES

- PRECAST CONCRETE TOLERANCES
- CRSI TOLERANCES
- ACTUAL DUCT O.D.
- COVER REQUIREMENTS



TOLERANCES




JOINT DETAILS

- POUR BACK STRIP WITH PROJECTING BARS




JOINT DETAILS

- FORMED FACES/SHEAR KEYS WITH EPOXY



JOINT DETAILS

- MATCH CAST FACES WITH THIN EPOXY BOND



RIDING SURFACE

- PANEL FINISHED SURFACE AS RIDING SURFACE
 - ISSUES WITH PANEL IRREGULARITIES & DIFFERENTIAL CAMBER
- PANEL WITH SACRIFICIAL THICKNESS FOR GRINDING / GROOVING
 - BEST RESULTS FOR RIDEABILITY
 - FASTER APPROACH TO PUT PANELS IN SERVICE VERSUS AN OVERLAY
 - QUALITY OF THE CONCRETE FOR THE RIDING SURFACE IS INHERENT TO THE PANEL CONCRETE
- PANEL WITH ROUGHENED SURFACE FOR BONDING TO OVERLAY



PANEL TO GIRDER SHEAR CONNECTIONS

- TWO FOOT SPACING OVER EACH GIRDER LINE (AASHTO REQ.)
- STEEL BEAMS – STUDS CAN BE SHOT AFTER PANEL PLACEMENT
- CONCRETE BEAMS – STUDS CAN BE GROUTED IN PLACE
- CONCRETE BEAMS – STUDS CAN BE CAST IN TOP OF GIRDERS
- SHEAR POCKET SPACING COULD BE INCREASED

DECK PANEL GEOMETRY

- TRUCKING ISSUES TYPICALLY REQUIRE 8'-0" TO 10'-0" MAX WIDTH
- KEEP DIMENSIONS RELATIVELY CONSISTENT TO REDUCE COSTS
- CONSIDER PANEL WEIGHTS FOR SHIPPING
- DIFFERENTIAL CAMBER BETWEEN PIECES MAY OCCUR





FORMWORK

- **MATCH CAST FORM WORK IS EXPENSIVE (ESP.W/ PRESTRESSING) AND TIME CONSUMING**
- **RIGID/MACHINED SIDE FORMS FOR SHEAR KEY – SHOULD ELIMINATE THE “NEED” FOR MATCH CASTING**
- **MAXIMIZE PANEL LAYOUT FOR PRESTRESS BEDS**
- **LOCATE PRESTRESS STRAND ON 2-INCH SPACING**






Deck Panel Research at Virginia Tech


Matt Swenty

Construction of Full Depth Concrete Bridge Deck Panels






Research Areas





Full Scale Mock-Up

Long Term Behavior- Woodrow Wilson Bridge



Time Dependent Behavior

Specification for Haunch and Pocket Grout

- Compressive and Tensile Strength
- Low Shrinkage
- Good Flow
- Good Cohesion
- Evaluate through ASTM and mock-up tests







Horizontal Shear Connectors - Push Off Tests




Examined a wide variety of connector details and grout types

AASHTO equation for horizontal shear strength of smooth surfaces was best design equation

Lab Mockup



5 Precast deck panels



Pocket spacing

3 Post-tensioning ducts

2 AASHTO Type II girders

Shear connectors

Grouted female-female joints and epoxied male-female joints.



Time Dependent Behavior

- Deck panels are post-tensioned and then connected to girders (steel or concrete)
- Over time the deck wants to creep and shrink but is restrained by the girders
- Self-equilibrating stresses develop over time, along with restraint stresses in continuous systems
- Deck loses precompression over time

Design Recommendations

Girder Type	Number of Spans	Required Initial P/T (psi)
Steel	1	200
	2	650
	3 or more	500
PCBT	1	200
	2	200
	3 or more	200
AASHTO	1	200
	2	200
	3 or more	200

Panel to Panel Connections

Narrow non-prestressed joint with drop-in rebar

Female-female narrow keyed grouted post-tensioned joint

Wide cast-in-place joint with interlocking hairpin reinforcement



Woodrow Wilson Bridge Inspection



Continuing and Future Work

- Panel-to-panel joint evaluation
- Shear stud pocket performance
- Field implementation and testing

Thank You