DESIGN ANALYSIS REPORT

TERMINAL 4 PHASE I REMOVAL ACTION PORT OF PORTLAND, PORTLAND OREGON

DRAFT DOCUMENT: DO NOT QUOTE OR CITE

This document has not been reviewed or approved by USEPA and its federal, state and tribal partners and is subject to change in whole or in part

Prepared for

Port of Portland Portland, Oregon

Prepared by

Anchor Environmental, L.L.C. 6650 SW Redwood Lane, Suite 333 Portland, Oregon 97224

In Association with

NewFields
Ash Creek Associates, Inc.

April 9, 2008



DESIGN ANALYSIS REPORT

TERMINAL 4 PHASE I REMOVAL ACTION PORT OF PORTLAND, PORTLAND OREGON

DRAFT DOCUMENT: DO NOT QUOTE OR CITE

This document has not been reviewed or approved by USEPA and its federal, state and tribal partners and is subject to change in whole or in part

Prepared for

Port of Portland Portland, Oregon

Prepared by

Anchor Environmental, L.L.C. 6650 SW Redwood Lane, Suite 333 Portland, Oregon 97224

In Association with

NewFields
Ash Creek Associates, Inc.

April 9, 2008

1	INTRO	DUCTION	1
	1.1 Ba	ackground	1
	1.2 O	rganization of this Document	3
2	PHASE	E I REMOVAL ACTION DESCRIPTION	5
		hase I Removal Action Area	
		hase I Removal Action Objectives and Activities	
		erformance Standards	
		te-specific Sediment Quality Objectives	
		rea-specific Activities	
	2.5.1	Slip 3 – Combination of Dredging and Capping at Head of Slip	
	2.5.2	North of Berth 414 – Dredging	
	2.5.3	Wheeler Bay – Shoreline Stabilization	
3	EXISTI	NG CONDITIONS	12
	3.1 Pl	hysical Site Characteristics	12
	3.1.1	Terminal 4 Uplands	12
	3.1.2	Wheeler Bay Physical Characteristics	13
	3.1.3	Slip 3 Physical Characteristics	14
	3.2 H	ydrodynamic Characteristics	15
	3.3 W	vind Conditions	16
	3.4 G	eotechnical Conditions in Dredge and Cap Areas	16
	3.5 Se	ediment Quality in Slip 3 Dredging Areas	17
	3.5.1	Existing Sediment Chemistry Data	18
	3.5.2	Additional Pre-construction Data	19
	3.5.3	Sediment Quality Data Used for Dredge Design	19
	3.6 A	dditional Site Information	19
	3.6.1	Site Uses	19
	3.6.2	Typical Vessels that Call at Terminal 4	20
	3.6.3	Source Control	
4	DRFD	GE AND DISPOSAL PLAN	23
T		eneral Dredging Approach	
		erth 411 "Plus" Area	
	4.2.1	Basis of Design	
	4.2.2	Dredge Design	
		erth 410	
	4.3.1	Basis of Design	
	4.3.1	Dredge Design	
		quipment Selection – Mechanical Dredging	
		ediment Transport and Disposal	
	1.0	ament transport and Disposar	94

DRAFT DOCUMENT: DO NOT QUOTE OR CITE

This document has not been reviewed or approved by USEPA and its federal, state and tribal partners and is subject to change in whole or in part.



	4.6 Dr	edging Implementation Approach	35
	4.6.1	Dredging of Berth 411 "Plus" Sediments	35
	4.6.2	Dredging of Berth 410 Sediments	37
	4.7 Co	onstruction Quality Control Related to Dredging	37
5	C A DDIN	NG AND STABILIZATION PLAN	20
9		ead of Slip 3 Cap Design	
	5.1.1	Basis of Design	
	5.1.1	Chemical Isolation and Sheen Control Component	
	5.1.2	Erosion Component	
	5.1.3	Slope Stability (Geotechnical)	
	5.1.4	Bioturbation Component	
	5.1.6	Consolidation Component	
	5.1.7	Operational Component	
	5.1.8	Cap Design Summary and Sequencing	
		heeler Bay Stabilization Design	
	5.2.1	Basis of Design	
	5.2.2	Geotechnical Component	
	5.2.3	Erosion Component	
	5.2.4	Shoreline Stabilization Summary and Sequencing	
		urce Material for Capping and Stabilization	
		onstruction Quality Control During Capping and Stabilization Construction	
		olumes	
		uipment Selection and Placement Techniques	
_			- /
6		R QUALITY	
		onstruction Water Quality Criteria	
	6.1.1	Turbidity	
	6.1.2	Dissolved Oxygen	
	6.1.3	Chemicals of Concern	
	6.1.4	Background Criteria	
		ompliance Boundaries	
		redging Elutriate Testing	
		ater Quality Effects During Phase I Removal Action	
	6.4.1	Water Quality during Dredging Activities	
	6.4.2	Water Quality during Capping, Sand Layer Placement, and Stabilization Activ	
	6.4.3	Water Quality during Sediment Transport and Offloading	61
7	PERMIT	F EXEMPTION AND APPLICABLE OR RELEVANT AND APPROPRIATE	
R	.EQUIREM	IENTS	63
		rmit Exemption	
	7.2 Ap	oplicable or Relevant and Appropriate Requirements	63

DRAFT DOCUMENT: DO NOT QUOTE OR CITE

This document has not been reviewed or approved by USEPA and its federal, state and tribal partners and is subject to change in whole or in part.



7.3 ESA	Compliance	63
8 CONSTRU	JCTION SCHEDULE AND SEQUENCING	66
	e I – Focused Slip 3 Dredging, Capping, and Shoreline Stabilization	
	ish Exclusion	
	Oredging of Slip 3 and Berth 414	
	Capping and Stabilization	
	Monitoring	
8.2 Phas	e II – Completion of the Removal Action	68
9 ACCESS A	AND EASEMENT REQUIREMENTS	69
10 IMPACT	MINIMIZATION	70
10.1 Envi	ronment	70
10.2 Com	munity	70
11 INSTITUT	TONAL CONTROLS	71
12 REFEREN	CES	73
List of Tables	S	
Table 1	Terminal 4 Sediment Quality Guidelines	
Table 2	Terminal 4 Exceedance Ratios by Phase I Remediation Areas	
Table 3	10x PEC Elevations for Different Sampling Locations Within Berth 410 and Bert	h
	411 "Plus" Dredge Prisms	
Table 4	Surface and Maximum PEC Ratios at Core Locations Within Berth 411 "Plus"	
	Dredge Prism	
Table 5	Import Material Chemical Goals	
Table 6	Water Quality Criteria and Guidelines	
Table 7	Ambient Background Concentrations, Willamette River, Portland	
Table 8	DRET Elutriate Chemistry Results	
Table 9	DREDGE Model Input Parameters	
Table 10	ARARs for Shoreline Stabilization, Capping, and Dredging and Disposal	
List of Figure	es e	
Figure 1	Site Plan and Vicinity Map	
Figure 2	Summary of Phase I Removal Action	
Figure 3	Summary of Physical Conditions	
Figure 4	Removal Action Area Surface Sediment Concentrations and Phase I Dredge	
	Boundaries	

DRAFT DOCUMENT: DO NOT QUOTE OR CITE

This document has not been reviewed or approved by USEPA and its federal, state and tribal partners and is subject to change in whole or in part. April 2008



050332-01

Figure 5	Dredge Plan – Slip 3 and North of Berth 414
Figure 6	Dredge Sections – Berth 411 "Plus"
Figure 7	Dredge Cuts of the Proposed Berth 411 "Plus" Dredge Prism (plus 0.5'
	Overdredge)
Figure 8	Conceptual Dredge Pass Sequencing at Berth 411 "Plus"
Figure 9	Cap Section – Head of Slip 3
Figure 10	Wheeler Bay – Shoreline Stabilization Plan
Figure 11	Wheeler Bay – Stabilization Sections
Figure 12	Dredge Model Results

List of Appendices

Appendix A	Construction Quality Assurance Plan
Appendix B	Water Quality Monitoring Plan
Appendix C	Interim Monitoring and Reporting Plan (Outline)
Appendix D	Construction Drawings
Appendix E	Construction Specifications
Appendix F	Transportation and Disposal Plan
Appendix G	Pre-construction Sampling Data Report
Appendix H	Removal Action Construction Sampling and Analysis Plan
Appendix I	Removal Action Construction Quality Assurance Project Plan
Appendix J	Removal Action Construction Health and Safety Plan

1 INTRODUCTION

1.1 Background

In 2000, the U.S. Environmental Protection Agency (USEPA) added the Portland Harbor Superfund Site to the National Priorities List. The Port of Portland (Port) is one of 10 potentially responsible parties that entered into an Administrative Order on Consent with USEPA for a Remedial Investigation/Feasibility Study (RI/FS) of the Superfund Site in fall 2001. The Administrative Order on Consent allows Early Actions to be conducted to address known contamination at specific locations within the Superfund Site.

Contaminants found in Terminal 4 (T4) sediment samples during a remedial investigation directed by the Oregon Department of Environmental Quality (DEQ) led to a determination that a Removal Action at T4 is warranted. Accordingly, the Port is conducting a Non-Time-Critical Removal Action (NTCRA) under an Administrative Order on Consent for Removal Action (the AOC) executed by the Port and USEPA in October 2003. Figure 1 shows the Removal Action boundary at T4.

The AOC sets forth the general legal requirements that govern the execution of the Early Action. Appendix A to the AOC is the statement of work (SOW) for the implementation of the Removal Action. The SOW provides a list of deliverables, their submittal schedule, and the technical requirements each deliverable has to meet in order to implement the Early Action.

As part of the execution of the Early Action, the Port completed an engineering evaluation and cost analysis (EE/CA; BBL 2005) in which various Removal Action alternatives were identified, compared, and ranked for their relative performance at meeting specific objectives associated with the evaluation criteria of effectiveness, implementability, and cost. Based on the alternatives evaluated in the EE/CA, the USEPA issued an Action Memorandum (Action Memo) on May 11, 2006 (USEPA 2006a) that documented the selection of the Removal Action. The Removal Action documented in the Action Memo included a combination of monitored natural recovery, capping, and dredging with placement of contaminated sediments in a confined disposal facility (CDF) to be built on site.



The Port proceeded down a path to implement the Removal Action, which included several steps (30, 60, and 100 percent design deliverables) in the Remedial Design process. The Port submitted the T4 Early Action 60 Percent Design Submittal in December 2006, and from early 2007 through November 2007, the Port and USEPA teams (note: USEPA's team partners include the Tribes, DEQ, and National Oceanic and Atmospheric Administration [NOAA]) worked collaboratively on resolving technical questions and issues associated with the design.

As part of the collaborative resolution process, it was determined that many of the design issues are linked to the overall harbor-wide RI/FS process. For this reason, the Parties agreed to revise the schedule for implementation of the T4 Removal Action to realign the project with the harbor-wide RI/FS schedule. As a condition of the approval of the schedule realignment, USEPA is requiring the Port to implement an abatement action during the 2008 in-water work window to reduce risks present at the T4 site (USEPA 2007). Essentially, this action results in the division of the Removal Action project into two phases. Phase I (the abatement action) is planned for the 2008 in-water work window and encompasses abatement measures that could be initiated in the near term to reduce risk and address any imminent and substantial endangerment at T4 that may exist. Phase II (including construction of the CDF) will commence once the project is realigned with the harbor-wide RI/FS process. The Port submitted an Abatement Measures Proposal (Phase I remedy) in October 2007 (Anchor 2007a). USEPA provided comments on the proposal in November 2007, and based on those comments and their resolution, a final Phase I Removal Action abatement remedy was identified.

Phase I of the Removal Action includes the following components:

- Dredging and off-site disposal of sediment exhibiting the highest chemical concentration, providing a permanent solution of contaminant mass removal
- Construction of a nearshore cap to isolate petroleum-contaminated sediments from aquatic receptors and control a potential ongoing source to nearby areas
- Stabilization of the Wheeler Bay bank to minimize contaminant migration to the river

DRAFT DOCUMENT: DO NOT QUOTE OR CITE



 Dredging and off-site disposal of contaminated sediments in Slip 3 at Berth 410 to support water-dependent maritime use in a manner consistent with the Action Memo (USEPA 2006a) and in support of overall risk reduction in the Removal Action Area (RAA)

This Draft Design Analysis Report (DAR) presents the design details for that agreed-to Phase I remedy, which is described further in Section 2.2 and 2.4.

1.2 Organization of this Document

The remainder of this document provides detailed information on the development of the Prefinal Design as follows:

- Section 2 Phase I Removal Action Description describes the setting of the Phase I
 work, summarizes the Phase I objectives and performance standards, and details the
 Phase I activities by subarea.
- Section 3 Existing Conditions summarizes the information and data collected
 within the Phase I Area that will be used as the basis of the design, including
 physical conditions, hydrogeologic and geotechnical conditions, hydrodynamic
 characteristics, sediment quality, and site uses.
- **Section 4 Dredge and Disposal Plan** provides the conceptual dredge plan for Phase I, including the basis for design, design approach, dredge design surface, volumes, equipment selection, and construction quality control.
- Section 5 Capping and Shoreline Stabilization Plan provides the conceptual cap design at the Head of Slip 3, including the basis for design, design approach, source material description, volumes, and equipment selection. The section also provides the Wheeler Bay shoreline stabilization plan, including design, source material descriptions, volumes, and equipment selection.
- Section 6 Water Quality discusses water quality criteria, contaminant mobility testing, and predicted water quality for the different Removal Action elements.
- Section 7 Substantive Requirements of Permits discusses the regulatory requirements that must be achieved during the implementation of the Removal Action.



- Section 8 Construction Schedule and Sequencing describes the duration and order of the anticipated Phase I Removal Action construction activities.
- Section 9 Access and Easement Requirements provides access and easement information related to implementation of the Phase I Removal Action.
- **Section 10 Impact Minimization** discusses measures to minimize impacts to the environment and community.
- **Section 11 Institutional Controls** details the actions required to maintain capped areas.
- Section 12 References summarizes the references used in the document.

The appendices provide the following information:

- Appendix A Construction Quality Assurance Plan (CQAP)
- Appendix B Water Quality Monitoring Plan (WQMP)
- Appendix C Outline of the Interim Monitoring and Reporting Plan (IMRP)
- Appendix D Construction Drawings
- Appendix E Construction Specifications
- Appendix F Annotated Outline of the Transportation and Disposal Plan (TDP)
- Appendix G Pre-construction Sampling Data Report
- Appendix H Removal Action Construction Sampling and Analysis Plan (SAP)
- Appendix I Removal Action Construction Quality Assurance Project Plan (QAPP)
- Appendix J Removal Action Construction Health and Safety Plan (HASP)