



A long-range reservoir operating plan study.

Mississippi River Headwaters Reservoir Operating Plan Evaluation (ROPE)

A Partnership between:
the U.S. Army Corps of Engineers
and the U.S Forest Service.



**US Army Corps
of Engineers**
St. Paul District





**US Army Corps
of Engineers**
St. Paul
District



Objective of Today's Meeting

Provide an opportunity for the public to comment on the proposed operating plan for the Headwaters reservoirs as developed and described in the Draft ROPE report and Environmental Impact Statement (EIS).



**US Army Corps
of Engineers®**
St. Paul
District



Today's Topics

Introduction and Background
Plan Development and Selection
Proposed Plan Details
Effects of the Proposed Plan
Wrap-up



**US Army Corps
of Engineers**
St. Paul
District



Introduction and Background



US Army Corps
of Engineers®
St. Paul
District



What is the ROPE Study?

Reservoir Operating Plan Evaluation


- Process used to assess the current and potential future operating plans of reservoirs.



US Army Corps
of Engineers
St. Paul
District



ROPE Study Area



Large Study Area:

7 inter-connected
Federal reservoirs
(6 COE, 1 USFS).

415 square miles of
affected lake
surface.

484 miles of
affected rivers.



US Army Corps
of Engineers®
St. Paul
District



Why Was the ROPE Study Initiated?

- MHB requested a review of Operating Plans in a letter to the Corps.
- Congressional interest in the Recon and ROPE.
- Improved understanding of the physical limits of the system.
- Human use of the system has increased.
- Higher value is being placed on environmental health.



**US Army Corps
of Engineers**
St. Paul
District



USFS Role in ROPE

- USFS signed on as partner in 2003 to include Knutson Dam on Cass Lake in the study.
- USFS will be issuing a separate decision for operation of Cass Lake/Knutson Dam



US Army Corps
of Engineers®
St. Paul
District



Key Agency and Public Involvement

Public meetings in 1999, 2004, and 2006.

Numerous “Task Force” and Lake groups were assembled to help identify problems and opportunities.

Meetings were held periodically with Mille Lacs & Leech Lake Bands of Ojibwe to identify issues and assist in plan development.



**US Army Corps
of Engineers**
St. Paul
District



Agencies and Groups

U.S. Forest Service
Environmental Protection Agency
Minnesota Department of Natural Resources
Minnesota Pollution Control Agency
Leech Lake and Mille Lacs Bands of Ojibwe
Mississippi Headwaters Board
The Nature Conservancy
Audubon Society
Aitkin City and County
Star Island Protective League
Whitefish Area Property Owners Association
Round Lake Improvement Association
Big Sandy Lake Association
Gull Lake Association
Brainerd Rotary Club
Ottertail Power
Minnesota Power



**US Army Corps
of Engineers**
St. Paul
District



Plan Development and Selection



US Army Corps
of Engineers®
St. Paul
District



Corps Headwaters Reservoirs Project Purposes

- Navigation
- Tribal Trust
- Flood Damage Reduction
- Recreation
- Water Quality & Water Supply
- Fish and Wildlife





US Army Corps
of Engineers®
St. Paul
District



Operating Plan Alternatives

- **Current Plan** – No change.
- **R Plan** – Maximizes recreational and economic benefits.
- **E Plan** – Increases environmental benefits.
- **T Plan** – Maximizes environmental benefits through a 6” drop in water levels
- **P Plan** – Increases benefits to many resources while minimizes negative effects.



**US Army Corps
of Engineers**

St. Paul
District

Potential Effects Of Plan Alternatives



Alternative	Current Plan	R Plan	E Plan	T Plan	Proposed
Air Quality	0	-1	+1	+1	+1
Terrestrial Habitat	-1	-1	+1	+2	+1
Sedimentation and Bank Erosion	-1	-1	+1	+3	+1
Wetlands	-1	-1	+1	+1	+1
Aquatic Habitat	-1	-1	+1	+3	+1
Fishery	-1	-1	+1	+3	+1
Biological Productivity	-1	-1	+1	+2	+1
Biological Diversity	-1	-1	+1	+2	+1
Water Quality	-1	-1	+1	+2	+1
Threatened & Endangered Species	0	0	0	0	0
Recreational Opportunities	0	+1	-2	-3	-1
Public Health/Safety	0	0	-1	-1	0
Community Cohesion	0	0	-1	-2	0
Community Growth and Development	0	+1	-1	-1	0
Controversy	0	-1	-2	-3	-1
Property Values	0	+1	-1	-2	0
Regional Growth	0	0	0	0	0
Employment	0	0	-1	-1	0
Business Activity	0	0	-1	-2	0
Flooding Effects	0	-1	+1	+2	+1
Historic Architectural	0	0	0	0	0
Archeological	-1	-1	+1	+1	+1




US Army Corps
of Engineers®
St. Paul
District



General Benefits of the Proposed Plan

- Protect and enhance all the resources and uses in the Headwaters for future generations.





US Army Corps
of Engineers®
St. Paul
District



Proposed Plan Myths

- Dramatic declines in water levels.
- Declines in water levels are being proposed to enhance water supply downstream.
- Environmental benefits are for downstream areas (reservoir habitat would not benefit)



US Army Corps
of Engineers®
St. Paul
District



Plan Implementation and Adaptive Management

- Retain the ability to modify the plan to reinstate components of the current plan.
- 5-year “break-in” period
- Annual meeting to review operating plan performance and potential modifications.



**US Army Corps
of Engineers**
St. Paul
District



Proposed Plan Details Cass Lake



US Army Corps
of Engineers
St. Paul
District




Current vs. Proposed Plan

CASS LAKE OPERATING RULES		
	CURRENT	PROPOSED
Summer Band (elev. - ft.)	1301.4 - 1301.28	1302.25 - 1301.35
Summer Target (elev. - ft.)	1302.25-1301.43	1302.0- 1301.6 (May 15- Sep 15)
Band Width (ft.)	0.3	0.5
Normal Drawdown (elev. - ft.)	1300.25	1300.4
Maximum Drawdown (elev. - ft.)	1300.25	1300.25
Rate of Release (change/day)	20-30%	20-30%
Spring Pulse	NA	840 cfs
Minimum Flow Requirements April through September	all water levels: 100 cfs	>= (bottom of band): 130 cfs
		< (bottom of band) >= (bottom of band - 15"): 80 cfs
		< (bottom of band - 15"): 40 cfs
Minimum Flow Requirements October through March	all water levels: 100 cfs	>= (target - 6"): 80 cfs
		< (target - 6"): 40 cfs



US Army Corps
of Engineers®
St. Paul
District


Current vs. Proposed Plan





US Army Corps
of Engineers®
St. Paul
District


2006-2008 Water Levels





US Army Corps
of Engineers®
St. Paul
District


2006-2008 Water Levels





US Army Corps
of Engineers®
St. Paul
District


2006-2008 Water Levels





US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels






US Army Corps
of Engineers®
St. Paul
District



Cass Minimum Releases





**US Army Corps
of Engineers**
St. Paul
District



Proposed Plan Details Lake Winnibigoshish



US Army Corps
of Engineers®
St. Paul
District




Adverse Effects of the Current Plan

- Stable water levels impact vegetation and the aquatic community.
- Low minimum flows impact downstream river habitat.
- Rapid decline in water levels in late fall and winter impact reservoir and river habitat.
- Delayed high spring flows impact spawning and nesting.



US Army Corps
of Engineers
St. Paul
District

Winnibigoshish Stages





US Army Corps
of Engineers
St. Paul
District



Current vs. Proposed Plan


LAKE WINNIBIGOSHISH OPERATING RULES		
	CURRENT	PROPOSED
Summer Band (elev. - ft.)	1297.94 -1298.44	1297.94 -1298.44
Summer Target (elev. - ft.)	1298.19	1298.19 (May 1 – Jul 15)
Band Width (ft.)	0.5	0.5
Normal Drawdown (elev. - ft.)	1296.94	1296.94
Maximum Drawdown (elev. - ft.)	1294.94	1294.94
Rate of Release (change/day)	200 cfs or 0.5 ft. of TW change	20-30%
Spring Pulse	NA	1060 cfs
Minimum Flow Requirements April through September	$\geq(1294.94)$: 100 cfs	$(\geq$ bottom of band): 160 cfs
		$<$ (bottom of band) \geq (bottom of band - 15"): 110 cfs
	$<(1294.94)$: 50 cfs	$<$ (bottom of band - 15"): 50 cfs
Minimum Flow Requirements October through March	$\geq(1294.94)$: 100 cfs	\geq (target - 6"): 110 cfs
	$<(1294.94)$: 50 cfs	$<$ (target - 6"): 50 cfs



US Army Corps
of Engineers®
St. Paul
District



Current vs. Proposed Plan






US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels



Winnibigoshish Operating Hydrograph






US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels



Winnibigoshish Operating Hydrograph






US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels



Winnibigoshish Operating Hydrograph






US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels



Winnibigoshish Operating Hydrograph






US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels



Winnibigoshish Operating Hydrograph






US Army Corps
of Engineers®
St. Paul
District



Winni Minimum Releases





**US Army Corps
of Engineers**
St. Paul
District



Proposed Plan Details Leech Lake



US Army Corps
of Engineers
St. Paul
District

Current vs. Proposed Plan




LEECH LAKE OPERATING RULES		
	CURRENT	PROPOSED
Summer Band (elev. - ft.)	1294.50-1294.90	1294.45-1294.95
Summer Target (elev. - ft.)	1294.70	1294.70 (May 1 – Jul 15)
Band Width (ft.)	0.4	0.5
Normal Drawdown (elev. - ft.)	1293.80	1293.80
Maximum Drawdown (elev. - ft.)	1292.70	1292.70
Rate of Release (change/day)	100 cfs or 0.25 ft. of TW change	20-30%
Spring Pulse	NA	790 cfs
Minimum Flow Requirements April through September	$\geq(1292.70)$: 100 cfs	\geq bottom of band): 120 cfs
		$<$ (bottom of band) \geq (bottom of band – 15"): 80 cfs
	$<(1292.70)$: 50 cfs	$<$ (bottom of band – 15"): 40 cfs
Minimum Flow Requirements October through March	$\geq(1292.70)$: 100 cfs	\geq (target - 6"): 80 cfs
	$<(1292.70)$: 50 cfs	$<$ (target - 6"): 40 cfs



US Army Corps
of Engineers®
St. Paul
District



Current vs. Proposed Plan






US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels



Leech Operating Hydrograph






US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels



Leech Operating Hydrograph






US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels




Leech Operating Hydrograph





US Army Corps
of Engineers®
St. Paul
District


2006-2008 Water Levels





US Army Corps
of Engineers®
St. Paul
District

2006-2008 Water Levels





**US Army Corps
of Engineers**
St. Paul
District



Effects of the Proposed Plan



US Army Corps
of Engineers®
St. Paul
District



General Ecological Benefits of the Proposed Plan

- More natural flows and reservoir stages will benefit the health of aquatic and wetland communities and ensure their integrity for future generations.

Fish
Waterfowl
Mammals
Reptiles
Amphibians
Wetland Birds



US Army Corps
of Engineers®
St. Paul
District



Benefits of the Gradual Summer Decline

- Improved conditions for aquatic vegetation, including wild rice.
- Reduced shoreline erosion (property values, archeological resources, habitat)
- Benefits to reptiles and amphibians that overwinter in wetlands.
- Reduced winter flows in rivers to benefit fish.



US Army Corps
of Engineers®
St. Paul
District



Benefits of the Spring Pulse Flows

- Improve fish spawning success.
- Cleans silt from rocky habitat in the rivers.
- Benefits to waterfowl nesting.





US Army Corps
of Engineers®
St. Paul
District



Benefits of the Increased Minimum Releases

- Improved habitat conditions during dry conditions.
- Hydropower generation benefits.
- River recreation benefits.



US Army Corps
of Engineers®
St. Paul
District



Other Benefits of the Proposed Plan

- More natural hydrology would encourage “spin-off” environmental restoration projects.
- Protecting environmental health will ensure quality future recreational opportunities.





US Army Corps
of Engineers®
St. Paul
District



Adverse effects of the Proposed Plan

- Lower normal water levels in late summer and fall. Reduced boat access in shallow areas including channels, boat docks, lifts, and ramps.
- Slight additional reduction in water levels during droughts – normally less than 2 inches.



**US Army Corps
of Engineers®**
St. Paul
District



Wrap-up



**US Army Corps
of Engineers**
St. Paul
District

ROPE Schedule



Public Meetings on Draft Proposed Operating Plan and EIS	TODAY
Public Review Period Ends for Draft EIS	November 3rd
Release of Final EIS for Public Review	Winter 2008-2009
Record of Decision is Signed and Released	Spring 2009



**US Army Corps
of Engineers®**
St. Paul
District

For More Information



Webpage

www.mvp.usace.army.mil/rope

Emails

cemvp-pm-rope@mvp02.usace.army.mil

Agency Contacts

Steve Clark, ROPE Project Manager	651-290-5278
Luke Rutten, US Forest Service	218-335-8666
Kenton Spading, Hydrology	651-290-5623
Rick Carlson, Economics	651-290-5259