

| Public Notice No. | Project Name/ Application No./ Comment Period | | Applicant | Location, Project Description & Project Manager | | |
|-------------------|---|---------|-------------------|---|--|---|
| | Issued | Closing | | | | |
| PN 05-09 | BALTIMORE MAINE CTR/DREDGE 05-60580 <table border="1"> <tr> <td>December 20, 2004</td> <td>January 20, 2005</td> </tr> </table> | | December 20, 2004 | January 20, 2005 | Baltimore Marine Center LLC Attn: Mr. Dan Naor Suite 626 2700 Lighthouse Point East Baltimore, MD 21224 | <p>Location: Patapsco River, Baltimore City, Maryland</p> <p>To mechanically dredge an approximately 1.3 acre area to 7 feet below mean low water and to place the approximately 1,700 cubic yards of dredged material at the Hart Miller Island disposal site.</p> <p>Project Manager: Jon Romeo 410-962-6079</p> |
| December 20, 2004 | January 20, 2005 | | | | | |
| PN 05-07 | AISQUITH CREEK CHARITABLE 04-65204 <table border="1"> <tr> <td>December 6, 2004</td> <td>January 5, 2005</td> </tr> </table> | | December 6, 2004 | January 5, 2005 | Asquith Creek Charitable Trust c/o Paul Cinquegrana 1252 Fenwick Garth Arnold, MD 21012 | <p>Location: Asquith Creek and the Severn River, Anne Arundel County, Maryland</p> <p>To maintenance dredge by mechanical method a 970-foot by 50-foot (48,500 square feet) channel and a 335-foot by 50-foot (16,750 square feet) channel to a maximum depth of -7 feet at Mean Low Water (MLW).</p> <p>Project Manager: Claudia R. Steele 410-962-5675</p> |
| December 6, 2004 | January 5, 2005 | | | | | |
| PN 05-08 | ERAMUS PROPERTIES/DREDGE 04-60758 <table border="1"> <tr> <td>December 20, 2004</td> <td>January 20, 2005</td> </tr> </table> | | December 20, 2004 | January 20, 2005 | Erasmus Properties LLC Attn: Mr. Rupert Denney 1201 Wallace Street Baltimore, MD 21230 | <p>Location: Patapsco River (Northwest Branch), Baltimore City, Maryland</p> <p>To mechanically dredge two ship berthing areas 160 feet wide, and approx. 1,200 feet long and 170 feet wide, and approx. 600 feet long to 36 feet below mean low water, and to</p> |
| December 20, 2004 | January 20, 2005 | | | | | |

| | | | | | |
|---------------------------|---|-------------------|---|---|---|
| | | | <p>deposit the approx. 31,000 cubic yards of dredged material at the Hart Miller Island or the Cox Creek disposal sites.</p> <p>Project Manager: Jon Romeo 410-962-6079</p> | | |
| SPN 05-02 | <p>Special Public Notice 05-02 Establishment of Restricted Areas</p> <table border="1"> <tr> <td>December 7, 2004</td> <td>January 7, 2005</td> </tr> </table> | December 7, 2004 | January 7, 2005 | n/a | <p>U. S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/Notice VIII/December 7, 2004 - January 7, 2005</p> <p>Project Manager: John Roop 410-962-5688</p> |
| December 7, 2004 | January 7, 2005 | | | | |
| PN 05-06 | <p>CIANBRO CORP/BULKHEAD & DREDGING</p> <p>04-65643</p> <table border="1"> <tr> <td>December 6, 2004</td> <td>December 27, 2004</td> </tr> </table> | December 6, 2004 | December 27, 2004 | <p>Cianbro Corporation Attn: Mr. Tom Ruksznis One Hunnewell Square P.O. Box 1000 Pittsfield, ME 04967</p> | <p>Location: Curtis Creek, Anne Arundel County, Maryland</p> <p>To mechanically dredge an approx. 92,000 square foot area to 16 feet below mean low water, and to deposit the approx. 27,050 cubic yards of dredged material at the Hart Miller Island disposal site; and to construct 250 linear feet of new sheetpile bulkhead and relieving platform to replace the existing structures.</p> <p>Project Manager: Jon Romeo 410-962-6079</p> |
| December 6, 2004 | December 27, 2004 | | | | |
| PN 05-05 | <p>BA DEPRM/GREENHILL/DREDGING</p> <p>05-60163</p> <table border="1"> <tr> <td>November 23, 2004</td> <td>December 23, 2004</td> </tr> </table> | November 23, 2004 | December 23, 2004 | <p>Baltimore Co Environmental Protection & Resource Management Attn: Candace Croswell Suite 416</p> | <p>Location: Greenhill Cove, Baltimore County, Maryland</p> <p>To hydraulically or mechanically dredge a 4,280 foot long by 30 to 50 foot wide main</p> |
| November 23, 2004 | December 23, 2004 | | | | |

| | | | | | |
|-------------------|---|---|--|---|--|
| | | 401 Bosley Avenue Towson, Maryland 21204-4488 | channel to 4.5 feet below mean low water, and to deposit the approximately 11,900 cubic yards of dredged material at the Hart Miler Island disposal site. Project Manager: Jon Romeo 410-962-6079 | | |
| PN 05-04 | BA DEPRM/MUDDY GUT/DREDGING 05-60167 <table border="1"> <tr> <td>November 23, 2004</td> <td>December 23, 2004</td> </tr> </table> | November 23, 2004 | December 23, 2004 | Baltimore County Department of Environmental Protection & Resource Management Attn: Candace Croswell Suite 416 401 Bosley Avenue Towson, Maryland 21204-4488 | Location: Muddy Gut, Baltimore County, Maryland To hydraulically or mechanically dredge two main channels; segment "A" is 2,900 feet long, 50 feet wide and is to be dredged to 4.5 feet below mean low water; segment "B" is 800 feet long, 30 feet wide and is to be dredged to 4.5 feet below mean low water. The approximately 14,900 cubic yards of dredged material is to be deposited at the Hart Miller Island disposal site. Project Manager: Jon Romeo 410-962-6079 |
| November 23, 2004 | December 23, 2004 | | | | |
| PN 05-03 | BA DEPRM/LYNCH POINT/DREDGE 05-60168 <table border="1"> <tr> <td>November 23, 2004</td> <td>December 23, 2004</td> </tr> </table> | November 23, 2004 | December 23, 2004 | Baltimore County Department of Environmental Protection & Resource Management Attn: Candace Croswell Suite 416 401 Bosley Avenue Towson, Maryland 21204-4488 | Location: Lynch Point Cove, Baltimore County, Maryland To hydraulically or mechanically dredge a 2,355 foot long by 50 foot wide channel to 4.5 feet below mean low water, and to deposit the approximately 7,200 cubic yards of dredged material at the Hart Miller Island disposal site. Project Manager: Jon Romeo 410-962-6079 |
| November 23, 2004 | December 23, 2004 | | | | |

| | | | | | |
|----------------------------------|--|----------------------|----------------------|--|---|
| <p>PN 05-02</p> | <p>CH PLANNING & GROWTH/CROSS COUNTYCONNECTOR/RD XING)</p> <p>04-63344-19</p> <table border="1" data-bbox="467 394 849 478"> <tr> <td data-bbox="467 394 662 478">November 22, 2004</td> <td data-bbox="662 394 849 478">December 22, 2004</td> </tr> </table> | November 22, 2004 | December 22, 2004 | <p>Charles County Planning & Growth Management Attn: Mr. Melvin C. Beall PO Box 2200 La Plata, Maryland 20646</p> | <p>Location: North of existing Billingsley Road, in Waldorf, Charles County, Maryland</p> <p>To permanently impact 164,832 square feet (3.78 acres) of jurisdictional non-tidal wetlands for the construction of Phase 5 of the Charles County Cross County Connector. Phase 5 of the Cross County Connector extends approximately 2.2 miles from Middletown Road to MD 229.</p> <p>Project Manager: Michael Hitchings 410-962-5685</p> |
| November 22, 2004 | December 22, 2004 | | | | |
| <p>SPN 05-01</p> | <p>Special Public Notice 05-01 Establishment of Restricted Areas</p> <table border="1" data-bbox="467 993 849 1077"> <tr> <td data-bbox="467 993 662 1077">November 7, 2004</td> <td data-bbox="662 993 849 1077">December 7, 2004</td> </tr> </table> | November 7, 2004 | December 7, 2004 | <p>n/a</p> | <p>U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/Notice VIII/November 7, 2004 - December 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> |
| November 7, 2004 | December 7, 2004 | | | | |
| <p>PN 05-01</p> | <p>SM DPW&T/SOUTHERN PRONG/DREDGING</p> <p>04-65611</p> <table border="1" data-bbox="467 1497 849 1581"> <tr> <td data-bbox="467 1497 662 1581">October 29, 2004</td> <td data-bbox="662 1497 849 1581">November 29, 2004</td> </tr> </table> | October 29, 2004 | November 29, 2004 | <p>St. Mary's County Department of Public Works & Transportation c/o Mr. Scott Alexander P.O. Box 508 California, Maryland 20619</p> | <p>Location: In the Southern Prong of St. Jerome Creek at Ridge, St. Mary's County, Maryland</p> <p>To maintenance dredge by hydraulic method a 50-foot wide by 2,230-foot long entrance channel to -5.0 feet mean low water (MLW). The resulting approximately 10,000 cubic yards of sand and silt is to be deposited at an upland (non-wetland) disposal site at</p> |
| October 29, 2004 | November 29, 2004 | | | | |

| | | | | | |
|-------------------------|---|-------------------------|---|---|--|
| | | | <p>Orebaugh Farm. This project is proposed in conjunction with the U.S. Army Corps of Engineers St. Jerome Creek Federal navigation channel maintenance dredging project.</p> <p>Project Manager: Kathy Anderson 410-962-5690</p> | | |
| <p>PN 04-41</p> | <p>HORNING BROTHERS/PISCATAWAY CREEK EST/RDXING & UTILITY LINE</p> <p>04-63695</p> <table border="1" data-bbox="467 772 849 852"> <tr> <td data-bbox="467 772 651 852"> <p>October 15, 2004</p> </td> <td data-bbox="651 772 849 852"> <p>November 4, 2004</p> </td> </tr> </table> | <p>October 15, 2004</p> | <p>November 4, 2004</p> | <p>Horning Brothers Attn: Robert Love 1350 Connecticut Avenue, NW Washington, DC 20036</p> | <p>Location: In Piscataway Creek, Prince Georges County, Maryland</p> <p>To permanently impact approximately 385 LF of stream channel (7,032 SF) for the construction of three road crossings and a stormwater management outfall and permanently impact approximately 16,508 SF of forested nontidal wetlands for the widening and relocation of Surratts Road. Construction of utility lines will temporarily impact approximately 39,623 SF of forested nontidal wetlands.</p> <p>Project Manager: Jack Dinne 410-962-6005</p> |
| <p>October 15, 2004</p> | <p>November 4, 2004</p> | | | | |
| <p>PN 04-39</p> | <p>MORRIS, JEFFREY/PATUXENT RIVER/SONARTRAINING FIELD</p> <p>04-65164</p> <table border="1" data-bbox="467 1528 849 1608"> <tr> <td data-bbox="467 1528 651 1608"> <p>October 8, 2004</p> </td> <td data-bbox="651 1528 849 1608"> <p>November 8, 2004</p> </td> </tr> </table> | <p>October 8, 2004</p> | <p>November 8, 2004</p> | <p>Azulmar Research Mr. Jeffrey Morris 3235 Southern Pine Lane Port Republic, Maryland 20676</p> | <p>Location: In the Patuxent River at Broomes Island, Calvert County, Maryland. The following coordinates bound the area: 38 23.770N/76 32.745W, 38 23.028N/76 31.088W, 38 23.243N/76 30.992W, 38 23.982N/76 32.559W</p> <p>To create a 1 1/2 mile by 1/2-mile seeded field of target objects including submarine</p> |
| <p>October 8, 2004</p> | <p>November 8, 2004</p> | | | | |

| | | | | | |
|---------------------------|--|--------------------|---|---|---|
| | | | <p>cable, empty steel barrels, truck tires, iron pipe, cast concrete shapes, and various small objects anchored to the bottom substrate using concrete cinder blocks and galvanized chain and moored 3 to 5 feet above the bottom substrate. All objects will be placed with a minimum clearance of 20 feet below mean low water.</p> <p>Project Manager: Kathy Anderson 410-962-5690</p> | | |
| SPN 04-14 | Special Public Notice 04-14 Establishment of Restricted Areas <table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td style="padding: 5px;">October 7, 2004</td> <td style="padding: 5px;">November 7, 2004</td> </tr> </table> | October 7, 2004 | November 7, 2004 | n/a | U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/Notice VIII/October 7, 2004 - November 7, 2004 Project Manager: John Roop 410-962-5688 |
| October 7, 2004 | November 7, 2004 | | | | |
| PN 04-40 | AA RECYCLE & SAND/PENNINGTON 04-65571 <table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td style="padding: 5px;">October 7, 2004</td> <td style="padding: 5px;">October 20, 2004</td> </tr> </table> | October 7, 2004 | October 20, 2004 | AA Recycle & Sand, Inc. Attn: Mr. William DeBaugh P.O. Box 412 Linthicum, MD 21090 | <p>Location: The project is located at the end of Fairfax Avenue off Pennington Avenue on the Baltimore City and Anne Arundel County line in the Cabin Branch watershed, Anne Arundel County, Maryland.</p> <p>The proposed work is to construct a leaf recycling and compost facility.</p> <p>Project Manager: Richard Kibby 410-962-0694</p> |
| October 7, 2004 | October 20, 2004 | | | | |
| SPN 04-13 | Special Public Notice 04-13 | n/a | U.S. Repairs Following Heavy Rains | | |

| | | | |
|--|---|---|---|
| | U.S. Repairs Following Heavy Rains <div style="border: 1px solid black; padding: 2px; display: inline-block;">October 4, 2004</div> <div style="border: 1px solid black; padding: 2px; display: inline-block; margin-left: 20px;">n/a</div> | | |
| SPN 04-11 w/ Attachments | Special Public Notice 04-11 Incorporating PADEP BWM -GP-11 into the PASPGP-2 Pennsylvania State Programmatic General Permit <div style="border: 1px solid black; padding: 2px; display: inline-block;">October 4, 2004</div> <div style="border: 1px solid black; padding: 2px; display: inline-block; margin-left: 20px;">n/a</div> | n/a | Incorporating PADEP BWM -GP-11 into the Pennsylvania State Programmatic General Permit -2 (P ASPGP-2) Project Manager: Pat Strong 410-962-1847 |
| SPN 04-12 w/ Attachments | Special Public Notice 04-12 Final Mitigation and Monitoring Guidelines <div style="border: 1px solid black; padding: 2px; display: inline-block;">October 2, 2004</div> <div style="border: 1px solid black; padding: 2px; display: inline-block; margin-left: 20px;">n/a</div> | n/a | Final Mitigation and Monitoring Guidelines Project Manager: Beth Bachur 410-962-4336 |
| PN 04-38 | US NAVY/PATUXENT RIVER NAS/GOOSE CREEKCAMPGROUND/SILLS, GROINS & VEG ST AB 04-65166 <div style="border: 1px solid black; padding: 2px; display: inline-block;">October 1, 2004</div> <div style="border: 1px solid black; padding: 2px; display: inline-block; margin-left: 20px;">November 1, 2004</div> | Mr. Kyle Rambo U.S. Navy Patuxent River NAS c/o Mr. Bruce Young St. Mary's Soil Conservation District Mr. Bruce Young 22660 Washington Street P.O. Box 810 Leonardtwn, Maryland 20650 | Location: In Goose Creek off the Chesapeake Bay at the Patuxent River Naval Air Station, St Mary's County, Maryland The applicant proposes, in accordance with the attached plans, to create a marsh along 1,550 linear feet of shoreline by depositing approximately 3,000 cubic yards of sloped, clean select sand fill stabilized with <i>Spartina alterniflora</i> and <i>S. patens</i> ; to construct 19.5-foot by 250-foot and 19.5-foot by 100-foot stone sills; and to construct 24, 9-foot by 35-foot stone groins at 50 feet on center. Project Manager: Kathy Anderson 410-962-5690 |
| PN 04-37 | US FWS/STEWARTS CANAL/WEIR 04-64180 | U.S. Fish & Wildlife Service Attn: Mr. Glenn A. Carowan, Jr. 2145 Key Wallace | Location: In Stewarts Canal (a man-made ditch) off of Parsons Creek near |

| | | | |
|---------------------------|---|---|---|
| | <div style="display: flex; justify-content: space-around; border: 1px solid black; padding: 2px;"> September 22, 2004 October 22, 2004 </div> | Drive Cambridge, Maryland 21613 | Smithville, Dorchester County, Maryland. The applicant proposes to construct a 600 linear foot aluminum weir and a 100 linear foot aluminum bulkhead to be backfilled with rock; and to install a water control structure at the centerline of Stewarts Canal channel. Project Manager: Maria Lasek 410-962-4501 |
| PN 04-36 | DUVALL FARMS LLC 04-64507 <div style="display: flex; justify-content: space-around; border: 1px solid black; padding: 2px;"> September 27, 2004 October 27, 2004 </div> | Duvall Farm, LLC c/o Lane Engineering, Inc 15 Washington Street Cambridge, Maryland 21613 | Location: In Trippe Creek near Oxford, Talbot County To construct 1,496 linear feet of low profile rip-rap not to extend more than 4 feet channelward of the mean high water shoreline and landward of the existing marsh vegetation and to construct 5,468 linear feet of low profile rip- rap approximately 2 feet to 3 feet channelward of the existing marsh vegetation, not to extend more than 6 feet channelward of the mean high water shoreline. Project Manager: Lynette Rhodes 410-962-5686 |
| SPN 04-10 | Special Public Notice 04-10 Establishment of Restricted Areas <div style="display: flex; justify-content: space-around; border: 1px solid black; padding: 2px;"> September 7, 2004 October 7, 2004 </div> | n/a | U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/Notice VIII/September 7, |

| | | | | | |
|-------------------|---|-------------------|--|--|---|
| | | | <p>2004 - October 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> | | |
| PN 04-35 | <p>CONSTELLATION GENERATION GROUP/CP CRANEPower PLANT/DREDGING</p> <p>04-64913</p> <table border="1"> <tr> <td>September 1, 2004</td> <td>October 1, 2004</td> </tr> </table> | September 1, 2004 | October 1, 2004 | <p>Constellation Generation Group LLC Attn: Mr. James Burkman 1005 Brandon Shores Road Baltimore, MD 21226</p> | <p>Location: In Seneca Creek and the Chesapeake Bay, near Middle River, Baltimore County, Maryland</p> <p>To mechanically or hydraulically dredge - to extend and deepen the existing barge channel from 3,700 feet to 14,500 feet and from -9 MLW to -12 MLW.</p> <p>Project Manager: Mary A. Frazier 410-962-5679</p> |
| September 1, 2004 | October 1, 2004 | | | | |
| PN 04-34 | <p>PEACHBLOSSOM COVE HOA/DREDGING</p> <p>04-64086-3</p> <table border="1"> <tr> <td>August 27, 2004</td> <td>September 28, 2004</td> </tr> </table> | August 27, 2004 | September 28, 2004 | <p>Peachblossom Cove HOA c/o Mr. Hugh M. Smith 218 N. Washington Street Easton, Maryland 21601-0119</p> | <p>Location: In Peachblossom Cove, Talbot County, Maryland</p> <p>To hydraulically or mechanically, maintenance dredge an 1170-foot long by 40 to 50-foot wide main channel in Peachblossom Cove to a depth of -4.5 feet below mean low water connecting to Peachblossom Creek. Additionally, 7 spur channels listed below are proposed.</p> <p>Project Manager: Lynette Rhodes 410-962-5686</p> |
| August 27, 2004 | September 28, 2004 | | | | |
| PN 04-33 | <p>AUSHERMAN DEV CORP/WOODBURY/SWM POND</p> <p>04-61061-16</p> <table border="1"> <tr> <td>August 25, 2004</td> <td>September 25, 2004</td> </tr> </table> | August 25, 2004 | September 25, 2004 | <p>Ausherman Development Corporation Attn: Mr. Jim MacGillivray 8031 Reichs Ford Road Frederick, Maryland 21704</p> | <p>Location: Israel Creek, Frederick County, Maryland</p> <p>Discharges of dredged or fill material into waters of the U.S. associated with construction of a 37</p> |
| August 25, 2004 | September 25, 2004 | | | | |

| | | | | | |
|-----------------|---|-----------------|--|---|--|
| | | | <p>lot subdivision. The project will result in the relocation and restoration of 522 linear feet of stream and removal of an existing in-stream pond and its reconfiguration to off-line stormwater management.</p> <p>Project Manager: Joseph P. DaVia 410-962-4527</p> | | |
| PN 04-32 | <p>CH DPW/ST CHARLES PKY-ROSEWICK RD EXT/RDXING, CULVERT & BRIDGE)</p> <p>04-62521-19</p> <table border="1"> <tr> <td>August 24, 2004</td> <td>September 24, 2004</td> </tr> </table> | August 24, 2004 | September 24, 2004 | <p>Charles County Department of Public Works ATTN: Melvin C. Beall, Jr. Planning & Growth Management PO Box 2150 La Plata, Maryland 20646</p> | <p>Location: In Clarks Run and Kerrick Swamp, near La Plata, Charles County, Maryland</p> <p>Charles County is proposing to construct an extension of St. Charles Parkway to connect with Rosewick Road, and widen Rosewick Road to Washington Boulevard in the St. Charles and La Plata areas.</p> <p>Project Manager: Michael Hitchings 410-962-5685</p> |
| August 24, 2004 | September 24, 2004 | | | | |
| PN 04-31 | <p>PAULSEN, CHERYL/DREDGING</p> <p>04-63296-13</p> <table border="1"> <tr> <td>August 16, 2004</td> <td>September 16, 2004</td> </tr> </table> | August 16, 2004 | September 16, 2004 | <p>Cheryl Paulsen 516 Long Point Road Grasonville, Maryland 21638</p> | <p>Location: In an unnamed canal off Jackson Creek, at Long Point, near Grasonville, Queen Annes, Maryland</p> <p>To hydraulically maintain dredge an existing canal off Jackson Creek to a depth of 4 feet below mean low water, the resulting approximately 5,151 cubic yards of dredged material to be deposited in geotextile bags and, after de-watering, the dredged material will be trucked to Bakers Landfill.</p> |
| August 16, 2004 | September 16, 2004 | | | | |

| | | | | | |
|--------------------|---|--------------------|--|---|---|
| | | | Project Manager: Rodney Schwarm 410-962-4500 | | |
| PN 04-30 | <p>MARINETICS INC/SITE B/AQUACULTURE)</p> <p>04-63121</p> <table border="1"> <tr> <td>August 16, 2004</td> <td>September 16, 2004</td> </tr> </table> | August 16, 2004 | September 16, 2004 | <p>Marinetics, Inc. Attn: Mr. Kevin McClarren 6035 Castle Haven Road Cambridge, Maryland 21613</p> | <p>Location: In the Choptank River and LeCompte Bay near Castle Haven, Dorchester County, Maryland</p> <p>The applicant proposes to emplace oyster aquaculture floats positioned -4 inches below the water surface within a 4.13 acre area (Site A) surrounding an existing commercial pier not to exceed 400 feet channelward of the approximate mean high water shoreline and within a 1.06 acre area (Site B) surrounding an existing pier not to exceed 200 feet channel ward of the approximate mean high water shoreline.</p> <p>Project Manager: Maria Lasek 410-962-4501</p> |
| August 16, 2004 | September 16, 2004 | | | | |
| PN 04-29 | <p>PUTNAM, BLUFORD/DREDGING & PIER</p> <p>04-63874</p> <table border="1"> <tr> <td>August 10, 2004</td> <td>August 31, 2004</td> </tr> </table> | August 10, 2004 | August 31, 2004 | <p>Mr. Bluford H. Putnam Bayesian Edge Technology & Solutions 48800 Hattie's Lane Ridge, Maryland 20680</p> | <p>Location: In Rawley Bay and the Potomac River near Ridge, St Mary's County, Maryland</p> <p>The applicant proposes, in accordance with the attached plans, to dredge by hydraulic and mechanical methods, a 50-foot by 1,400-foot main entrance navigation channel and a 30-foot by 650-foot spur channel to -5.0 feet mean low water (MLW), resulting in approximately 12,000 cubic yards of sand and silt to be deposited at a disposal area in an</p> |
| August 10, 2004 | August 31, 2004 | | | | |

| | | | | | |
|---------------------------|--|------------------------------------|--|--|---|
| | | | <p>existing farm field. To construct a 6-foot by 50-foot fixed pier to a 6-foot by 150-foot floating pier with a 10-foot by 20-foot "T" head to extend no more than 200 feet channelward of the approximate mean high water shoreline.</p> <p>Project Manager: Kathy Anderson 410-962-5690</p> | | |
| SPN 04-09 | Special Public Notice 04-09 Establishment of Restricted Areas <table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td style="padding: 2px;">August 7, 2004</td> <td style="padding: 2px;">September 7, 2004</td> </tr> </table> | August 7, 2004 | September 7, 2004 | n/a | <p>U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/ Notice VIII/August 7, 2004 - September 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> |
| August 7, 2004 | September 7, 2004 | | | | |
| PN 04-28 | BA DEPRM/PLEASURE ISLAND/MAINTENANCE DREDGING 03-63400 <table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td style="padding: 2px;">July 26, 2004</td> <td style="padding: 2px;">August 9, 2004</td> </tr> </table> | July 26, 2004 | August 9, 2004 | Baltimore County DEPRM Attn: Candace Croswell Suite 416 401 Bosley Avenue Towson, Maryland 21204 | <p>Location: Chesapeake Bay, near Miller's Island Baltimore County, Maryland</p> <p>The applicant proposes to hydraulically dredge the remainder of the channel previously authorized by Department of the Army permit CENAB-OP-RW(BA DEPRM/Pleasure Island Channel Dredging) 94-60757-14 on July 26, 1994. The project is to dredge a 1,200 foot long, 100-foot wide channel to 6 feet below mean low water.</p> <p>Project Manager: Jon Romeo 410-962-6079</p> |
| July 26, 2004 | August 9, 2004 | | | | |
| PN 04-27 | MD DNR/CHESAPEAKE BAY | MD Department of Natural Resources | Location: In Prospect | | |

| | | | |
|----------------------------------|--|---|---|
| | <p>ENVIRONMENTAL CENTER/formerly HORSEHEAD WETLANDS CENTER</p> <p>01-65334</p> <p>July 27, 2004 August 17, 2004</p> | <p>Attn: Mr. Kevin Smith Watershed Restoration Division Tawes State Office Building E-2 Annapolis, Maryland 21401</p> | <p>Bay and Cabin Creek at the Chesapeake Bay Environmental Center (formerly Horsehead Wetlands Center) near Grasonville, Queen Annes County, Maryland</p> <p>The applicant proposes to place a 12 inch thickness of 4 to 8 inch stone with a veneer of oyster shells and spat of <i>Crassostrea virginica</i> (Eastern oyster) over a 5 acre area not to exceed a maximum of 1,150 feet channelward of the approximate mean high water shoreline; and to place 120, 3 foot diameter x 2 foot tall concrete reef balls over another 2 acre area not to exceed a maximum of 900 feet channelward of the approximate mean high water shoreline, to improve and enhance oyster and fisheries habitat.</p> <p>Project Manager: Marie Lasek 410-962-4501</p> |
| <p>SPN 04-08</p> | <p>Special Public Notice 04-08 Establishment of Restricted Areas</p> <p>July 7, 2004 August 7, 2004</p> | <p>n/a</p> | <p>U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/ Notice VIII/July 7, 2004 - August 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> |
| <p>PN 04-26</p> | <p>MD DGS/FRANK BENTZ DAM/REHAB</p> <p>03-61495</p> <p>July 6, 2004 July 27, 2004</p> | <p>Maryland Department of General Services Attn: Ahmed S. K. Naji 301 West Preston</p> | <p>Location: Hunting Creek, Frederick County, Maryland</p> <p>To mechanically maintenance dredge</p> |

| | | | | | |
|---------------|--|---|--|---|--|
| | | Street, Room 1405 Baltimore, Maryland 21201 | <p>approximately 1,300 cubic yards of sediment from an approximate 1.4 acre area within Frank Bentz Memorial Lake, and to perform repair and maintenance activities on the Frank Bentz Dam, resulting in total impacts to approximately 1.5 acres of non-vegetated waters of the U.S.</p> <p>Project Manager: Joseph P. DaVia 410-962-4527</p> | | |
| PN 04-25 | <p>BA DPW/WINDLASS RUN SEWER INTERCEPTOR/UTILITY LINE</p> <p>04-63386</p> <table border="1"> <tr> <td>July 6, 2004</td> <td>August 6, 2004</td> </tr> </table> | July 6, 2004 | August 6, 2004 | <p>Baltimore County Dept of Public Works Attn: Mr. Ed Adams 111 W. Chesapeake Avenue Towson, Maryland 21204</p> | <p>Location: Windlass Run, near Bird River Road, Baltimore County, Maryland</p> <p>To impact 145 linear feet of stream and 89,425 square feet (approximately 2.05 acres) on nontidal forested wetlands for the installation of a 5,275 linear foot, 24-inch sanitary sewer interceptor.</p> <p>Project Manager: Jon Romeo 410- 962-6082</p> |
| July 6, 2004 | August 6, 2004 | | | | |
| PN 04-24 | <p>ST SERVICES/PINEY PT FUEL TERM</p> <p>04-61420-4</p> <table border="1"> <tr> <td>June 23, 2004</td> <td>July 23, 2004</td> </tr> </table> | June 23, 2004 | July 23, 2004 | <p>ST Services Mr. Rick Meadows c/o Coastline Design, P.C P.O. Box 157 Achilles, Virginia 23001</p> | <p>Location: In the Potomac River at Piney Point, St. Mary's County, Maryland</p> <p>To maintenance dredge by mechanical method a approximate 50-foot by 1,200-foot area to -38.0 feet mean low water (MLW). The resulting approximately 6,000 cubic yards of sand and silt is to be deposited at an existing upland (non-wetland) bermed disposal site at the project site property.</p> |
| June 23, 2004 | July 23, 2004 | | | | |

| | | | | | |
|---------------------------|---|---------------|--|---|--|
| | | | Project Manager: Kathy Anderson 410-962-5690 | | |
| PN 04-23 | <p>NAVY/NAVAL RESEARCH LAB, CHESAPEAKEBAY/BULKHEAD</p> <p>04-63443</p> <table border="1"> <tr> <td>June 11, 2004</td> <td>July 12, 2004</td> </tr> </table> | June 11, 2004 | July 12, 2004 | <p>Department of Navy Ms. Theresa Shaner Naval Research Laboratory Chesapeake Bay Detachment 5813 Bayside Road Chesapeake Beach, Maryland 20732</p> | <p>Location: In the Chesapeake Bay at Randle Cliff Beach, Calvert County, Maryland</p> <p>To emplace 4,600 linear feet of stone revetment averaging 35 feet wide, to extend no more than 25 feet channel ward of the face of the existing deteriorated bulkhead.</p> <p>Project Manager: Kathy Anderson 410-962-5690</p> |
| June 11, 2004 | July 12, 2004 | | | | |
| PN 04-22 | <p>CNX MARINE TERMINALS INC/DREDGING</p> <p>04-60762</p> <table border="1"> <tr> <td>June 11, 2004</td> <td>July 11, 2004</td> </tr> </table> | June 11, 2004 | July 11, 2004 | <p>CNX Marine Terminals, Inc. Attn: Mr. Regis Peternel 3800 Newgate Avenue Baltimore, MD 21224</p> | <p>Location: Patapsco River, Baltimore City, Maryland</p> <p>To mechanically dredge an approximately 90.5-acre area to 42 to 50 feet below mean low water at an existing marine terminal, and to deposit the approximately 1.8 million cubic yards of dredged material at an approved disposal site.</p> <p>Project Manager: Jon Romeo 410-962-6079</p> |
| June 11, 2004 | July 11, 2004 | | | | |
| SPN 04-07 | <p>Special Public Notice 04-07 Establishment of Restricted Areas</p> <table border="1"> <tr> <td>June 7, 2004</td> <td>July 7, 2004</td> </tr> </table> | June 7, 2004 | July 7, 2004 | n/a | <p>U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/ Notice VIII/June 7, 2004 - July 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> |
| June 7, 2004 | July 7, 2004 | | | | |

| | | | | | |
|----------------------------------|---|--------------|--|---|--|
| <p>PN 04-21</p> | <p>ARUNDEL CORP/GREENSPRING</p> <p>00-65114-4</p> <table border="1" data-bbox="467 317 849 369"> <tr> <td data-bbox="467 317 667 369">May 18, 2004</td> <td data-bbox="667 317 849 369">July 2, 2004</td> </tr> </table> | May 18, 2004 | July 2, 2004 | <p>The Arundel Corporation Attn: Mr. Owen Neighbours 34 Loveton Circle P.O. Box 5000 Sparks, MD 21152</p> | <p>Location: In the northern and southern (Wellwood Branch) tributaries of Moore's Branch and their adjacent wetlands, at the Greenspring Quarry site, Baltimore County, Maryland.</p> <p>The applicant's purpose is to reclaim an inactive quarry site, to provide additional usable land for proposed commercial development, and to provide access and utility lines to service a proposed mixed-use residential and commercial development.</p> <p>Project Manager: Abbie Hopkins 410-962-6080</p> |
| May 18, 2004 | July 2, 2004 | | | | |
| <p>PN 04-20</p> | <p>KINDER MORGAN CHESAPEAKE BULK/DREDGING</p> <p>04-61863-3</p> <table border="1" data-bbox="467 1066 849 1119"> <tr> <td data-bbox="467 1066 651 1119">May 27, 2004</td> <td data-bbox="651 1066 849 1119">June 27, 2004</td> </tr> </table> | May 27, 2004 | June 27, 2004 | <p>Kinder Morgan Chesapeake Bulk Attn: John A Manzari 1575 Sparrows Point Blvd Baltimore, Maryland 21219-1029</p> | <p>Location: Patapsco River, Baltimore County, Maryland</p> <p>To maintenance dredge in front of an existing bulkhead, adjacent basin, and entrance channel from a line north of the ISG Sparrow Point pier to the above mentioned basin. Dredging will maintain 41 feet of depth at MLW in order that Panamax vessels can be berthed at the old ore dock and barges can be berthed at barge dock at 23 feet MLW. Approx. 375,000 cubic yards of silt and mud will be clam bucket dredged and deposited at the MPA Hart-Miller Disposal Facility.</p> <p>Project Manager: Steve Harman 410-962-6082</p> |
| May 27, 2004 | June 27, 2004 | | | | |
| <p>SPN 04-06</p> | <p>Special Public Notice 04-06</p> | <p>n/a</p> | <p>U.S. Army Corps of Engineers' Action Granting Legal</p> | | |

| | | | |
|----------|--|--|---|
| | <p>Establishment of Restricted Areas</p> <p>May 7, 2004 June 7, 2004</p> | | <p>Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/ Notice VIII/May 7, 2004 - June 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> |
| PN 04-19 | <p>US NAVY PATUXENT RIVER NAS/O CL</p> <p>04-62001</p> <p>May 3, 2004 June 3, 2004</p> | | |
| PN 04-18 | <p>THE GENERAL SHIP REPAIR</p> <p>04-60755</p> <p>May 3, 2004 May 24, 2004</p> | <p>The General Ship Repair Corporation Attn: Mr. Cary Lynch 1449 Key Highway Baltimore, MD 21230</p> | <p>Location: Patapsco River, at Key Highway, Baltimore City, Maryland</p> <p>To mechanically dredge three berthing areas as follows: 260 feet long by 65 feet wide, and 580 feet long by 75 feet wide to 22 feet below mean low water; and 550 feet long by 100 to 125 feet wide to 30 feet below mean low water. The approximately 25,000 cubic yards of dredged material are to be deposited at the Hart Miller Island disposal site.</p> <p>Project Manager: Jon Romeo 410-962-6079</p> |
| PN 04-17 | <p>BLUEWATER DEVELOPMENT CORP/DREDGING</p> <p>04-60269-1</p> <p>April 23, 2004 May 23, 2004</p> | <p>Bluewater Development Corporation c/o John Burbage, Jr. 9428 Stephen Decatur Highway Berlin, Maryland 21811</p> | <p>Location: In the Isle of Wight Bay, West Ocean City, Worcester County, Maryland</p> <p>To maintenance dredge an existing channel by hydraulic and or mechanical method encompassing an approximate 65,800 square foot</p> |

| | | | | | |
|----------------|--|----------------|--|---|--|
| | | | <p>area (1.5 acres) to a depth of -4 feet below mean low water and deposit the resulting approximate 6,500 cubic yards of dredged material on an approved upland disposal site.</p> <p>Project Manager: Woody Francis 410-962-5689</p> | | |
| PN 04-16 | <p>DO HIGHWAYS/HURST CREEK/DREDGING</p> <p>04-61476-7</p> <table border="1"> <tr> <td>April 14, 2004</td> <td>May 14, 2004</td> </tr> </table> | April 14, 2004 | May 14, 2004 | <p>Dorchester County Highway Department Attn: Mr. Charles G. Blades II 5435 Handley Road Cambridge, Maryland 21613</p> | <p>Location: In Hurst Creek at Cambridge, Dorchester County, Maryland</p> <p>To mechanically and/or hydraulically maintenance dredge a 4,500-foot long by 30-foot wide navigation channel to a depth of -4 feet below mean low water. Depending on the method of dredging that is selected, approximately 2,500 cubic yards of sandy, dredged material will be deposited in a previously utilized, upland disposal site, or pumped to a new, upland disposal site.</p> <p>Project Manager: Marie Lasek 410-962-4501</p> |
| April 14, 2004 | May 14, 2004 | | | | |
| PN 04-15 | <p>BGE/BRANDON SHORES HA WAGNER</p> <p>04-60753-24</p> <table border="1"> <tr> <td>April 9, 2004</td> <td>May 9, 2004</td> </tr> </table> | April 9, 2004 | May 9, 2004 | <p>BGE Attn: James Burkman 1005 Brandop Shores Road Baltimore, Maryland 21226</p> | <p>Location: In Patapsco River, Anne Arundel County, Maryland</p> <p>To mechanically maintenance dredge a 9000 foot by 275 foot barge channel to -17 MLW and to place the 20,000 cubic yards in an approved DMP site. The initial dredged material will be placed at the Hart-Miller Island Spoils Placement Facility and additional material will be placed at the Cox</p> |
| April 9, 2004 | May 9, 2004 | | | | |

| | | | | | |
|----------------|---|----------------|---|--|---|
| | | | <p>Creek Facility.</p> <p>Project Manager: Mary A. Frazier 410-962-5679</p> | | |
| PN 04-14 | <p>MILLENIUM CHEMICAL/DREDGING</p> <p>04-60752</p> <table border="1"> <tr> <td>April 9 , 2004</td> <td>May 9, 2004</td> </tr> </table> | April 9 , 2004 | May 9, 2004 | <p>Millennium Chemicals 3901 Fort Armistead Road Baltimore, Maryland 21226</p> | <p>Location: In Patapsco River, Anne Arundel County, Maryland</p> <p>To mechanically maintenance dredge an 800 by 200 foot area to -11 MLW in the Patapsco River near Hawkins Point, Anne Arundel County, Maryland. The 18,000 cubic yards of dredged material will be deposited at the Cox Creek DMP site, an approved upland disposal site.</p> <p>Project Manager: Mary A. Frazier 410-962-5679</p> |
| April 9 , 2004 | May 9, 2004 | | | | |
| PN 04-13 | <p>MONA, VINCENT P/ PORT TOBACCO MARINA&CAMPGROUND/DREDGING</p> <p>04-61474-19</p> <table border="1"> <tr> <td>June 11, 2004</td> <td>July 12, 2004</td> </tr> </table> | June 11, 2004 | July 12, 2004 | <p>Vincent P. Mona 8023 Malcolm Road Clinton, Maryland 20735</p> | <p>Location: In Port Tobacco Creek near Port Tobacco, Charles County, Maryland</p> <p>To mechanically maintenance dredge three channels (1,600, 1,610, and 540 feet long by 20 feet wide) in Port Tobacco Creek. Dredging will result in the removal of approximately 4,233 cubic yards of dredge material from an area approximately 3,810 feet long with an average width of 20 feet dredged to -4.0 feet mean low water. The dredged material will be removed and deposited at an upland site.</p> <p>Project Manager: Michael Hitchings 410-962-5685</p> |
| June 11, 2004 | July 12, 2004 | | | | |

| | | | | | |
|---------------------------|--|----------------|----------------|---|--|
| SPN 04-06 | <p>Special Public Notice 04-06 Establishment of Restricted Areas</p> <table border="1" data-bbox="467 317 849 365"> <tr> <td data-bbox="467 317 654 365">May 7, 2004</td> <td data-bbox="654 317 849 365">June 7, 2004</td> </tr> </table> | May 7, 2004 | June 7, 2004 | <p>n/a</p> | <p>U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/ Notice VIII/May 7, 2004 - June 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> |
| May 7, 2004 | June 7, 2004 | | | | |
| SPN 04-05 | <p>Special Public Notice 04-05 Establishment of Restricted Areas</p> <table border="1" data-bbox="467 728 849 777"> <tr> <td data-bbox="467 728 654 777">April 7, 2004</td> <td data-bbox="654 728 849 777">May 7, 2004</td> </tr> </table> | April 7, 2004 | May 7, 2004 | <p>n/a</p> | <p>U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/ Notice VIII/April 7, 2004 - May 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> |
| April 7, 2004 | May 7, 2004 | | | | |
| <p>PN 04-12</p> | <p>SALISBURY DPW/BEAVERDAM CREEK/DREDGING & REVETMENT</p> <p>04-61940-2</p> <table border="1" data-bbox="467 1173 849 1251"> <tr> <td data-bbox="467 1173 654 1251">March 30, 2004</td> <td data-bbox="654 1173 849 1251">April 30, 2004</td> </tr> </table> | March 30, 2004 | April 30, 2004 | <p>City of Salisbury Dept of Public Works 125 North Division Street Salisbury, Maryland 21801</p> | <p>Location: In Beaverdam Creek and non-tidal wetlands adjacent to this waterway in Salisbury, Wicomico County, Maryland</p> <p>To deposit 4500 cubic yards of riprap along the north and south banks of 3800 feet of eroding creek bank, none of the proposed work is to extend more than 8 feet channel ward of the ordinary high water mark. To mechanically dredge 2500 feet of the creek which is not under the Corps jurisdiction. Approx. 75 cubic yards of stone is to be deposited over a pipe on an existing base of riprap to construct a 20-foot wide temporary road crossing of the creek.</p> |
| March 30, 2004 | April 30, 2004 | | | | |

| | | | |
|----------|--|---|---|
| | | | Project Manager: Mr. John Roop 410-962-5688 |
| PN 04-11 | HARBOUR LIGHT LLC 04-61254-2 <div style="border: 1px solid black; padding: 2px; display: inline-block;"> March 30, 2004 April 30, 2004 </div> | Harbour Light LLC c/o Gary O. Williams Andrews, Miller & Associates, Inc. 401 Academy Street Suite 1 Cambridge, Maryland 21613 | <p>Location: In the Little Annesmessex River and non-tidal wetlands adjacent to this waterway, in Crisfield, Somerset County, Maryland</p> <p>To construct a 72 slip marina. The proposed work includes: replacement bulkhead to extend an average of 18" channelward of an existing deteriorated bulkhead; to excavate a 40' X 21' area landward of an existing bulkhead (to be removed) to the ambient water depths; to deposit excavated material landward of the proposed bulkhead in the area of the existing travel lift and boat ramp; to deposit common fill landward of the remaining proposed bulkhead; to construct five piers; to install 221 mooring pilings; to construct 403 feet of stone revetment to extend 27' (maximum) channelward of the approximate MHWS and to vegetate with wetland species; to vegetate landward of the proposed revetment on the north end of the site with wetland species; to construct wooden breakwater along the northwestern side of the proposed project site; to construct walkway along the north and west sides of the proposed project site; to construct a 130' stone sill to extend 42' (max.) channelward</p> |

| | | | | | |
|---------------------------|--|----------------------|---|---|---|
| | | | <p>of the approx. MHWS and to deposit 92 cubic yards of clean sand landward of the proposed sill; and to vegetate with wetland species; and to construct a 240' retaining wall landward of the proposed marsh creation area.</p> <p>Project Manager: John Roop 410-962-5688</p> | | |
| SPN 04-04 | Special Public Notice 04-04 Establishment of Restricted Areas <table border="1" data-bbox="467 743 849 800"> <tr> <td>March 7, 2004</td> <td>April 7, 2004</td> </tr> </table> | March 7, 2004 | April 7, 2004 | n/a | U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/ Notice VIII/March 7, 2004 - April 7, 2004 Project Manager: John Roop 410-962-5688 |
| March 7, 2004 | April 7, 2004 | | | | |
| PN 04-10 | RELIABLE CONTRACTING CO & HALE CO/ODENTON TOWN CENTER/RD XING, OUTFALL 03-63340 <table border="1" data-bbox="467 1241 849 1318"> <tr> <td>February 25, 2004</td> <td>March 25, 2004</td> </tr> </table> | February 25, 2004 | March 25, 2004 | Odenton Fire Station 1425 Annapolis Road Odenton, Maryland 21113 | <p>Location: In the Patuxent and Severn Run watersheds, at the intersection of Maryland Route 32 and Maryland Route 175, Odenton, Anne Arundel County, Maryland</p> <p>To develop a mixed use development (residential, office, retail) at the proposed Odenton Town Center. The applicants propose to permanently impact 6.87 acres and temporarily impact 0.32 acres of waters of the United States including jurisdictional wetlands to construct lots, roads, and storm-water management outfalls. In addition, the applicants propose to fill 0.57 acre of isolated nontidal wetlands which are</p> |
| February 25, 2004 | March 25, 2004 | | | | |

| | | | | | |
|-------------------|---|---|---|--|--|
| | | | <p>waters of the State (not federally regulated) for lot development.</p> <p>Project Manager: Steve Harman 410-962-6082</p> | | |
| PN 04-09 | <p>GRACE DIVISION/CURTIS BAY FACILITY/DREDGING</p> <p>04-60759</p> <table border="1"> <tr> <td>February 20, 2004</td> <td>March 12, 2004</td> </tr> </table> | February 20, 2004 | March 12, 2004 | <p>Grace Division c/o Mr. James M. Diepold Whitney, Bailey, Cox & Magnani LLC 849 Fairmount Avenue Baltimore, Maryland 21286</p> | <p>Location: Curtis Bay, Baltimore City, Maryland</p> <p>To mechanically dredge two access channels each approximately 150 feet wide and 920 feet long to a depth of no more than 31 feet below mean low water, and to deposit the approximately 160,500 cubic yards of dredged material at either the Hart Miller Island disposal site or a disposal site at Sledd's Point.</p> <p>Project Manager: Jon Romeo 410-962-6079</p> |
| February 20, 2004 | March 12, 2004 | | | | |
| PN 04-08 | <p>THE RIDGES AT BRANDYWINE LLC/THE RIDGES II & III/RD XINGS & UTILITY LINES</p> <p>03-63869-15</p> <table border="1"> <tr> <td>February 27, 2004</td> <td>March 29, 2004</td> </tr> </table> | February 27, 2004 | March 29, 2004 | <p>The Ridges at Brandywine LLC Attn: John C. Pyles 2812 Chesterfield Place, NW Washington, DC 20008</p> | <p>Location: In Burch Branch, Prince George's County, Maryland</p> <p>To construct six road crossings permanently impacting approx. 13,966 square feet of nontidal wetlands and 1,217 LF (14,611 SF) of stream channel and to install sewer lines temporarily impacting approx. 21,932 SF of nontidal wetlands and 207 LF (3,669 SF) of stream.</p> <p>Project Manager: Jack Dinne 410-962-6005</p> |
| February 27, 2004 | March 29, 2004 | | | | |
| PN 04-07 | <p>MARYLAND COASTAL BAYS PROGRAM/OYSTERAQUACULTURE</p> <p>04-60834-1</p> | <p>Maryland Coastal Bays Program 9609 Stephen Decauster Highway</p> | <p>Location: In the St. Martin River, Worcester County, Maryland</p> | | |

| | | | |
|---------------------------|---|---|--|
| | <div style="display: flex; justify-content: space-around;"> <div style="border: 1px solid black; padding: 2px;">February 13, 2004</div> <div style="border: 1px solid black; padding: 2px;">March 15, 2004</div> </div> | Berlin, Maryland 21811 | <p>To construct a 10 acre oyster reef through expansion of an existing previously authorized reef structure by depositing approx. 10,000 bushels of shell per acre. Live oysters will also be transplanted to the site.</p> <p>Project Manager: Woody Francis 410-962-5689</p> |
| PN 04-06 | <p style="text-align: center;">NATELLI COMMUNITIES/SUNSET ISLAND/BEACHENHANCEMENT & PIER</p> <p style="text-align: center;">03-65263-1</p> <div style="display: flex; justify-content: space-around;"> <div style="border: 1px solid black; padding: 2px;">February 13, 2004</div> <div style="border: 1px solid black; padding: 2px;">March 15, 2004</div> </div> | Natelli Communities c/o Lawrence T. Whitlock Association 9040 Worcester Highway P.O. Box 110 Berlin, Maryland 21811-0110 | <p>Location: In the Assawoman Bay at 67th Street, Ocean City, Worcester County, Maryland</p> <p>To construct: 2725 linear feet of low profile stone rip rap for shoreline stabilization and marsh protection; 160 linear feet of bulkhead; 3 beach areas totaling 26510 square feet through deposition of sandy fill material (contained by low profile stone rip rap); one 18 foot by 20 deck, one 20 by 20 deck, and one 3 foot by 15 foot finger pier, 5 mooring piles creating two boat slips; 120 foot pier with a 200 square foot deck, extending 100 feet channelward of the MHWS; articulated concrete mats for erosion control and for an out-fall structure.</p> <p>Project Manager: Woody Francis 410-962-5689</p> |
| SPN 04-02 | <p style="text-align: center;">Special Public Notice 04-02 Establishment of Restricted Areas</p> <div style="display: flex; justify-content: space-around;"> <div style="border: 1px solid black; padding: 2px;">February 7, 2004</div> <div style="border: 1px solid black; padding: 2px;">March 7, 2004</div> </div> | n/a | U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During |

| | | | | | |
|---------------------------|---|---------------------|--|---|--|
| | | | <p>Charlie or Delta/ Notice VIII/February 7, 2004 - March 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> | | |
| SPN 04-01 | <p>Special Public Notice 04-01</p> <p>2nd Maryland Consultants Workshop</p> <table border="1"> <tr> <td>February 6, 2004</td> <td>n/a</td> </tr> </table> | February 6, 2004 | n/a | n/a | <p>2nd Maryland Consultants Workshop - The Baltimore District will conduct a public information workshop in Annapolis, Maryland, on Wednesday, March 3, 2004 from 9:00 a.m. to 5:00 p.m. at Anne Arundel Community College, Pascal Center for Performing Arts, 101 College Parkway, Arnold, Maryland</p> |
| February 6, 2004 | n/a | | | | |
| PN 04-05 | <p>US NAVY/PATUXENT NAS, GATE 4/SHORE EROSION CONTROL & JETTY PROJECT</p> <p>04-60878</p> <table border="1"> <tr> <td>January 26, 2004</td> <td>February 26, 2004</td> </tr> </table> | January 26, 2004 | February 26, 2004 | <p>Mr. Kyle Rambo US Naval Air Station c/o Mr. Bruce Young St. Mary's Soil Conservation District 22660 Washington Street, P.o. Box 8110 Leonardtown, Maryland 20650</p> | <p>Location: In the Patuxent River at the Patuxent River Naval Air Station, St. Mary's County, Maryland</p> <p>To create 65,700 square feet of tidal marsh/dune system along approx 1,000 linear feet of shoreline by depositing approx. 5,470 cubic yards of sloped, clean sand fill stabilized marsh species and by depositing approx. 20,000 cubic yards of sloped, clean sand fill, as beach nourish- ment, stabilized with stone groin to extend no more than 90 feet channelward of the approx. MHWS; to install breakwaters to extend no more than 1170 feet channel- ward of the approx. MHWS; to install two breakwater spurs to extend no more than 190 feet channel ward of the approx. MHWS; and to install 300 linear feet of revet-</p> |
| January 26, 2004 | February 26, 2004 | | | | |

| | | | | | |
|------------------|---|---|--|---|---|
| | | | <p>ment, to extend no more than 60 feet channel ward of the approx. MHWS; to emplace 1,000 linear feet of revetment to extend no more than 60 feet channelward of the existing bulkhead and to construct a stone jetty, to extend no more than 190 feet channel ward of the existing bulkhead.</p> <p>Project Manager: Kathy Anderson 410-962-5690</p> | | |
| PN 04-04 | <p>CAMBRIDGE DPW/MARINA EXPANSION</p> <p>04-60897-7</p> <table border="1"> <tr> <td>January 23, 2004</td> <td>February 23, 2004</td> </tr> </table> | January 23, 2004 | February 23, 2004 | <p>City of Cambridge Department of Public Works Attn: Mr. George W. Hyde 705 Leonard Lane Cambridge, Maryland 21613</p> | <p>Location: In the Choptank River within the City of Cambridge, Dorchester County, Maryland</p> <p>To remove two existing earthen mole breakwaters; to mechanically dredge an approx. 6 acre area of open water to a depth of -6 below mean low water; to transport approx. 14,300 cubic yards of dredged material to an upland disposal site; to install 1,809 linear feet of 14-foot wide floating breakwater; to construct 180 linear feet of segmented timber breakwater; to construct 240 linear feet of fixed timber breakwater; to construct 3,307 linear feet of timber collector pier; to construct 114 finger piers; and to install 356 mooring piles.</p> <p>Project Manager: Marie Lasek 410-962-4501</p> |
| January 23, 2004 | February 23, 2004 | | | | |
| PN 04-03 | <p>MIKE DAVIDSON SAND & GRAVEL/SURFACE MINE & STREAM</p> | <p>Mike Davidson Sand & Gravel LLC Attn: Mike Davidson</p> | <p>Location: In an unnamed tributary of the Choptank River,</p> | | |

| | | | | | |
|----------------------------------|---|---------------------|----------------------|---|--|
| | <p style="text-align: center;">RESTORATION</p> <p style="text-align: center;">04-60509</p> <table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td style="text-align: center;">January 13, 2004</td> <td style="text-align: center;">February 13, 2004</td> </tr> </table> | January 13, 2004 | February 13, 2004 | <p>220 Clarks Corner Road Centreville, Maryland 21617</p> | <p>near Henderson, Caroline County, Maryland</p> <p>To relocate approx. 600 linear feet of stream/ditch, to maintain approx. 800 linear feet of stream/ditch, and to fill approx. 400 linear feet of stream/ditch. The maintained and relocated stream/ditch will be utilized as the source of hydrology for a 5.88 acre wetland creation which is the Maryland Department of the Environment required mitigation for isolated farm wetland (Corps non-jurisdictional) impacts, in tributary headwaters of the Choptank River.</p> <p>Project Manager: Ron Schwarm 410- 820-8550</p> |
| January 13, 2004 | February 13, 2004 | | | | |
| <p>SPN 04-01</p> | <p style="text-align: center;">Special Public Notice 04-01 Establishment of Restricted Areas</p> <table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td style="text-align: center;">January 7, 2004</td> <td style="text-align: center;">February 7, 2004</td> </tr> </table> | January 7, 2004 | February 7, 2004 | <p style="text-align: center;">n/a</p> | <p>U.S. Army Corps of Engineers' Action Granting Legal Authorities to Support the Protection of Military Assets During Threat Conditions Charlie or Delta/ Notice VIII/January 7, 2004 - February 7, 2004</p> <p>Project Manager: John Roop 410-962-5688</p> |
| January 7, 2004 | February 7, 2004 | | | | |