



US Army Corps
of Engineers
Pittsburgh District

Notice to Navigation Interests

In reply refer to
Notice No. below

US Army Corps of Engineers, Pittsburgh District
1000 Liberty Avenue, Pittsburgh, PA 15222-4186
(412) 395-7183
http://www.lrd.usace.army.mil/op/nav_notice.asp

Notice No. 03-56

Date: December 8, 2003

1. The following is the Pittsburgh District Repair Fleet's planned schedule of lock maintenance work that will result in lock closures or delays to navigation traffic during calendar years 2004 and 2005.

Repair/Maintenance Schedule for 2004

<u>Month/Duration</u>	<u>Location/Activity</u>
2 March through 23 March 2004 (22 Days)	<u>DASHIELDS L/D, OHIO RIVER</u> Replace Middle Wall Filling and Emptying Valves, and Renovate Operating Machinery. Large Chamber (110' x 600') Open Small Chamber (56' x 360') Closed Minor Delays to Navigation
23 March through 26 March 2004 (4 Days)	<u>DASHIELDS L/D, OHIO RIVER</u> Repairs to the Upstream Land Wall Gate Damaged in Navigation Accident. Large Chamber (110' x 600') Closed Small Chamber (56' x 360') Open Major Delays to Navigation
19 April through 29 April 2004 (11 Days)	<u>MORGANTOWN L/D, MONONGAHELA RIVER</u> Replace Land Wall Filling Valve and Renovate Operating Machinery. Single Chamber (84' x 600') Open Minor Delays to Navigation
3 May through 27 May 2004 (25 Days)	<u>HILDEBRAND L/D, MONONGAHELA RIVER</u> Dewater Single 84' x 600' Lock Chamber, Repair Gates and Seals. Single Chamber (84' x 600') Closed No River Traffic Can Pass Through Lock

Repair/Maintenance Schedule for 2004

<u>Month/Duration</u>	<u>Location/Activity</u>
12 July through 6 August 2004 (26 Days)	<u>MONTGOMERY L/D, OHIO RIVER</u> Dewater 56' x 360' Lock Chamber and Renovate Downstream Gate Sill. Large Chamber (110' x 600') Open Small Chamber (56' x 360') Closed Minor Delays to Navigation
17 August through 27 August 2004 (11 Days)	<u>LOCK 3, ALLEGHENY RIVER</u> Replace River Wall Emptying Valve and Renovate Operating Machinery. Single Chamber (56' x 360') Open Minor Delays to Navigation
7 September through 10 October 2004 (34 Days)	<u>EMSWORTH L/D, OHIO RIVER</u> Repair Filling Valves for 110' x 600' Lock Chamber. Large Chamber (110' x 600') Open Small Chamber (56' x 360') Closed Moderate Delays to Navigation (Tow Width Restriction in the 110' x 600' Land Chamber)
18 October through 2 November 2004 (16 Days)	<u>PIKE ISLAND L/D, OHIO RIVER</u> Replace River Wall Filling Valve and Renovate Operating Machinery. Large Chamber (110' x 1200') Open Small Chamber (110' x 600') Closed Minor Delays to Navigation
4 November through 19 November 2004 (16 Days)	<u>HANNIBAL L/D, OHIO RIVER</u> Replace River Wall Filling Valve and Renovate Operating Machinery. Large Chamber (110' x 1200') Open Small Chamber (110' x 600') Closed Minor Delays to Navigation
7 December through 9 December 2004 (3 Days)	<u>LOCK 5, ALLEGHENY RIVER</u> Replace Upstream Lock Gates. Single Chamber (56' x 360') Closed No River Traffic Can Pass Through Lock

Repair/Maintenance Schedule for 2005

<u>Month/Duration</u>	<u>Location/Activity</u>
28 March through 15 April 2005 (19 Days)	<u>NEW CUMBERLAND L/D, OHIO RIVER</u> Repairs to the Service Bridge Lift Span over the 110' x 600' Land Chamber. Large Chamber (110' x 1200') Open Small Chamber (110' x 600') Closed Minor Delays to Navigation
2 May through 15 June 2005 (45 Days)	<u>MAXWELL L/D, MONONGAHELA RIVER</u> Dewater 84' x 720' River Chamber, Repair Gates, Sills and Anchorages. Land Chamber (84' x 720') Open River Chamber (84' x 720') Closed Minor Delays to Navigation
20 June through 3 July 2005 (14 Days)	<u>POINT MARION L/D, MONONGAHELA RIVER</u> Dewater Single 84' x 720' Lock Chamber, Inspect Gates and Sills. Single Chamber (84' x 720') Closed No River Traffic Can Pass Through Lock
18 July through 31 August 2005 (45 Days)	<u>NEW CUMBERLAND L/D, OHIO RIVER</u> Dewater 110 x 600' Land Chamber, Repair Gates, Sills and Anchorages. Large Chamber (110' x 1200') Open Small Chamber (110' x 600') Closed Minor Delays to Navigation
3 October through 21 October 2005 (19 Days)	<u>PIKE ISLAND L/D, OHIO RIVER</u> Replace Land Wall Filling Valve and Renovate Operating Machinery. Large Chamber (110' x 1200') Open Small Chamber (110' x 600') Closed Minor Delays to Navigation
24 October through 10 November 2005 (18 Days)	<u>HANNIBAL L/D, OHIO RIVER</u> Replace Land Wall Emptying Valve and Renovate Operating Machinery. Large Chamber (110' x 1200') Open Small Chamber (110' x 600') Closed Minor Delays to Navigation

CELRP-OR-T
Navigation Notice No. 03-56

2. The above schedules were developed in cooperation with the Waterways Association of Pittsburgh and are subject to change due to emergency or unusual conditions. A supplemental notice will be issued approximately one (1) month prior to the start of each job outlined above.

FOR THE DISTRICT ENGINEER:

/signed/

James J. Rockovich, P.E.
Acting Chief, Operations and
Readiness Division