

Notice to Navigation Interests

In reply refer to Notice No. below US Army Corps of Engineers, Pittsburgh District 1000 Liberty Avenue, Pittsburgh, PA 15222-4186 (412) 395-7183 http://www.lrd.usace.army.mil/op/nav_notice.htm

Notice No. 04-28

US Army Corps of Engineers

Pittsburgh District

Date: May 13, 2004

Installation of Flashboards Lock & Dam 9, Allegheny River, Mile 62.2

1. **Reference:** Notice to Navigation Interest No. 04-24, dated April 30, 2004. Due to high water the dates for flashboard installation are revised.

2. **TO WHOM IT MAY CONCERN:** Sithe Hydro Operations plan to install the temporary flashboard system, river conditions permitting, on Dam 9, Allegheny River between the hours of 8:00 AM and 8:00 PM daily beginning May 24, 2004 with the anticipated completion date of May 28, 2004.

3. In association with this work, the upper pool will be temporarily drawn down by the hydropower project approximately to elevation 821.7 to permit installation of steel bars and timber boards across the crest of the dam. This elevation equates to an upper pool gage reading of 8.5 or a water level at 0.5 feet below the crest of the dam. This will result in a total change of approximately 1-foot below the pool level.

4. Navigators are cautioned to travel within the limits of the navigation channel during this temporary lowering of the upper pool. In addition marina owners and owners of private docking facilities upstream of the dam may be temporarily affected by this work and the associated pool draw down.

5. The temporary flashboard system is being installed to increase the upper pool elevation to obtain pre-hydro project conditions. The temporary flashboard system will consist of 2" X 15" oak timbers secured to the crest of the dam using steel bars and Ubolts. The flashboard will be installed and maintained by Sithe Hydro Operations until November 1, 2004.

FOR THE DISTRICT ENGINEER:

/signed/

Richard C. Lockwood Chief, Operations and Readiness Division