US Army Corps of Engineers
Charleston District

MARK	DESCRIPTION	DATE	APPRV	MARK	DESCRIPTION	DATE	APPRV

U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
CHARLESTON, SOUTH CAROLINA

Designed by:	Date: SEPT 08	Rev:
Drawn by: MRV	Chkd by:	Design file no. 9233
Reviewed by:		Drawing Order
Submitted by:		File name: P:\dr date:
		Dwg scale: 1" = 200'

ATLANTIC INTRACOASTAL WATERWAY
LITTLE RIVER TO WINYAH BAY
CONDITION SURVEY
9233
STA. 366+02 TO STA. 432+42
HORRY AND GEORGETOWN COUNTIES, SOUTH CAROLINA

SHEET 6 OF 24

SCALE OF FEET
1" = 200'
200 0 200 400

NOTES:
1. SOUNDINGS ARE IN FEET AND TENTHS AND REFER TO MEAN LOW WATER.
2. HORIZONTAL DATUM IS NAD 1983.
3. THIS CONDITION SURVEY PLOTTED ON THIS SHEET IS INTENDED TO REPLACE NAUTICAL CHARTS PUBLISHED BY NATIONAL OCEAN SERVICE, U.S. COAST GUARD AIDS TO NAVIGATION, OR U.S. COAST GUARD NOTICES TO MARINERS. THE SOUNDINGS ON THIS DRAWING ONLY INDICATE THE GENERAL CONDITION OF THE CHANNEL AT THE TIME SURVEYED, AND ARE NOT INTENDED TO BE USED FOR NAVIGATION PURPOSES.
4. DATE OF SURVEY: 19, 23 SEPT.2008 CONDITION

STATION	DESCRIPTION	ELEV.	OFFSET	SIDE	NAD83 COORDINATES EASTING	NAD83 COORDINATES NORTHING	OLD STATION	NAD27 COORDINATES EASTING	NAD27 COORDINATES NORTHING
366+78.13	CENTERLINE PI		249.91	LEFT	2,713,033.13	744,862.78	388+05.18 BK	2713045.24	319344.61
			155.98	LEFT	2,713,128.18	744,931.48	386+06.10 AH	2713192.92	319408.51
			155.98	LEFT	2,713,128.18	744,931.48		2713192.92	319408.51
			184.98	LEFT	2,712,972.92	743,561.62		2713039.70	319238.65
369+23.26			184.98	LEFT	2,712,972.92	743,561.62		2713039.70	319238.65
372+00.95			193.98	LEFT	2,712,771.42	743,370.32		2712838.25	319047.24
379+57.53			187.09	LEFT	2,712,201.58	742,872.59	380+88.93	2712268.51	318549.20
385+00.27			155.98	LEFT	2,711,733.23	742,492.23	386+91.00	2711800.24	318168.58
390+49.73			155.98	LEFT	2,711,258.56	742,107.84		2711325.58	317783.94
393+93.95			189.99	LEFT	2,711,024.51	741,826.43	389+50.00	2711091.60	317503.61
399+52.26			160.16	RIGHT	2,710,480.44	741,806.22	400+84.00	2710547.52	317481.95
400+68.24			249.98	LEFT	2,710,666.38	741,422.70	402+00.00	2710733.65	317098.45
			199.98	LEFT	2,710,633.15	741,460.05		2710700.40	317135.79
407+28.70			254.98	LEFT	2,710,116.12	740,975.84		2710243.50	316655.34
414+71.71			254.98	LEFT	2,709,553.36	740,552.61	416+05.70	2709680.74	316232.06
428+67.194			199.97	LEFT	2,708,541.50	739,599.30	429+74.00 BK 430+00.00 AH	2708609.16	315273.88