US Army Corps of Engineers
Charleston District

MARK	DESCRIPTION	DATE	APPRV

MARK	DESCRIPTION	DATE	APPRV

U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
CHARLESTON, SOUTH CAROLINA

Designed by:
Drawn by: MRV
Chkd by:
Design file no.
Reviewed by:
Submitted by:
Dwg scale: 1" = 200'
Date: SEPT. 08
Rev:
Drawing Code: 9233
File name:
Plot date:

ATLANTIC INTRACOASTAL WATERWAY
LITTLE RIVER TO WINYAH BAY
9233
CONDITION SURVEY
STA. 432+42 TO STA. 498+77
HORRY AND GEORGETOWN COUNTIES, SOUTH CAROLINA

SHEET 7 OF 24

NOTES:
1. SOUNDINGS ARE IN FEET AND TENTHS AND REFER TO MEAN LOW WATER.
2. HORIZONTAL DATUM IS NAD 1983.
3. THE CONDITION SURVEY DEPICTED ON THIS DRAWING IS NOT INTENDED TO REPLACE NAUTICAL CHARTS PUBLISHED BY NATIONAL OCEAN SERVICE, U.S. COAST GUARD AIDS TO NAVIGATION, OR U.S. COAST GUARD NOTICES TO MARINERS. THE SOUNDINGS ON THIS DRAWING ONLY INDICATE THE GENERAL CONDITION OF THE CHANNEL ON THE DATE OF SURVEY, AND ARE NOT INTENDED TO BE USED FOR NAVIGATION PURPOSES.
4. DATE OF SURVEY: 19- 23 SEPT. 2008 CONDITION

SCALE OF FEET
1" = 200'
200 0 200 400

STATION	DESCRIPTION	ELEV.	OFFSET	SIDE	NAD83 COORDINATES EASTING	NORTHING	OLD STATION	NAD27 COORDINATES EASTING	NORTHING
443+67.53	----------	----	219.96	LEFT	2,707,434.26	738,587.52	445+00.30	2707502.15	314261.49
	----------	----	199.97	LEFT	2,707,420.97	738,602.46		2707488.85	314276.43
458+78.49	CENTERLINE_PI	----	----	----	2,706,395.17	737,741.58	460+10.90	2706371.72	313525.02
	CENTERLINE_PI	----	219.96	LEFT	2,706,378.90	737,743.63			
463+78.04	CENTERLINE_PI	----	219.96	LEFT	2,705,378.90	737,243.63	465+10.90	2705371.72	313025.02
	----------	----	219.96	LEFT	2706917.92	737253.10		2,705,986.10	312,496.24
468+77.59	CENTERLINE_PI	----	----	----	2,705,384.99	737,116.42	470+10.90		
	----------	----	219.96	LEFT	2705516.30	736940.04		2,705,584.74	312,612.91
473+77.13	CENTERLINE_PI	----	----	----	2,704,984.15	736,642.54	475+10.90		
	----------	----	219.96	LEFT	2,705,101.42	736,644.28		2705169.70	312316.99
	----------	----	264.95	LEFT	2,704,770.90	736,318.97		2704839.23	312051.50
477+93.07	CENTERLINE_PI	----	----	----	----------	----------	481+44.95	----------	----------
480+10.55	CENTERLINE_PI	----	----	----	2,704,444.69	736,484.70			
	----------	----	219.96	LEFT	2,704,458.03	736,465.56			
486+43.00	CENTERLINE_PI	----	----	----	2,703,884.54	736,179.08	487+78.00	2,704,026.84	311,968.69
	----------	----	219.97	LEFT	2,704,023.47	735,981.83		2,704,066.38	311,651.17
491+42.49	CENTERLINE_PI	----	----	----	2,703,446.34	735,948.59	492+78.00		
	----------	----	219.96	LEFT	2,703,542.93	735,743.95		2,703,611.31	311,421.08
496+42.01	CENTERLINE_PI	----	----	----	2,703,088.33	735,541.55	497+78.00		
	----------	----	219.96	LEFT	2,703,076.76	735,541.05		2703,147.14	311,212.76