

STANDING INSTRUCTIONS TO THE PROJECT OPERATOR
FOR WATER CONTROL
LYTLE CREEK INTAKE STRUCTURE

TABLE OF CONTENTS

Section	Title	Page
I. BACKGROUND AND RESPONSIBILITIES		
A.	General Information	I-1
1.	Purpose of Document	I-1
2.	Purpose of Project	I-2
3.	Chain of Command In Flood Emergencies	I-2
4.	Project Location & Brief Description of Water Control Structures	I-3
5.	Project History	I-4
a.	Construction Legislation	I-4
b.	Description of Water Control Structures	I-4
6.	Hydrology	I-6
7.	Geology and Groundwater	I-7
a.	Geology	I-7
b.	Groundwater	I-7
8.	Problems Encountered	I-8
a.	Erosion	I-8
b.	Sedimentation	I-8
9.	Constraints on Physical Operation of Water Control Structure	I-9
a.	Official Staff Gauge	I-9
b.	Rating Curves	I-9
c.	Upper Devore Levee	I-10
d.	Trash Buildup	I-10
10.	Lytle-Cajon Floodway Improvements	I-10
B.	Role of the Project Operator	
1.	Normal Conditions	I-10
2.	Emergency Conditions (Flood or Drought)	I-10
a.	Superintendent Responsibility during Flood Conditions	I-11
b.	Drought Conditions	I-13
II. DATA COLLECTION AND REPORTING		
A.	Normal Conditions	II-1
B.	Flood Conditions	II-1
C.	Regional Hydrometeorological Conditions	II-1

TABLE OF CONTENTS (CONTD.)

Section	Title	Page
III. WATER CONTROL ANCTION AND REPORTING		
A.	Normal Conditions	III-1
B.	Flood Conditions	III-1
C.	Inquiries	III-2
D.	Water Control Problems	III-2
E.	Communication Network in Flood Situations	III-2
F.	Communication Outage	III-3

List of Figures

Figure Number	Page
1.	Diagram of Lytle-Cajon Flood Control Structures - Photo Index i
2.	Diagram of Lytle Creek Intake Structure - Photo Index ii
3.	Lytle Creek Intake Structure Looking SW at Control House at West Branch Intake. East Wing Levee in Background Fig-i
4.	Lytle Creek intake Structure. West Branch Intake with Tainter Gate Housing. Looking SW with West Wing Levee Beyond Intake Fig-i
5.	West Branch Lytle Creek Intake Channel with 60'x25' Tainter Gate. Looking South Fig-ii
6.	West Branch Lytle Creek Channel Looking SW at Tainter Gate During Gate Test. Unused Bypass to East Branch of Lytle Creek in Foreground; No Longer Used After Construction of the East Branch Lytle Creek Channel Fig-ii
7.	60' x 25' Tainter Gate in Lytle Creek West Branch Channel Looking West during Gate Test. Lytle Creek Intake Structure ... Fig-iii
8.	Lytle Creek intake Structure and Control House. Looking NE Showing 60' x 25' Tainter Gate During Gate Test Fig-iii
9.	Lytle Creek Inlet Structure at West Branch Intake Looking NE at Lytle Creek Channel with Muscoy Levee in Background Fig-iv
10.	Lytle Creek Intake Structure Looking SW from Intake to West Branch Channel at The West Wing Levee, 1,000 ft. Long Fig-iv
11.	Official Staff Gauge at Lytle Creek Intake Structure, Located on East Wall of West Branch Inlet Just North of Control House Looking NE Fig-v
12.	Lytle Creek Intake Structure Looking East Along Wing Levee Toward East Branch Channel Inlet. Haul Road for Gravel Works Crosses over Inlet Structure Before East Branch Inlet Fig-v
13.	Invert to Lytle Creek East Branch Channel. Elev. 1143.0 Looking East Fig-vi
14.	East Branch Lytle Creek Channel Looking SE. The 58,000 c.f.s. 132 Foot Intervals Fig-vi

TABLE OF CONTENTS (CONTD)

Figure Number	Page
15. Invert of Lytle Creek East Branch Channel, Elev. 1143.0, with Haul Road Crossing toward Muscoy Levee. Looking East. A Portion of Lytle Creek Inlet Structure	Fig-vii
16. Looking SE Along Lytle Creek East Branch Channel. Flows above 22,800 c.f.s. Will Begin to Flow Around The Left Wing Levee and A Portion Will Begin to Flow Down The East Branch Channel	Fig-vii
17. Lytle Creek East Branch Inlet Looking NE. On Right is the Spillway Levee at Elev. 1160 ft. Added Onto the Original Bypass Spillway When the East Branch Channel Was Modified. Top of Levee Wall is at Elevation 1160 feet	Fig-viii
18. Looking SW along Spillway Levee Wall Modification to Original Bypass Spillway Toward Inlet to Lytle Creek East Branch Channel and Control House at Lytle Creek West Branch Channel	Fig-viii
19. Looking NW Along Grouted Quarry Stone of Muscoy Levee Near the Junction of East Side of Lytle Creek Intake Structure With Muscoy Levee	Fig-ix
20. East Junction of Lytle Creek Intake Structure with Muscoy Levee At Edge of Original Bypass Spillway. Looking NW, Showing Original Stage Recorder for Bypass Spillway. Gauge Is No Longer Used. Lytle-Cajon Flood Control Improvements	Fig-ix
21. Upper Devore Levee on Cajon Creek Looking South. Showing One Of Two Transcontinental Railroad Bridges at Location	Fig-x
22. Upper Devore Levee Looking SE Showing Two Transcontinental Railroad Tracks Crossing Cajon Creek	Fig-x
23. Devil Creek Diversion Structure Looking Downstream (SW) From 3rd Avenue Extension	Fig-xi
24. Levee Road On Muscoy Groin No.2 Looking South (Downstream) At Grouted Quarry Stone with Cajon Creek Channel on Right	Fig-xi
25. Railroad Crossing Lytle-Cajon Drainage at Highland Avenue Looking South with Island Levee at Right Embankment	Fig-xii
26. Grouted Quarry Stone of Island Levee at Highland Avenue Looking South on Lytle-Cajon Drainage	Fig-xii

List Of Plates

Plate 1	Reference to LAD COE Documents pertaining to Lytle-Cajon Flood Control Improvements
Plate 2	Project Location
Plate 3A	Aerial Photograph Showing Locations of Lytle-Cajon Water Control Structures
Plate 3B	O & M Diagram of Water Control Structures With Fault Zones
Plate 4	Construction Diagram Showing West Branch Lytle Creek Intake and Original Bypass Plan, Profile, and Sections
Plate 5	Construction Diagram Showing Tainter Gate & Control House
Plate 6	Construction Diagram Showing Modified East Branch Inlet

TABLE OF CONTENTS (CONTD)

LIST OF PLATES

Plate 7	Hydrologic Map Showing Instrument Locations & Isohyets of Precipitation Frequency
Plate 8	SPF Hydrographs for Santa Ana River Watershed
Plate 9	SPF Routed Discharges Intake Structure Lytle Creek East & West Branch Channels
Plate 10	Project Earthquake Epicenter and Fault Location Map
Plate 11	Rating Curves for Lytle Creek Intake Combined East and West Branch Discharges

List Of Exhibits

Exhibit A	Lytle Creek Intake Structure Regulation Schedule
Exhibit B	Hydrology - Runoff, Precipitation, Standard Project Flood
Exhibit C	Tainter Gate and Backup Generator Operating Instructions
Exhibit D	USACOE Suggested Forms for Data Reporting
Exhibit E	Environmental Assessment
Exhibit F	Chain of Correspondence for Approval of Standing Instructions

Abbreviations Used

CD	Climatological Data
COE	Corps of Engineers
c.f.s	Cubic Feet Per Second
EM	Engineering Manual
ER	Engineering Regulation
FAX	Facsimile Transmission
ft	Feet
fps	Feet Per Second
HPD	Hourly Precipitation Data
LAD	Los Angeles District
LATS	Los Angeles Telemetry System
MSL	Mean Sea Level
NGVD	National Geodetic Vertical Datum of 1929
NOAA	National Oceanic and Atmospheric Administration
PMF	Probable Maximum Flood
ROC	LAD Reservoir Operations Center
SBCFCD	San Bernardino County Flood Control District
SPF	Standard Project Flood
sq-mi	Square Miles
TELEM	Interactive Program on Water Control Data System in LATS
USACOE	United States Army Corps of Engineers
USGS	United States Geological Survey