

**Prado Dam
Interim Water Control Plan During Construction
Table of Contents**

I - INTRODUCTION.....	1-1
1-01. <u>Background</u>	1-2
1-02. <u>Purpose</u>	1-3
1-03. <u>Project Features</u>	1-3
a. <u>Dam Embankment and Cofferdam</u>	1-3
b. <u>Existing Outlet Works</u>	1-3
c. <u>Stilling Basin</u>	1-4
d. <u>Spillway</u>	1-4
II - WATERSHED CHARACTERISTICS	2-1
2-01 <u>General Characteristics</u>	2-2
2-02 <u>Topography</u>	2-2
2-03 <u>Structures Affecting Runoff</u>	2-2
III - CONSTRUCTION SCHEDULE	3-1
3-01 <u>General</u>	3-1
3-02 <u>Prado Dam Construction Schedule</u>	3-1
a. <u>Construction Stage 1</u>	3-1
b. <u>Construction Stage 2A, 2B, and 2C</u>	3-2
c. <u>Construction Stage 3</u>	3-2
3-03 <u>Lower Santa Ana River Construction Project (Reach 9)</u>	3-3
a. <u>Upper Highway 91 Embankment</u>	3-3
b. <u>Green River Housing Estate</u>	3-4
c. <u>Green River Mobile Home Park</u>	3-4
d. <u>Green River Golf Course</u>	3-4
e. <u>Lower Highway 91 Embankment</u>	3-4
f. <u>Car Wash and Strip Mall Protection</u>	3-5
IV - DIVERSION AND CONTROL OF WATER DURING CONSTRUCTION	4-1
4-01 <u>General</u>	4-1
4-02 <u>Possible Downstream Channel Limitations</u>	4-1
a. <u>Existing Santa Ana River Interceptor Line (SARI)</u>	4-1
b. <u>Possible Construction Activities - Lower Santa Ana River (Reach 9)</u>	4-2
c. <u>Possible Construction Activities during the Relocation of the SARI Line</u>	4-2
d. <u>Bank Protection and Bridges within the Santa Ana River between Prado Dam and Weir Canyon Road</u>	4-2
e. <u>Construction of the Groundwater Replenishment System (GWRS) Pipeline</u>	4-3
4-03 <u>Interim Water Control Plan</u>	4-3

a.	<u>Plan A - Using the Existing Outlet Works</u>	4-3
	(1) <u>WSE 460.0 - 490.0 (Debris Pool)</u>	4-4
	(2) <u>WSE 490.0 - 494.0/505.0 (Buffer Pool)</u>	4-5
	(i) <u>Winter Flood Season</u>	4-5
	(ii) <u>Non-Flood Season</u>	4-6
	(3) <u>WSE 494.0/505.0 - 520.0 feet, NGVD</u>	4-8
	(4) <u>WSE 520.0 - 525.0 feet, NGVD</u>	4-9
	(5) <u>WSE 525.0 - 543.0 feet, NGVD</u>	4-10
	(6) <u>WSE 543 and above (Spillway Flow)</u>	4-10
4-04	<u>Channel Observation Teams</u>	4-11
4-05	<u>Rate of Release Change</u>	4-11
4-06	<u>Level of Protection</u>	4-12
4-07	<u>Flood Emergency Action Plan</u>	4-12
V - FLOOD NOTIFICATION PLAN		5-1
5-01	<u>Hydrologic Gathering Network</u>	5-1
5-02	<u>Notification and Coordination Plan</u>	5-2
5-03	<u>Downstream Evacuation</u>	5-3
VI - Summary		6-1

TABLES AND FIGURES

TABLE 2-1. Major Water Storage Facilities Within the Santa Ana River Watershed

TABLE 4-1. Suggested Rate of Release Change – Prado Dam

FIGURE 3-1. Prado Dam Embankment and Outlet Works Construction Schedule

FIGURE 3-2. Santa Ana River Construction Schedule (Reach 9)

PLATE NO.	PLATES
2-01	Santa Ana River Drainage Area
2-02	Schematic of the Santa Ana River Watershed
3-01	Stage 1 Construction
3-02	Stage 2A Construction
3-03	Stage 2B Construction
3-04	Stage 2C Construction
3-05	Stage 3 Construction
3-06	Lower Santa Ana River Construction (Reach 9)
4-01	Water Control Diagram - Plan A
4-02	Prado Reservoir Storage Allocation Diagram (During Construction - Plan A)
5-01	Hydrometeorological Instrumentation Pertinent to Prado Dam
5-02	Precipitation Stations Pertinent to Prado Dam
5-03	Santa Ana River Interceptor (SARI Line) – Potential Scour Areas
5-04 to 5-11	Prado Dam Emergency Action Plan Inundation Maps (Downstream and Upstream)

LIST OF ABBREVIATIONS

ac-ft	Acre-feet
cfs	Cubic feet per second
COE	Corps of Engineers
CWMS	Corps Water Management System
EM	Engineering Manual
EOC	Emergency Operations Center of the U.S. Army Corps of Engineers (Construction-Operations Division)
ER	Engineering Regulation
ft	feet
GDM	General Design Memorandum
LAD	Los Angeles District, Corps of Engineers
LATS	Los Angeles Telemetry System
HECDSS	Hydrologic Engineering Center Data Storage System
LAD	Los Angeles District
MOA	Memorandum of Agreement
NGVD	National Geodetic Vertical Datum
NWS	National Weather Service
OCPF&RD	Orange County Public Facilities and Resources Department
OCWD	Orange County Water District
PL	Public Law
PMF	Probable Maximum Flood
ROC	Reservoir Operations Center (LAD Engineering Division)
SPF	Standard Project Flood
sq mi	Square mile
USACE	U.S. Army Corps of Engineers
USFWS	U.S. Fish and Wildlife Service
USGS	U.S. Geological Survey
WCDS	Water Control Data System
WSE	Water Surface Elevation