

if the owner or operator obtains certification by a qualified engineer that alternate design features or operating plans will, to the best of his knowledge and opinion, prevent overtopping of the dike. The certification, along with a written identification of alternate design features or operating plans preventing overtopping, must be maintained at the facility.

(h) Surface impoundments that are newly subject to RCRA section 3005(j)(1) due to the promulgation of additional listings or characteristics for the identification of hazardous waste must be in compliance with paragraphs (a), (c) and (d) of this section not later than 48 months after the promulgation of the additional listing or characteristic. This compliance period shall not be cut short as the result of the promulgation of land disposal prohibitions under part 268 of this chapter or the granting of an extension to the effective date of a prohibition pursuant to § 268.5 of this chapter, within this 48-month period.

[50 FR 16048, Apr. 23, 1985. Redesignated at 57 FR 3492, Jan. 29, 1992. 50 FR 28749, July 15, 1985, as amended at 55 FR 11876, Mar. 29, 1990; 57 FR 3492, Jan. 29, 1992; 57 FR 37267, Aug. 18, 1992; 71 FR 16911, Apr. 4, 2006; 71 FR 40275, July 14, 2006]

§ 265.222 Action leakage rate.

(a) The owner or operator of surface impoundment units subject to § 265.221(a) must submit a proposed action leakage rate to the Regional Administrator when submitting the notice required under § 265.221(b). Within 60 days of receipt of the notification, the Regional Administrator will: Establish an action leakage rate, either as proposed by the owner or operator or modified using the criteria in this section; or extend the review period for up to 30 days. If no action is taken by the Regional Administrator before the original 60 or extended 90 day review periods, the action leakage rate will be approved as proposed by the owner or operator.

(b) The Regional Administrator shall approve an action leakage rate for surface impoundment units subject to § 265.221(a). The action leakage rate is the maximum design flow rate that the leak detection system (LDS) can re-

move without the fluid head on the bottom liner exceeding 1 foot. The action leakage rate must include an adequate safety margin to allow for uncertainties in the design (e.g., slope, hydraulic conductivity, thickness of drainage material), construction, operation, and location of the LDS, waste and leachate characteristics, likelihood and amounts of other sources of liquids in the LDS, and proposed response actions (e.g., the action leakage rate must consider decreases in the flow capacity of the system over time resulting from siltation and clogging, rib layover and creep of synthetic components of the system, overburden pressures, etc.).

(c) To determine if the action leakage rate has been exceeded, the owner or operator must convert the weekly or monthly flow rate from the monitoring data obtained under § 265.226(b), to an average daily flow rate (gallons per acre per day) for each sump. Unless the Regional Administrator approves a different calculation, the average daily flow rate for each sump must be calculated weekly during the active life and closure period, and if the unit closes in accordance with § 265.228(a)(2), monthly during the post-closure care period when monthly monitoring is required under § 265.226(b).

[57 FR 3492, Jan. 29, 1992]

§ 265.223 Containment system.

All earthen dikes must have a protective cover, such as grass, shale, or rock, to minimize wind and water erosion and to preserve their structural integrity.

§ 265.224 Response actions.

(a) The owner or operator of surface impoundment units subject to § 265.221(a) must develop and keep on site until closure of the facility a response action plan. The response action plan must set forth the actions to be taken if the action leakage rate has been exceeded. At a minimum, the response action plan must describe the actions specified in paragraph (b) of this section.

(b) If the flow rate into the leak detection system exceeds the action leakage rate for any sump, the owner or operator must: