



















































What are the Real Costs?			
Capping Material	Minimum Depth Required (cm)	Material Cost (\$/m3) Delivery Included	Cost for Capping Area (\$/m2)
Reactive (2 layers)			
Apatite Layer	2.5	\$ 135.00	\$ 3.38
Sand Layer	15	\$ 10.00	\$ 1.50
		Total	\$ 4.88
Conventional (1 layer)			
Sand Layer	75	\$ 10.00	\$ 7.50
	Dredged Material A	Assessment and Manag	ement Seminar – April 28th







