

*Constructing Rural Village Water
Systems in Central America:
Experiential Learning 101*

OSU EWB Meeting – 4 June 2007

Michael E. Campana

Director

**Institute for Water &
Watersheds**

President

**Ann Campana Judge
Foundation**

www.acjfoundation.org

Talk Organization

- **Water projects in developing countries**
- **Panama Project – Epera Indians**
Description, Accomplishments, & Shortcomings
- **Honduras Projects - students**
Description, Accomplishments, & Shortcomings
- **Concluding Remarks**

Some Facts

“Over 1 billion people lack access to clean drinking water and almost 2.4 billion people lack access to any kind of improved sanitation services.” - **World Health Organization, 2000.**

“Every 8 seconds a child dies of a water-related disease.” – **WHO, 1996, Fact Sheet 112.**

Millennium Development Goals

- ▶ By 2015, reduce by 50% the number of people who do not have access to safe drinking water or sanitation
- ▶ Requires that each day until 2015, must provide safe drinking water to about 250,000 people and sanitary facilities to about 500,000 people

Developing Countries I

- **Appropriate technology**
- **Community involvement of *all* (*women, children!*)**
- **Sustainability**
- **Communications/Logistics**
- **Land ownership/access; water rights**

Developing Countries II

- Don't make promises you can't keep
- Cultural/religious/social sensitivity – need to acknowledge and honor
- *Tranquilo, por favor* – serenity now!
- *Sustainability*

Panama Project

- **Train Epera Indians (Comarca No. 2 – 10,000 people) to drill and complete wells, build, and install hand pumps**
- **Use of LS-100 drilling rig (www.lonestarbit.com)**
- **Provide on-site instruction, multiple trips**

Project Background

- Conducted under the auspices of Lifewater International
- Invited by Epera Indians of Panama's S. Darien Province
- Survey trip in March 1999 and "shopping trip" in January 2000
- 2-week training trip in May 2000
- Cost: about \$30,000



Copyright 2006 Geology.com



Southern Darien – looking west



The Team

- **Michael Campana (hydrologist) - team leader, driller, pump installer**
- **Loring Green (geologist) - lead trainer, mechanic, stockbroker**
- **Bob Jarrett (engineer) - trainer, mechanic, medic**
- **Craig Woodring (engineer)-trainer**

Loring Green Instructing on the LS-100



Drilling the Well



Examining Cuttings



Installing the Gravel Pack



Finished!



Accomplishments

- Trained 6-man team
- Team drilled three wells: two producers (c. 25 gpm) and one dry hole (< 1 gpm)
- Team installed one submersible and one hand pump
- Provided one LS-100, mud pump, 500 feet of 4" ID PVC, drilling mud, 3 hand pumps, cement, submersible pump, tools

Shortcomings

- **Poor USA-Panama communications with locals; made coordination and planning difficult**
- **No follow-up – future trips were canceled because of dangerous conditions (Colombian civil war)**
- **Lost touch with team after training**

Honduras Projects

- From 2001-2005, I conducted the required summer field course for U of NM Master of Water Resources students in Honduras. Spent 3 weeks in country each June.
- We worked with *Hondureños* Alex del Cid Vásquez, Rolando López, SANAA, and local villagers to build gravity-flow water systems (dam-storage tank-piping) to provide a tap to each home.

Honduras Projects - more

- Constructed systems in 5 villages: Miramar, Nueva Vida, Nueva Florida, Santa Teresa, Santa Cruz
- Number of villagers: 2,000
- Number of students in five years: 70.
- Fundraising: yours truly
- How did the program start? Serendipity



Alex del Cid Vásquez, "el jefe de agua"

Nueva Florida



Located in the Sierra de Omoa...a rugged mountain range ~20 km NW of San Pedro Sula

Population: ~308

Elevation: 650 m AMSL

Climate: Very warm and humid year-round with an average rainfall of 245 cm (~96 inches). Distinct wet, dry seasons.



Building the Dam

- A dam site was cleared above the village at ~800 m above sea level, near a spring with an average flow of 100 gallons per minute
- A local mason was hired to build the forms and work with the concrete
- Using only a chainsaw and machete, forms were hand-hewn on site using timber
- Sand from the streambed along with nearly 30 bags (1.5 tons) of cement were used
- It took 6 days to build the dam and then 14 days for the concrete to cure.



Building the Dam

Villagers clearing and leveling the site



Cindy, Kerry, Alex, Michael & Michele work on stream channel




Our favorite pastime...rearranging rock!



Cindy and Manuel (mason) building rebar reinforcement cages

Uresa laja desarenador



Dam plans

Tank Site & Distribution

- We leveled a site above the village for a 5000 gallon water tank and dug a pit for the tank platform
- After the tank site was cleared, 1½ inch diameter galvanized iron (GI) pipe was laid between the dam and the tank site
- The pipe was provided by SANAA, the Honduran government agency responsible for rural water supply
- The head of rural water for SANAA's northern division inspected the dam and pipeline and was impressed



Now that's a lot of cement!



Matt, Amy and Michele work to level the site



Side trip to the sugar cane press



The water tank will look similar to this one at Nueva Vida



Pipe cutting and threading





Signing the agreement with Ing. Denis Gutierrez of SANAA, Alex del Cid, Michael and village leaders



The final night at Nueva Florida

Some Facts

- The total cost of the project was 187, 383 lempiras or just under \$12,000 U.S.
- 44 domestic connections with an average of 7 persons per house
- Water use is ~35 gallons per person per day
- ½ inch GI tubing and control valves were installed to permit an efficient and regulated quantity of water to each household
- System was completed in fall 2003

Accomplishments

- Helped build five gravity-flow potable water systems serving about 2,000 people
- Provided instruction in sanitation
- Cross-cultural, life-changing (for some) experience for over 70 students
- Empowered women – can do other things besides “gathering water”; girls can go to school
- Gringos can be “good neighbors”
- Led to student thesis, project work

Shortcomings

- **No follow-up – SANAA “dropped the ball”**
- **Need continued training, support**
- **Sustainability**
- **Change in social dynamics of villages?
Is this good?**

It's obvious...

*Clean water, sanitation,
and good health go
hand-in-hand , ergo...*

*water professionals
have **great power** to
“do good” in the
developing world.*

Says who?

***"I really envy you guys.
You have the power to
keep people from getting
sick. By the time I'm
called in, it's invariably
too late."***

***--A medical doctor, talking
to some water
professionals.***



Thank you!

Michael E. Campana

aquadoc@oregonstate.edu

WaterWired blog:

aquadoc.typepad.com/waterwired