

directions of plate motion. Transform valleys and their bordering steep ridges mark plate boundaries where the plates grind horizontally past each other, accompanied by earthquakes (see main map). Along oceanic transforms, faulting locally exposes deep crustal rocks, but volcanism is rare. Divergent plate boundaries and associated transforms form the crest of the global Mid-Oceanic Ridge (MOR) (figs. 4, 5, 7). This linear bulge on the deep ocean floor is Earth's longest and most prominent mountain range—about 65,000 km long, as much as 1,000 km wide, and rising 3,000 m or more above the flanking deep basins. The MOR results from thermal expansion: the closer to the ridge crest, the younger and hotter the plate; therefore the more expanded and higher above the colder, older plate, hence deeper sea floor. Relief along the MOR is greatest along transform faults that offset the spreading ridge, forming the characteristic step-like plate margin pattern (see main map and interpretive map of plate tectonics, on front). For example, in the equatorial Atlantic Ocean, the Romanche Fracture Zone-7,728 m at its deepest—is even deeper than several subduction zone trenches (see inset II). Spreading (total opening) rates range from about 150 mm/yr along the East Pacific Rise (figs. 5, 8) to less than 10 mm/yr along the Arctic extension of the Mid-Atlantic Ridge. Scientists generally consider rates of less than 60 mm/yr as "slow" and rates greater than 90 mm/yr as "fast." Spreading "half rates" are not always the same on opposing sides of the plate boundary, however. Note how the present boundary is closer to the eastern than to the western lines of equal age (0.78 Ma) in the southern part of figure 7.

Local relief and structures along the ridge crests range widely, depending or




Figure 8.—A, Computer image of multibeam-mapped topography (mapped from a surface ship) of the fastest spreading (146 mm/yr) part of the East Pacific Rise, showing the axial high, small seamounts, and abyssal hills on its flanks. Gray patches indicate areas of no data. B, Detailed topography showing a very small part of the axial high, as mapped by the submarine free-swimming, but remotely operated (from surface ship), autonomous Benthic Explorer (ABE) skimming back and forth 5 to 40 m above the deep sea floor. Note the narrow (50-m-wide), 10-m-deep central fissure valley, the remains of a long lava lake that drained through channels feeding lobes to the west. Images from Marie-Hélène Cormier (Lamont-Doherty Earth Observatory).

REFERENCES CITED

Bird, Peter, 2003, An updated digital model of plate boundaries: Geochemistry, Geophysics, Geosystems,


structure and rock types at a slow-spreading plate boundary along the Mid-Atlantic Ridge. Along such A' boundaries, the maximum local relief can be as much as 2,000 m. Modified from Pearce (2002). B, Computer image of multibeam-mapped topography (see "More about this map" discussion) of a slow-spreading part (here 22 mm/vr) of the Mid-Atlantic Ridge, illustrating a transform fault (black line) and other discontinuities offsetting the spreading axis (red line). Modified from Carbotte and Scheirer (2004). Used with permission of fast-spreading segments typically have lower relief (<1 km), lack median valleys, and exhibit smoother, volcanism-dominated topography (figs. 5, 8), with welldefined narrow ridges along their crests. Along intermediate-spreading ridges, axial valleys, if present, tend to be less prominent topographically. Because the rocks along fast-spreading ridges are young and hot, earthquakes occurring there are too weak to be measured by distant seismic instruments. The difference between these types of ridges reflects different temperature conditions. At the ridge crest, faster spreading prevents deep penetration of the overlying ocean's cold temperatures, thereby favoring higher temperatures and allowing more molten rock (magma) to be produced at shallower depths. many millions of years. Other ridge offsets, especially along fast-spreading boundaries (fig. 5B), are active for much shorter times and may move along some ridges that lengthen (propagate) during spreading. MOR spreading boundaries are not always perpendicular to the nearest transform. Oblique (non-perpendicular) spreading (for example, north of 30.5° N. in fig. 4B) is most common at slowspreading ridges. Some rifts may even overlap along fast-spreading boundaries Luckily for scientists, the oceanic crust operates like a giant "tape recorder" that remembers its creation and thus the rates at which its plates separated over time. As new oceanic crust forms along the MOR axis, it cools and becomes magnetized, locking in Earth's magnetic field at the time. Most of this magnetization

(magnetic striping). Magnetic-anomaly maps made by ships or airplanes can be used to calculate the magnetization of the crust (fig. 7). Because the times of magnetic reversals have been independently dated, the stripe-like pattern of normally and reversely magnetized crust allows the calculation of past rates of sea floor spreading. From these data, and traces of transform faults, past plate motions can be reconstructed and continents reassembled! Figure 5.—A. Schematic cross section showing inferred structure and rock types The "embryo" of a future midocean ridge segment begins to take shape when below a fast-spreading plate boundary along the East Pacific Rise. Here, the local continental crust starts to split apart along active rift zones, as in east Africa. relief is only tens of meters, much less than that along slow-spreading ridges There, geologically young volcanoes (Mt. Kilimanjaro), basins formed by down-(compare with fig. 4A). Modified from Pearce (2002). B, Computer image of dropped crustal blocks (Lake Tanganyika), and earthquake activity all foreshadow ibeam-mapped topography of a fast-spreading part (here 110 mm/yr) of the a future oceanic ridge segment between the Nubia and Somalia plates. With East Pacific Rise, showing two transform faults and an overlapping southwardcontinued continental rifting, a new ocean basin such as the Red Sea is born. Over propagating rift (too small to show on the main map). Modified from Carbotte and Scheirer (2004). Used with permission of Cambridge University Press. the long span of geologic time, new rifts break through some plates, other plate boundaries become inactive (see interpretive map), and existing plate boundaries migrate over the deeper mantle in an ever-shifting mosaic of plates. Oceans eventually die, as oceanic crust is recycled by subduction and continents collide, leaving only new mountain chains as evidence of their passing (see inset III). Figure 7.—Example of the "magnetic

resides in tiny magnetite crystals "frozen" in the erupted lava as it solidifies into

rock. Occasional reversals of Earth's magnetic field are recorded by the oceanic

crust as small but measurable, ridge-parallel stripe-like magnetic anomalies



uggested citation: Simkin, Tom, Tilling, R.I., Vogt, P.R., Kirby, S.H., Kimberly, Paul, and Stewart, D.B., 2006, This dynamic planet; World map of volcanoes, earthquakes, impact craters, and plate tectonics: U.S. Geological Survey Geologic Investigations Series Map I–2800, 1 two-sided sheet, scale 1:30,000,000 Any use of trade, product, or firm names in this publication is for descriptive purposes only and does not imply endorsement by the U.S. Government. Although this map is in the public domain, permission must be secured from the individual copyright owners to reproduce any copyrighted materials For sale by U.S. Geological Survey, Information Services, Box 25286, Federal Center, Denver, CO 80225; telephone 1-888-ASK-USGS; World Wide Web: http://www.usgs.gov/

Multiply By To obtain

Figure 6.—Iceland is a "hotspot" (see interpretive map of plate tectonics, on

emerges above sea level. This southeast-looking aerial view shows Krafla

front) and one of the few places where the global Mid-Oceanic Ridge system

Volcano, Iceland, erupting on September 8, 1977. Lava fountains spout from

a 900-m-long fissure—part of the spreading Mid-Atlantic Ridge—and feed

lava flows advancing over snow-covered ground. During this intermittent

eruption, lasting from 1975 to 1984, the fissure widened by 8 m.

MORE ABOUT THIS MAP

INTRODUCTION Our Earth is a dynamic planet, as clearly illustrated on the main map (on front) by its opography, over 1,500 volcanoes, 44,000 earthquakes, and 170 impact craters. These features largely reflect the movements of Earth's major tectonic plates and many smaller plates or fragments of plates (including *microplates*). Volcanic eruptions and earthquakes are awe-inspiring displays of the powerful forces of nature and can be extraordinarily destructive. On average, about 60 of Earth's 550 historically active volcanoes are in eruption each year. In 2004 alone, over 160 earthquakes were

THE DYNAMIC EARTH As the main map shows, earthquakes and volcanoes are not randomly scattered over it has been only in the past 40 years that a concept has emerged to satisfactorily link 1996), is now widely accepted and has revolutionized the earth sciences. Table 4 in the online version of this map (http://www.minerals.si.edu/minsci/tdpmap) lists some notable milestones and pioneers in the development of the plate tectonics theory. Earth's outermost layer (the relatively stiff and rocky lithosphere) is a mosaic of large tectonic plates that move relative to one another at speeds measured in tens of millimeters per year—or about the same rate as our fingernails grow. Plates are cold, dense, and strong enough to resist most large deformation. They average about 80 km thick, but are generally thicker under continents than under oceans. Plates are composed of Earth's relatively thin surface rind (the crust) and the topmost 75 km of its 2,900-km-thick mantle. Over 50 separate plates are recognized by some specialists (for example, Bird, 2003), but the 15 that we name cover more than 95 percent of Plates move on a viscous, slowly flowing layer of hotter, softer mantle (the asthenosphere). Plate movement represents the top of a large-scale circulation system convection)—driven by Earth's escaping heat—that extends deep into the mantle. Mantle flow is like the sluggish movement in a pot of thick soup boiling on a stove. Such flow transports the plates horizontally on Earth's surface. Where plates grind against each other, stresses can build up and be relieved intermittently when rocks break or slide along faults, causing earthquakes. Near some plate boundaries, molten rock (magma) can rise to the surface from as deep as many tens of kilometers and erupt to form volcanoes. Some plate boundaries cannot be narrowly defined, but instead are diffuse, encompassing broad areas (see interpretive map of plate tectonics Most deformation associated with plate movements is concentrated in the boundary zones between shifting plates, explaining why so many earthquakes and volcanoes are found along or near plate boundaries. Nevertheless, active volcanism and large earthquakes also can occur in plate interiors, which are not immune from plate tectonic

FEATURES OF THE MAP

Earth's topographic features are largely the expression of plate tectonics, modified by ocean surface from satellites. This mapping technique (satellite radar altimetry) involves the measurement of small undulations of the sea surface—tens of kilometers surface height mimic, and are proportional to, the actual topographic features of the sea floor. Satellite-radar data provide global coverage, but resolve only the larger seafloor features. Photographs or high-resolution topography are available for only a tiny fraction of 1 percent of the world's ocean floor. (See inset I for examples of sea-floor apping at various scales.)

The sea-floor topography shown on the main map was produced from satellite-radar

the sea-floor topography shown on the main map was produced from satellite-radar


the sea-floor topography shown on the main map was produced from satellite-radar

the sea-floor topography shown on the main map was produced from satellite-radar mapping of the sea surface, augmented in places by data obtained by ship-based acoustic (echo-sounding) techniques. Sea-floor topography is typically "visualized" as computer-generated, colored maps. In reality, however, the deep ocean floor is sunless, totally dark, unless artificially and briefly lit. Land-surface topography is obtained by using similar satellite technology, but here radar mapping from space gives a direct measure of surface features. Shading—as if the topographic images were illuminated by an artificial sun at 20° above the northwestern horizon—helps the visualization of A Mercator map projection is used, both for its familiarity and for ease of transferring information from other Mercator projection maps. This projection exaggerates the relative size of high-latitude areas, and we have omitted coverage beyond 72° N. and 70° S. on the main map. Polar projections in lower corners (65°–90°) complete the coverage of the planet at the equatorial scale of the main map.

Earthquakes are vibrational motions produced mostly by rupture of rock along faults. The most common measure of earthquake "size," based on the amount of seismic ground motion, is called *magnitude*. This concept was introduced in the mid-1930s by seismologist Charles F. Richter. He measured a seismic-wave characteristic called *implitude* (the height of the peak seismic wave recorded by standard seismographs at a standard distance from the earthquake source). Because peak amplitudes vary over such an enormous range among earthquakes, the Richter scale is logarithmic: a magnitude-6 earthquake has 10 times the peak amplitude and releases about 30 times more energy than a magnitude-5 earthquake. A magnitude-3 earthquake is about the smallest that can be felt by humans, and the largest ever recorded was 9.5. In general, the larger the magnitude, the larger the rupture area and movement along the fault. Small-magnitude earthquakes occur much more frequently than large-magnitude earthquakes (see earthquake explanation on front).

Man locations of parthquakes (anicanters) are determined from the precise arrival lap locations of earthquakes (epicenters) are determined from the precise arrival the principle of triangulation. Our ability to locate earthquake epicenters has greatly improved during the last decade because of sensitive digital seismic instruments and improved data processing. On the main map, modern accurate epicenters show that most earthquakes are closely clustered along plate boundaries. The most demanding test of earthquake-location accuracy is along oceanic plate boundaries that are typically distant from seismic stations on land. Comparison of the new earthquake locations with A small number of intraplate earthquakes are shown (as hexagons) on the main map despite their pre-1900 dates or failure to meet the precise location criteria of the main data set. These—as shown by notable earthquakes nos. 1, 4, and 5 (table 3)—are important reminders that devastating earthquakes also occur, albeit rarely, far from

Volcanoes are shown in four categories on the basis of their most recent known eruption in the past 10,000 years. Because repose intervals between eruptions can be thousands of years, and because the historical record in many parts of the world is only a few hundred years, we have made only minor graphical distinction between the map symbols for the first three categories. Thus, any one of them might erupt within our lifetimes. Remember, though, that most of Earth's volcanism occurs along the





Discoveries during the past decade allow us to show 30 more impact craters than we did on the 1994 edition of the map (Simkin and others, 1994). Still, the evidence of other impact craters has been destroyed or hidden by post-impact geologic processes; the presently known craters simply serve as a reminder of this cataclysmic process, particularly early in the history of the Earth-Moon system (see inset VI and timeline).

Divergent plate speeds, measured largely from separations of magnetic stripes at white numerals. Convergent plate motions (stubby arrows with numerals) are calculated from the same model. Thin arrows in plate interiors show less accurate "absolute" plate motions (over the deeper mantle).


This map is a joint product of the Volcano Hazards Program and the Earthquake the Smithsonian Institution, and the U.S. Naval Research Laboratory. Many institutions and individuals helped us in its preparation in important ways, most notably R.G. Bilham and E.R. Engdahl (University of Colorado); S.M. Carbotte

(Lamont-Doherty Earth Observatory); D.C. DeMets (University of Wisconsin); J Hasse (Naval Ice Center); M. Holzer (Chatham High School, N.J.); W.-Y. Jung (U.S. Naval Research Laboratory); J.R. Keith, J.E. Robinson, M.J. Rymer, S.P. Schilling Naval Research Laboratory); J.R. Keith, J.E. Robinson, M.J. Rymer, S.P. Schilling, and D.W. Scholl (all U.S. Geological Survey); and S. Stein (Northwestern University). Additional valuable help has been provided by: S. Aramaki, M. Beddoe, C.R. Bentley, S. Bhardwaj, G.P. Bird, S.C. Cande, M. Collier, M.-H. Cormier, D.J. Fornari, B.M. French, C. Gaina, L. Gordon, R.G. Gordon, M.C. Guffanti, J.K. Hall, R.N. Hey, D.R. Hutchinson, M. Jakobsson, O.B. James, A.C. Johnston, M.C. Kleinrock, R.D. Larter, R.A. Livermore, J.F. Luhr, K. Marks, T.J. McCoy, W.J Morgan, R.D. Müller, C.G. Newhall, E.A. Okal, G. Plafker, R.W. Purdey, W.E Rankin, P.A. Rona, P. Rossi, C.R. Scotese, A.K. Shah, J.S. Shelton, L.G. Siebert W.H.F. Smith, S.S. Sorensen, S. Steinthorsson, B. Taylor, W.R. Thatcher, E. Thurnau, and J.F. Vigil. We also express our appreciation to the many colleagues geoscience teachers, and students who provided thoughtful comments and helpful advice on how to improve the previous editions (1989, 1994) of this map and text.





American Geophysical Union.



2 Ma Huge eruption (2,500 km³ of magma) blanketed western U.S. with ash (>2 cm in California, 1,500 km away; see inset V).

540±90 Explosive eruption formed caldera, later filled by the sea; regional volcano observatory established after 1937 eruption.

1952 Seismograms of this well-recorded in a earthquake showed early evidence of slow, whole-earth violations.

1957 At M9.1, one of only five earthquakes in the magnitude 9 range, four in a 12-year period, since global recording began around 1895.

1960 Largest earthquake (M9.5) yet recorded, confirming whole-earth vibrations; triggered a giant Pacific-wide tsunami.

1964 Second largest recorded earthquake (M9.2) caused extensive soil failure in Anchorage area and widespread tsunami damage.

Within Nazca slab at 73-km depth, killing ~54,000, including 25,000 at Yungay, a town buried by an associated rock avalanche.

Devastated the city, causing the most fatalities for a 20th century earthquake—estimates range from 255,000 (official) to 655,000 (unofficial).

Rocked the Los Angeles basin; economic losses estimated to exceed \$20 billion, a record for U.S. earthquakes.

Deepest large-magnitude earthquake (M8.3 at 636 km), with shaking felt to Canada; study of this event greatly refined Earth's structure.


Major port city devastated: 5,500 dead, 310,000 homeless, and world record \$150 billion in earthquake and fire losses.

1640 B.C. Bronze Age caldera-forming eruption influenced decline of Minoan civilization; tsunami may have inspired biblical flood legends.
1500 B.C. First historically documented eruption; Europe's largest volcano, Etna has been frequently active since.
A.D. 79 Pompeii and Herculaneum buried; earliest known written account for any eruption, by Pliny the Younger.

~180 16,000 km² (15 percent of North Island) devastated; only a tranquil caldera lake now marks the eruption site.



2 Santorini (Greece)
3 Etna (Italy)
4 Vesuvius (Italy)
5 Taupo (New Zealand)



Foulger, G.R., Natland, J.H., Presnall, D.C., and Anderson, D.L., eds., 2005, Plates, plumes, and paradigms: Geological Society of America Special Paper 388, 881 p. French, B.M., 1998, Traces of catastrophe; A handbook of shock-metamorphic effects in terrestrial meteorite impact structures: Houston, Tex., Lunar and Planetary Institute, LPI Contribution No. 954, Gripp, A.E., and Gordon, R.G., 2002, Young tracks of hotspots and current plate velocities: Geophysical Journal International, v. 150, no. 2, p. 321–361. Hough, S.E., 2002, Earthshaking science; What we know (and don't know) about earthquakes: Princeton, Jakobsson, Martin, Grantz, Arthur, Kristoffersen, Yngve, and Macnab, Ron, 2003, Physiographic provinces of the Arctic Ocean seafloor: Geological Society of America Bulletin, v. 115, p. 1443–1455. Johnston, A.C., 1996, Seismic moment assessment of earthquakes in stable continental regions-II. Kearey, Philip, and Vine, F.J., 1996, Global tectonics (2d ed.): Oxford, Blackwell Science Ltd., 333 p. Kleinrock, M.C., and Humphris, S.E., 1996, Structural asymmetry of the TAG rift valley; Evidence from near-bottom survey for episodic spreading: Geophysical Research Letters, v. 23, no. 23, p. 3439–3442.

near-bottom survey for episodic spreading: Geophysical Research Letters, v. 23, no. 23, p. 3439–3442.

Lee, W.H.K., Kanamori, Hiroo, Jennings, P.C., and Kisslinger, Carl, eds., International handbook of earthquake and engineering seismology, Part A: Boston, Academic Press, 933 p.

Luhr, J.F., ed., 2003, Earth: New York, Dorling Kindersley, 520 p.

Palmer, A.R., 1989, The Earth has a history: Boulder, Colo., Geological Society of America, 20-minute videocassette with 7-p. supplemental teacher's manual.

Redfern, Ron, 2001, Origins; The evolution of continents, oceans, and life: Tulsa, University of Oklahoma Series GVP-3. (Available online at http://www.volcano.si.edu/world/ Sigurdsson, Haraldur, ed., 2000, Encyclopedia of volcanoes: San Diego, Academic Press, 1417 p. Stein, Seth, and Wysession, Michael, 2003, An introduction to seismology, earthquakes, and Earth structure: Malden, Mass., Blackwell Science, 498 p.






Figure 2.—Oblique view of the principal Hawaiian Islands and (the still submarine) Lōʻihi Volcano. Inset gives a closer view of three of the five volcanoes that form the Island of Hawai'i (historical lava flows are shown in red). The longest duration historical eruption on Kīlauea's east-rift zone at Pu'u 'Ō'ō (inset), which began in January 1983, continues unabated (as of spring 2006). View prepared by Joel E. Robinson (USGS).

PACIFIC PLATE The Hawaiian Hotspot Figure 3.—A schematic cut-away view along the island chain, showing the inferred mantle plume that has sustained the Hawaiian hotspot on the overriding Pacific plate. The geologic ages of the oldest volcano on each island are progressively older to the northwest, consistent with the hotspot model for the origin of the Hawaiian Ridge-Emperor Seamount Chain. View prepared by Joel E. Robinson (USGS).



active plate boundaries.

Many scientists attribute the Hawaiian and some other hotspots to narrow plumes of hot, but not molten, material rising through the mantle (fig. 3). Partial nelting of the mantle produces new magma that collects into blobs that rise through the overriding plate and ultimately erupt to form a new volcano on the sea floor. After many eruptions, the growing submarine volcano may emerge above sea level as an island volcano. Continued movement of the Pacific plate eventually carries each volcano away from the sustaining hotspot. Then, severed from their feeding magma sources, the eruptions ultimately cease. Even as a new volcano grows over the hotspot, it undergoes erosion. However, once eruptive activity stops, the volcano subsides as the plate cools and contracts, eventually sinking below sea level to form a flat-topped seamount. Recently active Hawaiian volcanoes—Kīlauea, Mauna Loa, and the present-day submarine but growing Lō'ihi (figs. 2, 3)—presumably still lie above, and are presently tapping, the Hawaiian hotspot. Midplate oceanic lavas are more fluid than those that build *stratovolcanoes* along convergent plate boundaries; they usually erupt nonexplosively, and some eruptions can last for decades (figs. 2, 4). Over geologic time, repeated outpourings of fluid lava, which can travel great distances from eruptive vents, form gently sloping shield volcanoes such as Hawaii's Mauna Loa (fig. 5). Intraplate volcanism also occurs in continental interiors. For example, the Yellowstone Volcano (Yellowstone National Park) has produced three cataclysmic eruptions (fig. 6)—each associated with caldera collapse—during the past 2 million years. When an explosive eruption expels magma from a subsurface reservoir, the overlying volcano may collapse into the resulting void, leaving a shallow depression, or caldera, in place of the more familiar conically shaped volcano. Ash-fall deposits from these huge eruptions have been mapped thousands of kilometers from their source calderas (fig. 6). The Yellowstone volcanic plateau lies at the northeastern end of the Snake River Plain, a zone of geologically young (<17 Ma) volcanism that slashes across the Rocky Mountains, a mountain belt composed primarily of much older rocks (2,790–65 Ma). The geologic ages of the volcanic centers of the Snake River Plain are progressively older to the southwest (fig. 7). This age progression has been interpreted as resulting from volcanism associated with the passage of the North America plate over a Yellowstone hotspot, presumably sustained by a longlived, relatively fixed, mantle plume. However, we emphasize that commonly held ideas such as rooting of thermal plumes deep in the mantle (>200 km) are topics of ongoing scientific debate. Yellowstone's most recent volcanic activity occurred about 70,000 years ago, but ground-deformation measurements indicate that the caldera is restless. The dynamics of its still-hot subsurface



gure 4.—A high lava fountain


nelicopter (circled) gives scale.


atting from the Pu'u 'Ō'ō vent on Kīlauea's east-rift zone in 1984;

Photograph by Mardie Lane (Hawaii


Mauna Loa, a classic shield volcano, as

viewed from the Hawaiian Volcano Observatory. Photograph by Robert I.






by more than 1,000 km.











million years ago (Ma)


,600 million years ago (Ma)

















Oldest megascopic algae



F Youngest lunar volcanism

Explosion of multicellular life





52.8° N. 159.5° E. 51.3° N. 175.8° W.

magmatic system are evident from its present-day spectacular expressions of

geothermal energy, including Earth's most active geyser system (fig. 8).