

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Medical Center				Ambulatory Care				Clinical Improvements			
		New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation
Bay Pines, FL	2,411.6	\$329	\$257	\$167	\$88	\$282	\$219	\$142	\$75	\$321	\$248	\$161	\$85
Gainesville, FL	2,052.6	\$280	\$219	\$142	\$75	\$240	\$187	\$121	\$64	\$273	\$211	\$137	\$72
Lake City, FL	2,052.6	\$280	\$219	\$142	\$75	\$240	\$187	\$121	\$64	\$273	\$211	\$137	\$72
Miami, FL	2,310.7	\$315	\$246	\$160	\$84	\$270	\$210	\$137	\$72	\$307	\$238	\$155	\$81
Orlando, FL	1,835.8	\$251	\$196	\$127	\$67	\$215	\$167	\$108	\$57	\$244	\$189	\$123	\$65
San Juan, PR	2,404.6	\$328	\$256	\$166	\$87	\$281	\$219	\$142	\$75	\$320	\$248	\$161	\$84
Tampa, FL	2,411.6	\$329	\$257	\$167	\$88	\$282	\$219	\$142	\$75	\$321	\$248	\$161	\$85
West Palm Beach, FL	2,047.8	\$279	\$218	\$142	\$74	\$239	\$186	\$121	\$64	\$272	\$211	\$137	\$72
		\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market condition

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

Allow additional funds for known adverse sub-surface conditions, seismic, and hurricane loading.

Allow additional funds for special construction requirements such as: phasing; unusual site constraints; tie-in to existing structure; shoring; vertical expansion.

Allow additional funds for compliance with VA Physical Security Standards and Sustainability Guidelines for 5' outside of Building Envelope. Funds are included for Building Envelope.

Sitework and site utility costs will vary greatly for each project. Early identification of requirements is critical.

For conceptual estimates on projects up to \$25M, 15% added building cost is a reasonable rule of thumb for sitework and site utilities. Factor may decrease to 10% for larger projects.

Ambulatory Care is considered a "9 to 5" soft clinic - few heavy labs, diagnostic areas, or beds. Functions consist of those found in exam rooms, minor surgery, small radiology suites, clinics, etc.

Clinical Improvements include intensive clinical space - diagnostics, labs, surgical suites. These represent the most expensive departments.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Bed Tower Replacement				Domiciliary				Stand Alone Outpatient Clinic			
		New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation
Bay Pines, FL	2,411.6	\$340	\$272	\$177	\$93	\$197	\$135	\$88	\$46	\$272	\$209	\$136	\$71
Gainesville, FL	2,052.6	\$289	\$231	\$150	\$79	\$168	\$115	\$75	\$39	\$231	\$178	\$116	\$61
Lake City, FL	2,052.6	\$289	\$231	\$150	\$79	\$168	\$115	\$75	\$39	\$231	\$178	\$116	\$61
Miami, FL	2,310.7	\$326	\$260	\$169	\$89	\$189	\$130	\$84	\$44	\$260	\$200	\$130	\$68
Orlando, FL	1,835.8	\$259	\$207	\$135	\$71	\$150	\$103	\$67	\$35	\$207	\$159	\$103	\$54
San Juan, PR	2,404.6	\$339	\$271	\$176	\$92	\$196	\$135	\$88	\$46	\$271	\$209	\$136	\$71
Tampa, FL	2,411.6	\$340	\$272	\$177	\$93	\$197	\$135	\$88	\$46	\$272	\$209	\$136	\$71
West Palm Beach, FL	2,047.8	\$289	\$231	\$150	\$79	\$167	\$115	\$75	\$39	\$231	\$178	\$115	\$61
		\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market condition;

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

Allow additional funds for known adverse sub-surface conditions, seismic, and hurricane loading.

Allow additional funds for special construction requirements such as: phasing; unusual site constraints; tie-in to existing structure; shoring; vertical expansion.

Allow additional funds for compliance with VA Physical Security Standards and Sustainability Guidelines for 5' outside of Building Envelope. Funds are included for Building Envelope.

Sitework and site utility costs will vary greatly for each project. Early identification of requirements is critical.

For conceptual estimates on projects up to \$25M, 15% added building cost is a reasonable rule of thumb for sitework and site utilities. Factor may decrease to 10% for larger projects.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Acute Psychiatric				Mental Health				Poly Trauma			
		New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation
Bay Pines, FL	2,411.6	\$337	\$269	\$175	\$92	\$279	\$217	\$141	\$74	\$321	\$253	\$165	\$86
Gainesville, FL	2,052.6	\$287	\$229	\$149	\$78	\$237	\$185	\$120	\$63	\$274	\$216	\$140	\$74
Lake City, FL	2,052.6	\$287	\$229	\$149	\$78	\$237	\$185	\$120	\$63	\$274	\$216	\$140	\$74
Miami, FL	2,310.7	\$323	\$258	\$168	\$88	\$267	\$208	\$135	\$71	\$308	\$243	\$158	\$83
Orlando, FL	1,835.8	\$257	\$205	\$133	\$70	\$212	\$165	\$108	\$56	\$245	\$193	\$125	\$66
San Juan, PR	2,404.6	\$337	\$269	\$175	\$92	\$278	\$217	\$141	\$74	\$321	\$253	\$164	\$86
Tampa, FL	2,411.6	\$337	\$269	\$175	\$92	\$279	\$217	\$141	\$74	\$321	\$253	\$165	\$86
West Palm Beach, FL	2,047.8	\$287	\$229	\$149	\$78	\$237	\$185	\$120	\$63	\$273	\$215	\$140	\$73
		\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market condition

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

Allow additional funds for known adverse sub-surface conditions, seismic, and hurricane loading.

Allow additional funds for special construction requirements such as: phasing; unusual site constraints; tie-in to existing structure; shoring; vertical expansion.

Allow additional funds for compliance with VA Physical Security Standards and Sustainability Guidelines for 5' outside of Building Envelope. Funds are included for Building Envelope.

Sitework and site utility costs will vary greatly for each project. Early identification of requirements is critical.

For conceptual estimates on projects up to \$25M, 15% added building cost is a reasonable rule of thumb for sitework and site utilities. Factor may decrease to 10% for larger projects.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Spinal Cord Injury (SCI)				Nursing Home Care Unit (NHCU)				Blind Rehabilitation			
		New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation
Bay Pines, FL	2,411.6	\$294	\$239	\$155	\$81	\$269	\$214	\$139	\$73	\$292	\$223	\$145	\$76
Gainesville, FL	2,052.6	\$250	\$203	\$132	\$69	\$229	\$182	\$118	\$62	\$248	\$190	\$123	\$65
Lake City, FL	2,052.6	\$250	\$203	\$132	\$69	\$229	\$182	\$118	\$62	\$248	\$190	\$123	\$65
Miami, FL	2,310.7	\$281	\$229	\$149	\$78	\$258	\$205	\$133	\$70	\$280	\$213	\$139	\$73
Orlando, FL	1,835.8	\$224	\$182	\$118	\$62	\$205	\$163	\$106	\$56	\$222	\$170	\$110	\$58
San Juan, PR	2,404.6	\$293	\$238	\$155	\$81	\$268	\$213	\$139	\$73	\$291	\$222	\$144	\$76
Tampa, FL	2,411.6	\$294	\$239	\$155	\$81	\$269	\$214	\$139	\$73	\$292	\$223	\$145	\$76
West Palm Beach, FL	2,047.8	\$249	\$203	\$132	\$69	\$229	\$182	\$118	\$62	\$248	\$189	\$123	\$65
		\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market condition;

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

Allow additional funds for known adverse sub-surface conditions, seismic, and hurricane loading.

Allow additional funds for special construction requirements such as: phasing; unusual site constraints; tie-in to existing structure; shoring; vertical expansion.

Allow additional funds for compliance with VA Physical Security Standards and Sustainability Guidelines for 5' outside of Building Envelope. Funds are included for Building Envelope.

Sitework and site utility costs will vary greatly for each project. Early identification of requirements is critical.

For conceptual estimates on projects up to \$25M, 15% added building cost is a reasonable rule of thumb for sitework and site utilities. Factor may decrease to 10% for larger projects.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Research - Heavy; Wetlabs & Animals				Surgery and PACU				Research - Normal; Mix Heavy & Offices			
		New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation
Bay Pines, FL	2,411.6	\$510	\$433	\$282	\$148	\$452	\$370	\$241	\$126	\$368	\$312	\$203	\$106
Gainesville, FL	2,052.6	\$434	\$369	\$240	\$126	\$385	\$315	\$205	\$108	\$313	\$266	\$173	\$91
Lake City, FL	2,052.6	\$434	\$369	\$240	\$126	\$385	\$315	\$205	\$108	\$313	\$266	\$173	\$91
Miami, FL	2,310.7	\$488	\$415	\$270	\$142	\$433	\$355	\$231	\$121	\$352	\$299	\$194	\$102
Orlando, FL	1,835.8	\$388	\$330	\$214	\$113	\$344	\$282	\$183	\$96	\$280	\$238	\$154	\$81
San Juan, PR	2,404.6	\$508	\$432	\$281	\$147	\$451	\$369	\$240	\$126	\$367	\$311	\$202	\$106
Tampa, FL	2,411.6	\$510	\$433	\$282	\$148	\$452	\$370	\$241	\$126	\$368	\$312	\$203	\$106
West Palm Beach, FL	2,047.8	\$433	\$368	\$239	\$126	\$384	\$314	\$204	\$107	\$312	\$265	\$172	\$90
		\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market condition

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

Allow additional funds for known adverse sub-surface conditions, seismic, and hurricane loading.

Allow additional funds for special construction requirements such as: phasing; unusual site constraints; tie-in to existing structure; shoring; vertical expansion.

Allow additional funds for compliance with VA Physical Security Standards and Sustainability Guidelines for 5' outside of Building Envelope. Funds are included for Building Envelope.

Sitework and site utility costs will vary greatly for each project. Early identification of requirements is critical.

For conceptual estimates on projects up to \$25M, 15% added building cost is a reasonable rule of thumb for sitework and site utilities. Factor may decrease to 10% for larger projects.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Administration Space; Housed in Main Hospital				Parking Garage				Surface Parking - Priced Per Parking Space			
		New	Total Renovation	Medium Renovation	Light Renovation	New	Total Renovation	Medium Renovation	Light Renovation	New Space			
Bay Pines, FL	2,411.6	\$207	\$162	\$105	\$55	\$48	\$21	\$14	\$7	\$2,698	\$0	\$0	\$0
Gainesville, FL	2,052.6	\$177	\$138	\$90	\$47	\$41	\$18	\$12	\$6	\$2,296	\$0	\$0	\$0
Lake City, FL	2,052.6	\$177	\$138	\$90	\$47	\$41	\$18	\$12	\$6	\$2,296	\$0	\$0	\$0
Miami, FL	2,310.7	\$199	\$155	\$101	\$53	\$46	\$20	\$13	\$7	\$2,585	\$0	\$0	\$0
Orlando, FL	1,835.8	\$158	\$123	\$80	\$42	\$36	\$16	\$11	\$6	\$2,054	\$0	\$0	\$0
San Juan, PR	2,404.6	\$207	\$162	\$105	\$55	\$48	\$21	\$14	\$7	\$2,690	\$0	\$0	\$0
Tampa, FL	2,411.6	\$207	\$162	\$105	\$55	\$48	\$21	\$14	\$7	\$2,698	\$0	\$0	\$0
West Palm Beach, FL	2,047.8	\$176	\$138	\$90	\$47	\$41	\$18	\$12	\$6	\$2,291	\$0	\$0	\$0
		\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market condition:

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

Allow additional funds for known adverse sub-surface conditions, seismic, and hurricane loading.

Allow additional funds for special construction requirements such as: phasing; unusual site constraints; tie-in to existing structure; shoring; vertical expansion.

Allow additional funds for compliance with VA Physical Security Standards and Sustainability Guidelines for 5' outside of Building Envelope. Funds are included for Building Envelope.

Sitework and site utility costs will vary greatly for each project. Early identification of requirements is critical.

For conceptual estimates on projects up to \$25M, 15% added building cost is a reasonable rule of thumb for sitework and site utilities. Factor may decrease to 10% for larger projects.

Parking garage costs are for above grade parking. Allow additional funds for any levels below grade.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

**CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT
USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING**

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Warehouses -w/ Offices											
		New	Total Renovation	Medium Renovation	Light Renovation								
Bay Pines, FL	2,411.6	\$162	\$117	\$76	\$40	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Gainesville, FL	2,052.6	\$138	\$99	\$65	\$34	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Lake City, FL	2,052.6	\$138	\$99	\$65	\$34	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Miami, FL	2,310.7	\$155	\$112	\$73	\$38	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Orlando, FL	1,835.8	\$123	\$89	\$58	\$30	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
San Juan, PR	2,404.6	\$162	\$117	\$76	\$40	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Tampa, FL	2,411.6	\$162	\$117	\$76	\$40	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
West Palm Beach, FL	2,047.8	\$138	\$99	\$65	\$34	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
		\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market condition;

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

Allow additional funds for known adverse sub-surface conditions, seismic, and hurricane loading.

Allow additional funds for special construction requirements such as: phasing; unusual site constraints; tie-in to existing structure; shoring; vertical expansion.

Allow additional funds for compliance with VA Physical Security Standards and Sustainability Guidelines for 5' outside of Building Envelope. Funds are included for Building Envelope.

Sitework and site utility costs will vary greatly for each project. Early identification of requirements is critical.

For conceptual estimates on projects up to \$25M, 15% added building cost is a reasonable rule of thumb for sitework and site utilities. Factor may decrease to 10% for larger projects.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Demolition Cost for an Existing Building				Leased Space - Need To Provide Specific Build-Out				Operating and Mothball Costs			
		Demolition Cost Only	Haul & Dump			Yearly Rate Per Square Foot				"Full" Operational Costs	Adjacent Mothball Costs	Alone Mothball Costs	
Bay Pines, FL	2,411.6	\$8.73	\$9.90	\$0.00	\$0.00	\$31.04	\$0.00	\$0.00	\$0.00	\$19.22	\$11.22	\$5.16	\$0.00
Gainesville, FL	2,052.6	\$7.43	\$8.43	\$0.00	\$0.00	\$26.42	\$0.00	\$0.00	\$0.00	\$16.36	\$9.55	\$4.39	\$0.00
Lake City, FL	2,052.6	\$7.43	\$8.43	\$0.00	\$0.00	\$26.42	\$0.00	\$0.00	\$0.00	\$16.36	\$9.55	\$4.39	\$0.00
Miami, FL	2,310.7	\$8.36	\$9.49	\$0.00	\$0.00	\$29.74	\$0.00	\$0.00	\$0.00	\$18.41	\$10.75	\$4.94	\$0.00
Orlando, FL	1,835.8	\$6.64	\$7.54	\$0.00	\$0.00	\$23.63	\$0.00	\$0.00	\$0.00	\$14.63	\$8.54	\$3.93	\$0.00
San Juan, PR	2,404.6	\$8.70	\$9.88	\$0.00	\$0.00	\$30.95	\$0.00	\$0.00	\$0.00	\$19.16	\$11.18	\$5.15	\$0.00
Tampa, FL	2,411.6	\$8.73	\$9.90	\$0.00	\$0.00	\$31.04	\$0.00	\$0.00	\$0.00	\$19.22	\$11.22	\$5.16	\$0.00
West Palm Beach, FL	2,047.8	\$7.41	\$8.41	\$0.00	\$0.00	\$26.36	\$0.00	\$0.00	\$0.00	\$16.32	\$9.52	\$4.38	\$0.00
		\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market conditions

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

"Demolition Costs Only" is based on razing the entire structure and disposing of the waste material on-site. Haul & Dump is not included. Hazardous material abatement is not included.

"Haul & Dump" includes cost for a 20 mile haul and the appropriate dump fees for construction materials. Disposal of hazardous materials is not included. Additional funds should be included for known adverse conditions, length of haul, inflated dump fees, closed dump and refuge facilities

To calculate savings for mothballed structures, subtract which type of "Mothballing" is being utilized (Adjacent or Stand Alone) from the "Full" Operating Costs. The "Full" Operating Costs include: Electric, water, gas, sewage, major systems maintenance, building shell maintenance, janitorial, and security

Based on the type of "Mothballing" to be used, percentages have been utilized to account for maintaining the integrity of the building envelope, maintaining non-freezing conditions for sprinklers & utilities, maintenance, security, and ensuring JHCO compliance

Leasing yearly rates only includes: land, site improvements, building shell, taxes, utilities, insurance, shell and outside maintenance -

Similar to a sole occupancy of a "Spec" building - HOUSEKEEPING COSTS ARE NOT INCLUDED - Assumes normal operating days and hours - NOT 24/7

Lease cost does not include initial build out (tenant improvement) of space for the specific function. To calculate build out cost, use "Total Renovation" cost for the specific building type.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Roof Replacement				Modernize Restrooms for UFAS/ADA				Fire Alarms			
		EDPM	Built Up	Shingles	Metal	Total Renovation				New	Total Renovation		
Bay Pines, FL	2,411.6	\$8.34	\$7.96	\$5.11	\$6.72	\$208.30	\$0.00	\$0.00	\$0.00	\$7.17	\$8.43	\$0.00	\$0.00
Gainesville, FL	2,052.6	\$7.10	\$6.78	\$4.35	\$5.72	\$177.30	\$0.00	\$0.00	\$0.00	\$6.10	\$7.18	\$0.00	\$0.00
Lake City, FL	2,052.6	\$7.10	\$6.78	\$4.35	\$5.72	\$177.30	\$0.00	\$0.00	\$0.00	\$6.10	\$7.18	\$0.00	\$0.00
Miami, FL	2,310.7	\$8.00	\$7.63	\$4.90	\$6.44	\$199.59	\$0.00	\$0.00	\$0.00	\$6.87	\$8.08	\$0.00	\$0.00
Orlando, FL	1,835.8	\$6.35	\$6.06	\$3.89	\$5.12	\$158.57	\$0.00	\$0.00	\$0.00	\$5.46	\$6.42	\$0.00	\$0.00
San Juan, PR	2,404.6	\$8.32	\$7.94	\$5.10	\$6.70	\$207.70	\$0.00	\$0.00	\$0.00	\$7.15	\$8.41	\$0.00	\$0.00
Tampa, FL	2,411.6	\$8.34	\$7.96	\$5.11	\$6.72	\$208.30	\$0.00	\$0.00	\$0.00	\$7.17	\$8.43	\$0.00	\$0.00
West Palm Beach, FL	2,047.8	\$7.09	\$6.76	\$4.34	\$5.71	\$176.88	\$0.00	\$0.00	\$0.00	\$6.09	\$7.16	\$0.00	\$0.00
		\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00

NOTES:

Unit costs have been updated using the most current projects and VA/PACES, to reflect the dynamics of the delivery of healthcare

Cost shown are averages to be used for establishing an order of magnitude. Actual costs will vary depending on complexity and unique conditions of each project.

Costs shown are for building construction only. Additional costs to be considered include: Pre-Design allowance; escalation to contract award date; construction contingencies; technical services; impact costs; utility agreements; site improvements; site utilities; CM fees; and current local market condition;

Costs are as of the time of BOECKH Index period shown. Adjust to latest available BOECKH Index. Multiply unit costs by the current BOECKH Index and divide by the index shown in table.

Roof replacement costs do not include asbestos removal or disposal. Verify presence of asbestos in existing roof and include additional funds as necessary.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

CURRENT BUILDING ONLY CONSTRUCTION UNIT COST PER SQUARE FOOT

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1B)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location		Escalation Rates				Escalation Rates				Escalation Rates			
		2,009	2,010	2,011	2,012	2,013	2,014	2,015	2,016				
Bay Pines, FL	2,411.6	5.00%	5.00%	6.00%	6.00%	5.00%	5.00%	5.00%	5.00%				
Gainesville, FL	2,052.6	5.00%	5.00%	6.00%	6.00%	5.00%	5.00%	5.00%	5.00%				
Lake City, FL	2,052.6	5.00%	5.00%	6.00%	6.00%	5.00%	5.00%	5.00%	5.00%				
Miami, FL	2,310.7	5.00%	5.00%	6.00%	6.00%	5.00%	5.00%	5.00%	5.00%				
Orlando, FL	1,835.8	5.00%	5.00%	6.00%	6.00%	5.00%	5.00%	5.00%	5.00%				
San Juan, PR	2,404.6	6.00%	6.00%	6.00%	6.00%	5.00%	5.00%	5.00%	7.00%				
Tampa, FL	2,411.6	5.00%	5.00%	6.00%	6.00%	5.00%	5.00%	5.00%	5.00%				
West Palm Beach, FL	2,047.8	5.00%	5.00%	6.00%	6.00%	5.00%	5.00%	5.00%	5.00%				

NOTES: Escalation rates sheet has been updated on January 7, 2009 per current market/economic conditions.

When using the above Escalation Rates over a number of years. These will need to be compounded to show true escalation.

MARKET CONDITIONS:

San Juan, PR is experiencing extensive labor shortage and material shipping costs are higher than normal - end result is the need to add 35% to all construction cost for the time being.

The entire Gulf Coast region has been devastated by a rash of hurricanes for consecutive years, this has resulted in a 10% premium the estimator needs to add this premium to all current costs, building only, site, roads, utilities, etc...

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.

VISN COSTING GUIDE - BUILDING TYPE

VISN 8: SUNSHINE Veterans Healthcare Network

RELATIVE COST FACTOR COMPARISONS BETWEEN VAMCs

USE FOR STRATEGIC PLANNING PURPOSES ONLY - NOT FOR BUDGETING

PREPARED BY: Office of Construction & Facilities Management Cost Estimating & A/E Evaluation Service (00CFM1)

Date Prepared: July 15, 2008

Index Basis: Boeckh Index = MAY-JUN 2008

Location	Boeckh Indexes	Cost Factor	EXPLANATION
Bay Pines, FL	2,411.6	1.00	Example: San Juan, PR is 1.18 higher than West Palm Beach, FL.
Gainesville, FL	2,052.6	0.85	To calculate, use San Juan, PR's factor of 1.00
Lake City, FL	2,052.6	0.85	and divide West Palm Beach, FL's factor of 0.85 into it.
Miami, FL	2,310.7	0.96	That is $1.00/0.85 = 1.18$.
Orlando, FL	1,835.8	0.76	
San Juan, PR	2,404.6	1.00	If one dollar (\$1.00) was spent in West Palm Beach, FL
Tampa, FL	2,411.6	1.00	then to get the equivalent building in San Juan, PR
West Palm Beach, FL	2,047.8	0.85	one dollar and eighteen cents (\$1.18) would be required.
		0.00	
		0.00	Example: Gainesville, FL is 0.87 of Tampa, FL.
		0.00	This is calculated by dividing Gainesville, FL's cost factor of 0.85
		0.00	by Tampa, FL's cost factor of 1.00 or $0.85/1.00 = 0.86$.
		0.00	That means that for every dollar (\$1.00) spent in Tampa, FL
		0.00	it would cost eighty-six cents (\$0.86)
		0.00	for an equivalent building in Gainesville, FL.
		0.00	
		0.00	These relative cost factors are based on
		0.00	the Boeckh Indexes for MAY-JUN 2008,
		0.00	and are useful to obtain quick rough ideas of
		0.00	probable costs relative from one city to another.
		0.00	
		0.00	REMINDER: Each project is unique.
		0.00	This document - for strategic planning only

In addition, local economic market conditions can significantly impact costs.

For additional assistance, contact Bob Smoot (00CFM1B) at bob.smoot@va.gov or at 202-461-8220.