

NASA Ames Arc Jet Complex Overview



Chuck Smith, Chief
SPACE TECHNOLOGY DIVISION

George Raiche, Chief


Scott Eddlemon, Deputy Chief

Imelda Terrazas-Salinas, Lead Test Engineer

John Balboni, Chief Engineer


Jim Blount, Jacobs-Sierra Lobo Site Manager
THERMOPHYSICS FACILITIES BRANCH

NASA Entry Vehicles/Missions Supported by Ames Arc Jets




Rationale for Arc Jet Testing

- **R&D:** *provide critical data for the research and development of thermal protection (TPS) materials*



PAET



NASP



SHARP B1 & B2



X-33



FALCON/CAV



X-37

- **Flight Qualification/Sustaining Engineering:** *qualify/certify TPS materials and processes for National Programs*




APOLLO



SPACE SHUTTLE



VIKING



GALILEO




MARS
PATHFINDER



MER



Orion




PIONEER-VENUS



MAGELLAN



STARDUST




PHOENIX

- **Instrumentation:** *Develop surface and in-depth instruments and sensors*

- **Space Ops:** *Support TPS damage assessment and verification of repair techniques for crewed spacecraft*



Stagnation Enthalpy and Flow Duration Domains for Hypervelocity Simulation Facilities



Comparison of TPS Facility Types by Capability

| <p>THERMAL PROTECTION SYSTEMS</p> <p>Test Facility Type vs. Capability</p> | Heat Flux | Convective-Radiative Coupling | Gas Chemical Physics | Pressure | Aerodynamic Shear | Mass Transfer | Test Time |
|--|-----------|-------------------------------|----------------------|----------|-------------------|---------------|-----------|
| Arc Jets | F | | F | F | p | F | F |
| Combustion Facilities | p | | p | p | p | F | F |
| Radiant Lamps | F | | | | | | F |
| Laser | F | | | | | | F |
| Torch | p | | p | | | | F |
| Furnace | | | p | | | | F |


KEY



Full Capability




Partial Capability




Arc Jet Schematic

Objective: Simulate entry heating in a ground-test facility

Goal: Verify a thermal protection material/system design before flight; support continuing engineering during operations




Method: Heat a test gas (air) to plasma temperatures by an electric arc, then accelerate into a vacuum chamber and onto a stationary test article



Arc Jet Facility Components

EACH ARC JET LEG IS SUPPORTED BY COMMON FACILITY INFRASTRUCTURE




Arc Jet Facility Overview

Power supply: 150 MW/100 MW continuous
Steam Vacuum System: 10 lbs/sec, 0.1 psi
Steam Generator: 250 000 lbs/hr
Approximately 1.5 mi pipe/ductwork

Not pictured:

- Arc heater coolant circulation: 12 500 gpm
- High pressure air storage; 1.2M CF
- Independent 20 MW power supply
- Control and isolation systems




FOUR ACTIVE TEST LEGS; ONE SET OF SHARED UTILITIES



Ames Arc Jet Legs

Aerodynamic Heating Facility
20 MW - TPS
Free Jet Testing





Interaction Heating Facility
60 MW - TPS Free Jet and Panel Testing



Panel Test Facility
20 MW - TPS Panel Testing



2"x9" Turbulent Flow Duct
20 MW - TPS Panel Testing



Ames Arc Jet FOMs


| Facility | Gas | Input Power (MW) | Type of Test Article | Nozzle Exit (inches) | Mach Number | Bulk Enthalpy (Btu/lb _m) | Surface Pressure (atm) | Convective Heating Rates* (Btu/ft ² -sec) |
|---------------------------|-----------------------|------------------|-----------------------------------|---|--------------|--------------------------------------|------------------------------------|--|
| AHF | Air N ₂ | 20 | Stagnation Point, Inclined | Conical 12, 18, 24, 30, 36 ∅ | 4-12 | 500 to 14,000 | 0.005 to 0.125, 0.001 | 20 to 225, 0.05 to 22 |
| AHF/Huels | Air N ₂ | 20 | Stagnation Point, Inclined | Conical 12, 18, 24, 30, 36 ∅ | 4-12 | 1,500 to 4,500 | 0.02 to 0.3 | 20 to 225 |
| IHF | Air | 60 | Stagnation Point, Inclined, Panel | Conical 6,13,21,30,41 ∅ Semi-elliptical 8 x 32 | < 7.5 5.5 | 3,000 to 20,000 | 0.010 to 1.2, 0.0001 to 0.02 | 50 to 1500, 0.5 to 45 |
| PTF | Air | 20 | Panel | Semielliptical 4 x 17 | 5.5 | 3,000 to 15,000 | 0.0006 to 0.05 | 0.5 to 30 |
| Turbulent Flow Duct (2x9) | Air N ₂ | 12 | Panel | 2 x 9 | 3.5 | 1,300 to 4,000 | 0.02 to 0.15 | 2 to 60 |

Arc Jet capabilities at Ames Research Center (US customary units)


*Heating rate is a cold wall, fully catalytic value on a 4-inch diameter hemisphere.



Overview of Arc Jet Design Considerations



DC Power Supplies




- **Direct grid connection, 138 kV**
- **Two continuous DC rectifier power supplies 20 MW and 150 MW**
- **Typical output: 2.4 kA @ 6 kV (20 MW)
6 kA @ 7.2 kV (60 MW)**
- **Interlocked access and distribution switching allows single facility control/operation from multiple control stations/test bays**
- **150 MW supply: three transformers, five operational rectifier modules**
- **Dedicated on-site support staff; widely respected experts**
- **Transformers are “original” equipment (mid-1970s)**
- **Recent CoF upgrades to rectifiers and expanded control monitoring**



Steam Vacuum System

- Vacuum for the Arc Jet complex is created by a five stage steam ejector pumping system Flow rates at plenums: 100 μHg @ 0.5 lb/sec; 5000 μHg @ 10 lb/s
- Steam Generator (Boiler)
 - Babcox and Wilcox M-type naval boiler recovered from USS Helena (CA-75; C. 1945; fabricated 1943)
 - Converted from diesel to natural gas burners at Ames
 - Ejection system: 5-stage steam jet system, 11 ejectors
 - 253,000 lb/hr capacity, 634 psig max, typically throttled to 300 psi
 - Annual inspection by National Board / CA State Inspector
- Pollution Control System scrubs effluents from Arc Jet exhaust prior to atmospheric release; compliant with all local regulations



ARC Arc Jet Facility Statistics

| FY04 | | | | | | | | | | STARTS |
|-----------------------|------------|-----------------------|------------|------------------------------|------------|------------|-----------------------|--------------|------|--------|
| CHARGED SHIFT DAYS | | DAYS POSSIBLE | | SCHD/STBY/RUN DAYS AVAILABLE | | UNSCH DOWN | | AVAILABILITY | | |
| 2X9 | 0 | 2X9 | 217 | 2X9 | 217 | 0 | 2X9 | | 1.00 | 310 |
| AHF | 67 | AHF | 218 | AHF | 207 | 11 | AHF | | 0.95 | |
| IHF | 118 | IHF | 220 | IHF | 207 | 13 | IHF | | 0.94 | |
| PTF | 10 | PTF | 215 | PTF | 215 | 0 | PTF | | 1.00 | |
| TOTAL TO DATE: | 195 | TOTAL TO DATE: | 882 | TOTAL TO DATE: | 858 | 24 | TOTAL TO DATE: | 0.97 | | |

| FY05 | | | | | | | | | | STARTS |
|-----------------------|------------|-----------------------|------------|------------------------------|------------|------------|-----------------------|--------------|------|--------|
| CHARGED SHIFT DAYS | | DAYS POSSIBLE | | SCHD/STBY/RUN DAYS AVAILABLE | | UNSCH DOWN | | AVAILABILITY | | |
| 2X9 | 0 | 2X9 | 227 | 2X9 | 192 | 0 | 2X9 | | 1.00 | 453 |
| AHF | 126 | AHF | 227 | AHF | 213 | 14 | AHF | | 0.94 | |
| IHF | 143 | IHF | 230 | IHF | 202 | 21 | IHF | | 0.91 | |
| PTF | 1 | PTF | 227 | PTF | 227 | 0 | PTF | | 1.00 | |
| TOTAL TO DATE: | 270 | TOTAL TO DATE: | 911 | TOTAL TO DATE: | 834 | 35 | TOTAL TO DATE: | 0.96 | | |

| FY06 | | | | | | | | | | STARTS |
|-----------------------|------------|-----------------------|------------|------------------------------|------------|------------|-----------------------|--------------|------|--------|
| CHARGED SHIFT DAYS | | DAYS POSSIBLE | | SCHD/STBY/RUN DAYS AVAILABLE | | UNSCH DOWN | | AVAILABILITY | | |
| 2X9 | 8 | 2X9 | 62 | 2X9 | 27 | 0 | 2X9 | | 1.00 | 331 |
| AHF | 35 | AHF | 215 | AHF | 201 | 0 | AHF | | 1.00 | |
| IHF | 114 | IHF | 210 | IHF | 145 | 39 | IHF | | 0.79 | |
| PTF | 26 | PTF | 197 | PTF | 185 | 12 | PTF | | 0.94 | |
| TOTAL TO DATE: | 183 | TOTAL TO DATE: | 684 | TOTAL TO DATE: | 558 | 51 | TOTAL TO DATE: | 0.92 | | |

| FY07 | | | | | | | | | | STARTS |
|-----------------------|------------|-----------------------|------------|------------------------------|------------|------------|-----------------------|--------------|------|--------|
| CHARGED SHIFT DAYS | | DAYS POSSIBLE | | SCHD/STBY/RUN DAYS AVAILABLE | | UNSCH DOWN | | AVAILABILITY | | |
| 2X9 | 19 | 2X9 | 225 | 2X9 | 158 | 8 | 2X9 | | 0.95 | 429 |
| AHF | 96 | AHF | 225 | AHF | 206 | 14 | AHF | | 0.94 | |
| IHF | 96 | IHF | 225 | IHF | 113 | 46 | IHF | | 0.71 | |
| PTF | 37 | PTF | 225 | PTF | 181 | 8 | PTF | | 0.96 | |
| TOTAL TO DATE: | 248 | TOTAL TO DATE: | 900 | TOTAL TO DATE: | 658 | 76 | TOTAL TO DATE: | 0.90 | | |

| | Starts/ year | Models/ year | Injections/ year | Average OD/yr | Models/ OD | Insertions/ OD |
|------------------|--------------|--------------|------------------|---------------|------------|----------------|
| AHF | 120 | 161 | 440 | 81 | 1.98 | 5.43 |
| IHF | 230 | 224 | 414 | 117 | 1.9 | 3.51 |
| AHF + IHF | 350 | 385 | 858 | 198 | | |
| All legs | 391 | | | 224 | | |

