

 \Box

Ö

DATE

DESCRIPTION

SHEET TITLE:

EXISTING PARTIAL FLOOR
PLAN - DEMOLITION

DRAWING SCALE:

1/4" = 1'- 0"

32217014

PROJECT NUMBER:

CHECKED BY:

GR

DATE:

10/25/07

SD

10/25/07

SEAL:

ineering Services Street NW, Ste 300 ington, DC 20006

 \Box

GREENVILLE, NC TRANSMITTING STATION SITE B

Task Order 14 100% CONTRACT DRAWINGS

KEYPLAN:

LOW VOLTAGE
SWITCHBOARDS
REPLACEMENT

4

REMOVE GE DISTRIBUTION BOARDS PARTS 1, 2, & 3 AND AUXILIARY SWITCHBOARD. REMOVE SWITCHBOARDS PARTS 1, 2, & 3 OFFSITE.

CONDUCTORS INSIDE SWITCHBOARD TO REMAIN FOR CONNECTION TO NEW EQUIPMENT. REMOVE EXISTING UPS AND BATTERY CABINET COMPLETELY. DEMOLISH CONDUIT AND WIRE BACK TO SOURCE. TURN OVER UPS, BATTERY CABINET AND AUXILIARY SWITCHBOARD TO GOVERNMENT.

REPAIR FLOOR AND TRENCH UNDER AUXILIARY SWITCHBOARD TO MATCH EXISTING.

3 2

DEMOLITION NOTES

SEE E-002 FOR ELECTRICAL ABBREVIATIONS, SYMBOLS AND ADDITIONAL INFORMATION.

GENERAL NOTES

