**Commission Briefing on GSI-191** 

### Industry Perspectives on GSI-191

October 25, 2006



# **Industry Panel**

Tony Pietrangelo
VP Regulatory Affairs, NEI

#### Joe Donahue

VP Nuclear Engineering and Services, Progress Energy Chairman, PWR Owners Group Executive Committee

Amir Shahkarami
Sr. VP Engineering and Technical Services, Exelon



### Overview

- A highly conservative, deterministic approach was developed to address GSI-191
- Conservative test methods are also being applied
- Licensees are moving forward with significant design and operational enhancements
- Industry wants to achieve closure expeditiously



### **Evaluation Methodology (NEI-04-07)**

- Developed as a conservative screening tool to identify areas for licensee action
- Necessary to bound spectrum of plant configurations and materials
- Did not include guidance on chemical effects and downstream effects
  - Resolution activities initiated in parallel with joint industry/NRC chemical effects testing

# Examples of Bounding Assumptions

- Instantaneous double-ended break of largest pipe at worst location (< 1 E-7/yr)</li>
  - Maximize head loss
  - No credit for Leak Before Break
- Spherical zone of influence (up to 28.6 D)
- All non-qualified coatings inside containment assumed to fail
- 100% transport to screens



# **Chemical Effects**

- Joint industry/NRC tests demonstrated need to consider chemical precipitants
- PWROG developed guidance for plant-specific chemical effects treatment
  - Conservative estimation of precipitant formation
  - Neglects inhibition effects
- Combination of high fiber load, high precipitant formation leads to prediction of high head loss
- Industry pursuing range of actions to resolve
  - Combination of refinements to methodology, test protocols and design changes



### **Industry Resolution Activities**

- Analysis and mock-up testing being performed in support of strainer replacements
- Plant activities extend well beyond installation of larger strainers
- Plant-specific designs are a driver in the resolution path taken
- Installation of new screens has begun and will continue to 1<sup>st</sup> Quarter 2008



### Licensee Actions Taken or Considered

- Install very large screens
- Utilize alternate buffers
- Install trash racks/debris interceptors
- Remove fibrous insulation
- Numerous compensatory actions
- Water management initiative



### **PWROG Activities**

- Industry guidance documents have been developed to address
  - Debris generation and transport
  - Downstream effects evaluation
  - Chemical effects
  - Alternate buffers
- Conservative treatment of individual phenomena and operational parameters
  - Overall result is highly conservative



# **Progress Energy Activities**

#### Crystal River

- Original sump screen:
  - Design: Wire mesh with 1/4" square openings
  - Size: 86 ft<sup>2</sup>
- Replacement sump screen:
  - Design: Concentric rolled and perforated plates (tophat design) with 1/8" diameter holes
  - Size: 1140 ft<sup>2</sup> (thirteen times larger than original)
  - 50% screen head loss margin reserved for chemical effects
- Separate flow diverter and debris interceptor upstream of screen
- Status: Installed in fall 2005



### **Progress Energy Activities** Crystal River Tophat Strainers








# **Progress Energy Activities**

#### H. B. Robinson

- Original sump screen:
  - Design: Wire mesh with 7/32" square openings
  - ◆ Size: 116 ft<sup>2</sup>
- Replacement sump screen:
  - Design: Tophat with 3/32" diameter holes and integral woven mesh to minimize debris penetration
  - Size: 4200 ft<sup>2</sup> (thirty-six times larger than original)
  - >50% screen head loss margin reserved for chemical effects
- Status: Will be installed in spring 2007



### H. B. Robinson Strainer Layout



PLAN VIEW

# **Progress Energy Activities**

- Material head loss testing
- Screen penetration testing
- Coating destruction pressure (ZOI) testing
- Chemical effects
  - Working closely with NEI and PWROG to resolve chemical effects issue
  - Additional testing may be required to quantify head loss impact
  - Using industry predictive spreadsheet to identify actions most effective in reducing chemical precipitates



# **EXELON PWRs**

- Byron Station Units 1 and 2
- Braidwood Station Units 1 and 2
- Three Mile Island Unit 1
- Salem Units 1 and 2



- Byron & Braidwood Stations
  - Original sump screen:
    - Design: Wire mesh with 3/16" square openings
    - 150 ft<sup>2</sup> total both sumps Size:
  - Replacement sump screen
    - Design: "Pocket" design with 1/12" holes
    - 3000 ft<sup>2</sup>/sump, 6000 ft<sup>2</sup> total Size:
    - Design complete including head loss and chemical effects testing
  - Status:

    - Byron Unit 1 : installed Sept. 2006
    - Braidwood Unit 2 : will be installed Oct. 2006

    - Byron Unit 2 : will be installed April 2007
      - Braidwood Unit 1 : will be installed Oct. 2007



#### Byron & Braidwood Stations

- Additional Hardware Modifications
  - Remove/replace fiberglass insulation within ZOI with Reflective Metal Insulation
  - Install trash racks for large debris interception
  - Replace ECCS throttle valve trim
- Operational Modifications
  - Improved loose debris surveillances
  - EOP changes for increased cool down rates for Small Break LOCA (Bulletin 2003-01)

#### Byron/Braidwood Replacement Sump Screen





- Salem Units 1 and 2
  - Original sump screen:
    - Design: Wire mesh with 1/8"x1/8" square openings
    - Size: 85 ft<sup>2</sup>
  - Replacement sump screen
    - Design: "Pocket" design with 1/12" holes
    - Size: 5000 ft<sup>2</sup> total
    - Screen design complete
    - Chemical effects testing scheduled for Nov. 2006
  - Status:
    - Unit 2 will be installed October 2006
    - Unit 1 will be installed February 2007




#### Salem Units 1 and 2

- Additional Hardware Modifications:
  - Remove/replace Calcium Silicate and Min K insulation within ZOI with Reflective Metal Insulation
  - Install trash racks for large debris interception
- No equipment modifications anticipated to address Downstream Effects



### **Salem Replacement Strainers**



### Closure = Reasonable Assurance of Long Term Cooling

- GSI-191 in context
  - Low risk significant event
  - Significant safety enhancements
- Chemical effects is the challenge
  - No silver bullet
  - Screens sized with margin
  - Working with staff on more realistic treatment
- Closure is recognition that the above actions achieve reasonable assurance

