

RECEIVED

APR 18 1996

OSTI

DOE/METC-96/1028-Vol. 2

**METC/Shell Cooperative Agreement CRADA 93-011  
High Temperature High Pressure Filtration and  
Sorbent Test Program**

**Final Report, Volume II**

June 1995

U.S. Department of Energy  
Office of Fossil Energy  
Morgantown Energy Technology Center  
3610 Collins Ferry Road  
Morgantown, WV 26505

and


Shell Synthetic Fuels Incorporated  
Two Shell Plaza  
P.O. Box 2099  
Houston, TX 77252

Contributors:

J.M. Rockey, J.R. Bird, E. Galloway, A.P. Lui,  
D. Eckels, J. Rutten, M.S. Tucker, P.C. Yue,  
R.L. Pineault, J.C. Pack, T. Thomson

**MASTER**

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED *dx*



## Table of Contents

Volume I	<u>PAGE</u>
1. Executive Summary . . . . .	4-5
2. Objective . . . . .	6
3. Gasifier and Cleanup Facility Description . . . . .	6-14
4. Gasifier and Cleanup Facility Operation . . . . .	15
A. Test Run 93FBG/MGC04 . . . . .	15
a. Test Objectives . . . . .	15
b. Run Highlights . . . . .	15
c. Summary of Gasifier Operating Conditions . . . . .	16
d. Product Analysis . . . . .	17
e. Summary of Cleanup Rig Conditions . . . . .	18
B. Test Run 93FBG/MGC05 . . . . .	19
a. Test Objectives . . . . .	19
b. Run Highlights . . . . .	19
c. Summary of Gasifier Operating Conditions . . . . .	20
d. Product Analysis . . . . .	21
e. Summary of Cleanup Rig Conditions . . . . .	22
C. Test Run 93FBG/MGC06 . . . . .	23
a. Test Objectives . . . . .	23
b. Run Highlights . . . . .	23
c. Summary of Gasifier Operating Conditions . . . . .	24
d. Product Analysis . . . . .	25
e. Summary of Cleanup Rig Conditions . . . . .	26
D. Test Run 94FBG/MGC07 . . . . .	27
a. Test Objectives . . . . .	27
b. Run Highlights . . . . .	27
c. Summary of Gasifier Operating Conditions . . . . .	28
d. Product Analysis . . . . .	29-31
e. Summary of Cleanup Rig Conditions . . . . .	32
E. Test Run 94FBG/MGC08 . . . . .	33
a. Test Objectives . . . . .	33
b. Run Highlights . . . . .	33
c. Summary of Gasifier Operating Conditions . . . . .	34
d. Product Analysis . . . . .	35-37
e. Summary of Cleanup Rig Conditions . . . . .	38

F.	Test Run 94FBG/MGC09 . . . . .	39
a.	Test Objectives . . . . .	39
b.	Run Highlights . . . . .	39
c.	Summary of Gasifier Operating Conditions . . . . .	40
d.	Product Analysis . . . . .	41-42
e.	Summary of Cleanup Rig Conditions . . . . .	43
G.	Test Run 94FBG/MGC10 . . . . .	44
a.	Test Objectives . . . . .	44
b.	Run Highlights . . . . .	44
c.	Summary of Gasifier Operating Conditions . . . . .	45
d.	Product Analysis . . . . .	46-47
e.	Summary of Cleanup Rig Conditions . . . . .	48

Volume II

Appendix 1:	Summary of Particulate Monitoring Results . . . . .	A1
Appendix 2:	Summary of Alkali Monitoring Results . . . . .	A2
Appendix 3:	Detailed Chronology of Significant Run Events . . . . .	A3
Appendix 4:	Daily Process Variable Plots . . . . .	A4
Appendix 5:	Process and Instrumentation Drawings . . . . .	A5

**APPENDIX 1**

**SUMMARY OF PARTICULATE MONITORING RESULTS**



## Appendix 1: Summary of Particulate Monitoring Results

This report is a summary of the results of activities of the particulate monitoring group in support of the METC/Shell CRADA 93-011. Online particulate monitoring began in August, 1993 and ended in October, 1994. The particulate monitoring group participated in six MGCR runs (#5 through #10). The instrument used in measuring the particle loadings (particle counts and size distribution) is the Particle Measuring Systems Classical Scattering Aerosol Spectrometer Probe High Temperature and High Pressure (PMS Model CSASP-100-HTHP). This PMS unit is rated to operate at temperatures up to 540°C and gage pressures up to 2.07 MPa.

Gas stream conditions, temperature at 540°C, gage pressure at 2.93 MPa, and gas flowrate at 0.0157 SCM per second, precluded the direct measurement of particulate loadings in the gas stream with the PMS unit. A side stream was extracted from the gas stream after it came over to the MGCR, (Modular Gas Cleanup Rig), from the FBG, pressurized fluidized-bed gasifier, but before it entered the filter testing vessel. A sampling probe of 0.635 cm O.D. thin wall stainless steel tubing was used for extracting the sample gas isokinetically based on the expected flowrate. The sample gas stream was further split into two streams; one was directed to the PMS unit and the other to the alkali monitor unit.

The gas flowrate to the PMS unit was controlled by a plate orifice in run #5 but was replaced with a critical orifice in subsequent runs to minimize particle loss. The actual sample gas flowrate was recorded continuously by the DDAS, Distributed Data Acquisition System.

The PMS unit was set to a measuring cycle of 90 seconds which resulted in about 40 measuring cycles per hour. At the end of each cycle it reported the total particle count and particle count in each size group. These were recorded by a PC. To obtain the particle loadings from measurements (i.e. particle number density and particle mass loading) it was necessary to perform post measurement calculations with flow data recorded by the DDAS which also recorded other operation parameters of the FBG and the MGCR.

The record of flow data was found to be incomplete. There were no flow data recorded in runs #7 and #10. However, all data were processed with flowrate values either actually recorded or a fixed value observed during the run. In cases where actual flow information was available an average of 15 flow values was used to process each data set of 90 seconds (DDAS recorded flow data at a 6 second interval). We only processed data sets containing 6 or more hours of continuous records in order to obtain a time history of the data trend.

In each data set presented, each data point represents a 15-minute ensemble average (an average of 10 measurements). Three plots of the ensemble averages were generated from each data set; mean particle diameter, mean number concentration, and mean mass loading. For mass loading calculations, a particle mass density value of 1.0 gram per cubic centimeter (1 gm/cc) was used, following the general practice used by some optical particle monitor vendors. The actual mass loading can be easily obtained by multiplying the mass loading with the appropriate particle mass density. For these FBG/MGCR runs the particle mass density varied from 2.2 to 2.5 gm/cc depending on the specific runs. A nominal value of 2.3 gm/cc has been suggested for use.

In the following, for each run presented is an example of an unprocessed particle size distribution of one 90 second measuring cycle and an example of a 15-minute averaged size distribution. Then for each data set, 3 plots are presented, one for the ensemble mean values of diameters, number concentration, and mass loading over each measuring period. In an ideal situation, when we have constant particle loadings and particle size distribution, we would expect a straight line curve for these last three plots. But there are many factors that may contribute to the measured variations of particle loading and size; gasifier operations conditions, gas stream flow and pressure fluctuations, particle deposition on and re-entrainment from pipes and valves, etc.

#### PMS at MGCR Run #5

Figure 1a shows an "unprocessed" particle size distribution as reported by the PMS unit in a measuring cycle on 8/4/93. Figure 1b is the 15-minute averaged size distribution of particle loading (that is, particle number per standard cubic meter, #/SCM). As can be seen the averaged particle size distribution plot is very much similar to the individual distribution plot indicating the particle size distribution generally did not experience large changes during the 15 minutes period. This can also be inferred from the plot of ensemble mean particle diameters over a 10-hour period (Figure 1c), which shows relatively constant mean values except toward the end of the measuring period. However, the particle number concentration

#### PMS at MGCR Run #9

Two sets of particulate measurements were taken in this run. On 9/13/94, 7 hours of particulate data were collected. Again, the size distribution is consistent between a single measuring cycle (Figure 9a) and the 15-minute averaged sized distribution (Figure 9b). The ensemble mean particle diameters are relatively large, about 0.8 microns, as shown in Figure 9c. The number concentration plot (Figure 9d) and the mass loading plot (Figure 9e) showed relatively constant values except a sharp drop at around 1300 hours. The data collected between 9/15 and 9/16 show that the ensemble mean diameters (Figure 10a) varied more than those taken on 9/13. The mean particle concentrations also show large variations (Figure 10b). The mass loadings (Figure 10c) seem to amplify the variations in number concentration.



Supplemental to the online particulate monitoring, the following table provides the hours of filtration and the pounds of solid filtered with respect to the filtration vessel.

Run Number	Hours of Filtration per Run	Pounds of Solid Collected
4	108	3.78
5	146	4.76
6	130	1.82
7	119	2.12
8	189	5.62
9	86	3.38
10	89	2.56

Averaged Particle Size Distribution  
 MGCR Run #5 93/08/04 11:00,




Figure 1a. Unprocessed particle size distribution from a single measurement.

Particle Size Distribution  
MGCR Run #5 93/08/04 11:00:51




Figure 1b. A 15-minute averaged particle size distribution.

PMS at MGCR Run #5  
8/4/93




Figure 1c. Ensemble mean particle diameters.

PMS at MGCR Run #5  
8/4/93




Figure 1d. Ensemble mean particle number concentrations.

PMS at MGCR Run #5  
8/4/93




Figure 1e. Ensemble mean particle mass loadings.

PMS at MGCR Run #5  
8/7/93




Figure 2a. Ensemble mean particle diameters.

PMS at MGCR Run #5  
8/7/93




Figure 2b. Ensemble mean particle number concentrations.



PMS at MGCR Run #5  
8/7/93




Figure 2c. Ensemble mean mass loadings.

Particle Size Distribution  
MGCR Run #6 93/11/04 10:01:45




Figure 3a. Unprocessed particle size distribution from a single measurement.

Averaged Particle Size Distribution  
 MGCR Run #6 93/11/04 10:45




Figure 3b. A 15-minute averaged particle size distribution.

PMS at MGCR Run #6  
11/4/93




Figure 3c. Ensemble mean particle diameters.

PMS at MGCR Run #6  
11/4/93




Figure 3d. Ensemble mean particle number concentrations.

PMS at MGCR Run #6  
11/4/93




Figure 3e. Ensemble mean mass loadings.

PMS at MGCR Run #6  
11/6/93




Figure 4a. Ensemble mean particle diameters.

PMS at MGCR Run #6  
11/6/93




Figure 4b. Ensemble mean particle number concentrations.



PMS at MGCR Run #6  
11/6/93




Figure 4c. Ensemble mean particle mass loadings.

Particle Size Distribution  
MGCR Run #7 94/06/14 01:01:26




Figure 5a. Unprocessed particle size distribution from a single measurement.

Averaged Particle Size Distribution  
 MGCR Run #7 94/06/14 01:00




Figure 5b. A 15-minute averaged particle size distribution.

PMS at MGCR Run #7  
6/14/94




Figure 5c. Ensemble mean particle diameters.

PMS at MGCR Run #7  
6/14/94




Figure 5d. Ensemble mean particle concentrations.

PMS at MGCR Run #7  
6/14/94




Figure 5e. Ensemble mean mass loadings.

Particle Size Distribution  
MGCR Run #8 94/07/19 12:00:13




Figure 6a. Unprocessed particle size distribution from a single measurement.

Averaged Particle Size Distribution  
 MGR Run #8 94/07/19 12:00




Figure 6b. A 15-minute averaged particle size distribution.



PMS at MGCR Run #8  
7/19/94




Figure 6c. Ensemble mean particle diameters.

PMS at MGCR Run #8  
7/19/94




Figure 6d. Ensemble mean particle concentrations.

PMS at MGCR Run #8  
7/19/94




Figure 6e. Ensemble mean mass loadings.

PMS at MGCR Run #8  
7/21/94




Figure 7a. Ensemble mean particle diameters.

PMS at MGCR Run #8  
7/21/94




Figure 7b. Ensemble mean particle concentrations.

PMS at MGCR Run #8  
7/21/94




Figure 7c. Ensemble mean mass loadings.

PMS at MGCR Run #8  
7/22/94




Figure 8a. Ensemble mean particle diameters.

# PMS at MGCR Run #8

7/22/94




Figure 8b. Ensemble mean particle concentrations.



PMS at MGCR Run #8  
7/22/94




Figure 8c. Ensemble mean mass loadings.

Particle Size Distribution  
MGCR Run #9 94/09/13 10:30:58




Figure 9a. Unprocessed particle size distribution from a single measurement.

Averaged Particle Size Distribution  
 MGCR Run #9 49/09/13 10:30





Figure 9b. A 15-minute averaged particle size distribution.

PMS at MGCR Run #9  
9/13/94



Time of Day

Figure 9c. Ensemble mean particle diameters.

PMS at MGCR Run #9  
9/13/94





Figure 9d. Ensemble mean particle concentrations.

PMS at MGCR Run #9  
9/13/94



Time of Day

Figure 9e. Ensemble mean mass loadings.

PMS at MGCR Run #9  
9/15-16/94




Figure 10a. Ensemble mean particle diameters.

PMS at MGCR Run #9  
9/15-16/94




Figure 10b. Ensemble mean particle concentrations.



PMS at MGCR Run #9  
9/15-16/94




Figure 10c. Ensemble mean mass loadings.

Particle Size Distribution  
 MGCR Run #10 94/10/26 10:01:10




Figure 11a. Unprocessed particle size distribution from a single measurement.

Averaged Particle Size Distribution  
 MGCR Run #10 94/10/26 10:00




Figure 11b. A 15-minute averaged particle size distribution.

PMS at MGCR Run #10  
10/26/94




Figure 11c. Ensemble mean particle diameters.

PMS at MGCR Run #10  
10/26/94




Figure 11d. Ensemble mean particle concentrations.

PMS at MGCR Run #10  
10/26/94




Figure 11e. Ensemble mean mass loadings.

**APPENDIX 2**

**SUMMARY OF ALKALI MONITORING RESULTS NOVEMBER 1993**








Ames Laboratory  
280 HH Metals Development  
Iowa State University  
Ames, Iowa 50011  
(515)-294-3758  
FAX (515) 294-3091

**Summary of  
Alkali Monitoring Results  
for November 1993  
at Morgantown Energy Technology Center**

Enclosed are graphs of our 2 November through 8 November 1993 alkali monitoring results from the Modular Gasification Cleanup Rig (MGCR) at Morgantown Energy Technology Center (METC) in Morgantown, West Virginia. The alkali (sodium and potassium) concentrations are plotted as ppb by weight versus time of the day in hours. In addition, the calcium concentrations and a signal proportional to the sample flow into the monitor's burner are plotted. During the operation of the gasifier from 1 November until the 9 November, approximately 33 hours of on-line alkali and calcium data were collected. The primary sampling point for the alkali monitor was shared with the Particle Monitoring System (PMS) and was upstream from the MGCR's filter used to test sorbent material.

The alkali concentrations for the particulate laden process gas varied from lows of approximately 50 ppbw for sodium and 20 ppbw for potassium to a highs of approximately 400 ppbw for sodium and 150 ppbw for potassium. The monitoring of vapor phase alkali occurred several times in the time frame from 2 November to 8 November. To monitor vapor phase alkali, a sintered metal inertial gas sampling filter was used to remove the particulate material from the process gas. There was very little vapor phase alkali detected. The observed concentration levels were less than 1 ppbw for both sodium and potassium. The alkali monitor's sample line was routinely operated at approximately 1000°F (538°C).

Six mass loading samples were collected by Paul Yue of METC during the time the alkali monitor was measuring the sodium and potassium content of the particulate matter in the sample stream. The average sodium to potassium concentration ratio of the material collected during each mass loading measurement was determined by METC personnel to be 5.4 with a standard deviation of 1.2. An examination of the sodium to potassium concentration ratio for the 4 days of sampling with the alkali monitor shows the ratio varied from approximately 3 to 6.





280 Ames Laboratory  
Metals Development  
Iowa State University  
Ames, Iowa 50011  
(515)-294-3758  
FAX (515) 294-3091

## Alkali Monitoring Results for November 1993 at Morgantown Energy Technology Center

Enclosed are graphs of our 2 November through 8 November 1993 alkali monitoring results from the Modular Gasification Cleanup Rig (MGCR) at Morgantown Energy Technology Center (METC) in Morgantown, West Virginia. The alkali (sodium and potassium) concentrations are plotted as ppb by weight versus time of the day in hours. In addition, the calcium concentrations and a signal proportional to the sample flow into the monitor's burner are plotted. On 3 November, data were not collected as the gasifier was shut down that day to remove a clinker. Data for 6 and 7 November were not collected due to difficulties with the alkali monitor sample line caused by an obstruction of the primary flow control orifice. On November 6, several attempts at unplugging the orifice on by purging with compressed nitrogen were unsuccessful. Consequently, on 7 November, the orifice was removed and replaced. Operation of the alkali monitor was resumed on 8 November.

The primary sampling point for the alkali monitor was shared with the Particle Monitoring System (PMS) and was upstream from the MGCR's filter used to test sorbent material. A double gas sampling technique was employed to select a representative sample for the alkali monitor. First, a high volume sample flow was isokinetically selected from the process gas flow with most of the sampled gas exhausting into the vent line from the secondary sampling chamber. Second, a much lower gas flow that matched the flow requirement of the alkali monitor was isokinetically sampled in the secondary sampling chamber. Two critical flow orifices were employed to control the sample flow from the process gas stream at 415 psig (2.96 MPa) and 1100°F (593°C) to the alkali monitor. The primary flow orifice was 0.028" in diameter to allow 190 SCFH (90 standard L/min) flow in the primary sampling line to the secondary sampling chamber. The secondary flow orifice, which was downstream from the secondary sampling chamber, was 0.035" in diameter to allow the required 19 SCFH (9 standard L/min) flow in the secondary sampling line to the alkali monitor's flame. The flow to the alkali monitor's flame was controlled by adjusting the pressure in the secondary sampling chamber to approximately 20-25 psig with a Nupro flow control valve in the vent line from the secondary sampling chamber.

The first full day of alkali sampling was 2 November. The flow control orifices worked

well for the entire day. Once the proper flow to the alkali monitor was established, the sample flow remained approximately constant for hours. The measured concentrations for the day are for total alkali. The sample stream from the MGCR during this period was not filtered to remove the particulates. Particulates in the sample stream contain both alkali and calcium from the coal added to the gasifier. For the period from approximately 12:05 to 14:30, the measured concentrations were approximately 200-300 ppbw for sodium, 75-150 ppbw for potassium, and 150-300 ppbw for calcium. The presence of a significant calcium signal indicates that particulate matter was present in the sample stream. Vapor phase calcium was not expected in the sample stream because the vapor pressures of the calcium compounds present in the fly ash are very low at these gas temperatures (under 600°C or 1112°F). All of the calcium results during this period were more than an order of magnitude above the minimum observational limit of approximately 4 ppbw for calcium. For the period from approximately 14:30 to 18:00, the measured concentrations were approximately 50-100 ppbw for sodium, 10-25 ppbw for potassium, and 15-30 ppbw for calcium.

alkali sample stream. The flame optical emission technique employed for alkali measurements cannot distinguish between condensed phase alkali associated with particulates and vapor phase alkali. The monitor measures all the alkali independent of the form that enters the flame. Therefore, to measure vapor phase alkali, the particulates need to be removed from the sample stream. The absence of a calcium signal for the filtered sample gas indicates a sample stream very low in particulate matter and, consequently, condensed phase alkali. While monitoring sample gas from the inertial filter from approximately 20:15 to 20:55, the measured alkali concentrations were approximately 1 ppbw or less and the calcium concentrations were less than the minimum observational limit of 4 ppbw. The increase in alkali concentrations at approximately 20:40 is probably a result of reentrainment of particulate matter in the secondary sample line during and after the readjustment of the sample flow. The low calcium concentrations suggest that very little particulate material was passing through the filter and entering the alkali monitor's flame. The low alkali concentrations indicate that no measurable alkali vapor was present in the sample stream with the sample gas temperature of approximately 1030°F (555°C). At this sample gas temperature, measurable quantities of vapor phase alkali would not be expected. Therefore, the low measured alkali concentrations are further validation that at least 99% of the particulate matter present in the alkali sample stream was removed by the inertial gas sampling filter. At approximately 20:55 the sample flow to the alkali monitor was stopped and alkali monitoring was terminated for 4 November.

During the vapor phase alkali measurements, partial clogging of the sintered metal filter was observed. For the vapor phase alkali measurements on 4 August 1993, a differential pressure of approximately 25 psi was needed to obtain the required 19 SCFH (9 standard L/min) for the alkali monitor, but for the period from approximately 20:15 to 20:55 on 4 November, a pressure of 70 to 80 psi was necessary. The sintered Hastelloy X metal filter for alkali monitoring in November is the same filter employed on 4 August. The filter had not been cleaned and was left in place after the 4 August measurements. Corrosion of the filter material or agglomeration of the particulate matter on the filter media may have occurred during the intervening time span between August and November. Removal and initial examination of the filter was recently done in March 1994. The inside of the filter, which has an internal diameter of ½ inch, was filled with what appears to be agglomerated particulate matter. Apparently, a considerable amount of particulate matter from both the

pressure required to obtain the proper sample flow to the alkali monitor was approximately 45 psig, which is similar to the pressure requirement on 4 November.

For the period from 16:35 to 17:40, the sample gas was filtered and vapor phase alkali concentrations were determined. The concentrations results are similar to the vapor phase alkali determinations on 4 November. The alkali concentrations are below 1 ppbw for both sodium and potassium and the calcium concentrations are below the observation limit of 4 ppbw. The alkali and calcium concentrations did increase momentarily at approximately 16:55 as a result of stopping and restarting the sample flow in order to purge the sintered metal filter. The differential pressure across the filter required to obtain the proper flow (9 standard L/min) to the alkali monitor was approximately 80 psi. The backward flow of nitrogen to purge the filter did not reduce the differential pressure required. The necessary differential pressure after the resumption of sample flow increased to approximately 90 psi.

For the next period from approximately 17:40 to 20:25, the sample gas was not filtered and total alkali concentrations were determined. The measured sodium concentrations varied in a narrow range from approximately 150-300 ppbw but the potassium and calcium concentrations varied from 40 to 130 ppbw for potassium and from 10 to 150 ppbw for calcium. The sample flow was not constant during this period and varied from approximately 15 SCFH (7 standard L/min) to 20 SCFH (9.5 standard L/min) with frequent readjustment of the sample flow. The concentrations of calcium and potassium sometimes seem to have a larger dependence upon sample flow than the sodium concentrations. This dependence also occurred from approximately 18:15 to 20:15 on 4 November.

Also, during the period from approximately 16:55 to 20:25 on 5 November, there was an increasing problem with the primary flow control orifice. The proper flow to the alkali monitor could not be obtained unless the vent flow control valve was almost closed. Initially, on 2 November approximately 150 SCFH (70 standard L/min) was flowing in the primary sample line but by this period on 5 November only 95 SCFH (45 standard L/min) was available. On 6 November repeated purging of the orifice with the sample line heaters both on and off did not clear the partial obstruction. Consequently, on 7 November the orifice was replaced. Upon examination, the orifice was not plugged but a considerable amount of particulate matter was covering the upstream side of the orifice. The line containing the orifice was mounted vertically for both the primary and secondary orifice with the sample gas flowing downward. In contrast, the flow orifice for the PMS was mounted horizontally and did not experience as much sample flow problems although it did eventually plug and could not be cleared. Also, upon further examination a considerable amount of corrosion was present on the body of the orifice. Both orifices along with the inertial gas sampling filter had been left in place after the August MGCR operation. As a consequence, material may have been present from August.

The next day of sampling was 8 November. Initially, the sample flow was very erratic from 13:20 to 14:00. For the period from approximately 14:00 to 17:30, the sample flow was unfiltered and varied slowly. The sample flow was readjusted once at 16:00. The primary sample flow was approximately 220 SCFH ( 105 standard L/min) during this period. This

primary sample flow was more than double the primary flow (95 SCFH) before the replacement of the primary flow control orifice. The alkali concentrations during this period were approximately 210-280 ppbw for sodium and 50-60 ppbw for potassium. The calcium concentrations had more variation from approximately 5 to 20 ppbw. At approximately 17:30 sampling of the process gas from the gasifier was suspended. The secondary flow orifice and filter were purged repeatedly and for long periods of time while alkali measurements were made on the nitrogen purge gas. From approximately 17:45 to 18:15, nitrogen flowed through the inertial gas filter to the alkali monitor and from approximately 18:15 to 18:30, unfiltered nitrogen flowed through the secondary flow orifice to the alkali monitor. From approximately 18:40 to 18:50, filtered sample process gas was measured although the results are not very reliable because the required sample flow of 19 SCFH (9 standard L/min) could not be obtained as shown in the sample flow trace. The sample flow during this time was only approximately 10 SCFH (4.7 standard L/min). From approximately 19:00 to 21:35, unfiltered process gas was measured. The alkali concentrations during this period were approximately 270-290 ppbw for sodium and 50-70 ppbw for potassium. The calcium concentrations varied from approximately 20-30 ppbw. The spike in the potassium and calcium concentrations at approximately 20:50 is a result of a readjustment of the sample flow.


The alkali monitor was calibrated on 31 October 1993 using an aerosol made from aqueous solutions containing known concentrations of calcium chloride and sodium and potassium sulfate in a surrogate sample stream of nitrogen flowing at 150 standard cm<sup>3</sup>/s (9 standard L/min or 19 SCFH). The surrogate sample stream containing the aerosol was electrically heated and entered the alkali monitor's burner at a temperature of 1090°F (588°C). This temperature was close to the expected temperature of the sample gas from the MGCR.

After the next MGCR operation, the solid material that has accumulated on the MGCR's filter assembly will be removed and analyzed. At that time, the sodium, potassium, and calcium concentrations of the collected fly ash can be compared to the sodium, potassium, and calcium concentrations determined by the alkali monitor. Also, sodium and potassium analysis of the material collected during the mass loading measurements was recently completed by METC personnel. The average sodium to potassium ratio for the 6 mass loading measurements was 5.4 with a standard deviation of 1.2. An examination of the sodium to potassium ratio for the 4 days of sampling for the alkali monitor shows the ratio varying from approximately 3 to 6.


Dave Eckels  
Alkali Monitor Project  
(515) 294-7943 Office  
(515) 294-3058 Fax

xc: W. Haas  
W. Buttermore  
R. Romanosky  
T. Dorchak

# MGCR at METC on 2 Nov 1993




# MGCR at METC on 4 Nov 1993






# MGCR at METC on 5 Nov 1993



Sample Flow (arbitrary units)

Time of Day

# MGCR at METC on 8 Nov 1993




Time of Day

Sample Flow (arbitrary units)

**APPENDIX 3**

**DETAILED CHRONOLOGY OF SIGNIFICANT RUN EVENTS**



**Table 1 . SUMMARY OF MAJOR EVENTS DURING TEST RUN**  
 (Test No. 93FBG04)

May 16-26, 1993

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
5/16 (14:00)		• Started <u>System Start-up</u> procedure.
5/16 (15:45) - 5/17 (01:42)	9 hr 57 min.	• Heated up reactor to 800°F. • Loaded 90 lbm of char into feed hopper. • Coal feed line was found hot. Used cold convey air to cool it off once awhile. • Found crushed copper tubing on Sampling Line "B" nearby FLT-805B. Removed the bad section.
5/17 (01:42) - (02:40)	52 min.	• Started <u>Combustion mode</u> by feeding 6"-FBG char into reactor intermittently. Reactor temp. increased to 1,050°F at the 2nd lift. Reduced feed rate from 8 to 16 rpm. Maintained the temp. for 15 min. for temp. below 1,500 and for 30 min when it reaches 1,500°F.
5/17 (02:40) - (02:48)	8 min.	• Purge reactor with N <sub>2</sub> until O <sub>2</sub> content < 10%.
5/17 (03:45) - (05:17)	4 hr 42 min.	• Stop combustion mode due to coal feeder stuck.
5/17 (05:17) - (09:00)	3 hr 43 min.	• Resume <u>Combustion mode</u> to heat reactor to 1,600°F.
5/17 (09:00) - (11:45)	2 hr 45 min.	• Started <u>Gasification mode</u> .
5/17 (11:45) - (14:20)	2 hr 35 min.	• <u>Controlled Shutdown</u> after the CO alarm in cell went off for 35 min. with no sources being identified. • Found major leaks around the coal batch hopper and boiler sight-glass and fixed them. • Repressurized the system and fed coal.
5/17 (14:20) - (16:15)	1 hr 55 min.	• CO level in cell up to 100 ppm; Clinker dumped from underflow/overflow; lots of leaks from FV-912 back to the lockhopper. • Performed <u>Normal System Shutdown</u> .
5/17 (17:25) - (21:45)	3 hr 20 min.	• Removed Reactor Bottom and cleaned out clinker. Reinstalled and retorqued the bottom.

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
5/17 (21:45)		• Reheating the reactor from 350°F
5/17 (23:50) - 5/18 (01:30)	1 hr 40 min.	• Discovered FV-753 leak. Depressurized reactor, not flanged off FV-753. Found leaks on valve body, not on flanges. Reinsulated FV-753.
5/18 (00:05)		• Discovered <u>Small Fire</u> on the insulation of piping out of air preheater. Extinguished it, burned area was chalked.
5/18 (01:30) - (08:07)	6 hr 37 min.	• Repressurized the system. • Reposition TE-701 to have same reading as TE-700. • Blew and replaced PSE-753 (manifold rupture disc).
5/18 (08:07) - (10:02)	1 hr 55 min.	• Started <u>Combustion mode</u> when TIR-700 read 780°F.
5/18 (10:02) - (10:32)	30 min.	• Started <u>Gasification mode</u> .
5/18 (10:32) - 5/19 (12:50)	26 hr 18 min.	• <u>Steady State #1</u> . a. CO alarm in cell (up to 40 ppm) b. CO alarm in cell (up to 40 ppm) c. CO alarm in cell (up to 50 ppm) d. CO alarm in cell (up to 60 ppm) e. CO alarm in cell (up to 40 ppm) f. CO alarm in cell (up to 38 ppm) Discovered the cell alarm went off every time at solid dumping. g. ES&H measured the air flow to be 100 fpm with cell fan turned ON, and 60 fpm with cell fan turned OFF. h. Found and fixed problem of keeping FV-913 open by purging FV-452 with FV-913 open. i. 3 CO alarms in alley went off with overflow, primary and secondary cyclone lockhopper dumping. j. CO alarms in alley (40 ppm) went off with Overflow, Primary and secondary cyclone lockhopper dumping. k. Decreased coal feed rate from 34 to 27 rpm. l. CO alarms in alley (40 ppm) went off with Overflow, Primary and secondary cyclone lockhopper dumping. m. Increased steam flow from 45 to 54 lb/h.
(16:42)		
(18:58)		
(21:48)		
(23:45)		
5/19 (00:02)		
(00:45)		
(02:06)		

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u> (03:58)
5/19 (05:37)		n. Turned off Sampling Loop "B" to locate the leaks in Blue M system. Leaks were not found.
(05:50)		o. Turned off Sampling Loop "A" to locate the leaks by pressure/leak test of Blue M system.
(06:30)		p. Increased coal feed rate from 27 to 33 rpm.
(07:20)		q. Decreased coal feed rate back to 27 rpm.
(08:20)		r. Discovered <u>Fire</u> on catwalk to MGCR around Zone 5 of line heaters.
(09:35)		s. Found plugging of bottom drain line from Blue M system and switched to the other knockout pot with DOE project engineer's consent.
(11:50)		t. Increased coal feed rate from 27 to 33 rpm and purged reactor bottom with N <sub>2</sub> through FV-434 due to rising of temperature (TIR-701) to 1,725°F.
(12:40)		u. Loss of coal feed due to clinker in bed. TIR-701 read 1,050°F.
5/19 (12:50) - 5/20 (11:00)	22 hr 10 min.	v. Open HV-112 to purge system with 1,200 psig N <sub>2</sub> . • <u>Controlled Shutdown</u> to remove clinker from bed. a. Removed reactor bottom and insert. Found clinker covered across the entire cross section of insert. Put a new insert, buttoned up the reactor bottom, pressurized manifold, and fix leaks. b. Replaced the insulation on electrical heater connections with glass tape. c. Replaced TE-504.
5/20 (11:00) - (16:00)	4 hr	• Continue to replace insulation on all heater connectors.
5/20 (16:00)		• Started <u>System Start-up</u> procedure.
5/20 (17:25) - 5/21 (01:00)	7 hr 35 min.	• Heated up reactor to 780°F.
5/21 (01:25) - (03:23)	1 hr 58 min.	• Started <u>Combustion mode</u> by feeding Montana #5 coal at 22 lb/h.

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
5/21 (03:23) - (03:40)	17 min.	<ul style="list-style-type: none"> <li>• Purge reactor with N<sub>2</sub> through: (1) FV-406 (700 scfh) and convey loop, and (2) FV-313 (740 scfh) until O<sub>2</sub> content &lt; 2%.</li> </ul>
5/21 (03:40) - (04:10)	30 min.	<ul style="list-style-type: none"> <li>• Started <u>Gasification mode</u>. (coal feed at 75 lb/h)</li> </ul>
5/21 (04:10) - (05:50)	52 hr 36 min.	<ul style="list-style-type: none"> <li>• <u>Steady State #2</u>.</li> </ul>
(06:25)		<ul style="list-style-type: none"> <li>a. Switched convey N<sub>2</sub> to convey air (650 scfh).</li> </ul>
(06:40)		<ul style="list-style-type: none"> <li>b. Fluffed bed with N<sub>2</sub> through FV-434.</li> </ul>
(22:00)		<ul style="list-style-type: none"> <li>c. Increased coal feed to 90 lb/h.</li> </ul>
5/22 (00:30)		<ul style="list-style-type: none"> <li>d. Discovered CO leak into control room from Mass Spec. vacuum pump exhaust hose hanging loose in the gas sampling station. Fixed it by connect the hose to the ventilation system in the sampling station.</li> </ul>
(10:45)		<ul style="list-style-type: none"> <li>e. Found that if FV-754 is shut, manifold temperature controllers will be erroneous. Kept FV-754 open.</li> </ul>
(05:10)		<ul style="list-style-type: none"> <li>f. Found incinerator stack cap fell down and blocked the exhaust. Knocked off the cap from the stack.</li> </ul>
(05:46)		<ul style="list-style-type: none"> <li>g. CO alarm in cell at purging of primary cyclone.</li> </ul>
(05:50)		<ul style="list-style-type: none"> <li>i. CO alarm in cell (20 ppm).</li> </ul>
(05:58)		<ul style="list-style-type: none"> <li>j. Fluffed bed with N<sub>2</sub> through FV-434 to bring reactor temperature from around 1,500 to 1,400°F.</li> </ul>
(06:00)		<ul style="list-style-type: none"> <li>k. Discovered a leak from the incinerator bottom door. Stuffed the opening around the door with insulation blanket to stop the leak.</li> </ul>
(09:08) - (17:15)	8 hr 7 min.	<ul style="list-style-type: none"> <li>1. Found condensate dripping out from the dump valve (FV-923) of overflow lockhopper. Raised the vessel temperature controller from 500 to 700°F.</li> </ul>
(09:51)		<ul style="list-style-type: none"> <li>• Put on "<u>Hot-Hold</u>" condition to fix the plugging problem in coal feed line.</li> </ul>
(11:40)		<ul style="list-style-type: none"> <li>a. Replaced FV-923 with a newly rebuilt one.</li> </ul>
(12:00)		<ul style="list-style-type: none"> <li>b. Discovered the 480V isolation transformer feeding to the motor controller for coal feeding is bad. Ground it to 3 phases: 58, 136 and 240V.</li> </ul>
		<ul style="list-style-type: none"> <li>c. Developed a restart procedure from "Hot-Hold" condition.</li> </ul>



<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
5/23 (15:30)		d. Attempted to restart the reactor but coal line plugged again.
5/23 (17:00)		f. Fixed the coal feed line and started to purge reactor with N <sub>2</sub> to reduce O <sub>2</sub> conc. in reactor.
5/23 (18:30) - (19:00)	30 min.	• Started <u>Gasification mode</u> .
5/23 (19:00) - (21:00)	23 hr	• <u>Steady State #3</u> .
5/24 (10:42)		a. Coal transfer line plugged and fixed.
5/24 (17:00)		b. Got CO exposure to 2 technicians (60 ppm). They were sent to OHU for blood test.
5/24 (18:00) - (21:00)	32 hr 15 min.	c. Discovered the exit line from rupture disc (PSE-753) is hot, indicating a rupture disc was blown.
5/24 (23:40)		• <u>Controlled Shutdown</u> to replace bad rupture disc.
5/25 (02:20)		a. Isolated FV-755 from the system because of serious leak on the valve body, and repaired.
5/25 (02:31)		b. Blew rupture disc (PSE-602) in batch hopper.
5/25 (03:20) - (14:50)		c. Installed new rupture disc for PSE-753.
5/25 (14:50) - (19:30)	4 hr 40 min.	d. Unplugged line to PT-602.
5/25 (19:30)		• Attempted to bring up the reactor pressure and start coal feed but failed for 6 times. Finally, clinker was detected in the reactor, which caused the plugging of feed line.
5/25 (19:40) - (21:20)	1 hr 40 min.	• Depressurized the reactor and removed the bottom to clean up clinker.
		• Put back reactor bottom and underflow system.
		• Started <u>System Start-up</u> procedure.
		• Heated up reactor from around 600 to 750°F.

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
5/25 (21:20) - 5/26 (00:52)	3 hr 32 min.	<ul style="list-style-type: none"> <li>• Attempted to start combustion mode at 750°F but failed due to purged N<sub>2</sub> leaking into the reactor. Switched to convey air (HS-106).</li> </ul>
5/26 (00:52) - (02:15)	1 hr 23 min.	<ul style="list-style-type: none"> <li>• Started <u>Combustion mode</u> again to bring reactor temperature between 1,300 - 1,500°F</li> <li>• Purged reactor with N<sub>2</sub> to reduce O<sub>2</sub> conc. in bed.</li> </ul>
5/26 (02:15) - (03:00)	45 min.	<ul style="list-style-type: none"> <li>• Started <u>Gasification mode</u>.</li> </ul>
(02:20)		a. Increased coal feed from 73.4 to 85 lb/h to control bed temperature.
(02:45)		b. Reduced N <sub>2</sub> (FV-313) and raised reactor air (FV-115).
5/26 (03:00) - (03:10)	13 hr 30 min.	<ul style="list-style-type: none"> <li>• <u>Steady State #4</u>.</li> </ul>
(03:10)		a. Had pressure spike (PI-756) when flow (FT-501) dropped during MGCR coming on line. Need to set PCV-756 open in manual whenever MGCR comes on line to avoid the same occurrence.
(07:00)		b. Decreased coal feed to 73.4 lb/h to raise bed temp.
(07:15)		c. Used combination of coal feed rate, reactor air flow and fluffing of bed with N <sub>2</sub> to keep the bed temperature at the desirable level.
(15:15)		d. Lost coal feed during coal transfer from batch to feed hoppers. Recovered coal feed by purging the feed line with N <sub>2</sub> through FV-409. Reduced reactor air, increased coal feed to maintain pressure drop across feeder (PDI-424) at 80" H <sub>2</sub> O.
(16:00)		e. Discovered PDI-424 dropped very fast whenever pressurizing the overflow lockhopper with N <sub>2</sub> through FV-448. Switched to using YV-919P.
		f. Got CO exposure on one tech. at the end of loading coal at the top of silo. (300 increased to 1,200 ppm on Dragger monitor).
		g. Got another CO exposure on one tech. during changing of primary cycle receiving bucket. Got an alarm from the Neotronic monitor at around 999 ppm.



**Table 1 . SUMMARY OF MAJOR EVENTS DURING TEST RUN**  
(Test No. 93FBG05)

Aug. 1-13, 1993

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
8/1 (15:00)		• Started <u>System Start-up</u> procedure.
8/1 (21:20) - 8/2 (15:59)	18 hr 39 min.	• Attempted to <u>heat up reactor</u> to 800°F, but failed due to reactor air flow restriction at FSV-506. TIR-700 was about 700°F.
8/2 (15:35)		• Replace spring and gasket in FSV-506.
8/2 (15:59) - (20:15)	4 hr 16 min.	• Continued to <u>heat up reactor</u> to 800°F.
8/2 (20:15) - (20:49)	34 min.	• Started <u>Combustion mode</u> . Set coal feed at 34 lb/h (16 rpm) to raise bed temp. to 900-1,100°F.
8/2 (20:49) - (21:05)	16 min.	• Raised and kept temp. between 1,200 - 1,500°F with coal feeding at 14 rpm.
8/2 (21:05) - (21:50)	45 min.	• Raised and kept temp. between 1,400 - 1,600°F with coal feeding at 14 rpm.
8/2 (21:50) - (22:02)	12 min.	• Purged reactor to reduce O <sub>2</sub> conc. to < 1% by replacing reactor air with N <sub>2</sub> .
8/2 (22:02) - (22:45)	43 min.	• Started <u>Gasification mode</u> .
8/2 (22:45) - 8/3 (05:20)	6 hr 35 min.	• <u>Steady State #1</u> .
8/3 (05:20) - (07:00)	1 hr 40 min.	• <u>Put on "Hot-Hold" condition</u> to fix coal feed line.
8/3 (07:00) - (12:00)	5 hr	• <u>Steady State #2</u> .
8/3 (12:00) - (18:00)	6 hr	• <u>Controlled Shutdown</u> due to loss of coal feed caused by clinker built up in bed and plugged feed nozzle.
		• Cooled reactor to below 600°F before dropping the reactor bottom.

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
8/3 (18:00) - (22:00)	4 hr	• Removed the reactor bottom. Found clinker formed across the 7'-to-10" insert. Replaced with a new 7"-to-10" insert.
8/3 (16:10)		• Coal for moisture analysis (4.85%wt H <sub>2</sub> O).
8/3 (22:00) - (23:15)	1 hr 15 min.	• Pressure test the reactor bottom and repressurized the reactor system back to 425 psig (PIR-713).
8/3 (23:15) - 8/4 (02:40)	3 hr 25 min.	• <u>Reheated the reactor</u> back to around 800°F.
8/4 (02:40) - (03:15)	35 min.	• Started <u>Combustion mode</u> .
8/4 (03:15) - (05:20)	2 hr 10 min.	• Stopped combustion and put back on <u>Heat-up mode</u> after several CO alarms on the 1st level of cell, caused by the gas leak through underflow dump valve (FV-940). Blocked off FV-940 with a piece of flat metal sheet.
8/4 (06:30) - (07:37)	1 hr 7 min.	• Restarted <u>Combustion mode</u> .
8/4 (07:37) - (08:15)	38 min.	• Purged reactor with N <sub>2</sub> before gasification.
8/4 (08:15) - (08:45)	30 min.	• Started <u>Gasification mode</u> .
8/4 (08:45) - (20:45)	12 hr	• <u>Steady State #3</u> .
8/4 (20:45) - (21:45)	1 hr	• Put on " <u>Hot-Hold</u> " condition due to loss of coal feed caused by Feeder "B" stalled and hammering).
8/4 (23:00) - (23:07)	7 min.	• Started <u>Combustion mode</u> .
8/4 (23:07) - 8/5 (00:10)	1 hr 3 min.	• Started <u>Gasification mode</u> .

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
8/5 (00:10) - (05:40)	5 hr 30 min.	• Put on "Hot-Hold" condition due to loss of coal feed caused by the stalled Feeder "B".
8/5 (00:10) - (04:00)	3 hr 50 min.	a. Replaced Feeder "B" with "A".
8/5 (04:00) - (05:40)	1 hr 40 min.	b. Experienced plugging of coal feed line. Try varying air flow to unplug it. Not successful.
8/5 (05:40) - (17:30)	11 hr 50 min.	• <u>Controlled Shutdown</u> to remove clinker from bed. a. Removed and cleaned the reactor bottom. Clinker formed across the 7"-to-10" reactor insert. Used a new 3"-to-10" insert. b. Flanged off the underflow dump valve (FV-940) with a 4" 600-psi flange.
8/5 (17:30) - (19:55)	2 hr 25 min.	• Started <u>System Start-up</u> procedure.
8/5 (19:55) - (20:50)	55 min.	• Started <u>Combustion mode</u> .
8/5 (20:50) - (20:56)	6 min.	• Purged reactor with N <sub>2</sub> .
8/5 (20:56) - (21:30)	34 min.	• Started <u>Gasification mode</u> .
8/5 (21:30) - 8/9 (16:15)	90 hr 45 min.	• <u>Steady State #4</u> . a. Mass Spectrometer kicked off to Standby by itself twice. b. CO alarm at the 1st level set off several times during cyclone dumping. c. Dump valve of the primary cyclone plugged and later on, unplugged. d. Need to manually close FV-610. e. Wet solid came out from secondary cyclone. f. Hi-side of PDT-707/424 plugged.
8/9 (16:15) - (21:29)	5 hr 14 min.	• Put on "Hot-Hold" condition due to boiler leaks, TAL-217 went off several times). a. Repaired boiler leaks temporarily by capping off the condensate trap. b. Restarted gasification mode again, but had both convey air and coal feed problems.



**Table 1 . SUMMARY OF MAJOR EVENTS DURING TEST RUN**  
(Test No. 93FBG06)

Nov. 1-9, 1993

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
11/1 (00:00)		<ul style="list-style-type: none"> <li>• Started <u>System Start-up</u> procedure.</li> <li>• New feed nozzle was installed for testing.</li> </ul>
11/1 (01:40) - (12:17)	10 hr 37 min.	<ul style="list-style-type: none"> <li>• Air Preheater ignited. Heated up reactor to 800°F (TIR-700 &amp;-701).</li> <li>• DDAS on-line.</li> </ul>
11/1 (12:17) - (13:16)	59 min.	<ul style="list-style-type: none"> <li>• Started <u>Combustion mode</u>.</li> </ul>
11/1 (13:16) - (13:30)	14 min.	<ul style="list-style-type: none"> <li>• Purged reactor to reduce O<sub>2</sub> conc. to &lt; 1% by replacing reactor air with N<sub>2</sub>.</li> </ul>
11/1 (13:30) - (14:00)	30 min.	<ul style="list-style-type: none"> <li>• Started <u>Gasification mode</u>.</li> </ul>
11/1 (14:00) - 11/2 (18:42)	28 hr 42 min.	<ul style="list-style-type: none"> <li>• <u>Steady State #1</u>. <ul style="list-style-type: none"> <li>a. Performed routine coal transfer from batch to feed hopper and from silo to batch hopper.</li> <li>b. Performed routine dumping of solids from all lockhoppers every hour; and purging all the vent valves and transmitters every 3 hours.</li> <li>c. DDAS locked up from 16:15 to 16:22; but not logging data until 18:25 on 11/1.</li> <li>d. %H<sub>2</sub>O in gas = 9.45; 7.63; 13.62; 12.62; 10.93; 8.48%.</li> <li>e. Meloy analyzer was found leaking and thus shut down the analyzer at 21:20 on 11/1.</li> <li>f. Had difficulty in controlling TIR-700 to keep below 1,650°F at 17:38 &amp; 21:30 on 11/1 and 1,800°F at 11:20 on 11/2. After struggled with raising steam and N<sub>2</sub> flow and reducing reactor air flow, TIR-700 was under control but the reactor temperature increases from bottom to top of bed (1,200-1,520°F), opposite to normal.</li> <li>g. Blew rupture disc PSE-753 at 14:50 on 11/2.</li> </ul> </li> </ul>



<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
11/2 (18:42)		• <u>Controlled Shutdown</u> to replace ruptured disc PSE-753.
11/2 (18:42) - (20:49)	2 hr 7 min.	• Purged out bed material as much as possible. Reactor cooled to < 1,100°F.
11/2 (20:49) - (21:49)	1 hr	• Removed the reactor bottom. Found clinker formed across the 3"-to-10" insert. Replaced with a new 3"-to-10" insert.
11/2 (21:50) - 11/3 (15:00)	17 hr 10 min.	• Removed clinker from bed and cleaned up the bed with special tools. Clinker that covered up the entire reactor cross section was 8" thick at the center & 10" on the wall). • Completed reinstalling the reactor bottom. • Used the old feed nozzle. • Shut down DDAS to fix GC problem from 21:50 to 23:15 on 11/2 and from 11:28 to 16:01 on 11/3.
11/3 (15:00) - (17:10)	2 hr 10 min.	• Pressure test of reactor and underflow system.
11/3 (17:10) - (21:45)	4 hr 35 min.	• Started heating up from 320-440°F to 800°F.
11/3 (21:45) - (22:55)	1 hr 10 min.	• Started <u>Combustion mode</u> by bringing reactor temperature up from 800 to 1,600°F in 3 stages.
11/3 (22:55) - 11/4 (01:00)	2 hr 5 min.	• Started <u>Gasification mode</u> .
11/4 (01:00) - (21:11)	20 hr 11 min.	• <u>Steady State #2</u> . a. PDIC-424 worked again (don't know the reason). b. PDIR-707 = 11"; -708 = 1.5"; -709 = 0.07"H <sub>2</sub> O. c. FV-725 would not open. d. %H <sub>2</sub> O in gas = 12.2; 8.45; 7.57; 10%. e. DDAS was down from 14:02 - 14:55 on 11/4. f. Sealed the leak on the baghouse. g. Patched the leak on baghouse (found at 14:20) at 17:45 on 11/4.

f. Events

..32; 15.4; 13.3; and

.. System cooled off.

State Time = 135 hr 43 min.  
hours).

Duration

Description of Events

h. Blew rupture disc PSE-753 again at 21:10 on 11/4.  
• Put on "Hot-Hold" condition to replace rupture disc.  
• Replaced rupture disc PSE-753.  
• Unplugged FT-425 and performed flow proving.

33 min. • Attempted to restart reactor from "Hot-Hold" condition but coal feed line was plugged.

00) 1 hr 10 min. • Started Gasification mode.

00) 60 hr • Steady State #3.

a. DDAS showed a lower feeder speed (actual=36 rpm).  
b. %H<sub>2</sub>O in gas = 10.82; 13.91; 8.74; 12.68; 12.37;  
14.5; 10.88; 13.16; 12.25; 11.97; 11.14; 13.13;  
14.05%.

c. Cleaned up the filter ports (FLT-801A & B).  
d. Removed a plug right before FLT-810 in gas sampling system.

e. Blew rupture disc PSE-753 again at 12:50 on 11/7 while FV-754 was plugged up.

• Emergency shut down due to fire around FV-754 flanges.

5 hr 51 min. • Repaired rupture disc blown. Replaced gasket on orifice of FV-754 and torqued to 45 ft-lbf. Pressurized reactor system and performed leak test.

1 hr 9 min. • Started Gasification mode.

3 hr 20 min. • Steady State #4.

a. Used FV-755 even though it was not flow proven.  
b. FV-913 plugged up.

Table 1 . SUMMARY OF MAJOR EVENTS DURING TEST RUN  
(Test No. 94FBG07)

June 6-15, 1994

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
6/6 (00:00)		<ul style="list-style-type: none"> <li>• Started <u>System Start-up</u> procedure.</li> <li>• Reactor insert with steam side-jets was used.</li> </ul>
6/6 (02:57) - (14:01)	11 hr 4 min.	<ul style="list-style-type: none"> <li>• Air Preheater ignited. Heated up reactor to 800°F (TIR-700, -701, -707 &amp; -733, whichever one reached first).</li> <li>• FCV-113 &amp; 115 could not provide 7000 scfh. Opened HV-503 to obtain the required air flow.</li> <li>• Repaired leaks around FV-221.</li> <li>• DDAS on-line, changed logging rate from 2 to 4 sec. But crashed 4-5 times.</li> </ul>
6/6 (14:01) - (16:10)	2 hr 9 min.	<ul style="list-style-type: none"> <li>• Started <u>Combustion mode</u>.</li> </ul>
6/6 (16:10) - (16:46)	36 min.	<ul style="list-style-type: none"> <li>• Purged reactor to reduce O<sub>2</sub> conc. to &lt; 3% by replacing reactor air with N<sub>2</sub>.</li> </ul>
6/6 (16:46) - (18:30)	1 hr 44 min.	<ul style="list-style-type: none"> <li>• Started <u>Gasification mode</u>. <ul style="list-style-type: none"> <li>a. Convey air at 850 scfh, Reactor air at 1200 scfh, side steam at 33 lb/h out of total 55 lb/h, underflow N<sub>2</sub> reduced from 400 to 350 scfh, and coal feed at 70.4 lb/h.</li> <li>b. Performed routine coal transfer from batch to feed hopper and from silo to batch hopper.</li> <li>c. Performed routine dumping of solids from all lockhoppers every hour; and purging all vent valves and transmitters every 4 hours.</li> </ul> </li> </ul>
6/6 (18:30) - 6/7 (05:38)	11 hr 8 min.	<ul style="list-style-type: none"> <li>• <u>Steady-State #1</u> (with Montana #6): <ul style="list-style-type: none"> <li>a. Change conditions many times to reduce the H<sub>2</sub>O in underflow dump: Increased convey air to 1,080 and reactor air to 1,500 scfh; reduced underflow N<sub>2</sub> to 200 scfh; increased set points in air preheater and superheater)</li> <li>b. TIR-701 reached 1,770°F at 01:40 on 6/7.</li> </ul> </li> </ul>

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
6/7 (05:38) - (15:45)	10 hr 7 min.	<ul style="list-style-type: none"> <li>c. Reset the conditions to : Convey Air = 900 scfh, Reactor air = 1,300 scfh; underflow N<sub>2</sub> = 320 scfh; side steam of 33 lb/h with 50 lb/h total; and coal feed = 70 lbm/h.</li> <li>d. DDAS crashed 2 times.</li> <li>e. High temperature excursion to 1,900°F on TIR-701.</li> <li>f. Loss of coal feed at 05:32.</li> </ul>
6/7 (15:45) - 6/8 (00:30)	8 hr 45 min.	<ul style="list-style-type: none"> <li>Controlled <u>Shutdown</u> due to loss of coal feed. Cooled reactor from 1,500 to 800°F.</li> <li>DDAS off-line at 10:25.</li> <li>Used air chisel to remove clinker from the wall that held the reactor insert in place. The reactor insert dropped out of the reactor at 23:50.</li> <li>Removed TE-707 and plugged the hole of the housing.</li> </ul>
6/8 (00:30) - (05:02)	4 hr 32 min.	<ul style="list-style-type: none"> <li>Started <u>System Start-up</u> procedure.</li> <li>Installed reactor insert with <u>no side-jets</u>.</li> </ul>
6/8 (05:02) - (10:40)	5 hr 38 min.	<ul style="list-style-type: none"> <li>Ignited air Preheater and incinerator. Heated up reactor to 800°F (TIR-700, -701, -707 &amp; -733, whichever reached first).</li> <li>DDAS back on-line at 08:00 but crashed once at approx. 09:40.</li> </ul>
6/8 (10:40) - (11:45)	1 hr 5 min.	<ul style="list-style-type: none"> <li>Started <u>Combustion mode</u>.</li> </ul>
6/8 (11:45) - (14:00)	2 hr 15 min.	<ul style="list-style-type: none"> <li>Dropped reactor pressure to fix coal plug in feed line.</li> </ul>
6/8 (14:00) - (16:20)	1 hr 40 min.	<ul style="list-style-type: none"> <li>Restarted <u>Combustion mode</u>.</li> </ul>
6/8 (16:20) - (16:32)	12 min.	<ul style="list-style-type: none"> <li>Purged reactor to reduce O<sub>2</sub> conc. to &lt; 3% by replacing reactor air with N<sub>2</sub>. TIR-700 at 1126°F.</li> </ul>



<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
6/12 (11:30) - 6/13 (04:21)	16 hr 51 min.	<ul style="list-style-type: none"> <li>• f. At 16:36 of 6/11, another temperature creeping occurred at TE-702 (apprx. 1,740°F). We tuned down the reactor air and up the underflow N<sub>2</sub> flow to bring down TIR-702 to 1,576 at 21:29.</li> <li>• g. Loaded 540 more lbm of Montana #6 coal into silo at 04:38 of 6/12 in order to have a scheduled shut down at 11:30.</li> <li>• <u>Controlled Shutdown</u> for MGCR to load sorbent. <ul style="list-style-type: none"> <li>a. Found and fixed the leak in the gas grab sampling system by putting in a check valve in the exit line after the gas grab bottle.</li> <li>b. Cooled off the reactor bottom and bed so that the workers could work on it). Cleaned out the clinker from the insert and bed (8'1" tall from the face of the bottom flange). Feed nozzle was brushed clean.</li> <li>c. Installed TE-707 back for combustion zone temperature.</li> <li>d. Purge all hand valves and push-button purge lines. We got a lot of dust out of the purge line.</li> </ul> </li> <li>• e. Replaced the MoGas valve (FV-908) that had a groves on the bottom seat with a new one.</li> </ul>
6/13 (04:21) - (13:30)	9 hr 9 min.	<ul style="list-style-type: none"> <li>• Started <u>System Start-up</u> procedure.</li> <li>• a. At 07:40, MGCR decided to scratch their Dry Chloride Removal (DCR) test plan. At 10:15, all chloride doped coal was removed from silo and replaced with regular coal.</li> </ul>
6/13 (13:30) - (15:00)	1 hr 30 min.	<ul style="list-style-type: none"> <li>• Start <u>Combustion mode</u>.</li> <li>• a. Added underflow N<sub>2</sub> during this mode.</li> </ul>
6/13 (15:00) - (15:10)	10 min.	<ul style="list-style-type: none"> <li>• Purged reactor to reduce O<sub>2</sub> conc. to &lt; 3% by replacing reactor air with N<sub>2</sub>.</li> </ul>

Date (Time)                      Duration                      Description of Events

6/13 (15:10) - (17:26)	2 hr 16 min.	• Started <u>Gasification mode</u> . a. At the start of this mode, the following condition was set: Convey air at 850 scfh, reactor air at 1105 scfh, steam at 63 lb/h, underflow N <sub>2</sub> at 478 scfh, and coal feed at 70.2 lb/h.
6/13 (17:26) - 6/15 (12:40)	43 hr 14 min.	• <u>Steady-State #3</u> (with Montana #6 coal). a. At 17:20, a different flow configuration was tried: Convey air at 1600 scfh, reactor air at 450 scfh, steam at 54 lb/h, underflow N <sub>2</sub> at 400 scfh and coal feed 70 lb/h. b. Performed routine coal transfer from batch to feed hopper and from silo to batch hopper. c. Performed routine dumping of solids from all lockhoppers every hour; and purging all vent valves and transmitters every 4 hours.
6/15 (12:40) - (24:00)	11 hr 20 min.	• <u>Normal System Shutdown</u> .

---

Total Gasification Time = 151 hr 74 min.      Total Steady-State Time = 143 hr 22 min.  
Total No. of Steady-State Periods = 3 (11.13; 89; and 43.23 hours).

n of Events

to loss of coal feed.  
and found no clinkers adhered on  
sert.

Steady State Time = 200 hr 5 min.

**SUMMARY OF MAJOR EVENTS DURING TEST RUN**  
(Test No. 94FBG08)

July 18-27, 1994

Description of Events

- Started System Start-up procedure.
- Reactor insert without side-jets was used (from the last S.S. period of Test Run 94FBG07).
- Montana Rosebud #6 coal in silo.
- Air Preheater ignited. Heated reactor to 800°F. (Based on TIR-700, -701, -707 & -733, whichever one reached first).
- Opened HV-503 and FCV-115 to obtain the high air flow (apprx. 7000 scfh).
- Repaired broken flexible coupling at VSL-906.
- Set all line heater temperatures to 500°F except Zone 6 & 7 to 1100°F (exits of both cyclones).
- Started Combustion mode.
- Purged reactor to reduce O<sub>2</sub> conc. to < 3% by replacing reactor air with N<sub>2</sub>.
- Started Gasification mode.
  - a. Convey air at 1600 scfh, Reactor air at 460 scfh, under-flow N<sub>2</sub> at 402 scfh, steam at 55 lb/h and coal feed at 69.6 lb/h.
  - b. Performed routine coal transfer from batch to feed hopper and from silo to batch hopper.
  - c. Performed routine dumping of solids from all lockhoppers every hour; and purging all vent valves and transmitters every 4 hours.
- Steady State #1 (with regular coal for METC-2 Sorbent Test and Filter Test).
  - a. Low sample loop flow (FIR-806) - 3.2 scfh - due to crystal -like material built up. Cleaned and flow resumed.
  - b. Sampling frequency: gas grab, detector tube, and condensate every hr., solids for every 4 hours.



**Table 1 . SUMMARY OF MAJOR EVENTS DURING TEST RUN**  
 (Test No. 94FBG09) September 12-16, 1994

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
9/12 (00:00)		<ul style="list-style-type: none"> <li>• Started <u>System Start-up</u> procedure.</li> <li>• Reactor insert without side-jets was used (from 94FBG08).</li> <li>• Montana Rosebud #7 coal (1,950 lbm) loaded in silo.</li> </ul>
9/12 (00:10) - (14:56)	14 hr 46 min.	<ul style="list-style-type: none"> <li>• Air Preheater ignited. Heated reactor to 800°F. (Based on TIR-700, -701, -707 &amp; -733, whichever one reached first).</li> <li>• Opened HV-503 and FCV-115 to obtain the high air flow (apprx. 4500 scfh max. vs 7,000 scfh max. in 94FBG08).</li> <li>• Set all line heater temperatures to 500°F except Zone 6 &amp; 7 to 1100°F (exits of both cyclones).</li> </ul>
9/12 (14:56) - (16:08)	1 hr 12 min.	<ul style="list-style-type: none"> <li>• Started <u>Combustion mode</u>.</li> <li>a. Raised the reactor temperature in 3 stages: 1,045 - 1,300 - 1,400 - 1,600°F).</li> </ul>
9/12 (16:08) - (16:22)	14 min.	<ul style="list-style-type: none"> <li>• Purged reactor to reduce O<sub>2</sub> conc. to &lt; 3% by replacing reactor air with N<sub>2</sub>.</li> </ul>
9/12 (16:22) - (16:52)	30 min. (assumed)	<ul style="list-style-type: none"> <li>• Started <u>Gasification mode</u>.</li> <li>a. Convey air at 1600 scfh, Reactor air at 525 scfh, underflow N<sub>2</sub> at 402 scfh, steam at 58 lb/h and Montana #7 coal fed at 70 lb/h (air/coal=2.32; steam/coal=0.83).</li> <li>b. Performed routine coal transfer from batch to feed hopper and from silo to batch hopper.</li> <li>c. Performed routine dumping of solids every hour except underflow every 30 min. and 2nd cyclone every 6 hours; and purging all vent valves and transmitters every 4 hours.</li> </ul>
9/12 (16:52) - 9/13 (06:15)	13 hr 23 min.	<ul style="list-style-type: none"> <li>• <u>Steady State #1</u> (with Montana #7 coal for METC-2 Sorbent Test and <u>Filter Test</u> with an air/coal of 2.32).</li> <li>a. Gas alarm went off twice (18:39 and 19:06) due to gas leak from the transition valve when dumping secondary cyclone.</li> <li>b. Sampling frequency: gas grab, detector tube and condensate every hr. until MGR sorbent breakthrough, then every 4 hours; solids every 2 hours except cyclone every 12 hours.</li> </ul>

<u>Time (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
(07:00) - (14:00)	7 hr	<ul style="list-style-type: none"> <li>i. At 06:01, reduce underflow N<sub>2</sub> from 500 to 475 scfh; at 06:11, reduce it to 460 scfh; and at 06:47, further reduced to 440 scfh.</li> <li>j. Moisture Contents of product gas = 10.4 and 9.2 %wt.</li> </ul>
(14:00) - (24:00)	10 hr	<ul style="list-style-type: none"> <li>• <u>Steady State #8</u> (with Illinois #6 coal) <ul style="list-style-type: none"> <li>a. From 07:02 to 07:25, reduced reactor air from 1,200 to 1,150 scfh, and underflow N<sub>2</sub> further down to 400 scfh.</li> <li>b. Moisture Contents of product gas = 13, 9.5 and 8.9 %wt.</li> </ul> </li> <li>• <u>Normal System Shutdown</u> as scheduled. <ul style="list-style-type: none"> <li>a. Changed convey and reactor air to N<sub>2</sub>.</li> <li>b. Turned of coal feeder and N<sub>2</sub> preheater.</li> <li>c. Bypassed steam from reactor.</li> <li>d. Weighed and secured all barrels of solids.</li> <li>e. Shut off portable boiler.</li> <li>f. Transferred all solids from silo through batch into feed hopper.</li> <li>g. Blew out all vent lines with HV-950 for 10 sec.</li> <li>h. Shut all N<sub>2</sub> and sir header valves.</li> <li>i. Removed the center (3/4") feed nozzle from reactor bottom.</li> <li>j. Calibrated coal feeder ("A") with Illinois #6 coal.</li> </ul> </li> <li>• Dropped the reactor bottom and found no clinkers adhered on the reactor wall and the insert.</li> </ul>
Morning		<ul style="list-style-type: none"> <li>CR. 10.7%wt.</li> <li>ent Test, air/coal to 825</li> <li>at 12:25.</li> <li>coal</li> <li>• (707).</li> <li>ud #6 with an</li> <li>4 reactor</li> <li>: 13.8,</li> <li>ilo.</li> <li>afh.</li> <li>ilo.</li> <li>ube.</li> <li>4 and</li> <li>Test). Montana</li> <li>ategy so arm.</li> <li>i.</li> <li>d.</li> </ul>
Gasification Time = 93 hr 38 min.		Total Test Time = 93 hr 8 min.
No. of Test Periods = 8 (13.38, 11.75, 16.37, 9.08, 10.72, 15.03, 9.8, and 7 hours).		

**Table 1. SUMMARY OF MAJOR EVENTS DURING TEST RUN**

(Test No. 94FBG10)

October 24-28, 1994


<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
10/24 (00:00)	11 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #1</u> (Heat-Up of the system)               <ul style="list-style-type: none"> <li>a. Started <u>System Start-up</u> procedure.</li> <li>b. Reactor insert with side-jets was used (Brand new design).</li> <li>c. Montana #7 coal (3,500 lbm) loaded in silo on 10/18.</li> <li>d. Air Preheater ignited. Heated reactor to 800°F. (Based on TIR-700, -701, -707 &amp; -733, whichever one reached first).</li> <li>e. Set cone N<sub>2</sub> to 50 scfh (FIR-311) and underflow N<sub>2</sub> (FIR-313) to 350 scfh with underflow N<sub>2</sub> preheater set at 350°F.</li> <li>f. Heated up reactor faster at lower pressure (100 psig).</li> <li>g. Set all line heater temperatures to 500°F except Zone 6 &amp; 7 to 1100°F (exits of both cyclones).</li> <li>h. At 07:45, reactor pressure was raised to 425 psig when the bottom temperatures reached to 750°F.</li> <li>i. At 08:30, fixed steam leak at PCV-221 and reinsulated the line. Another small leak was found around TE-220 and was not fixed.</li> </ul> </li> </ul>
10/24 (11:00) - (13:00)	2 hr	<ul style="list-style-type: none"> <li>• Started <u>Combustion mode</u>. Raised the reactor temperature in 3 stages: 1,045 - 1,300 - 1,400 - 1,600°F).</li> </ul>
10/24 (13:00) - (13:46)	46 min.	<ul style="list-style-type: none"> <li>• Purged reactor to reduce O<sub>2</sub> conc. to &lt; 3% by replacing reactor air with N<sub>2</sub>.</li> </ul>
10/24 (13:46) - (15:00)	1 hr 14 min.	<ul style="list-style-type: none"> <li>• Started <u>Gasification mode</u>.               <ul style="list-style-type: none"> <li>a. Convey air at 1600 scfh, Reactor air at 854 scfh, cone N<sub>2</sub> at 50 scfh and underflow N<sub>2</sub> at 350 scfh, steam at 60 lb/h and Montana #7 coal fed at 70 lb/h (Air/Coal (daf) = 3.3; Steam/Coal (daf) = 0.83).</li> <li>b. Performed routine coal transfer from batch to feed hopper and from silo to batch hopper.</li> <li>c. Performed routine dumping of solids every hour except underflow every 30 min. and 2nd cyclone every 6 hours; and purging all vent valves and transmitters every 4 hours.</li> </ul> </li> </ul>

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
10/24 (15:00) - (23:00)	8 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #2</u> (Filled bed with an Air/Coal (daf) of 3.3 and Steam/Coal (daf) at 0.83). <ul style="list-style-type: none"> <li>a. At 15:20, mass spec. (707) was turned on for MGCR.</li> <li>b. At 16:30, MGCR came on-line.</li> <li>c. Rupture disk 753A was blown and replaced with ES&amp;H personnel present (CO on 3rd floor of the cell = 9ppm).</li> <li>d. Small fire around the overflow pipe on the 2nd level of cell was found and extinguished.</li> <li>e. Sampling frequency: gas grab, detector tube and condensate every hr. until MGCR sorbent breakthrough, then every 4 hours; solids every 2 hours except cyclone at the end of each test period (6 or 12 hours).</li> <li>f. Averaged Moisture Content in product gas = 9.4 %wt.</li> <li>g. DDAS was down twice.</li> </ul> </li> </ul>
10/24 (23:00) - 10/25 (05:00)	6 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #3</u> (Bed stabilization with Montana #7 coal for ZT-04 Sorbent Test, Filter Test and test matrix with an increase of reactor air to 1,000 scfh and cone N<sub>2</sub> to 100 scfh, and a decrease of steam to 55 lb/h and underflow N<sub>2</sub> to 300 scfh. <ul style="list-style-type: none"> <li>a. Needed to purge the overflow line frequently to unplug it.</li> <li>b. Mass spec. (707) went off-line several times.</li> <li>c. Between 00:00 and 01:00, there was a breakthrough on ZT-04.</li> <li>d. Averaged Moisture Content in product gas = 8.9 %wt.</li> </ul> </li> </ul>
10/25 (05:00) - (17:00)	12 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #4</u> (with Montana #7 coal for test matrix with an increase of cone N<sub>2</sub> to 150 scfh). <ul style="list-style-type: none"> <li>a. Needed to purge the overflow line frequently to unplug it.</li> <li>b. Mass spec. (707) went off-line several times.</li> <li>c. At 14:40, MGCR called to shut off mass spec. (707).</li> <li>d. At 16:46, reactor temperatures were: 927 (TIR-700), 1242 (-701), 1,568 (-701), 903 (-703), and 1,010°F (-733).</li> <li>e. Averaged Moisture Content in product gas = 7.4 %wt.</li> </ul> </li> </ul>

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
10/25 (17:00) - 10/26 (05:00)	12 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #5</u> (with Montana #7 coal for test matrix with cone N<sub>2</sub> reset at 50 scfh).               <ul style="list-style-type: none"> <li>a. At 18:20, ES&amp;H personnel accompanied one technician and shift engineer to check the CO level at the 2nd level, which hit 35 ppm. Needed to insulate the overflow pipe.</li> <li>b. Needed to purge the overflow line frequently to unplug it.</li> <li>c. Averaged Moisture Contents of product gas = 7.0 %wt.</li> </ul> </li> </ul>
10/26 (05:00) - (11:00)	6 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #6</u> (with Montana #7 coal for test matrix with an increase of cone N<sub>2</sub> to 100 scfh).               <ul style="list-style-type: none"> <li>a. At 05:45, loaded 1,190 lbm of Cl- doped Montana #6 coal into silo.</li> <li>b. Averaged Moisture Content of product gas = 7.2 %wt.</li> </ul> </li> </ul>
10/26 (11:00) - 10/26 (23:00)	12 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #7</u> (with 3% chloride doped Montana #6 coal for DCR Test, Filter Test and test matrix with an Air/Coal (daf) of 3.82 and Steam/Coal (daf) of 0.83).               <ul style="list-style-type: none"> <li>a. At 16:14, reactor temperatures were: 1,027 (TIR-700), 1,277 (-701), 1,630 (-702), 940 (-903) and 1,027°F (-733).</li> <li>b. At 00:45, loaded 3,640 lb of Montana #7 coal into silo.</li> <li>c. Averaged Moisture Content of product gas = 8.3 %wt.</li> </ul> </li> </ul>
10/26 (23:00) - 10/27 (03:00)	4 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #8</u> (with 3% chloride doped Montana #6 coal for DCR Test, Filter Test and test matrix with an Air/Coal (daf) of 3.65 and Steam/Coal (daf) of 0.81).               <ul style="list-style-type: none"> <li>a. Reduced the reactor air flow to 940 scfh according to the test matrix planned.</li> </ul> </li> </ul>
10/27 (03:00) - (15:00)	12 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #9</u> (with Montana #7 coal for test matrix with a decrease of reactor air to 940 scfh. Air/Coal (daf) was 3.12 and steam/coal (daf) was 0.74)               <ul style="list-style-type: none"> <li>a. CO gas alarm in cell at 40 ppm.</li> <li>b. MGR was off-line from 13:16 to 13:29.</li> <li>c. Averaged Moisture Content of product gas = 8 %wt.</li> </ul> </li> </ul>
10/27 (15:00) - (21:00)	6 hr	<ul style="list-style-type: none"> <li>• <u>Test Period #10</u> (with Montana #7 coal for test matrix with an increase of reactor air to 1,000 scfh, Air/Coal (daf) = 3.17 and Steam/Coal (daf) of 0.85)</li> </ul>

<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
10/27 (21:00) - 10/28 (09:00)	12 hr	<ul style="list-style-type: none"> <li>a. At 19:16, the Neotronics monitor carried by a technician detected 15 ppm CO and ES&amp;H personnel was called in but detected no leak around the baghouse.</li> <li>b. Averaged Moisture Content in product gas = 9 %wt.</li> </ul>
		<ul style="list-style-type: none"> <li>• <u>Test Period #11</u> (with Montana #7 coal for test matrix with an increase of reactor pressure (PIR-713) to 440 psig) <ul style="list-style-type: none"> <li>a. At 23:12, had problems with the steam flow and gas leak in cell (getting worse). Thus, reduced reactor pressure back to 425 psig.</li> <li>b. At 00:10, increased cone N<sub>2</sub> from 100 to 200 scfh (an additional study in the Test Matrix).</li> <li>c. At 07:20, discovered steam flow creeping up from 55 to 70 lb/h. Reduced to 55 lb/h, but it crept back up 60 lb/h within 10 min. Again reduced it to 58 lb/h but discovered TIR-702 creeping up to 1,698°F. Stopped reducing steam and watch TIR-702 closely.</li> <li>d. Averaged Moisture Content of product gas = 7.2 %wt.</li> </ul> </li> </ul>
10/28 (09:00) - (13:30)	4 hr 30 min.	<ul style="list-style-type: none"> <li>• <u>Test Period #12</u> (with Montana #7 coal for test matrix with a decrease of reactor pressure to 400 psig) <ul style="list-style-type: none"> <li>a. At 09:00, CO alarm on 3rd level in cell went off at 35 ppm.</li> <li>b. At 09:03, reduced reactor pressure down to 400 psig and cone N<sub>2</sub> flow from 200 to 100 scfh, keeping underflow N<sub>2</sub> at 300 scfh, causing the reactor pressure to swing for about 10 min. before it stabilized at 400 psig.</li> <li>c. At 09:05, the bed slumped (PDIR-706) which stopped the underflow N<sub>2</sub> about 15 min. The product gas flow also varied between 2,000 to 9,000 scfh during this 15 min.</li> <li>d. At 09:30, steam flow declined from 62 to 30 lb/h in 35 min. and raised back to 58 lb/h afterward.</li> <li>e. At 10:35, MGCR got off-line to remove sorbent and switch filter vessels and clean the plugged incinerator lines.</li> <li>f. At 10:50, TIR-700 went up to 1,962°F. Reduced reactor air to 950 scfh and increase steam to 70 lb/h. Brought reactor pressure down to 425 psig to alleviate the overheating problem but failed.</li> <li>g. Averaged Moisture Content of product gas = 9 %wt.</li> </ul> </li> </ul>


<u>Date (Time)</u>	<u>Duration</u>	<u>Description of Events</u>
10/28 (13:30) - 10/29 (08:00)	18 hr 30 min.	<ul style="list-style-type: none"> <li>• <u>Quick Controlled Shutdown</u> (due to clinker formation and completely plugging in overflow line)               <ul style="list-style-type: none"> <li>a. Changed convey and reactor air to N<sub>2</sub>.</li> <li>b. Turned off coal feeder and N<sub>2</sub> preheater.</li> <li>c. Bypassed steam from reactor.</li> <li>d. Weighed and secured all barrels of solids.</li> <li>e. Shut off portable boiler and incinerator.</li> </ul> </li> <li>f. Transferred all solids from silo through batch into feed hopper.</li> <li>g. Blew out all vent lines with HV-950 for 10 sec.</li> <li>h. Shut all N<sub>2</sub> and air header valves.</li> <li>i. Removed the center (3/4") feed nozzle from reactor bottom.</li> <li>j. Calibrated coal feeder ("A") with Montana #7 coal.</li> <li>k. Dropped the reactor bottom and found a few clinkers adhered on the reactor wall and filled up the insert.</li> </ul>
Total Gasification Time = 95 hr 44 min. Entire Test Period = 128 hrs.		Test Matrix Time = 94 hr 30 min. No. of Test Periods = 11





#### Appendix 4: Daily Process Variable Plots

93MGC04	(05/17/93 - 05/26/93)
93MGC05	(08/02/93 - 08/13/93)
93MGC06	(11/01/93 - 11/09/93)
94MGC07	(06/06/94 - 06/15/94)
94MGC08	(07/18/94 - 07/27/94)
94MGC09	(09/12/94 - 09/16/94)
94MGC10	(10/24/94 - 10/28/94)




The following trend charts were created for runs 93MGC04 through 94MGC10. Although the charts contain several process variables, only FIR-501, TIR-248, TIR-224, PIR-247, PIR-458 and, PDIR- (also shown as PDT- or PIR-)155 and 459 are relevant. The table below provides a description of each of these process variables.


<u>Process Variable</u>	<u>Description</u>
FIR-501	Cumulative syngas volumetric flow rate to the filtration vessel and the particle measurement system
TIR-248	Inlet gas temperature of the filtration vessel
TIR-224	Outlet gas temperature of the filtration vessel
PIR-247	Inlet gas pressure of the filtration vessel
PIR-458	Filter blowback pressure
PDIR-155	Differential pressure of the filtration vessel
PDIR-459	Differential pressure of the filter

All other process variables may be referenced through the process and instrumentation diagrams provided.

Since the needs of the project have changed somewhat from run to run, the trend charts have also changed somewhat. However, these changes are not major ones and the charts have been separated by run number and arranged in the order listed above for convenience.




**93MGC04**  
**(05/17/93 - 05/26/93)**




# Inlet and Process Flow

05/16/93



# Inlet and Process Flow

05/17/93




● FIR-501 + FIR-260



# Inlet and Process Flow


05/18/93



● FIR-501 + FIR-260

# Inlet and Process Flow


05/19/93



● FIR-501 + FIR-260


# Inlet and Process Flow

05/20/93



# Inlet and Process Flow


05/21/93



● FIR-501 + FIR-260


# Inlet and Process Flow

05/22/93



# Inlet and Process Flow

05/23/93




Time

● FIR-501 + FIR-260

# Inlet and Process Flow

05/24/93




Time

●-FIR-501 +FIR-260

FX0524.CHT Lotus: F501Run4.WK1

# Inlet and Process Flow

05/25/93




Time

●-FIR-501 +FIR-260



# Inlet and Process Flow

## 05/26/93




●- FIR-501 + FIR-260

FX0526.CHT Lotus: F501Run4.WK1

# Process Gas Line Temp.


05/17/93



● TIR-321 + TIR-320 ▲ TIR-319 ⊞ TIR-317 ⊙ TIR-318 ◆ TIR-248

# Process Gas Line Temp.


05/18/93



● TIR-321 + TIR-320 ★ TIR-319 ⊠ TIR-317 ⊙ TIR-318 ◆ TIR-248

# Process Gas Line Temp.


05/19/93



● TIR-321 + TIR-320 ▲ TIR-319 ◻ TIR-317 ○ TIR-318 ◆ TIR-248

# Process Gas Line Temp.


05/20/93



MIT0520.CHT Lotus: MIT51728.WK1

# Process Gas Line Temp.

05/21/93




Time

●-TIR-321 +TIR-320 ▲TIR-319 ⊕TIR-319 ⊖TIR-317 ⊖TIR-318 ◆TIR-248

# Process Gas Line Temp.

05/22/93




●-TIR-321 ▲-TIR-320 ▲-TIR-319 ◻-TIR-317 ◊-TIR-318 ◆-TIR-248

MIT0522.CHT Lotus: MITS1728.WK1

# Process Gas Line Temp.

05/23/93




● TIR-321 + TIR-320 ▲ TIR-319 ⊖ TIR-317 ⊖ TIR-318 ◆ TIR-248



# Process Gas Line Temp.

05/24/93




● TIR-321 + TIR-320 ▲ TIR-319 ⊕ TIR-317 ⊖ TIR-318 ◆ TIR-248

MIT0524.CHT Lotus: MIT51728.WK1

# Process Gas Line Temp.


05/25/93



● TIR-321 + TIR-320 ▲ TIR-319 ■ TIR-317 ○ TIR-318 ◆ TIR-248

# Process Gas Line Temp.


05/26/93



MIT0526.CHT Lotus: MITS1728.WK1

# Process Temperatures

05/17/93




● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

MT0517.CHT Lotus: MT051728.WK1

# Process Temperatures

05/18/93




● TIR-224 + TIR-191 ◆ TIR-205 ◻ TIR-262

MT0518.CHT Lotus: MT051728.WK1

# Process Temperatures


05/19/93



● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

# Process Temperatures

05/20/93




●-TIR-224 +TIR-191 ◆TIR-205 ◻TIR-262

MT0520.CHT Lotus: MT051728.WK1

# Process Temperatures


05/21/93





# Process Temperatures


05/22/93



MT0522.CHT Lotus: MT051728.WK1

# Process Temperatures

05/23/93




Time

● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

MT0523.CHT Lotus: MT051728.WK1

# Process Temperatures


05/24/93



● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

# Process Temperatures


05/25/93



● TIR-224 + TIR-191 ◆ TIR-205 ⊠ TIR-262

# Process Temperatures

05/26/93




● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

MT0526.CHT Lotus: MT051728.WK1

# Process Pressure


05/17/93



●-PIR-254 □-PIR-247

# Process Pressure

05/18/93




● PIR-254 □ PIR-247

MP0518.CHT Lotus: MP051728.WK1

# Process Pressure

## 05/19/93




● PIR-254 □ PIR-247



# Process Pressure

## 05/20/93




Time

●-PIR-254 □-PIR-247

# Process Pressure


05/21/93



●-PIR-254 □-PIR-247

# Process Pressure

05/22/93




●-PIR-254 □-PIR-247

MP0522.CHT Lotus: MP051728.WK1

# Process Pressure

05/23/93




Time

●-PIR-254 □-PIR-247

MP0523.CHT Lotus: MP051728.WK1

# Process Pressure

05/24/93




●-PIR-254 □-PIR-247

MP0524.CHT Lotus: MP051728.WK1

# Process Pressure

05/25/93




Time

●-PIR-254 □-PIR-247

MP0525.CHT Lotus: MP051728.WK1

# Process Pressure

05/26/93




●-PIR-254 □-PIR-247

MP0526.CHT Lotus: MP051728.WK1

# Filter Blowback Pressure

05/17/93




Time

●-PIR-458



# Filter Blowback Pressure


05/18/93



MFBP0518.PRS Lotus: MBP51728.WK1

# Filter Blowback Pressure

05/19/93




Time

●-PIR-458

# Filter Blowback Pressure


05/20/93



MFBP0520.PRS Lotus: MBP51728.WK1

# Filter Blowback Pressure

05/21/93




Time

●-PIR-458

# Filter Blowback Pressure


## 05/22/93



MEBP0522.PRS Lotus: MBP51728.WK1


# Filter Blowback Pressure

05/23/93



# Filter Blowback Pressure

05/24/93




Time

●-PIR-458

MFBP0524.PRS Lotus: MBP51728.WK1

# Filter Blowback Pressure

05/25/93




Time

●-PIR-458



# Filter Blowback Pressure


05/26/93



MFBP0526.PRS Lotus: MBP51728.WK1

# F-100 Differential Pressure


05/17/93



●-PDT-155

# K-100 Differential Pressure


05/18/93



MFD0518.CHT Lotus: PD051728.WK1

# F-100 Differential Pressure


05/19/93



●-PDT-155

# H-100 Differential Pressure


## 05/20/93



MFDP0520.CHT Lotus: PD051728.WK1


# F-100 Differential Pressure

05/21/93



# K-100 Differential Pressure


05/22/93



MFD0522.CHT Lotus: PD051728.WKI

# F-100 Differential Pressure


05/23/93





# K-100 Differential Pressure


05/24/93



MFDP0524.CHT Lotus: PD051728.WK1

# F-100 Differential Pressure

05/25/93




Time

●-PDT-155


# F-100 Differential Pressure

05/26/93




# F-100 Filter Diff. Press.

05/17/93



# K-100 Filter Diff. Press.


05/18/93



MDFFP0518.CHT Lotus: PD051728.WK1


# F-100 Filter Diff. Press.

05/19/93




# K-100 Filter Diff. Press.

05/20/93



# F-100 Filter Diff. Press.

05/21/93




●-PDT-459




# K-100 Filter Diff. Press.

05/22/93




# F-100 Filter Diff. Press.

05/23/93



# K-100 Filter Diff. Press.

05/24/93




Time

●-PDT-459


MDFP0524.PRS Lotus: PD051728.WK1

# F-100 Filter Diff. Press.


05/25/93








**93MGC05**  
**(08/02/93 - 08/13/93)**





# Inlet and Process Flow

08/02/93




●-FIR-501 ×-FIR-260

F5010802.CHT Lotus: 5CORF501.WKI

# Inlet and Process Flow


08/03/93



●-FIR-501 ×-FIR-260

# Inlet and Process Flow

08/04/93




●-FIR-501 ×-FIR-260

F5010804.CHT Lotus: 5CORF501.WK1

# Inlet and Process Flow

08/05/93




Time

● FIR-501    × FIR-260

# Inlet and Process Flow


08/06/93



F5010806.CHT Lotus: SCORF501.WK1

# Inlet and Process Flow


08/07/93



● FIR-501 × FIR-260

# Inlet and Process Flow

08/08/93




●-FIR-501 ×-FIR-260

F5010808.CHT Lotus: 5CORF501.WKI

# Inlet and Process Flow

08/09/93




● FIR-501 × FIR-260



# Inlet and Process Flow

08/10/93




●-FIR-501 ✕FIR-260

F5010810.CHT Lotus: 5CORF501.WK1

# Inlet and Process Flow

08/11/93




Time

● FIR-501    ✕ FIR-260

# Inlet and Process Flow


08/12/93



F5010812.CHT Lotus: SCORF501.WKI

# Inlet and Process Flow


08/13/93



● FIR-501 × FIR-260

# Process Gas Line Temp.

08/02/93




● TIR-321 + TIR-320 ▲ TIR-319 ◻ TIR-317 ◉ TIR-318 ◆ TIR-248

MIT0802.CHT Lotus: MIT80213.WK1

# Process Gas Line Temp.

08/03/93




Time

●-TIR-321 + TIR-320 ▲ TIR-319 ◻ TIR-317 ◯ TIR-318 ◆ TIR-248

# Process Gas Line Temp.


08/04/93



● TIR-321 + TIR-320 ▲ TIR-319 ◻ TIR-317 ◯ TIR-318 ◆ TIR-248

# Process Gas Line Temp.

08/05/93




● TR-321 + TR-320 ▲ TR-319 ◻ TR-317 ◊ TR-318 ◆ TR-248



# Process Gas Line Temp.


08/06/93



● TIR-321 + TIR-320 ▲ TIR-319 ◻ TIR-318 ◯ TIR-318 ◆ TIR-248

# Process Gas Line Temp.


08/07/93



●-TIR-321 + TIR-320 ▲ TIR-319 ◻ TIR-318 ◊ TIR-248

# Process Gas Line Temp.

08/08/93




●-TIR-321 +TIR-320 ▲TIR-319 ◻TIR-318 ◊TIR-317 ◊TIR-318 ◆TIR-248

MIT0808.CHT Lotus: MIT80213.WK1

# Process Gas Line Temp.

08/09/93




Time

● TIR-321 ▲ TIR-320 □ TIR-319 ○ TIR-317 ⊖ TIR-318 ◆ TIR-248

# Process Gas Line Temp.

08/10/93




● TIR-321 + TIR-320 ▲ TIR-319 ◻ TIR-318 ◉ TIR-248

MIT0810.CHT Lotus: MIT80213.WK1

# Process Gas Line Temp.


08/11/93



●-TIR-321 + TIR-320 ▲ TIR-319 ⊕ TIR-317 ⊖ TIR-318 ◆ TIR-248

# Process Gas Line Temp.


08/12/93



MIT0812.CHT Lotus: MIT80213.WK1

# Process Gas Line Temp.


08/13/93





# Process Temperatures

08/02/93




● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

MT0802.CHT Lotus: MT080213.WK1

# Process Temperatures


08/03/93



● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

# Process Temperatures

08/04/93




● TIR-224 + TIR-191 ◆ TIR-205 ◻ TIR-262

MT0804.CHT Lotus: MT080213.WK1

# Process Temperatures


08/05/93



● TIR-224 + TIR-191 ◆ TIR-205 ◻ TIR-262

# Process Temperatures

08/06/93




● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

MT0806.CHT Lotus: MT080213,WK1

# Process Temperatures

08/07/93




Time

● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

MT0807.CHT Lotus: MT080213.WKI

# Process Temperatures

## 08/08/93




●-TIR-224 +TIR-191 ◆TIR-191 ◆TIR-205 ⊖TIR-262

MT0808.CHT Lotus: MT080213.WK1

# Process Temperatures

08/09/93




● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262



# Process Temperatures

08/10/93




●-TIR-224 +TIR-191 ◆-TIR-205 ◻-TIR-262

MT0810.CHT Lotus: MT080213.WK1

# Process Temperatures


08/11/93



MT0811.CHT Lotus: MT080213.WK1

# Process Temperatures

## 08/12/93




● TIR-224 + TIR-191 ◆ TIR-205 □ TIR-262

MT0812.CHT Lotus: MT080213.WK1

# Process Temperatures


08/13/93



● TIR-224 + TIR-191 ◆ TIR-205 ◻ TIR-262

# Process Pressure

08/02/93




●-PIR-254 □-PIR-247

MP0802.CHT Lotus: MP080213.WK1

# Process Pressure


## 08/03/93



● PIR-254 □ PIR-247

# Process Pressure

08/04/93




●-PIR-254 □-PIR-247

MP0804.CHT Lotus: MP080213.WK1

# Process Pressure

08/05/93




●-PIR-254 □-PIR-247



# Process Pressure

08/06/93




●-PIR-254 □-PIR-247

MP0806.CHT Lotus: MP080213.WK1

# Process Pressure

08/07/93




Time

●-PIR-254 □-PIR-247

MP0807.CHT Lotus: MP080213.WK1

# Process Pressure

08/08/93




●-PIR-254 □-PIR-247

MP0808.CHT Lotus: MP080213.WK1

# Process Pressure


08/09/93



●-PIR-254 □-PIR-247

# Process Pressure

08/10/93




●-PIR-254 □-PIR-247

MP0810.CHT Lotus: MP080213.WK1

# Process Pressure


08/11/93



● PIR-254 □ PIR-247

# Process Pressure

08/12/93




●-PIR-254 □-PIR-247

MP0812.CHT Lotus: MP080213.WKI

# Process Pressure

08/13/93




●-PIR-254 □-PIR-247



# Filter Blowback Pressure


08/02/93



MFBP0802.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure


08/03/93



●-PIR-458

# Filter Blowback Pressure

08/04/93




Time

●-PIR-458

MFBP0804.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure

08/05/93




●-PIR-458

MFBP0805.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure

08/06/93




● PIR-458

MFBP0806.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure

08/07/93




Time

●-PIR-458

MFBP0807.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure

08/08/93




Time

●-PIR-458

MFBP0808.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure

08/09/93




● PIR-458



# Filter Blowback Pressure


08/10/93



MF8P0810.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure

08/11/93




●-PIR-458

MFBP0811.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure

08/12/93




●-PIR-458

MFBP0812.CHT Lotus: MBP80213.WK1

# Filter Blowback Pressure

08/13/93




●-PIR-458

MFBP0813.CHT Lotus: MBP80213.WK1

# F-100 Differential Pressure


08/02/93



MFD0802.CHT Lotus: PD080213.WK1

# F-100 Differential Pressure

08/03/93




Time

●-PDT-155

# F-100 Differential Pressure


08/04/93



MFD0804.CHT Lotus: PD080213.WK1

# F-100 Differential Pressure


08/05/93





# F-100 Differential Pressure


08/06/93



MFDP0806.CHT Lotus: PD080213.WK1

# F-100 Differential Pressure


08/07/93



MFDP0807.CHT Lotus: PD080213.WK1

# K-100 Differential Pressure


08/08/93



MFDP0808.CHT Lotus: PD080213.WK1


# F-100 Differential Pressure

08/09/93



# F-100 Differential Pressure


08/10/93



MFDP0810.CHT Lotus: PD080213.WK1

# F-100 Differential Pressure

08/11/93




●-PDT-155

MFDP0811.CHT Lotus: PD080213.WK1

# F-100 Differential Pressure


08/12/93



MFD0812.CHT Lotus: PD080213.WK1

# F-100 Differential Pressure

## 08/13/93




MFDP0813.CHT Lotus: PD080213.WK1



# F-100 Filter Diff. Press.

08/02/93




●-PDT-459

MDFP0802.CHT Lotus: PD080213.WK1

# F-100 Filter Diff. Press.

08/03/93




● PDT-459

MDFP0803.CHT Lotus: PD080213.WK1

# F-100 Filter Diff. Press.

08/04/93




Time

●-PDT-459

MDFP0804.CHT Lotus: PD080213.WK1


# F-100 Filter Diff. Press.

08/05/93



# F-100 Filter Diff. Press.

08/06/93




●-PDT-459

MDFP0806.CHT Lotus: PDF80213.WK1

# F-100 Filter Diff. Press.

08/07/93




Time

●-PDT-459

# K-100 Filter Diff. Press.


08/08/93



MDFP0808.CHT Lotus: PD080213.WK1

# F-100 Filter Diff. Press.

08/09/93




●-PDT-459



# F-100 Filter Diff. Press.


08/10/93



MDFP0810.CHT Lotus: PD080213.WK1

# F-100 Filter Diff. Press.


08/11/93



MDFP0811.CHT Lotus: PD080213.WK1

# K-100 Filter Diff. Press.


08/12/93



MDFP0812.CHT Lotus: PD080213.WK1

# F-100 Filter Diff. Press.


08/13/93



●-PDT-459


MDFP0813.CHT Lotus: PD080213.WKI

**93MGC06**  
**(11/01/93 - 11/09/93)**




# Inlet and Process Flow

11/01/93



# Inlet and Process Flow Rate


11/02/93






# Inlet and Process Flow Rate

11/03/93



# Inlet and Process Flow Rate


11/04/93



●-FIR-501 +FIR-260

# Inlet and Process Flow Rate


## 11/05/93



FX1105.CHT Lotus: FX110111.WK1

# Inlet and Process Flow Rate

11/06/93




Time

●-FIR-501 +FIR-260

# Inlet and Process Flow Rate

11/07/93




●-FIR-501 +-FIR-260

FX1107.CHT Lotus: FX110111.WK1

# Inlet and Process Flow Rate

11/08/93




Time

● FIR-501 + FIR-260


# Inlet and Process Flow Rate

11/09/93



# MGCR Gas Line Temps.

11/01/93




◆ TIR-320 ● TIR-318 ○ TIR-248 □ TIR-224

ML1101.CHT Lotus: ML110110.WK1



# MGCR Gas Line Temps.

11/02/93




◆ TIR-320 ● TIR-318 ○ TIR-248 □ TIR-224

ML1102.CHT Lotus: ML110110.WK1

# MGCR Gas Line Temps.


11/03/93



◆ TIR-320 ● TIR-318 ○ TIR-248 ◻ TIR-224

# MGCR Gas Line Temps.


11/04/93



ML1104.CHT Lotus: ML110110.WK1

# MGCR Gas Line Temps.

11/05/93




Time

◆ TIR-320 ● TIR-318 ○ TIR-248 □ TIR-224

ML1105.CHT Lotus: ML110110.WK1

# MGCR Gas Line Temps.

11/06/93




◆ TIR-320 ● TIR-318 ○ TIR-248 □ TIR-224

ML1106.CHT Lotus: ML110110.WK1

# MGCR Gas Line Temps.

11/07/93




◆ TIR-320 ● TIR-318 ○ TIR-248 ▽ TIR-224

ML1107.CHT Lotus: ML110110.WK1

# MGCR Gas Line Temps.


11/08/93



ML1108.CHT Lotus: ML110110.WK1

# MGCR Gas Line Temps.

11/09/93




◆ TIR-320 ● TIR-318 ○ TIR-248 □ TIR-224



# MGCR Process Pressures


11/01/93



MP1101.CHT Lotus: MP110110.WK1

# MGCR Process Pressures

11/02/93




Time

◆ PIR-247 ● PIR-254 ○ PIR-458

# MGCR Process Pressures

11/03/93




◆ PIR-247 ● PIR-254 ○ PIR-458

MP1103.CHT Lotus: MP110110.WK1

# MGCR Process Pressures


11/04/93



◆-PIR-247 ●-PIR-254 ○-PIR-458

# MGCR Process Pressures

11/05/93




Time

MP1105.CHT Lotus: MP110110.WK1

# MGCR Process Pressures

11/06/93




◆ PIR-247 ● PIR-254 ○ PIR-458

MP1106.CHT Lotus: MP110110.WK1

# MGCR Process Pressures

11/07/93




◆ PIR-247 ● PIR-254 ○ PIR-458

MP1107.CHT Lotus: MP110110.WK1

# MGCR Process Pressures

11/08/93




◆ PIR-247 ● PIR-254 ○ PIR-458



# MIGCK Process Pressures

## 11/09/93




◆ PIR-247   ● PIR-254   ○ PIR-458

MPI1109.CHT Lotus: MPI110110.WKI

# MGCR Differential Press.

11/01/93




Time

◆-PDT-155 ●-PDT-242

# MGCK Differential Press.


11/02/93



PD1102.CHT Lotus: PD110110.WK1

# MGCR Differential Press.


11/03/93



PDI103.CHT Lotus: PDI10110.WKI

# MGCR Differential Press.


11/04/93



PD1104.CHT Lotus: PD110110.WK1

# MGCR Differential Press.


11/05/93



◆ PDT-155    ● PDT-242

# MGCK Differential Press.

11/06/93




◆-PDT-155 ●-PDT-242

PD1106.CHT Lotus: PD110110.WK1

# MGCR Differential Press.

11/07/93



Time


◆-PDT-155 ●-PDT-242

PD1107.CHT Lotus: PD110110.WK1



# MGCK Differential Press.


11/08/93



PD1108.CHT Lotus: PD110110.WK1

# MGCR Differential Press.

11/09/93




◆-PDT-155    ●-PDT-242

**PDIR-459**

**was not in use**

**during**

**Run 93MGC06.**




**94MGC07**  
**(06/06/94 - 06/15/94)**




# MCCR INLET AND EXIT FLOWS

## 94MGC07 - 06/06/94



# MGCR INLET AND EXIT FLOWS


## 94MGCC07 - 06/07/94






# MCCR INLET AND EXIT FLOWS


## 94MGC07 - 06/08/94



MGCR INLET AND EXIT FLOWS  
 94MGCC07 - 06/09/94




MGCR INLET AND EXIT FLOWS  
 94MGC07 - 06/10/94




# MGCR INLET AND EXIT FLOWS

## 94MGC07 - 06/11/94




# MGCR INLET AND EXIT FLOWS

## 94MGC07 - 06/12/94




MGCR INLET AND EXIT FLOWS  
 94MGC07 - 06/13/94




# MGCRC INLET AND EXIT FLOWS

## 94MGC07 - 06/14/94



# MGCR INLET AND EXIT FLOWS


## 94MGC07 - 06/15/94






# MGCR PROCESS GAS LINE TEMPERATURES

## 94MGCC07 - 06/06/94




# MGCR PROCESS GAS LINE TEMPERATURES

## 94MGC07 - 06/07/94




# MGCR PROCESS GAS LINE TEMPERATURES

94MGC07 - 06/08/94




# MGCR PROCESS GAS LINE TEMPERATURES

94MGC07 - 06/09/94




# MGCR PROCESS GAS LINE TEMPERATURES


94MGCC07 - 06/10/94




**MGCR PROCESS GAS LINE TEMPERATURES**  
**94MGC07 - 06/11/94**



MGCR PROCESS GAS LINE TEMPERATURES  
 94MGC07 - 06/12/94




MGCR PROCESS GAS LINE TEMPERATURES  
94MGC07 - 06/13/94







# MGCR PROCESS GAS LINE TEMPERATURES 94MGC07 - 06/14/94




MGCR PROCESS GAS LINE TEMPERATURES  
 94MGC07 - 06/15/94



FBG & MGCR PROCESS PRESSURES  
 94FBG07 - 94MGC07 - 06/06/94



**FBG & MCCR PROCESS PRESSURES**  
**94FBG07 - 94MGC07 - 06/07/94**



**FBG & MGR PROCESS PRESSURES**  
**94FBG07 - 94MGC07 - 06/08/94**






Chart1 (4)

FBG & MGCR PROCESS PRESSURE  
RUN 07, 06/09/94



FBG & MCCR PROCESS PRESSURE  
RUN 07, 06/10/94



PIR-713  
PIR-247  
PIR-254  
PIR-458

Chart1 (6)

FBG & MCCR PROCESS PRESSURE  
RUN 07, 06/11/94








Chart1 (7)

FBG & MGCRCR PROCESS PRESSURE  
RUN 07, 06/12/94




◆ PIR-713  
□ PIR-247  
△ PIR-254  
× PIR-458

FBG & MGCR PROCESS PRESSURES  
 94FBG07 - 94MGC07 - 06/13/94




FBG & MGCR PROCESS PRESSURES  
 94FBG07 - 94MGCC07 - 06/14/94




# FBG & MGCR PROCESS PRESSURES


## 94FBG07 - 94MGCC07 - 06/15/94




MGCR F-100 DIFFERENTIAL PRESSURE  
94MGCC07 - 06/06/94




MGCR F-100 DIFFERENTIAL PRESSURE  
94MGCC07 - 06/07/94



MGCR F-100 DIFFERENTIAL PRESSURE  
94MGCC07 - 06/08/94




MGCR F-100 DIFFERENTIAL PRESSURE  
94MGC07 - 06/09/94






MGCR F-100 DIFFERENTIAL PRESSURE  
94MGC07 - 06/10/94




MGCR F-100 DIFFERENTIAL PRESSURE  
94MGC07 - 06/11/94




# MGCR F-100 DIFFERENTIAL PRESSURE


94MGC07 - 06/12/94




MGCR F-100 DIFFERENTIAL PRESSURE  
94MGC07 - 06/13/94




MGCR F-100 DIFFERENTIAL PRESSURE  
94MGC07 - 06/14/94



MGCR F-100 DIFFERENTIAL PRESSURE  
94MGC07 - 06/15/94




**94MGC08**  
**(07/18/94 - 07/27/94)**







MGCR Inlet and Exit Flows  
Run 94MGCC08, 07/18/94




MGCR Inlet and Exit Flows  
Run 94MGCC08, 07/19/94




MGCR Inlet and Exit Flows  
Run 94MGCC08, 07/20/94




MGCR Inlet and Exit Flows  
Run 94MGCC08, 07/21/94




MGCR Inlet and Exit Flows  
Run 94MGCC08, 07/22/94




MGCR Inlet and Exit Flows  
Run 94MGC08, 07/23/94



MGCR Inlet and Exit Flows  
Run 94MGCC08, 07/24/94




MGCR Inlet and Exit Flows  
Run 94MGC08, 07/25/94




◆ FIR501-R  
■ FIR-260  
▲ FIR-211




MGCR Inlet and Exit Flows  
Run 94MGC08, 07/26/94




MGCR Inlet and Exit Flows  
 Run 94MGC08, 07/27/94




MGCR Process Gas Line Temperatures  
Run 94MGCC08, 07/18/94




MGCR Process Gas Line Temperatures  
Run 94MGCC08, 07/19/94




MGCR Process Gas Line Temperatures  
Run 94MGC08, 07/20/94




MGCR Process Gas Line Temperatures  
Run 94MGC08, 07/21/94



MGCR Process Gas Line Temperatures  
Run 94MGC08, 07/22/94




MGCCR Process Gas Line Temperatures  
Run 94MGC08, 07/23/94







MGCR Process Gas Line Temperatures  
Run 94MGCC08, 07/24/94




MGCR Process Gas Line Temperatures  
Run 94MGCC08, 07/25/94



MGCR Process Gas Line Temperatures  
Run 94MGC08, 07/26/94




MGCR Process Gas Line Temperatures  
Run 94MGC08, 07/27/94




# MCCR and FBG Process Pressures

## Run 94MGC08, 07/18/94




MGCR and FBG Process Pressures  
Run 94MGCC08, 07/19/94




□ PIR-713  
○ PIR-254  
△ PIR-247  
◇ PIR-458

MGCR and FBG Process Pressures  
 Run 94MGCC08, 07/20/94




MGCR and FBG Process Pressures  
Run 94MGCC08, 07/21/94






MGCR and FBG Process Pressures  
Run 94MGC08, 07/22/94




MGCR and FBG Process Pressures  
Run 94MGCC08, 07/23/94




PIR-713  
PIR-254  
PIR-247  
PIR-458

MGCR and FBG Process Pressures  
Run 94MGCC08, 07/24/94




MGCR and FBG Process Pressures  
Run 94MGCC08, 07/25/94




□ PIR-713  
○ PIR-254  
△ PIR-247  
◇ PIR-458

MGCR and FBG Process Pressures  
Run 94MGC08, 07/26/94




PIR-713  
PIR-254  
PIR-247  
PIR-458


MGCR and FBG Process Pressures  
Run 94MGCC08, 07/27/94



F-100 Differential Pressure  
Run 94MGC08, 07/18/94




F-100 Differential Pressure  
Run 94MGC08, 07/19/94







F-100 Differential Pressure  
Run 94MGC08, 07/20/94




F-100 Differential Pressure  
Run 94MGC08, 07/21/94




F-100 Differential Pressure  
Run 94MGC08, 07/22/94




F-100 Differential Pressure  
Run 94MGC08, 07/23/94




F-100 Differential Pressure  
Run 94MGC08, 07/24/94




F-100 Differential Pressure  
Run 94MGC08, 07/25/94



F-100 Differential Pressure  
Run 94MGCC08, 07/26/94




**F-100 Differential Pressure  
Run 94MGC08, 07/27/94**







**94MGC09**  
**(09/12/94 - 09/16/94)**




MGCR Inlet and Exit Flows  
 Run 94MGCC09, 09/12/94




MGCR Inlet and Exit Flows  
 Run 94MGC09, 09/13/94




MGCR Inlet and Exit Flows  
Run 94MGCC09, 09/14/94




MGCR Inlet and Exit Flows  
 Run 94MGCC09, 09/15/94



MGCR Inlet and Exit Flows  
Run 94MGCC09, 09/16/94




MGCR Process Gas Line Temperatures  
 Run 94MGCC09, 09/12/94







MGCR Process Gas Line Temperatures  
 Run 94MGCC09, 09/13/94




MGCR Process Gas Line Temperatures  
Run 94MGCC09, 09/14/94



MGCR Process Gas Line Temperatures  
Run 94MGCC09, 09/15/94




MGCR Process Gas Line Temperatures  
Run 94MGCC09, 09/16/94




◆ TIR-320B  
■ TIR-318B  
▲ TIR-224B  
× TIR-248B


FBG and MGCRC Process Pressures  
 Run 94FBG09, 09/12/94




FBG and MGCR Process Pressures  
 Run 94FBG09, 09/13/94



FBG and MGCR Process Pressures  
Run 94FBG09, 09/14/94




FBG and MGCR Process Pressures  
Run 94FBG09, 09/15/94







FBG and MGCR Process Pressures  
Run 94FBG09, 09/16/94




F-100 Differential Pressure  
Run 94MGC09, 09/12/94




F-100 Differential Pressure  
Run 94MGC09, 09/13/94




F-100 Differential Pressure  
Run 94MGCC09, 09/14/94




F-100 Differential Pressure  
Run 94MGC09, 09/15/94



F-100 Differential Pressure  
Run 94MGCC09, 09/16/94




**94MGC10**  
**(10/24/94 - 10/28/94)**







FBG EXIT FLOWS  
RUN 94FBG10, 10/24/94




FBG EXIT FLOWS  
RUN 94FBG10, 10/25/94




FBG EXIT FLOWS  
RUN 94FBG10, 10/26/94




FBG EXIT FLOWS  
RUN 94FBG10, 10/27/94




FBG EXIT FLOWS  
RUN 94FBG10, 10/28/94




MGCR Process Gas Line Temperatures  
Run 94MGC10, 10/24/94



MGCR Process Gas Line Temperatures  
Run 94MGC10, 10/25/94




MGCR Process Gas Line Temperatures  
Run 94MGC10, 10/26/94







MGCR Process Gas Line Temperatures  
Run 94MGC10, 10/27/94




MGCR Process Gas Line Temperatures  
Run 94MGC10, 10/28/94




FBG & MGCR Process Pressures  
Run 94MGC10, 10/24/94




FBG & MGCR Process Pressures  
Run 94MGC10, 10/25/94




FBG & MGCR Process Pressures  
Run 94MGC10, 10/26/94




FBG & MGCR Process Pressures  
Run 94MGC10, 10/27/94



FBG & MGCR Process Pressures  
Run 94MGC10, 10/28/94




F-100 Differential Pressure  
Run 94MGC10, 10/24/94






F-100 Differential Pressure  
Run 94MGC10, 10/25/94




F-100 Differential Pressure  
Run 94MGC10, 10/26/94




—◆— PDIR-155  
-■- PDIR-459

F-100 Differential Pressure  
Run 94MGC10, 10/27/94




F-100 Differential Pressure  
Run 94MGC10, 10/28/94




## **Appendix 5**

### **Process and Instrumentation Drawings**










0 &  
1



TO OUTLET  
FILTRATION

REVISION


ONE	REV	DESCRIPTION						DATE
EN.	6	MODIFIED AS PER MARKED PRINT; ISSUED FOR CONSTRUCTION						5/12/94
BY	Gary Kulchock	DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
	5/18/94	S. Conko	5/18/94	Dave Lunfeld	5/24/94			
BY	W. E. Lowry	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DOE (EESD)	DATE
	5/24/94	S. Renninger	5/18/94	John Rockey	5/18/94	John Rotunda	WJA	5/18/94
ONE	REV	DESCRIPTION						DATE
EN.	7	MODIFIED AS PER MARKED PRINT; ISSUED FOR CONSTRUCTION						8/17/94
BY	TERRY MCKISIC	DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
	8/17/94	GARY KULCHOCK	8/17/94	Dave Lunfeld	8/17/94			
BY	W. E. Lowry	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DOE (EESD)	DATE
		JOHN M. ROCKEY	8/18/94	JOHN M. ROCKEY	8/18/94	John Rotunda	WJA	8/18/94
ONE	REV	DESCRIPTION						DATE
EN.	8	MODIFIED AS PER MARKED PRINT; ISSUED FOR CONSTRUCTION						9/30/94
BY	<i>W. E. Lowry</i>	DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
	<i>10-3-94</i>	<i>Gary Kulchock</i>	<i>10/3/94</i>	<i>D. Lunfeld</i>	<i>10/5/94</i>			
BY	<i>W. E. Lowry</i>	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DOE (EESD)	DATE
		<i>John Rockey</i>	<i>10/3/94</i>			<i>John Rotunda</i>	<i>WJA</i>	<i>10/5/94</i>

H

G

F

F



SET e  
340 PSIG



I-19




U-600  
PSIG

SET e  
350 PSIG  
e 90°F



SET e  
1800 DEGF



SET e  
1900 DEGF

H-102A



SET e  
1250 DEGF



0-2400  
DEGF



12C

SET e  
1900 DEGF

H-102B



SET e  
1250 DEGF



0-2400  
DEGF



120

SET e  
1900 DEGF

H-102C



SET e  
1250 DEGF



0-2400  
DEGF






VAC



VAC



600 PSIG




O/C




0-290 PSIG


O/C




I/O




I/O





CFH  
SIG  
F



TIP

—


E

←

D


—






THERMOCOUPLE WELL  
PRESSURIZATION

FROM  
F-100




80(3)8/80(1)8






4" CS PIPE  
P320 SCH 40





JACKET PURGE



V-100  
BATCH REACTOR







- NO-
- 1.
  - 2.
  - 3.
  - 4.
  - 5.

REFERENCE D


THIS DRAWING IS PART  
OF THE EG&G DOCUMENT  
CONTROL SYSTEM

C

CONNECT WITH RESEARCH  
TRIANGLE INSTITUTE (RTI)  
DWG. No. ZTFBD\_01

DWG NO  
STD920080.08  
REV  
1


IMPULSE LINES ARE 3/8 UNLESS OTHERWISE NOTED.  
EV. BLOCK RANGE (0-425).  
CURRENT BLOCK RANGE (451-499) P&ID's 1,2,3,6.  
FIRST POINT NUMBER USED 36.  
FIRST TAG NUMBER USED 493.

DRAFTER Jimmy Thorton	DATE 10/28/93	 United States Department of Energy <b>MORGANTOWN ENERGY TECHNOLOGY CENTER</b> Morgantown, WV			
PROJECT ENGINEER John Rockey	DATE 11/2/93				
REQUESTOR John Rockey	DATE 11/2/93				
BRANCH MANAGER Larry Strickland	DATE 11/2/93	TITLE <b>B-12 ADVANCED GASIFICATION FACILITY          MODULAR GAS CLEANUP RIG (MGCR)          PROCESS AND INSTRUMENTATION          DRAWING (P&amp;ID1) BATCH MODE</b>			
DOE WJA John Rotunda	DATE 10/28/93				
	DATE	SIZE E	FSCM NO	DWG NO STD920080.08	REV 8

A

H

G



PS 80


Z 1

FC

VENT

-----







REG 1  
REG 2  
REG 3

M

80(2)2/80(3)2


80(2)3/80(3)3

80(2)4/80(3)4

80(2)5/80(3)5

### F-100 FILTER PURGES


AIR HOSE











TE 77A TE 77B TIR 77

CCv=1.84  
ACv=2.0  
FV FC  
68

TE 74  
FV FC  
72  
CCv=0.037  
ACv=0.053

HV 23

0-600  
PSIG  
PI 33


FSV 454

### VESSEL PURGE AND THERMOCOUPLE PRESSURIZATION


SS TUBE SCH STD 80(2)7/80(1)7



LOCKHOPPERS 80(2)31/930031

TIR







TTR











THIS DRAWING IS PART  
OF THE EG&G DOCUMENT  
CONTROL SYSTEM

REFERENCE DRAWINGS	DRAFTER	Jimi
	PROJECT L	Jo
	REQUESTOR	Jo.
	BRANCH M	Larr
	ESBH	
	DOE	Joh

TE  
187

80(2)6/80(3)6

**N2 PREHEAT AND  
FLUIDIZING**


C

16 --- 208VAC


NOTES:

1. ALL IMPULSE LINES 3/8" SS UNLESS OTHERWISE NOTED
- 2.
- 3.

DVG NO  
 STD920080.07  
 SH  
 2

DRAFTER Jimmy Thorton	DATE 10/28/93	 United States Department of Energy <b>MORGANTOWN ENERGY TECHNOLOGY CENTER</b> Morgantown, WV			
PROJECT ENGINEER John Rockey	DATE 11/2/93				
REQUESTOR - John Rockey	DATE 11/2/93				
BRANCH MANAGER Larry Strickland	DATE 11/2/93	TITLE <b>B-12 ADVANCED GASIFICATION FACILITY          MODULAR GAS CLEANUP RIG (MGCR)          PROCESS AND INSTRUMENTATION          DRAWING (P&amp;ID2) FACILITY SERVICES</b>			
ESLH	DATE				
DOE WJA John Rotunda	DATE 10/28/93				
	DATE	SIZE E	FSCM NO	DVG NO STD920080.07	REV 7


A




**NOTES:**

1. ALL IMPULSE LINES ARE 3/8" SS UNLESS OTHERWISE NOTED.
- 2.
- 3.

C  
DVG NO STD920080.07 SH 3


DRAFTER Jimmy Thorton	DATE 10/28/93	 <p>United States Department of Energy MORGANTOWN ENERGY TECHNOLOGY CENTER Morgantown, WV</p>			
PROJECT ENGINEER John Rockey	DATE 11/2/93				
REQUESTOR John Rockey	DATE 11/2/93				
BRANCH MANAGER Larry Strickland	DATE 11/2/93				
ES&H	DATE				
DOE WJA John Rotunda	DATE 10/28/93				
TITLE B-12 ADVANCED GASIFICATION FACILITY MODULAR GAS CLEANUP RIG (MGCR) PROCESS AND INSTRUMENTATION DRAWING (P&ID3) GAS TRANSPORT SYSTEM					
	DATE	SIZE E	FSCH NO	DVG NO STD920080.07	REV 7
	DATE	SCALE NONE	WEIGHT MGCR0307.DWG	SHEET 3 of 6	

A





F-100  
PARTICULATE FILTER

THIS DRAWING IS  
OF THE EG&G DOCUMENT  
CONTROL SYSTEM



208VAC

I-12



1" SS P7 SCH

TE  
318

FROM PIC-254  
V-100 OUTLET

80(1)10/80(3)10

H-103E

0-600 PSIG

PI  
461

0-2400  
DEGF

TIC  
177

TE  
177A

TIR  
177

JZ  
177

SET 1125F

TIK  
177

TAH  
177

FROM N2  
PREHEATERS

80(2)6/80(1)6

I-18


ZONE-2

208VAC

TR  
318


TE  
318

TO ALKALI  
SAMPLE SYSTEM  
AND PMS SYSTEM




0-600 PSIG

PI  
461




FROM N2  
PREHEATERS









E



D













H-1030

ZONE-3




H-1030

ZONE	REV	DESCRIPTION					DATE	
GEN.	6	MODIFIED AS PER MARKED PRINT; ISSUED FOR CONSTRUCTION					5/16/94	
RAFTER	JARY J. KULCHOCK	DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
		5/18/94	S. CONKO	5/18/94	DAVID LUNIFELD	5/24/94		
J&G ES&H	J.E. LOWRY	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DOE GEOSD	DATE
		5/24/94	S. RENNINGER	5/18/94	JOHN M. ROCKEY	5/18/94	WJA JOHN R. ROTUNDA	5/18/94
ZONE	REV	DESCRIPTION					DATE	
GEN.	7	MODIFIED AS PER MARKED PRINT; ISSUED FOR CONSTRUCTION					9/30/94	
RAFTER	<i>J. J. Kulchock</i>	DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
		10-3-94	<i>J. J. Kulchock</i>	10/3/94	<i>David Lunifeld</i>	10/5/94		
J&G ES&H	<i>J. E. Lowry</i>	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DOE GEOSD	DATE
		10/11/94	<i>S. Renninger</i>	10/11/94			<i>WJA</i>	10/15/94


H

G




TO BE ADDED FOR CONTINUOUS MODE OPERATIONS




F









FILTER BLOWBACK LINES







ZONE-5





H-103A

ZON






H


G

F




H

G



TO BE ADDED FOR CONTINUOUS MODE



1/2" SS TUBE  
P11 SCH STD


3/4"  
P48

TI  
192

TE  
192A


TE  
192B

TIR  
192



ZONE	REV		
GEN.	6	MODIFIED AS PER MARKED PRINT; IS	
DRAFTER	GARY J. KULCHOCK	DATE	5/18/94
EG&G ES&H	W.E. LOWRY	DATE	5/24/94
CHECKER	S. CONKO	PROJECT ENGR.	S. RENNINGER
ZONE	REV		
GEN.	7	MODIFIED AS PER MARKED PRINT; I	
DRAFTER	<i>W. J. Kulch</i>	DATE	10-3-94
EG&G ES&H	<i>W. E. Lowry</i>	DATE	10/17/94
CHECKER	<i>W. J. Kulch</i>	PROJECT ENGR.	<i>Scott Renning</i>

FROM GAS SAMPLING SYSTEM



REVISION

REV	DESCRIPTION	DATE
6	MODIFIED AS PER MARKED PRINT; ISSUED FOR CONSTRUCTION	5/16/94
DATE	CHECKER	DATE
5/18/94	S. CONKO	5/18/94
DATE	EG&G RESPONSIBLE ENGR.	DATE
5/18/94	DAVID LUNIFELD	5/24/94
DATE	REVIEWER	DATE
5/18/94	GARY J. KULCHOCK	5/18/94
DATE	PROJECT ENGR.	DATE
5/24/94	S. RENNINGER	5/18/94
DATE	BRANCH MANAGER	DATE
5/18/94	JOHN M. ROCKEY	5/18/94
DATE	DOE (ESD)	DATE
5/18/94	JOHN R. ROTUNDA	5/18/94
DATE	DOE (ESD)	DATE
5/18/94	WJA	5/18/94
7	MODIFIED AS PER MARKED PRINT; ISSUED FOR CONSTRUCTION	9/30/94
DATE	CHECKER	DATE
10-3-94	Gary J. Kulchock	10/3/94
DATE	EG&G RESPONSIBLE ENGR.	DATE
10/3/94	David Lunifeld	10/5/94
DATE	REVIEWER	DATE
10/3/94	GARY J. KULCHOCK	10/5/94
DATE	PROJECT ENGR.	DATE
10/3/94	S. RENNINGER	10/4/94
DATE	BRANCH MANAGER	DATE
10/3/94	JOHN M. ROCKEY	10/5/94
DATE	DOE (ESD)	DATE
10/3/94	JOHN R. ROTUNDA	10/5/94
DATE	DOE (ESD)	DATE
10/3/94	WJA	10/5/94

H

G



FROM PIC-254

80(1)21/80(6)21

FROM ESD

ASHH  
323



F



F

E

D

FILTER PURGE

FILTER PURGE

FILTER PURGE

FILTER PURGE

80(3)XX/80(1)XX

I-19

SET 340 PSIG

PAH  
AAA

PSH  
AAA



INCIN.

PSV  
BBB


SET 350 PSIG  
AT 70 DEGF  
AND 23760 SCFH


TI  
341

TE  
41A

TE  
41B









TO  
F-100  
OUTLET

80(6)27/80(3)27

?

?

ZI  
352B

ZS  
352B

?

FROM  
CONT  
MODE

80(5)28/80(6)28

1/2" SS TUBE  
P9 SCH STD



HCV  
352B  
FD

?

ZI  
351B

ZS  
351B


FROM  
BATCH  
MODE



80(1)16/80(6)16

1/2" SS TUBE  
P9A SCH STD



HCV  
351B  
FD






GAS  
AMPLING  
STEM  
CH-1 &  
CH-2

80(6)15/80(4)15

V  
3

HV  
115

HV  
182  
DRAIN



LOCKHOPPER 1

PLATFORM  
SCALES

0-5  
LB


CU

F  
10

P  
11

PI  
1





**DRUM 2**  
COND. COLLECTION  
3' x 2'

PLATFORM SCALES

0-500 LBS.

- NOTES:
1. ALL IMPULSE
  - 2.
  - 3.

REFERENCE DRAWING

PLATFORM SCALES

THIS DRAWING IS PART OF THE EG&G DOCUMENT CONTROL SYSTEM

80(2)7/80(1)7

WI 234

FROM SHT. 3

FSV  
457

1' CS PIPE  
P13 SCH 40


INCINERATOR

FSV  
486

INCINERATOR

1" S.S.


ALL LINES ARE 3/8" SS TUBING UNLESS OTHERWISE NOTED.

DRAFTER	DATE	 <p>United States Department of Energy MORGANTOWN ENERGY TECHNOLOGY CENTER Morgantown, WV</p>			
Jimmy Thorton	10/28/93				
PROJECT ENGINEER	DATE				
John Rockey	11/2/93				
REQUESTOR	DATE				
John Rockey	11/2/93	<p>TITLE: B-12 ADVANCED GASIFICATION FACILITY MODULAR GAS CLEANUP RIG (MGR) PROCESS AND INSTRUMENTATION DRAWING (P&amp;ID6) OUTLET FILTRATION</p>			
BRANCH MANAGER	DATE				
Larry Strickland	11/2/93				
ES&H	DATE				
DOE	DATE				
WJA John Rotunda	10/28/93	SIZE	FSCH NO	DWG NO	REV
		E		STD920080.07	7


H


G

F










REVISION				
ZONE	REV	DESCRIPTION		
GEN	0	ISSUED FOR CONSTRUCTION		
ZONE	REV	DESCRIPTION		
GEN.	1	MODIFIED AS PER MARKED PRINT: ISSUED FOR CONSTRUCTION		
DRAFTER	DATE	CHECKER	DATE	DESIGNER
GARY J. KULCHOCK	6/30/94	S. CONKO	6/30/94	C. ELAINE
ESDH	DATE	DOE (EESD)	DATE	
J.L. BUCKLEW	6/30/94	EDWIN GALLOWAY	6/30/94	ROBERT R
ZONE	REV	DESCRIPTION		
GEN.	2	MODIFIED AS PER MARKED PRINT: ISSUED FOR CONSTRUCTION		
DRAFTER	DATE	CHECKER	DATE	DESIGNER
<i>Gary Kulchok</i>	8/15/95	<i>S. Conko</i>	8-15-95	<i>50.76</i>
ESDH	DATE	DOE (EESD)	DATE	
<i>R. E. Long</i>	9/8/95	<i>John K...</i>	9/8/95	




REVISION									
ZONE	REV	DESCRIPTION							DATE
GEN	0	ISSUED FOR CONSTRUCTION							5/25/94
ZONE	REV	DESCRIPTION							DATE
GEN.	1	MODIFIED AS PER MARKED PRINT. ISSUED FOR CONSTRUCTION							6/24/94
AFTER	DATE	CHECKER	DATE	DESIGNER	DATE	RESPONSIBLE PERSON	DATE		
GARY J. KULCHOCK	6/30/94	S. CONKO	6/30/94	C. ELAINE EVERITT	6/30/94				
BY	DATE	DOE (EISD)	DATE	DESIGNER	DATE	RESPONSIBLE PERSON	DATE		
J.L. BUCKLEW	6/30/94	EDWIN GALLOWAY	6/30/94	ROBERT ROMANSKY	7/1/94	JOHN ROTUNDA	6/30/94		
ZONE	REV	DESCRIPTION							DATE
GEN.	2	MODIFIED AS PER MARKED PRINT. ISSUED FOR CONSTRUCTION							8/15/95
AFTER	DATE	CHECKER	DATE	DESIGNER	DATE	RESPONSIBLE PERSON	DATE		
<i>Joseph Kulchok</i>	8/15/95	<i>S. Conko</i>	8-15-95	<i>C. Elaine Everitt</i>	8/30/95	<i>John Rotunda</i>	8/1/95		
BY	DATE	DOE (EISD)	DATE	DESIGNER	DATE	RESPONSIBLE PERSON	DATE		
<i>V. E. Gray</i>	9/8/95	<i>John Rotunda</i>	9/8/95						

H

G

F





MGCR  
INCINERATOR  
HEADER


208 VAC } --

E

PREHEAT NITROGEN  
425 PSIG

80(2)-29/40(0)-29

D







CFH  
SIG  
F

FLOW  
CELL  
#2

$\Delta H=0-10''$   
 $H_2O$

TE 605B TE 605A

FT 606

FI 606

TIR 605

TYPE K

TE 429A TE 429B

TIR 429

TAHH 607 1150° F

TAH 607 1125° F

TI 607

TIR 607

TE 607B TE 607A

PROBE #2

1/4" TUBE-SS

PSV 449

SET @  
50 PSIG  
400° F

OUT OF SERVICE

MOTT  
FILTER  
XE-614


CALC Cv=0.48  
INSTALLED Cv=1.0


FV 606


FD

FY 606 I/P

IR







RESERVE FOR FUTURE USE

NOTES:

(1) "NOTE REMOVED"

(2) "NOTE REMOVED"

3 SUPPLIED BY AMES


(4) PREV. TAG # BLOCK RANGE ALLOCATED FOR THIS P&ID:  
425-450, 600-650, 701-725  
CURRENT BLOCK RANGE 800-850

(5) LAST TAG No. USED: HV-826

6 COMMERCIALY PURCHASED UNIT: MODEL No. PMS CSASP H


7 COMMERCIALY PURCHASED UNIT: MODEL LINDBERG; TYPE :


(8) TIR-609 AND FIR-611 ARE USED FOR MASS FLOW CALCUL






# PARTICLE MONITOR






ECN NO	DESCRIP
1	
2	
3	
4	

-RELEASED-  
 ISSUE DATE: 9/25/95  
 -FOR CONSTRUCTION-



REDRAWN FROM DRAWINGS STD93  
WITH CHANGES

ECN NO	DESCRIPTION	REFERENCE DRAWINGS	DRAFTER	DATE	 MD
1			Gary Kulchock	5/26/94	
2			S. Conko	5/26/94	
3			Dave Lunifeld	5/26/94	
			RESPONSIBLE PERSON	DATE	TITLE
			-NA-	-NA-	MGC SYSTEM
			ES&H	DATE	
			W. E. Lowry	5/31/94	
			DOE (EDSD)	DATE	
			Wm. P. Chisholm	5/31/94	SIZE
				DATE	FSCN NO
					E

OUT OF SERVICE


PCV  
819

0-25 PSIG

C

DWG NO  
E940040  
SH  
1

OWN FROM DRAWINGS STD930075 AND STD930008  
WITH CHANGES

DRAFTER Gary Kulchock	DATE 5/26/94	 <p>United States Department of Energy MORGANTOWN ENERGY TECHNOLOGY CENTER Morgantown, WV</p>			
CHECKER S. Conko	DATE 5/26/94				
DESIGNER Dave Lunifeld	DATE 5/26/94				
RESPONSIBLE PERSON -NA-	DATE -NA-				
ES&H W. E. Lowry	DATE 5/31/94	<p>BUILDING 12 MGCR PARTICLE MEASURING SYSTEM AND ALKALI MONITOR LOOP P&amp;ID</p>			
DOE (EOSD)	DATE				
DATE	DATE				
Wm. P. Chisholm	DATE 5/31/94	SIZE E	FSCH NO	DWG NO E940040	REV 2

A

D

SET 30  
PSID


PDAH	PDI
673	673


PDI  
673

C

ZI  
662

○






REVISION

REV	DESCRIPTION	DATE
1	MODIFIED AS PER MARKED PRINT, ISSUED FOR CONSTRUCTION	9/12/94
2	MODIFIED AS PER MARKED PRINT, ISSUED FOR CONSTRUCTION	9/30/94

DATE	CHECKER	DATE	ENGR RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
10/3/94	<i>[Signature]</i>	10/3/94	<i>[Signature]</i>	10/5/94		
DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DOE (EDSD)	DATE
10/12/94	<i>[Signature]</i>	10/3/94			<i>[Signature]</i>	10/3/94



D


C








B

A







DRUM#3  
CONDENSATE

80(1)34/01(1)34

THIS DRAWING IS PART  
OF THE P&ID DOCUMENT

REFERENCE DRAWINGS	
STD920080	DRW
	J
	CHE
	E
	EGT
	E
	EGT
	N
	EGT
	PRE
	DRW

H<sub>2</sub>O


FC  
HCV  
657

NOTES:

1. TAG# BLOCK RANGE ALLOCATED FOR THIS P&ID IS (651-700).
2. LAST TAG# USED HV-687
3. ALL IMPULSE LINES ARE 3/8" SS TUBING UNLESS OTHERWISE NOTED.
4. ALL PROCESS LINES ARE 1/2" SS TUBING UNLESS OTHERWISE NOTED.
5. TIC-676 AND JE-676 CHANGED FROM TIC-661 AND JZ-676.

B

OPERATING CONDITIONS
290 PSIG 500 DEGF 100 SCFH


DRAFTER	DATE	 <p>United States Department of Energy MORGANTOWN ENERGY TECHNOLOGY CENTER Morgantown, WV</p>
JIMMY THORNTON	01/20/94	
CHECKER	DATE	
EDWIN GALLOWAY	01/25/94	
EG&G RESPONSIBLE ENGR.	DATE	
EDWIN GALLOWAY	01/25/94	
EG&G REVIEWER	DATE	<p>TITLE: MODULAR GAS CLEANUP RIG (MGCR) DRY CHLORIDE REMOVAL SYSTEM(DCR) P&amp;ID</p>
N/A		
EG&G ESMH	DATE	
PROJECT ENGR.	DATE	
BRANCH MANAGER	DATE	SIZE   FSCH NO   DVG NO   REV


A

H



G

F











REVISION

ZONE	REV	DESCRIPTION			
GEN	1	UPDATED AS PER MARKED PRINT			
GEN		REVISED PER MARKED PRINT			
E-8		REMOVED HV-201 & PI-201			
B-6,7		REROUTED LINE BETWEEN HV-480 & PCV-308			
C-8		RELOCATED CAPPED LINE			
E-6 B-7,8		ADDED STEAM SITE LINE, HV & CV ADDED HV-402, 402A, 403A & 404			
DRAFTER S.P.C.		DATE 12/10/90	CHECKER G.J.K.	DATE 12/10/90	PROJECT E
		DATE		DATE	
ZONE	REV	DESCRIPTION			
GEN	2	UPDATED AS PER MARKED PRINT WITH W.D. #68547			
GEN		ADDED NEW DWG. FORMAT			
GEN		UPDATED AS PER MARKED PRINT WITH W.D. #70756			
GEN		UPDATED AS PER MARKED PRINT WITH WORK PLAN			
B-2 C-7 GEN		ADDED NOTE 8 AND NOTE DESIGNATIONS MODIFIED FILTER #208 SYMBOL ISSUED FOR CUSTOMER REVIEW AND COMMENT			
DRAFTER JIMMY SMITH		DATE 7/17/92	CHECKER GARY J. KULCHOCK	DATE 7/17/92	EG&G RESP JAY
EG&G RESPON SECT SUPV BURTON W. HARRELL		DATE 7/20/92	EG&G ESMH J. L. BUCKLEW	DATE 7/20/92	
ZONE	REV	DESCRIPTION			
A-1 GEN GEN	3	CHANGED DWG. TITLE			
		UPDATED AS PER MARKED PRINT WITH WORK PLAN			
		ISSUED FOR CONSTRUCTION			
E-7		ADDED ENTRAINED BOILER, VALVE HV-0601A, AND TIC-201			
G-7		'PI-104' WAS 'PI-105, AND 'PI-105' WAS 'PI-104'			
F-7		'650 PSIG' ON PAHL-214 WAS '500 PSIG'			
D-6		ADDED 'HS-217' TO 'JC-217'			
A-8 GEN		ADDED NOTE TO 'HV-401A' REVISED DESIGNATIONS ON ALL FLOW COMPUTERS FROM 'MO' BEHIND PANEL			
DRAFTER GARY J. KULCHOCK		DATE 11/18/92	CHECKER S. CONKO	DATE 11/18/92	EG&G RESP JAY
EG&G ESMH J. L. BUCKLEW		DATE 11/19/92	PROJECT ENGR.	DATE	BRANCH MA
ZONE	REV	DESCRIPTION			
GEN.	4	REVISED SHTR-201 TO INCLUDE THE MAX. PRESS. AND TEMP REMOVED ALL NUMBERS FROM ADACS SYMBOLS MODIFIED VARIOUS SCFH RATINGS ADDED FT-406, PT-406, HV-406A, HV-406B, HV-406C, TE-4			
DRAFTER GARY J. KULCHOCK		DATE 4/5/93	CHECKER S. CONKO	DATE 4/5/93	EG&G RESP JAY
EG&G ESMH J. L. BUCKLEW		DATE 4/7/93	PROJECT ENGR. JOHN ROCKEY	DATE 5/27/93	BRANCH MA LARRY
ZONE	REV	DESCRIPTION			
GEN.	5	ADDED NOTE 10; REVISED BOLD LINETYPE ON YY-209, PI-2 REVISED LINETYPE ON FV-103; REVISED LINE ROUTING IN ADDED "#2" TO N <sub>2</sub> , 2 PLACES PAHL-214, 700 PSIG RATING WAS 650 PSIG ADDED FSV-412, FV-412, AND ASSOCIATED PIPING ISSUED FOR CONSTRUCTION			
DRAFTER Gary Kulchock		DATE 9/10/93	CHECKER S. Conko	DATE 9/14/93	EG&G RESP Jay
EG&G ESMH Larry Bucklew		DATE 9/17/93	PROJECT ENGR. John Rockey	DATE 9/21/93	BRANCH MA Larr
ZONE	REV	DESCRIPTION			
GEN	6	EXTENSIVE CHANGES AS PER MARKED PRINT REDLINED BY JA ISSUED FOR CONSTRUCTION			
DRAFTER <i>Gary J. Kulchock</i>		DATE 10/17/94	CHECKER <i>S. Conko</i>	DATE 10-7-94	EG&G RESP <i>Jay</i>
EG&G ESMH <i>J. L. Bucklew</i>		DATE 10-11-94	PROJECT ENGR. <i>John M. Rockey</i>	DATE 10/13/94	BRANCH MA <i>Larry</i>

VENT

59  
011

VENT

REVISION

ZONE	REV	DESCRIPTION	DATE
GEN	1	UPDATED AS PER MARKED PRINT	4/25/90
GEN E-8 C-6,7 C-8 C-6 C-7,8	1	REVISED PER MARKED PRINT REMOVED HV-201 & PI-201 REROUTED LINE BETWEEN HV-480 & PCV-308 RELOCATED CAPPED LINE ADDED STEAM SITE LINE, HV & CV ADDED HV-402, 402A, 403A & 404	10/11/90
OWNER	S.P.C.	DATE 12/10/90	CHECKER G.J.K.
		DATE 12/10/90	PROJECT ENGINEER J.P.K.
		DATE 2/13/91	
		DATE	DATE

H

ZONE	REV	DESCRIPTION	DATE
GEN	2	UPDATED AS PER MARKED PRINT WITH W.D. #68547	10/3/91
GEN GEN GEN	2	ADDED NEW DWG. FORMAT UPDATED AS PER MARKED PRINT WITH W.D. #70756	1/10/92
GEN	2	UPDATED AS PER MARKED PRINT WITH WORK PLAN	3/6/92
B-2 C-7 GEN	2	ADDED NOTE 8 AND NOTE DESIGNATIONS MODIFIED FILTER #208 SYMBOL ISSUED FOR CUSTOMER REVIEW AND COMMENT	7/17/92
OWNER	JIMMY SMITH	DATE 7/17/92	CHECKER GARY J. KULCHOCK
		DATE 7/17/92	EG&G RESPON ENGINEER JAY RUTTEN
		DATE 7/17/92	EG&G REVIEWER D. LUNIFIELD
		DATE	DATE
EG RESPON SECT SUPV	MURTON W. HARRELL	DATE 7/20/92	EG&G ES&H J. L. BUCKLEW
		DATE 7/20/92	

ZONE	REV	DESCRIPTION	DATE
A-1 GEN GEN	3	CHANGED DWG. TITLE UPDATED AS PER MARKED PRINT WITH WORK PLAN ISSUED FOR CONSTRUCTION	9/16/92
E-7 G-7 F-7 D-6 A-8 GEN	3	ADDED ENTRAINED BOILER, VALVE HV-0601A, AND TIC-201 "PI-104" WAS "PI-105, AND "PI-105" WAS "PI-104" "650 PSIG" ON PAHL-214 WAS "500 PSIG" ADDED "HS-217" TO "JC-217" ADDED NOTE TO "HV-401A" REVISED DESIGNATIONS ON ALL FLOW COMPUTERS FROM "MOUNTED ON PANEL" TO "MOUNTED BEHIND PANEL"	11/16/92
OWNER	GARY J. KULCHOCK	DATE 11/18/92	CHECKER S. CONKO
		DATE 11/18/92	EG&G RESPONSIBLE ENGR. JAY RUTTEN
		DATE 11/19/92	REVIEWER D. LUNIFIELD
		DATE	DATE
EG ES&H	J. L. BUCKLEW	DATE 11/19/92	PROJECT ENGR. JOHN ROCKEY
		DATE	BRANCH MANAGER LARRY STRICKLAND
		DATE	DOE (EIOSD) JOHN ROTUNDA

G

ZONE	REV	DESCRIPTION	DATE
GEN.	4	REVISED SHTR-201 TO INCLUDE THE MAX. PRESS. AND TEMP. REMOVED ALL NUMBERS FROM ADACS SYMBOLS MODIFIED VARIOUS SCFH RATINGS ADDED FT-406, PT-406, HV-406A, HV-406B, HV-406C, TE-406A, TE-406B, AND ASSOCIATED ADACS SYMBOLS	4/1/93
OWNER	GARY J. KULCHOCK	DATE 4/5/93	CHECKER S. CONKO
		DATE 4/5/93	EG&G RESPONSIBLE ENGR. JAY RUTTEN
		DATE 4/7/93	REVIEWER D. LUNIFIELD
		DATE	DATE
EG ES&H	Larry Bucklew	DATE 4/7/93	PROJECT ENGR. JOHN ROCKEY
		DATE 5/27/93	BRANCH MANAGER LARRY STRICKLAND
		DATE 5/27/93	DOE (EIOSD) JOHN ROTUNDA

ZONE	REV	DESCRIPTION	DATE
GEN.	5	ADDED NOTE 10; REVISED BOLD LINETYPE ON YY-209, PI-207, & PI-208 REVISED LINETYPE ON FV-103; REVISED LINE ROUTING IN ZONE G-6 ADDED "#2" TO N <sub>2</sub> , 2 PLACES PAHL-214, 700 PSIG RATING WAS 650 PSIG ADDED FSV-412, FV-412, AND ASSOCIATED PIPING ISSUED FOR CONSTRUCTION	8/24/93
OWNER	Gary Kulchock	DATE 9/10/93	CHECKER S. Conko
		DATE 9/14/93	EG&G RESPONSIBLE ENGR. Jay Rutten
		DATE 9/15/93	REVIEWER Dave Lunifeld
		DATE	DATE
EG ES&H	Larry Bucklew	DATE 9/17/93	PROJECT ENGR. John Rockey
		DATE 9/21/93	BRANCH MANAGER Larry Shadle
		DATE 9/21/93	DOE (EIOSD) John Rotunda/WJA

ZONE	REV	DESCRIPTION	DATE
GEN	6	EXTENSIVE CHANGES AS PER MARKED PRINT REDLINED BY JAY RUTTEN ON 15 FEB 94. ISSUED FOR CONSTRUCTION	9/29/94
OWNER	<i>Gary Kulchock</i>	DATE 10/7/94	CHECKER <i>S. Conko</i>
		DATE 10-7-94	EG&G RESPONSIBLE ENGR. <i>Jay Rutten</i>
		DATE 10-11-94	REVIEWER <i>Dave Lunifeld</i>
		DATE	DATE
EG ES&H	<i>Larry Bucklew</i>	DATE 10-11-94	PROJECT ENGR. <i>John Rockey</i>
		DATE 10/13/94	BRANCH MANAGER <i>Larry Shadle</i>
		DATE 10-18-94	DOE (EIOSD) <i>John Rotunda/WJA</i>

F

NITROGEN COMPRESSOR SUPPLY 120 PSIG

F

1/4" SS TUBING

PI 212

HV 212D

HV 212A

HV 212B

HV 212C

PS 201

HV 212E

9

HV 212G

HV 212F

LG 202

LT 201

E

HV 212J

HV 212H

LG 201

HV 212I

HV 212K

CITY WATER 125 PSIG

8"

HV 202

HV 203

FQI 202

HV 204

1/2"

TO SINK

FSV 201

HV 205

FSV 202

TO DRAIN

BLR-201  
160 LB/HR  
PACKAGED  
STEAM  
GENERATOR  
1500 PSIG  
AT 579° F  
480 V 3 Ø  
60 HZ  
60 KW

HV 213A

5

D

PUMP 202

HV 211A















LS 201


LCV 211



HV 211B



STORAGE TANK

HV 211










H 80 CS

TO HV 161  
DWG. E900011

ZONE	REV	
GEN	6	EXTENSIVE CHANGES ISSUED FOR CONSTRU
DRAFTER	DATE	CHE
<i>James S. Kuhl</i>	10/7/99	<i>S</i>
ENGR/ESM	DATE	PRO
<i>J. K. Law</i>	10-11-99	<i>Dr</i>



TO SHTR-202 STEAM  
SUPER HEATER  
DWG. E900011

GEN

6

EXTENSIVE CHANGES AS PER MARKED PRINT REDLINED BY JAY RUTTEN ON 15 FEB 94.  
ISSUED FOR CONSTRUCTION

9/29/94


DATE	DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
10/7/94	10-7-94	S. Casika	10-7-94	Jay Rutten	10-11-94	Steenfeld	10/11/94
DATE	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DOE CELESTIO	DATE
10-11-94	10/13/94	J.M. Roebey	10/13/94	Jay Rutten	10-18-94	Steenfeld	10/11/94

F


E


D






PURIFICATION SYSTEM PUR-208






1/2" SS TUBING

1/2" SS TUBING



T  
C

S TUBING



TO FSV-315  
DWG. E900011



TO FSV 408  
DWG. E900011

- 1 PANEL-  
POSITIC  
60 HZ :
- 2 FV-106  
PANEL-  
VALVE  
D820030
- 3 HS-106,  
FV-106  
FV-107
- 4 HS-112,  
FV-112  
FV-113
- 5 WATER  
3-WAY
- 6 LB/HR
- 7 THIS D  
SUPERC  
NOTES,
- 8 DESIGN  
LOCKEI
- 9 BOILER  
PROBES  
PUMP C  
PUMP C
- 10 FV-112  
PANEL-  
VALVE
- 11 \*NOTE


REFERENCE DRAWINGS  E900011 E900012 E900013	DRAFTER S. CONKO	DA
	CHECKER A. R. KUBALA	DA
	PROJECT ENGINEER J. P. KANDSKY	DA
	_____	DA
	_____	DA
	_____	DA
	_____	DA

THIS DRAWING IS PART  
OF THE EG&G DOCUMENT  
CONTROL SYSTEM

- 1 WHICH IS NOT SHOWN ON THIS DWG. FOR CLARITY) PANEL-MOUNTED ON/OFF STATION (HAND SWITCH WITH POSITION INDICATION LAMPS), 24 VDC RELAY, 117 VAC 60 HZ SOLENOID VALVE.
- 2 FV-106 & FV-406 ARE ELECTRICALLY SELECTED BY A PANEL-MOUNTED 2-POSITION TOGGLE SWITCH. ONLY ONE VALVE CAN BE OPEN AT A TIME. REF. PRINT DWG D820030 SHTS 3 & 17.
- 3 HS-106, HS-107, AND HS-109 ARE ELECTRICALLY INTERLOCKED. FV-106 OPENS WHEN EITHER FV-107 OR FV-109 IS OPENED. FV-107 AND FV-109 CAN BOTH BE OPEN AT THE SAME TIME.
- 4 HS-112, HS-113 AND HS-115 ARE ELECTRICALLY INTERLOCKED. FV-112 OPENS WHEN EITHER FV-113 OR FV-115 IS OPENED. FV-113 AND FV-115 CAN BOTH BE OPEN AT THE SAME TIME.
- 5 WATER LEVEL SWITCH CONTROLS RELAY TO 117 VAC 60 HZ ~~3-WAY SOLENOID VALVE~~
- 6 LB/HR = (lb mass / hour)
- 7 THIS DWG. & DWGS. E900011, E900012 & E900013 SUPERCEDES DWG. R800524 (SEE DWG. E900013 FOR NOTES, TUBING & PIPING SUMMARY).
- 8 DESIGNATES THE CONTROL PANEL SWITCH IS PHYSICALLY LOCKED TO PREVENT ACCIDENTAL ACTUATION.
- 9 BOILER WATER LEVEL IS CONTROLLED BY 3 CAPACITANCE PROBES. SHORTEST PROBE SHUTS BOILER FEED WATER PUMP OFF. MIDDLE PROBE TURNS BOILER FEED WATER PUMP ON. LONGEST PROBE SHUTS THE BOILER DOWN.
- 10 FV-112 & FV-412 ARE ELECTRICALLY SELECTED BY A PANEL-MOUNTED 2-POSITION TOGGLE SWITCH. ONLY ONE VALVE CAN BE OPEN AT A TIME.
- 11 "NOTE REMOVED"

C

DWG NO  
E900010  
SH  
1


DRAFTER S. CONKO	DATE 3/6/90	 <p style="text-align: center;">United States Department of Energy MORGANTOWN ENERGY TECHNOLOGY CENTER Morgantown, WV</p>			
CHECKER A. R. KUBALA	DATE 3/6/90				
PROJECT ENGINEER J. P. KANSKY	DATE 3/6/90				
_____	DATE ___				
_____	DATE ___	<p style="text-align: center;">B-12 P&amp;ID FLUIDIZED BED GASIFIER A.G.C., CONCEPTUAL</p>			
_____	DATE ___				
_____	DATE ___				
_____	DATE ___				
_____	DATE ___	SIZE E	FSCM NO	DWG NO E900010	REV 6


A

H

G


F
















TO STORAGE  
CYCLONE CYC-907  
DWG. E900013, SHEET 1  
AREA B-8

BATCH HOPPER  
CYCLONE  
CYC-602  
SEE VESSEL  
DWG. D820083

BATCH  
HOPPER  
VSL-602  
SEE VESSEL  
DWG. D810007  
  
DESIGN  
PRESS. 1100 PSIG  
DESIGN TEMP. 150° F

ZONE	REV	CHG
A-1 GEN GEN	3	U I S R F
DRAFTER GARY KULCHI EG&G RESPON SECT : NA		
ZONE	REV	
GEN	4	
DRAFTER GARY KULCHI EG&G ES&H J. L. BUCKLEY		
ZONE	REV	
GEN	5	
DRAFTER Gary Kulch EG&G ES&H Larry Buch		
ZONE	REV	
GEN	6	
DRAFTER <i>Gary Kulch</i> EG&G ES&H <i>Larry Buch</i>		


H  
610

REVISION

ONE	REV	DESCRIPTION	DATE							
GEN	3	CHANGED DWG. TITLE UPDATED AS PER MARKED PRINT WITH WORK PLAN ISSUED FOR CONSTRUCTION	9/16/92							
		RELOCATED SAMPLE SYSTEM TO E900013_SHT_2 REVISED AS PER MARKED PRINT	11/16/92							
OWNER		DATE	CHECKER	DATE	EG&G RESPON ENGINEER	DATE	EG&G REVIEWER	DATE		
		GARY KULCHOCK	11/18/92		S CONKO	11/18/92	JAY RUTTEN	11/19/92	D. LUNIFIELD	11/19/92
		EG&G RESPON SECT SUPV	DATE	EG&G ESH	DATE		DATE		DATE	
		NA		J. L. BUCKLEW	11/19/92			JOHN ROTUNDA	11/24/92	
ONE	REV	DESCRIPTION	DATE							
GEN	4	ADDED DESIGN PRESS. AND TEMP. TO FDR-60L, VSL-602, & VSL-601 ADDED MAX. OPP. PRESS. AND COIL TEMP. TO SHTR-202 AND HTR-101 ADDED PSE-120, REMOVED NUMBERS FROM ALL ADACS SYMBOLS	4/1/93							
OWNER		DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE		
		GARY KULCHOCK	4/5/93		S CONKO	4/5/93	JAY RUTTEN	4/7/93	D. LUNIFIELD	4/7/93
		EG&G ESH	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DDE (EDSID)	DATE	
		J. L. BUCKLEW	4/7/93	JOHN ROCKEY	5/27/93	LARRY STRICKLAND	5/27/93	BILL AYERS	5/27/93	
ONE	REV	DESCRIPTION	DATE							
GEN	5	ADDED LT-602A, LT-603A, FSV-60L HV-321 & HV-320; MODIFIED LAHL 602 TO LAH-602 & LAL-602 MODIFIED LAHL 603 TO LAH-603 & LAL-603; ADDED "#1" TO N <sub>2</sub> ; ADDED NOTE 10 ADDED INCINERATOR NOTES TO (2) INCINERATOR DESIGNATIONS; ADDED NOTE TO VENT SYSTEM (G-4) REMOVED PSE-120, HCV-118, TCV-126 AND RELATED PIPING; RELOCATED FSV-315 ISSUED FOR CONSTRUCTION	9/01/93							
OWNER		DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE		
		Gary Kulchock	9/10/93		S. Conko	9/14/93	Jay Rutten	9/15/93	Dave Lunifeld	9/20/93
		EG&G ESH	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DDE (EDSID)	DATE	
		Larry Bucklew	9/17/93	John Rockey	9/21/93	Larry Shadle	9/21/93	John Rotunda/WJA	9/20/93	
ONE	REV	DESCRIPTION	DATE							
GEN	6	EXTENSIVE CHANGES AS PER MARKED PRINT REDLINED BY JAY RUTTEN ON 15 FEB 94. ISSUED FOR CONSTRUCTION	8/18/94							
OWNER		DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE		
		<i>Gary Kulchock</i>	10/17/94		<i>S. Conko</i>	10-7-94	<i>Jay Rutten</i>	10-11-94	<i>D. Lunifeld</i>	10/11/94
		EG&G ESH	DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DDE (EDSID)	DATE	
		<i>Larry Bucklew</i>	10-11-94	<i>John M. Rockey</i>	10/13/94	<i>Larry Shadle</i>	10-18-94	<i>John Rotunda/WJA</i>	10/14/94	

H

G



F

FROM FCV 115  
DWG. E900010

HV  
161

FV  
118

TE  
119A

TT  
119


TI  
119

0-2500 ° F

ZS  
118

HS  
118

FC



HTR-1  
AIR  
PREHEAT  
DWG. E810220

MAX. OP. COIL TEMP. 1200 ° F

REACTOR  
1" SCH 80 316 SS


1000 ° F

TE 119B


TI 119



HTR-101  
CONTROL/  
SAFETY SYSTEM  
DWG. C820018



PLANT  
AIR  
100 PSIG




NATURAL  
GAS  
35 PSIG

250,000 BTU/HR

MAX. OP. PRESS. 1100 PSIG  
MAX. OP. COIL TEMP. 1200 ° F  
480V, 12 KW  
SHTR-202  
STEAM SUPER HEATER  
DWG. E810220

FROM FCV 220  
DWG. E900010

650 ° F



1" SCH 80 316 SS

1000 ° F

10-160  
LB/HR

ELEMENT

COIL

0-2000 ° F

TE  
224B

TE  
224A

TE  
223A

TE  
223B

JC  
224

TI  
224

HS  
224

0-2000 ° F

TI  
223A

TT  
223A

TI  
223B

TT  
223B

TIC  
224

TT  
224

0-2000 ° F

TAH

TAH

SF

ZL  
226


ZS  
226



A

FC


E


D














90%

E

1/2" TUBING. →

TO HV 707  
DWG. E900012

HS 603

A

304 SS  
25-150 LB/HR COAL →

TO FLUID BED  
GASIFIER  
DWG. E900012

D

→

TO FLUID BED  
GASIFIER  
DWG. E900012

HV 505

→

TO FLUID BED  
GASIFIER  
DWG. E900012



TT 504

TE 504B

TE 504A

A


\*F



FROM FCV 312  
 DWG. E900010

1/2" SCH 80 304 SS  
 60 ° F 125-2000 SCFH


FSV 315



FROM FV 407  
 DWG. E900010

NITROGEN PURGE  
 0-1050 PSIG

FSV 408



N<sub>2</sub> PURGE  
 FROM FSV-  
 E900013 (SHT)

H  
 441C

C

B

A

1/2" SCH 80 316 SS

3/8" SS TUBING

500° F

TAH  
340

TT  
340

TE  
340B

HS  
340

A

TE  
340A

JC  
340

I

TIC  
340

HV  
320

HV  
321

HTR-340  
NITROGEN PREP


LEGEND:


G  
XXX

IDENTIFIES  
PURGE SYS  
NUMBER. THIS SYMBOL  
IS IN THE  
TRANSMITTER  
FV-440,  
FSV-XXX

H  
XXX




IDENTIFIES  
PURGE SYS  
NUMBER. THIS SYMBOL  
IS IN THE  
TRANSMITTER  
FV-440,













R-340  
PREHEATER

NOTES:



4



DEFINES THE CONNECTING SEGMENT OF THE TRANSMITTER SYSTEM, WHERE XXX IS THE SEGMENT IDENTIFICATION (SEE DWG. E900013, SHT. 2 OF 2 FOR DETAILS) SYMBOL INDICATES THAT THE FOLLOWING EQUIPMENT ON THE PURGE LINE FROM THE NITROGEN HEADER TO THE TRANSMITTER:  
FV-440, FSV-441, HV-441, HV-XXXX, FV-XXXX, & FSV-XXXX

DEFINES THE CONNECTING SEGMENT OF THE TRANSMITTER SYSTEM, WHERE XXX IS THE SEGMENT IDENTIFICATION (SEE DWG. E900013, SHT. 2 OF 2 FOR DETAILS) SYMBOL INDICATES THAT THE FOLLOWING EQUIPMENT ON THE PURGE LINE FROM THE NITROGEN HEADER TO THE TRANSMITTER:  
FV-440, FSV-441, HV-441, HV-XXXX, & FSV-XXXX.

DESIGNATES EQUIPMENT WHICH IS NOT SHOWN ON THIS DWG. FOR CLARITY, PANEL MOUNTED ON/OFF STATION (HAND SWITCH WITH POSITION INDICATION LAMPS), 24VDC RELAY, 117 VAC 60 Hz SOLENOID VALVES.

FV-610 & FV-610A WILL NOT OPEN UNTIL PDT-610 MEASURES A PRESSURE DIFFERENTIAL LESS THAN OR EQUAL TO 10 PSID. REF. DWGS: D820047 SHT 14 & D820030 SHT 9. THE PRESSURE IN VSL-602 MUST BE HIGHER THAN THE PRESSURE IN VSL-603.

RELAY INTERLOCKS DO NOT ALLOW THE TWO PAIRS OF PARALLEL FLOW VALVES (609 & 609A, 610 & 610A) TO BE OPEN AT THE SAME TIME. REFERENCE DRAWING: D920031

THIS DWG. & DWGS. E900010, E900012, & E900013 SUPERCEDES DWG. R800524 (SEE DWG. E900013 FOR NOTES, TUBING AND PIPING SUMMARY).

RELAY INTERLOCKS DO NOT ALLOW FV-602 AND FLOW VALVES 420 OR 427 TO BE OPEN AT THE SAME TIME.

RELAY INTERLOCKS DO NOT ALLOW FV-602 AND THE PAIR OF PARALLEL FLOW VALVES 610 & 610A TO BE OPEN AT THE SAME TIME.

"NOTE DELETED"

DESIGNATES THAT THE CONTROL PANEL SWITCH IS PHYSICALLY LOCKED TO PREVENT ACCIDENTAL ACTUATION.


FV-602 WILL NOT OPEN UNTIL PT-602 MEASURES A PRESSURE LESS THAN 20 PSIG.

THROUGH FV-912 TO VENT SYSTEM VSL-906, DWG. E900013, SHEET 1, (B-3)


INTERLOCKS PREVENT HTR-340 FROM OPERATING UNTIL NITROGEN FLOWS EXCEED 80 SCFH

INTERLOCKS PREVENT HTR-340 FROM OPERATING WHEN THE COIL TEMPERATURE EXCEEDS 500° F

THIS DRAWING IS PART  
OF THE EG&G DOCUMENT  
CONTROL SYSTEM




T13 FLUID  
GASIFIER  
DWG. E900012

REFERENCE DRAWINGS E900010 E900012 E900013	DRAFTER S. CONKO	DATE 3/6/90	 United States I MORGANTOWN ENER Morg
	CHECKER A. R. KUBALA	DATE 3/6/90	
	PROJECT ENGINEER J. P. KANDSKY	DATE 3/6/90	
	_____	DATE _____	TITLE: B-12 F FLUIDIZED BE: A.G.C
	_____	DATE _____	
	_____	DATE _____	
	_____	DATE _____	
_____	DATE _____	SIZE FSCH NO	DWG NO
_____	DATE _____	E	E9

ING IS PART  
&G DOCUMENT  
L SYSTEM






TO FLUID BED  
GASIFIER  
DWG. E900012

C


DWG NO  
E900011  
SH  
1


DRAFTER	S. CONKO	DATE	3/6/90	 United States Department of Energy <b>MORGANTOWN ENERGY TECHNOLOGY CENTER</b> Morgantown, WV
CHECKER	A. R. KUBALA	DATE	3/6/90	
PROJECT ENGINEER	J. P. KANSKY	DATE	3/6/90	
	_____	DATE	_____	TITLE: <b>B-12 P&amp;ID</b> <b>FLUIDIZED BED GASIFIER</b> <b>A.G.C.</b>
	_____	DATE	_____	
	_____	DATE	_____	
	_____	DATE	_____	
	_____	DATE	_____	SIZE FSCM NO DWG NO E _____ E900011
	_____	DATE	_____	REV 6

A


H

G










0-2000° F




TO INCINERATOR  
DWG E900013, SHT 1  
(D-4)







TO  
PCV 713  
& PCV 713A  
DWG. E900013  
(G-4)




TO HV 728  
DWG. E900013

HI 1275° F  
LD 1025° F




0-2000° F



TO HV 726  
DWG. E900013

TO SECONDARY  
CYCLONE  
DWG. E900013



ZONE	REV	
GEN		UPDATED AS
E-6		REVISED PRI
GEN	1	REVISED PEI
B-3		REMOVED LS
C-3		REMOVED LS
E-3		REMOVED LS
G-7		REMOVED N
F-6		NOTE 1150 *F

DRAFTER G.J.K. DATE 1/2  
DATE

ZONE	REV	
GEN		UPDATED AS
GEN	2	ADDED NEW
GEN		UPDATED AS
GEN		UPDATED AS
GEN		ISSUED FOR

DRAFTER JIMMY SMITH DATE 7/17  
EG&G RESPON SECT SUPV BURTON W. HARRELL DATE 7/20

ZONE	REV	
A-1		CHANGED DWG
GEN		UPDATED AS
GEN	3	ISSUED FOR
B-2		ADDED NOTES
GEN		UPDATED AS

DRAFTER GARY J. KULCHOCK DATE 11/18  
EG&G ES&H J. L. BUCKLEW DATE 11/19

ZONE	REV	
GEN	4	ADDED DESIGN VSL-904, VSL REMOVED NUM ISSUED FOR C

DRAFTER GARY J. KULCHOCK DATE 4/5/9  
EG&G ES&H J. L. BUCKLEW DATE 4/7/9

ZONE	REV	
GEN	5	ADDED NOTE "PDAH-934B", "FO" WAS "FI" T1-901, AND REVISED PIP ISSUED FOR

DRAFTER Gary Kulchock DATE 9/10/9  
EG&G ES&H Larry Bucklew DATE 9/17/9

ZONE	REV	
GEN	6	EXTENSIVE CHA ISSUED FOR CO

DRAFTER *Gary Kulchock* DATE 10/7/9  
EG&G ES&H *J.L. Bucklew* DATE 10-11-9

REVISION

ZONE	REV	DESCRIPTION	DATE
GEN	1	UPDATED AS PER MARKED PRINT	4/25/90
E-6		REVISED PRESSURE RATINGS	6/26/90
GEN B-3		REVISED PER MARKED PRINT	10/11/90
C-3		REMOVED LS AND LAH-904	
E-3	REMOVED LS AND LAH-903		
G-7		REMOVED LS AND LAH-902	
F-6		REWORDED NOTE FOR ADDITIVE FEED HOPPER NOTE 1150 °F WAS 1100 °F	

H

RAFTER	G.J.K.	DATE	1/3/91	CHECKER	D.F.	DATE	1/3/91	PROJECT ENGINEER	J.P.K.	DATE	2/13/91	DATE	
		DATE				DATE				DATE		DATE	

ZONE	REV	DESCRIPTION	DATE
GEN	2	UPDATED AS PER MARKED PRINT WITH W.D. #68547	10/3/91
GEN		ADDED NEW DWG. FORMAT	1/10/92
GEN		UPDATED AS PER MARKED PRINT WITH W.D. #70756	
GEN		UPDATED AS PER MARKED PRINT WITH WORK PLAN	7/17/92
GEN	ISSUED FOR CUSTOMER REVIEW AND COMMENT		

RAFTER	JIMMY SMITH	DATE	7/17/92	CHECKER	GARY J. KULCHOCK	DATE	7/17/92	EG&G RESPON ENGINEER	JAY RUTTEN	DATE	7/17/92	EG&G REVIEWER	D. LUNIFELD	DATE	7/17/92
EG&G RESPON SECT SUPV	URTON W. HARRELL	DATE	7/20/92	EG&G ESHH	J. L. BUCKLEW	DATE	7/20/92			DATE				DATE	

ZONE	REV	DESCRIPTION	DATE
A-1	3	CHANGED DWG. TITLE	9/10/92
GEN		UPDATED AS PER MARKED PRINT WITH WORK PLAN	
GEN		ISSUED FOR CONSTRUCTION	
B-2		ADDED NOTES 13 AND 14, AND CORRESPONDING INTERLOCKS	
GEN		UPDATED AS PER MARKED PRINT WITH WORK PLAN	11/16/92

G

RAFTER	GARY J. KULCHOCK	DATE	11/18/92	CHECKER	S CONKO	DATE	11/18/92	EG&G RESPONSIBLE ENGR.	JAY RUTTEN	DATE	11/19/92	REVIEWER	D. LUNIFELD	DATE	11/19/92
EG&G ESHH	J. L. BUCKLEW	DATE	11/19/92	PROJECT ENGR.		DATE		BRANCH MANAGER		DATE		DOE (EESD)	JOHN ROTUNDA	DATE	11/24/92

ZONE	REV	DESCRIPTION	DATE
GEN	4	ADDED DESIGN PRESSURE AND DESIGN TEMPERATURE TO VSL-901, VSL-902, VSL-903, VSL-904, VSL-604, RPV-701 AND CYC-701 REMOVED NUMBERS FROM ADACS SYMBOLS ISSUED FOR CONSTRUCTION	03/26/93

RAFTER	GARY J. KULCHOCK	DATE	4/5/93	CHECKER	S CONKO	DATE	4/5/93	EG&G RESPONSIBLE ENGR.	JAY RUTTEN	DATE	4/7/93	REVIEWER	D. LUNIFELD	DATE	4/7/93
EG&G ESHH	J. L. BUCKLEW	DATE	4/7/93	PROJECT ENGR.	JOHN ROCKEY	DATE	5/27/93	BRANCH MANAGER	LARRY STRICKLAND	DATE	5/27/93	DOE (EESD)	BILL AYERS	DATE	5/27/93

ZONE	REV	DESCRIPTION	DATE
GEN	5	ADDED NOTE ON ALL INCINERATOR DESIGNATIONS; "PLAL-934A" WAS "PLAL-934B"; "PDAH-934A" WAS "PDAH-934B"; "PDAH-934B" WAS "PDAH-934A"; MODIFIED PSID RANGE ON PDI-934, WAS "0-50" "FD" WAS "FC" ON FV-725; ADDED "#1" TO ALL N DESIGNATIONS; RELOCATED HV-436A, TE-901A, TI-901, AND TE-901B; ADDED HV-437 AND HV-438; ADDED NOTE TO VENT SYSTEM, ZONE A-6 REVISED PIPING AROUND VSL-901; ADDED LINE AHEAD OF FSV-435, ZONE C-8 & C-7 ISSUED FOR CONSTRUCTION	09/01/93

RAFTER	Gary Kulchöck	DATE	9/10/93	CHECKER	S. Conko	DATE	9/14/93	EG&G RESPONSIBLE ENGR.	Jay Rutten	DATE	9/15/93	REVIEWER	Dave Lunifeld	DATE	9/20/93
EG&G ESHH	Larry Bucklew	DATE	9/17/93	PROJECT ENGR.	John Rockey	DATE	9/21/93	BRANCH MANAGER	Larry Shadle	DATE	9/21/93	DOE (EESD)	John Rotunda/WJA	DATE	9/20/93

ZONE	REV	DESCRIPTION	DATE
GEN	6	EXTENSIVE CHANGES AS PER MARKED PRINT REDLINED BY JAY RUTTEN ON 15 FEB 94. ISSUED FOR CONSTRUCTION	9/30/94

RAFTER	<i>Gary Kulchöck</i>	DATE	10/7/94	CHECKER	<i>S. Conko</i>	DATE	10-7-94	EG&G RESPONSIBLE ENGR.	<i>Jay Rutten</i>	DATE	10-11-94	REVIEWER	<i>D. Lunifeld</i>	DATE	10/11/94
EG&G ESHH	<i>L. Bucklew</i>	DATE	10-11-94	PROJECT ENGR.	<i>John Rockey</i>	DATE	10/13/94	BRANCH MANAGER	<i>Larry Shadle</i>	DATE	10-18-94	DOE (EESD)	<i>John Rotunda/WJA</i>	DATE	10/11/94

F

TO INCINERATOR  
DWG E900013, SHT 1  
(D-4)

550 PSIG  
700° F  
15000 SCFH

200-550 PSIG  
1150° F  
500-13500 SCFH

1' SCH 160 316 SS

1' PIPE



PI 701A 0-1500 PSIG

PDT 710

PDT 431

PDT 709

PDT 708

PDT 707

HV 711

HV 710

HV 709

HV 708

HV 707

TI 760

HJS 1

TE 760

FLUIDIZED  
BED  
GASIFIER  
RPV-701

DESIGN PRESS.  
1100 PSIG

DESIGN STEEL TEMP.  
650° F

OPERATING PRESS.  
200-425 PSIG

OPERATING INTERNAL  
TEMPERATURE  
1400°-1800° F

SEE VESSEL  
DWG. E910191

TJR 10-8

TE 705B

TT 705

TI 705

0-2

TE 705A



TJR 10-7

TE 704B

TT 704

TI 704

0-2

TE 704A



TE 703A



TE 703B

TT 703

TI 703

0

TJR 10-6

TAH 703

1E

TE 702A




TE 702B

TT 702

TI 702

0





550 PSIG  
700° F  
15000 SCFH

PI 701A 0-1500 PSIG

TJR 10-8  
TE 05B TT 705 TI 705 0-2000° F

TE 05A A

TJR 10-7  
TE 704B TT 704 TI 704 0-2000° F

TE 704A A

TE 703A A  
TE 703B TT 703 TI 703 0-2000° F

TJR 10-6 TAH 703 1800° F

TE 02A A

TE 02B TT 702 TI 702 0-2000° F

35 PSID PDAH 935 PDT 935

1000° F

HS 914

ZL 914

ZS 914

FV 914

FD

ZL 442

ZS 442

HS 442

FV 442

200-1000 PSIG

PCV 442

T 90

0-200

#1

N<sub>2</sub>

I 14

TI 2 HJS 1

J 2

TIC 2


A

1/4


6

1/2" T 30  
200-1 PS.

40  
1/2









DATE	CHECKER	DATE	EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
10/7/94	J. Cantre	10-7-94	Gay Jantzen	10-11-94	A. Keimfeld	10/1/94
DATE	PROJECT ENGR.	DATE	BRANCH MANAGER	DATE	DOE (EIS/D)	DATE
10-11-94	J. M. Kober	10/13/94	Looney Shells	10-18-94	J. L. De-USA	10/12/94


F

GEND:

 = PIPED TO PACKAGED INCINERATOR SYSTEM


 = INPUT TO THE DDAS SYSTEM


 IDENTIFIES THE CONNECTING SEGMENT OF THE TRANSMITTER PURGE SYSTEM, WHERE XXX IS THE SEGMENT IDENTIFICATION NUMBER. (SEE DWG. E900013, SHT. 2 OF 2 FOR DETAILS.) THIS SYMBOL INDICATES THAT THE FOLLOWING EQUIPMENT IS IN THE PURGE LINE FROM THE NITROGEN HEADER TO THE TRANSMITTER:  
 FV-440, FSV-441, HV-441, HV-XXXX, FV-XXXX, & FSV-XXXX

 IDENTIFIES THE CONNECTING SEGMENT OF THE TRANSMITTER PURGE SYSTEM, WHERE XXX IS THE SEGMENT IDENTIFICATION NUMBER. (SEE DWG. E900013, SHT. 2 OF 2 FOR DETAILS.) THIS SYMBOL INDICATES THAT THE FOLLOWING EQUIPMENT IS IN THE PURGE LINE FROM THE NITROGEN HEADER TO THE TRANSMITTER:  
 FV-440, FSV-441, HV-441, HV-XXXX, & FSV-XXXX.

E

ES:


 THIS FLAGGED NOTE DESIGNATES THE FOLLOWING EQUIPMENT WHICH IS NOT SHOWN ON THIS DWG. FOR CLARITY; PANEL-MOUNTED ON/OFF STATION (HAND SWITCH WITH POSITION INDICATION LAMPS), 24 VDC RELAY, 117 VAC 60 HZ SOLENOID VALVE.


 FV-940 WILL NOT OPEN UNTIL PT-901 MEASURES A PRESSURE LESS THAN OR EQUAL TO 2 PSIG.


D

FROM HV 505  
DWG. E900011

FROM HV 320  
DWG. E900011














- 4 FV-919 & FV-919A WILL NOT OPEN UNTIL A PRESSURE DIFFERENTIAL LESS THAN OR EQUAL TO 5.0 PSID. REF. DWG. NO. D910 MUST BE HIGHER THAN THE PRESSURE IN THE LOWER
- 5 FV-923 WILL NOT OPEN UNTIL A PRESSURE DIFFERENTIAL LESS THAN OR EQUAL TO 2.0 PSID. REF. DWG. NO. D910 MUST BE HIGHER THAN THE PRESSURE IN THE LOWER
- 6 LOCKHOPPER FILL VALVE CANNOT BE OPENED UNTIL DUMP VALVE IS OPENED. DUMP VALVE CANNOT BE OPENED IF THE FILL OR DUMP VALVE IS OPENED.
- 7 RELAY INTERLOCKS PREVENT DUMP VALVE FROM BEING OPENED UNTIL FILL VALVE IS OPENED.
- 8 DESIGNATES THAT THE CONTROLLER IS LOCKED TO PREVENT ACCIDENTS FROM OCCURRING.
- 9 FV-913 WILL NOT OPEN UNTIL A PRESSURE DIFFERENTIAL LESS THAN OR EQUAL TO 5.0 PSID. THE PRESSURE IN THE LOWER THAN THE PRESSURE IN THE UPPER
- 10 FV-941 WILL NOT OPEN UNTIL A PRESSURE DIFFERENTIAL LESS THAN OR EQUAL TO 5.0 PSID. REF. DWG. NO. D910 MUST BE HIGHER THAN THE PRESSURE IN THE LOWER
- 11 RELAY INTERLOCKS PREVENT VALVES 909, 920 & 914 FROM OPENING UNTIL VALVE 923 IS OPENED.
- 12 THIS DWG. & DWGS. E900010, E900011, E900013 SUPERCEDES DWG. R800524 (TUBING & PIPING SUMMARY).
- 13 RELAY INTERLOCKS PREVENT VALVES FROM BEING OPENED UNTIL VALVE 923 IS OPENED.
- 14 RELAY INTERLOCKS PREVENT VALVES FROM OPENING UNLESS THE PRESSURE DIFFERENTIAL IS GREATER THAN 5.0 PSID. REF. DWG. NO. D910 MUST BE HIGHER THAN THE PRESSURE IN THE LOWER

THIS DRAWING IS PART OF THE EG&G DOCUMENT CONTROL SYSTEM

REFERENCE DRAWINGS	DRAFTER	DATE	UNITED STATES OF AMERICA DEPARTMENT OF ENERGY
E900010 E900011 E900013	S. CONKO	3/6/90	
	CHECKER	DATE	TITLE:  FLI
	A. R. KUBALA	3/6/90	
	PROJECT ENGINEER	DATE	SIZE   FSCH NO
	J.P. KANSKY	3/6/90	
		DATE	E
		DATE	
		DATE	
		DATE	
		DATE	

RPV-701.

FV-919 & FV-919A WILL NOT OPEN UNTIL PDT-919 MEASURES A PRESSURE DIFFERENTIAL LESS THAN OR EQUAL TO 5.0 PSID. REF. DWG. NO. D910379. THE PRESSURE IN VSL-903 MUST BE HIGHER THAN THE PRESSURE IN VSL-904.

FV-923 WILL NOT OPEN UNTIL PT-923 MEASURES A PRESSURE LESS THAN OR EQUAL TO 2 PSIG. REF. DWG. NO. D910379

LOCKHOPPER FILL VALVE CANNOT BE OPENED IF THE N2 CHARGING VALVE IS OPENED. DUMP VALVE CANNOT BE OPENED IF THE N2 CHARGING VALVE IS OPENED. N2 CHARGING VALVE CANNOT BE OPENED IF THE FILL OR DUMP VALVES ARE OPEN.

RELAY INTERLOCKS PREVENT THE LOCKHOPPER'S FILL VALVE AND VENT VALVE FROM BEING OPEN AT THE SAME TIME.

DESIGNATES THAT THE CONTROL PANEL SWITCH IS PHYSICALLY LOCKED TO PREVENT ACCIDENTAL ACTUATION.

FV-913 WILL NOT OPEN UNTIL PDT-934 MEASURES A PRESSURE DIFFERENTIAL LESS THAN OR EQUAL TO 5.0 PSID. THE PRESSURE IN VSL-902 MUST BE LOWER THAN THE PRESSURE IN CYC-701.

FV-941 WILL NOT OPEN UNTIL PT-902 MEASURES A PRESSURE LESS THAN OR EQUAL TO 2 PSIG.

RELAY INTERLOCKS PREVENT THE LOCKHOPPER VENT VALVES 909, 920 & 914 FROM OPENING UNLESS FV-912 IS OPEN.


THIS DWG. & DWGS. E900010, E900011 & E900013 SUPERCEDES DWG. R800524 (SEE DWG. E900013 FOR NOTES, TUBING & PIPING SUMMARY).

RELAY INTERLOCKS PREVENT THE LOCKHOPPER'S FILL AND DUMP VALVES FROM BEING OPEN AT THE SAME TIME.

RELAY INTERLOCKS PREVENT THE LOCKHOPPER'S DUMP VALVE FROM OPENING UNLESS THE VENT VALVE IS OPEN.


C

DWG NO  
E900012  
1


DRAFTER S. CONKO	DATE 3/6/90	 <p>United States Department of Energy MORGANTOWN ENERGY TECHNOLOGY CENTER Morgantown, WV</p>
CHECKER A. R. KUBALA	DATE 3/6/90	
PROJECT ENGINEER J.P. KANSKY	DATE 3/6/90	
	DATE	TITLE B-12 P&ID FLUIDIZED BED GASIFIER A.G.C.
	DATE	
	DATE	
	DATE	SIZE FSCN NO DWG NO E [ ] E900012
	DATE	REV 6

A



H






G



1" SCH 80 316 SS




DISCONNECTED AND DISABLED






TO VENT VSL-  
DWG. E90001 (B-3)

1" SCH 80 316 SS




DISABLED


FROM PY 713  
DWG. E900012  
(H-2)




SCH 80 316 SS

0-5000 SCFH  
@ 500 PSIG & 1000° F





SCH 80 SS



0-300 PSIG

ZONE		REV	REVISION	
GEN	4		ADDED DESIGN PRESSURE AND DESIGN TEMPERATURE CYC-906, CYC-908, AND CYC-702; MODIFIED FI-REMOVED ALL NUMBERS FROM ADACS SYMBOLS ADDED FD-451, HCV-317B & FSV-452 ISSUED FOR CONSTRUCTION	
DRAFTER		DATE	CHECKER	DATE
GARY J. KULCHOCK		4/5/93	S CONKO	4/5/93
EG&G ES&H		DATE	PROJECT ENGR.	DATE
J. L. BUCKLEW		4/7/93	JOHN ROCKEY	5/27/93
ZONE		REV	REVISION	
GEN	5		ADDED NOTE ON (2) INCINERATOR DESIGNATION. ADDED "#1" TO ALL N <sub>2</sub> DESIGNATIONS; REMOVED MODIFIED INCINERATOR DESCRIPTION IN LEGEND. ADDED NOTE TO VENT SYSTEM, ZONE F-5; ADDED CONNECTED PIPING FROM VENT SYSTEM, ZONE F-5. ISSUED FOR CONSTRUCTION	
DRAFTER		DATE	CHECKER	DATE
Gary Kulchock		9/10/93	S. Conko	9/14/93
EG&G ES&H		DATE	PROJECT ENGR.	DATE
Larry Bucklew		9/17/93	John Rockey	9/21/93
ZONE		REV	REVISION	
GEN	6		EXTENSIVE CHANGES AS PER MARKED PRINT REDLINED. ISSUED FOR CONSTRUCTION	
DRAFTER		DATE	CHECKER	DATE
<i>Gary Kulchock</i>		10/7/94	<i>S. Conko</i>	10-7-94
EG&G ES&H		DATE	PROJECT ENGR.	DATE
<i>J. L. Bucklew</i>		10-11-94	<i>John M. Rockey</i>	10/11/94

TUBING SUMMARY

SIZE	WALL THICKNESS
1/4"	0.035
1/2"	0.035
1/2"	0.065
1"	0.049

PIPING SUMMARY

SIZE	WALL THICKNESS
1/2"	SCH 40
1/2"	SCH 80
1/2"	SCH 80
1/2"	SCH 80

REVISION

ZONE	REV	DESCRIPTION	DATE
GEN	4	ADDED DESIGN PRESSURE AND DESIGN TEMPERATURE TO VSL-905, VSL-906, VSL-907, CYC-906, CYC-908, AND CYC-702; MODIFIED FI-501 AND VARIOUS SCFH'S REMOVED ALL NUMBERS FROM ADACS SYMBOLS ADDED FD-451, HCV-317B & FSV-452 ISSUED FOR CONSTRUCTION	04/01/93
OWNER		DATE	CHECKER
GARY J. KULCHOCK		4/5/93	S CONKO
EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
JAY RUTTEN	4/7/93	D. LUNIFELD	4/7/93
PROJECT ENGR.	DATE	DOE CEISSD	DATE
JOHN ROCKEY	5/27/93	BILL AYERS	5/27/93
BRANCH MANAGER	DATE	DOE CEISSD	DATE
LARRY STRICKLAND	5/27/93	BILL AYERS	5/27/93
ZONE	REV	DESCRIPTION	DATE
GEN	5	ADDED NOTE ON (2) INCINERATOR DESIGNATIONS; ADDED PIPE SIZE (ZONE C-6) ADDED "N1" TO ALL N2 DESIGNATIONS; REMOVED HV-932; REVISED AND RENAMED FV-931 "WAS HV-931" MODIFIED INCINERATOR DESCRIPTION IN "LEGEND"; ADDED TUBING SIZE TO SAMPLE SYSTEM B (ZONE D-3) ADDED NOTE TO VENT SYSTEM, ZONE F-5; ADDED HV-800B, HV-800A & TE-900 CONNECTED PIPING FROM VENT SYSTEM, ZONE A-7 & VSL-906 TO EXISTING SYSTEM ISSUED FOR CONSTRUCTION	09/01/93
OWNER		DATE	CHECKER
GARY KULCHOCK		9/10/93	S. Conko
EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
JAY RUTTEN	9/14/93	Dave Lunifeld	9/20/93
PROJECT ENGR.	DATE	DOE CEISSD	DATE
JOHN ROCKEY	9/21/93	John Rotunda/WJA	9/20/93
BRANCH MANAGER	DATE	DOE CEISSD	DATE
LARRY SHADLE	9/21/93	John Rotunda/WJA	9/20/93
ZONE	REV	DESCRIPTION	DATE
GEN	6	EXTENSIVE CHANGES AS PER MARKED PRINT REDLINED BY JAY RUTTEN ON 15 FEB 94. ISSUED FOR CONSTRUCTION	9/29/94
OWNER		DATE	CHECKER
GARY J. KULCHOCK		10/7/94	S. Conko
EG&G RESPONSIBLE ENGR.	DATE	REVIEWER	DATE
JAY RUTTEN	10-7-94	D. Lunifeld	10/11/94
PROJECT ENGR.	DATE	DOE CEISSD	DATE
JOHN ROCKEY	10/11/94	John Rotunda/WJA	10/11/94
BRANCH MANAGER	DATE	DOE CEISSD	DATE
LARRY SHADLE	10-11-94	John Rotunda/WJA	10/11/94

H

G

TUBING SUMMARY

SIZE	WALL THICKNESS	TYPE
1/4"	0.035	304 SS
1/2"	0.035	CU TYPE K
1/2"	0.065	304 SS
1"	0.049	CU TYPE K


PIPING SUMMARY

SIZE	WALL THICKNESS	TYPE
1/2"	SCH 40	CS
1/2"	SCH 80	CS
1/2"	SCH 80	304 SS
1/2"	SCH 80	316 SS


F





TO FV 452  
DWG. E900012










d = 1.163







**NOTES:**

- 1 T W P P 6
- 2 F I R \
- 3 F L
- 4 F
- 5 F
- 6 F
- 7 F
- 8 F
- 9 F

- 1/2'
- 1/2'
- 1/2'
- 1/2'
- 1'
- 1'
- 1'
- 1'
- 1'
- 2'
- 2'
- 2'
- 3'
- 4'
- 4'

TO SAMPLE SYSTEM B, HV-1  
DWG. E900013,  
SHEET 2:

TO SAMPLE SYSTEM A, HV-4  
DWG. E900013,  
SHEET 2

1/2"	SCH 40	CS
1/2"	SCH 80	CS
1/2"	SCH 80	304 SS
1/2"	SCH 80	316 SS
1"	SCH 40	CS
1"	SCH 80	CS
1"	SCH 80	304 SS
1"	SCH 80	316 SS
1"	SCH 160	316 SS
2"	SCH 40	CS
2"	SCH 80	304 SS
2"	SCH 80	316 SS
3"	SCH 160	316 SS
4"	SCH 40	CS
4"	SCH 40	304 SS

F

NOTES:

1

THIS FLAGGED NOTE DESIGNATES THE FOLLOWING EQUIPMENT WHICH IS NOT SHOWN ON THIS DWG. FOR CLARITY; PANEL-MOUNTED ON/OFF STATION (HAND SWITCH WITH POSITION INDICATION LAMPS), 24 VDC RELAY, 117 VAC 60 HZ SOLENOID VALVE.

E

2

FV-926 WILL NOT OPEN UNTIL PDT-926 MEASURES A PRESSURE DIFFERENTIAL LESS THAN OR EQUAL TO 5.0 PSID. REF. DWG. NO. D910378. THE PRESSURE IN VSL-905 MUST BE LOWER THAN THE PRESSURE IN CYC-702

3

FV-929 WILL NOT OPEN UNTIL PT-929 MEASURES A PRESSURE LESS THAN OR EQUAL TO 2 PSIG. REF. DWG. NO. D910378

4

THE (B-12) FBG'S HS-500 AND THE (B-4) SIDESTREAM'S HS-500 MUST BOTH BE ON FOR FV-500 TO OPEN.

5

HS-59 IS LOCATED ON THE MGCR CONTROL PANEL

6

2 LOCKHOPPER FILL VALVE CANNOT BE OPENED IF THE N<sub>2</sub> CHARGING VALVE IS OPENED. DUMP VALVE CANNOT BE OPENED IF THE N<sub>2</sub> CHARGING VALVE IS OPENED. N<sub>2</sub> CHARGING VALVE CANNOT BE OPENED IF THE FILL OR DUMP VALVES ARE OPEN.

7

RELAY INTERLOCKS PREVENT THE LOCKHOPPERS FILL VALVE AND VENT VALVE FROM BEING OPEN AT THE SAME TIME.

D

8


DESIGNATES THAT THE CONTROL PANEL SWITCH IS PHYSICALLY LOCKED TO PREVENT ACCIDENTAL ACTUATION.

9


RELAY INTERLOCKS PREVENT THE LOCKHOPPER VENT VALVE FV-927 FROM OPENING UNLESS FV-912 IS OPEN.

10

LINES TO GAUGES, TRANSMITTERS, & MANUAL PRESSURE RELIEF TO FLAIR ARE 1/2".



VENT



1 1/2" SCH 40 CS  
6000 SCFH

VENT  
CYCLONE  
CYC-908  
SEE VESSEL  
DWG.  
E810181

DESIGN PRESS.  
150 PSIG  
DESIGN TEMP.  
150° F

4"

FV  
933

TO DISPOSAL  
DRUM

PULSE JET  
CONTROLLER

VENT  
BAG  
FILTER  
FLT-908  
SEE DWG.  
D820016

6"

N<sub>2</sub>  
100 PSIG

HV  
476

55 GAL.  
BARREL

FILTER  
F-703  
A


FV  
760

FC  
2"




FROM B-12  
ENTRAINED UNIT



FROM SAMPLING  
SYSTEM  
DWG. E900013, SHT 2  
(G-1, H-6, F-6, E-3)




DISCONNECTED AND DISABLED



NATURAL GAS  
35 PSIG





- 12 SCF IS AT 14.7 PSIA
- 13 THIS DWG. & DWGS. SUPERCEDES DWG. R
- 14 RELAY INTERLOCKS VALVES FROM BEIN
- 15 RELAY INTERLOCKS FROM OPENING UNL

LEGEND:

- = RANGE SELECTOR S
- = MANIFOLD TO PACK
- = INPUT TO THE DDA
- IDENTIFIES THE C PURGE SYSTEM, WH NUMBER. (SEE DW. THIS SYMBOL INDIC IS IN THE PURGE I TRANSMITTER:  
FV-440, FSV-44 FSV-XXXP
- IDENTIFIES THE C PURGE SYSTEM, WH NUMBER. (SEE DW. THIS SYMBOL INDIC IS IN THE PURGE TRANSMITTER:  
FV-440, FSV-44

THIS DRAWING IS PART OF THE EG&G DOCUMENT CONTROL SYSTEM

REFERENCE DRAWINGS	DRAFTER	DATE
E900010 E900011 E900012 E920205	S. CONKO	3/6/90
	CHECKER	DATE
	A. R. KUBALA	3/6/90
	PROJECT ENGINEER	DATE
	J. P. KANOSKY	3/6/90
	_____	DATE
_____	DATE	
_____	DATE	
_____	DATE	

DATE

12

SCF IS AT 14.7 PSIA AND 60° F

13

THIS DWG. & DWGS. E900010, E900011, AND E900012  
SUPERCEDES DWG. R800524.

14

RELAY INTERLOCKS PREVENT THE LOCKHOPPERS FILL AND DUMP  
VALVES FROM BEING OPEN AT THE SAME TIME.

15

RELAY INTERLOCKS PREVENT THE LOCKHOPPERS DUMP VALVE  
FROM OPENING UNLESS THE VENT VALVE IS OPEN.

C

LEGEND:

RSS = RANGE SELECTOR SWITCH

I = MANIFOLD TO PACKAGED INCINERATOR SYSTEM


A = INPUT TO THE DDAS SYSTEM

G  
XXX  
IDENTIFIES THE CONNECTING SEGMENT OF THE TRANSMITTER  
PURGE SYSTEM, WHERE XXX IS THE SEGMENT IDENTIFICATION  
NUMBER. (SEE DWG. E900013, SHT. 2 OF 2 FOR DETAILS.)  
THIS SYMBOL INDICATES THAT THE FOLLOWING EQUIPMENT  
IS IN THE PURGE LINE FROM THE NITROGEN HEADER TO THE  
TRANSMITTER:  
FV-440, FSV-441, HV-441, HV-XXXP, FV-XXXP, &  
FSV-XXXP

H  
XXX  
IDENTIFIES THE CONNECTING SEGMENT OF THE TRANSMITTER  
PURGE SYSTEM, WHERE XXX IS THE SEGMENT IDENTIFICATION  
NUMBER. (SEE DWG. E900013, SHT. 2 OF 2 FOR DETAILS.)  
THIS SYMBOL INDICATES THAT THE FOLLOWING EQUIPMENT  
IS IN THE PURGE LINE FROM THE NITROGEN HEADER TO THE  
TRANSMITTER:  
FV-440, FSV-441, HV-441, HV-XXXP, & FSV-XXXP.

DWG NO  
E9000013  
SH  
1

DRAFTER	S. CONKO	DATE	3/6/90		
CHECKER	A. R. KUBALA	DATE	3/6/90		
PROJECT ENGINEER	J. P. KANOSKY	DATE	3/6/90		
	—	DATE	—		
	—	DATE	—		
	—	DATE	—		
	—	DATE	—		
		SIZE	FSC# NO	DWG NO	REV
		E		E900013	6



United States Department of Energy  
MORGANTOWN ENERGY TECHNOLOGY CENTER  
Morgantown, WV

B-12 P&ID  
FLUIDIZED BED GASIFIER  
A.G.C.

A