STATE	PROJECT	SHEET NUMBER
OR	RRP NEBA 100(1)	B.1

SUMMARY OF QUANTITIES

ITEM	DESCRIPTION	UNIT	SECTION C TYPICAL SECTION	SECTION D PLAN VIEW	SECTION E EROSION CONTROL	SECTION G TRAFFIC CONTROL										ESTIMATED QUANTITIES PLAN	ESTIMATED QUANTITIES BID SCHEDULE	
	PLAN SHEET SECTION -------->>																	
15101-0000	MOBILIZATION	LPSM														ALL	ALL	
15201-0000	CONSTRUCTION SURVEY AND STAKING	LPSM														ALL	ALL	
15301-0000	CONTRACTOR QUALITY CONTROL	LPSM														ALL	ALL	
15401-0000	CONTRACTOR TESTING	LPSM														ALL	ALL	
15501-0000	CONSTRUCTION SCHEDULE	LPSM														ALL	ALL	
15705-1500	SOIL EROSION CONTROL, SEDIMENT WATTLE	LNFT			2313.0											2313.0	2,450.0	
15801-0000	WATERING FOR DUST CONTROL	MGAL	43.15													43.15	50.00	
20301-1100	REMOVAL OF GATE	EACH		1												1	1	
20301-2700	REMOVAL OF STRUCTURE , GATE POST	EACH		2												2	2	
20401-0000	ROADWAY EXCAVATION	CUYD	493.0													493.0	493.0	(CQ)
20402-0000	SUBEXCAVATION	CUYD	56.9													56.9	65.0	
20701-0700	EARTHWORK GEOTEXTILE, TYPE II-A	SQYD	2885													2885	3,300	
21101-2000	ROADWAY OBLITERATION, METHOD 2	SQYD		209												209	250	
21201-0000	LINEAR GRADING	STA	2.99													2.99	3.50	
30802-1000	ROADWAY AGGREGATE, METHOD 1 , SURFACING COURSE	TON	1231.93													1231.93	1,500.00	
30802-1000	ROADWAY AGGREGATE, METHOD 1 , BASE COURSE	TON	2741.70													2741.70	3,000.00	
40301-0300	HOT ASPHALT CONCRETE PAVEMENT, GRADING C	TON	1124.77													1124.77	1,200.00	
41201-1000	TACK COAT GRADE CSS-1, CSS-1H, SS-1, OR SS-1H	TON	1.28													1.28	1.50	
60802-0500	PAVED WATERWAY, TYPE 5	LNFT	40.0													40.0	50.0	
60901-0400	CURB, CONCRETE, 6-INCH DEPTH	LNFT		295.0												295.0	310.0	
60915-1000	WHEELSTOP, CONCRETE	EACH		16												16	17	
61901-0000	FENCE	LNFT		1687.0												1687.0	1,800.0	
61902-0000	GATE , ELECTRIC	EACH		2												2	2	
62201-0050	DUMP TRUCK, 5 CUBIC YARD MINIMUM CAPACITY	HOUR															40.0	
62201-0400	BACKHOE LOADER, 2 CUBIC F00T MINIMUM RATED CAPACITY BUCKET, 12-INCH WIDTH	HOUR															40.0	
62201-2850	MOTOR GRADER, 12 FOOT MINIMUM BLADE	HOUR															40.0	
62301-0000	GENERAL LABOR	HOUR															40.0	
62405-0300	PLACING CONSERVED TOPSOIL, 4-INCH DEPTH	SQYD	1506													1506	1,550	

(CQ) means Contract Quantity

6/2007 Brian Wacker Designed by:
6/2007 Mike Johnson Checked by:
4-Oct-2007 7:44 AM
F:\HIGHWAYS\FHWA\Refuge05\Cannery

STATE	PROJECT	SHEET NUMBER
OR	RRP NEBA 100(1)	B.2

SUMMARY OF QUANTITIES

		PLAN SHEET SECTION -------->>	SECTION C TYPICAL SECTION	SECTION D PLAN VIEW	SECTION E EROSION CONTROL	SECTION G TRAFFIC CONTROL										ESTIMATED QUANTITIES	
ITEM	DESCRIPTION	UNIT														PLAN	BID SCHEDULE
62502-0000	TURF ESTABLISHMENT	SQYD	1209													1209	1,500
63302-0000	SIGN SYSTEM	SQFT				101.6										101.6	110.0
63315-0000	RUMBLE STRIP	SQYD				20										20	25
63401-0300	PAVEMENT MARKINGS, TYPE B, SOLID , WHITE	LNFT				8492										8492	8,900
63401-0450	PAVEMENT MARKINGS, TYPE B, DOTTED	LNFT				444										444	500
63405-0050	PAVEMENT MARKINGS, SYMBOLS , TYPE H, SLOW	EACH				2										2	2
63405-3250	PAVEMENT MARKINGS, TYPE H, ACCESSIBILITY SYMBOL	EACH				3										3	3
63406-0100	RAISED PAVEMENT MARKER TYPE A	EACH				124										124	140
63501-0000	TEMPORARY TRAFFIC CONTROL	LPSM														ALL	ALL
64601-1000	BUILDING, RESTROOM FACILITY	EACH		1												1	1
64602-2000	BUILDING, SUPPORT BUILDING , OVERLOOK STRUCTURE	LPSM														ALL	ALL
64603-0300	FIXTURE, BENCH	EACH		3												3	3
64603-0500	FIXTURE, BICYCLE STORAGE RACK	EACH		1												1	1
64603-0800	FIXTURE, KIOSK	EACH		1												1	1

F:\HIGHWAYS\FHWA\Refuge05\Cannery 4-Oct-2007 7:44 AM Designed by: Mike Johnson 6/2007 Checked by: Brian Wacker 6/2007