

## INP Meeting

# TRU Waste Processing Facility

May 18, 2005


Craig Bachmeier, PADNWP

# Mission Need

---

- NNSA has signed an agreement with NMED that requires RCRA closure of the TA-54 Area G MDA.
- To close the site will require suspension and relocation of all current waste management operations.
- TRU waste will be generated by ongoing NNSA program activities at the TA-55 plutonium facility.
- This project is needed to relocate TRU waste capabilities from Area G.

# Facilities Planning - Strategic




# TA-54 Area G – TRU Storage Facility



# Program Requirements

## Programs Generating TRU:\*

- Pit Manufacture/Stockpile Stewardship
- Mixed Oxide Fuel R&D
- Vault Disposition Programs (94-1)
- Pu-238 Clean-up and Stabilization
- Actinide R&D
- TA-18 Inventory Reduction
- Offsite Source Recovery Project



\* FY04 Waste Volume Forecast, LA-UR-04-6682

# Program Requirements

---

## Backlog:

- 3,400 Drums (700 M<sup>3</sup>)
- 115 SWBs/Boxes/Crates (350 M<sup>3</sup>)
- Backlog to be worked prior to 2010

## Newly Generated:


- 800-1,000 DE's
- 17 M<sup>3</sup> Large Items

## Production:


- NG Waste must be shipped within 12 months of generation per DOE order 435.1 and Appendix F to UC contract
- Ship Rate ~ 1 truck per week

# NG TRU Volume Forecast

## Historical Volumes (All Programs)



## Volume Forecast (NG Only) \*



\* This forecast is based on the 20 pits per year analyzed in the SWEIS. An increase to 40 pits per year would result in approximately 30% more TRU waste.

# Program Requirements

---

## Outyear Volume Forecast:

- In the post 2010 time frame TRU volumes are expected to be similar to the current volume of 800-1000 drums.
- Changes:
  - Outyear volume forecasts are updated annually by ENV-P2
  - Vault workoff will be complete
  - OSRP volumes will stabilize at 25-30 drum equivalents
  - Pit activity will increase but not beyond volumes analyzed in the SWEIS ~ 20 pits per year
  - Waste Minimization efforts will continue to drive down routine generation
  - ER volumes are updated annually
  - MOX program is expected to increase in FY06 – but long term forecasts remain unclear
  - Volumes related to future mission changes have not been included.
  - The design capacities for subsystems will include appropriate contingency for year to year variations



# Justification

---

- The project is required to meet assigned NNSA Pu mission requirements.
- Feasibility and top level alternatives for facility location and design will be developed as part of the CD-0 planning. The project scope justification and mission need will be enhanced at that time.

# Alternatives

---

- A “No Action” alternative to moving the TRU & LLW operations from Area G has not been identified. RCRA closure standards will require that operations cease.
- Operations Alternatives
  - M&O, CBFO-CCP, or DOE WM Subcontract
  - Production could be on-going or batch mode
  - Some capability could be housed in TA-55
- Siting alternatives include:
  - TA-54 West – co-located with RANT
  - TA-50/55 – co-located with other WM facilities
  - 35-Atlas Facility
  - Traditional siting will occur during CD-0 & CDR stages
- Design/Construction alternatives:
  - New vs. Modified Facilities
  - CD-0 planning will identify other scenarios

# Scope

---

## Planning Assumptions

- TRU legacy operations completed by 2012 with 2015 closure
- NG strategy must be implemented prior to Area G closure
- Generators and program missions remain largely unchanged
- Characterization requirements will change (w/Permit Mods):
  - Delete Head Space Gas Sampling (flammability still required)
  - Delete VE/Repack based on operating experience
  - 100% RTR reduced to Statistical RTR to confirm AK
- Additional WIPP requirements and LANL AB constraints can be optimized

# Scope

---

## Required Capabilities:

Results of initial scoping studies and basis for long-term solution:

- Staging
- Characterization
  - RTR
  - NDA
- Certification Activities
- Volume Reduction
- Shipping

# Scope

---


## Required Facilities & Equipment:

Results of initial scoping studies and basis for long-term solution:

- New or Modified Facility
- 10,000 sf
- HC2
- PC3
- CAT IV

# Preliminary Siting Alternatives

~~Potential TRU Facility Site @ TA-8~~



35-Atlas

Potential TRU Facility Sites ?


# TA-54 RANT - TRU Siting Alternative



UNCLASSIFIED

CIC-9: RN97-390-024

# Schedule





# Cost Estimate



**TEC: \$16-25M**

**OPC: \$ 4-5M**

**TPC: \$20-30M**

**Basis: Pre-conceptual**

## Funding Profile: (Conventional Schedule & 06 TYCSP)

\$K	Total	FY06	FY07	FY08	FY09	FY10	FY11	FY12
OPC	4,000	500	1,500	300	300	300	300	800
PE&D	4,000			2,000	2,000			
Const.	22,000					12,000	10,000	
TPC	30,000	500	1,500	2,300	2,300	12,300	10,300	800
<i>ICPP</i>	<i>40,000</i>			<i>5,000</i>	<i>8,000</i>	<i>12,000</i>	<i>15000</i>	

# Relationship to other Programs/Projects

---

- Completion of this project is not dependent on any other program or project.
- The core weapons program *is* dependent on this project for ongoing TRU waste management support.
- To complete Area G closure by 2015 requires:
  - NNSA RTBF to move LLW and TRU operations out of Area G
    - TRU Line item (funding identified)
    - LLW Access Control; GPP (funding not identified)
    - LLW Characterization Facility; GPP (funding not identified)
    - LLW Compaction Facility; GPP (funding not identified)
  - NNSA FIRP/RTBF to D/D the vacated structures & infrastructure – *out year FIRP schedules include these structures but work beyond FIRP is not programmed/funded yet*
  - EM Waste Disposition must complete the Legacy Waste project – *2010 Project is partially funded*
  - EM ER Program must complete closure of Area G – *funding is programmed and project planning is underway*

# CD-0 Plan

---

## ■ Scope

- Prepare CD-0 Package @ NNSA Requirements
  - Management Brief
  - Mission Need Statement
  - Program Requirements Document
  - Cost Estimate
  - Conceptual Design Execution Plan
  - IPR Review & CAP
  - ESAAB Briefing

## ■ Cost - \$400K


## ■ Schedule

- August 2005 - draft to LASO
- December 2005 – ESAAB

## ■ Integration

- The project has been included in draft FY06 TYCSP submittal
- LANL is working to include this project in the ICPP


# Schedule for CD-0 Package Development



*Perform Analysis, Planning, and Develop CD-0 Package*

*Sponsor/Management Review and Approvals*

# LANL WM Organization



## Issues/Concerns

---

- Impacts of DBT and RLWTF-U changes on facility siting.
- TSD Requirements – we need to understand whether these could be relaxed to reduce on site transportation expense. This would drive decisions on the RANT facility.
- Schedule – the conventional project schedule is reasonable for a HC 2 nuclear facility, however, the completion date will create risk of delay to the ER project final cover activity. After CD-0 definition work is complete, opportunities to accelerate should be considered.
- Funding for all of the projects has not been identified yet