



A000 7/17

AMENDMENT OF SOLICITATION/ MODIFICATION OF CONTRACT		1. CONTRACT ID CODE	PAGE 1 OF PAGES 2
2. AMENDMENT/ MODIFICATION NO. A00007	3. EFFECTIVE DATE 10/12/95	4. REQUISITION/ PURCHASE REQ. NO.	5. PROJECT NO. (If applicable) CIN-09
6. ISSUED BY U. S. Army Engineer District, New Orleans Corps of Engineers P.O. Box 60267 New Orleans, LA 70160-0267		7. ADMINISTERED BY (If other than Item 6)	
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code) B&K Construction Company, Inc. 1905 Highway 59 Mandeville, LA 70448		(X)	9A. AMENDMENT OF SOLICITATION NO.
CODE OGTN3		9B. DATED (See Item 11)	
FACILITY CODE		X	10A. MODIFICATION OF CONTRACT/ ORDER NO. DACW29-94-C-0079
		10B. DATED (See Item 13) 7/11/94	
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS			
<input type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input type="checkbox"/> is extended, <input type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.			
12. ACCOUNTING AND APPROPRIATION DATA (If required) Funds are decreased by \$428.96.			
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ ORDERS, IT MODIFIES THE CONTRACT/ ORDER NO. AS DESCRIBED IN ITEM 14.			
(X) X	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.		
	B. THE ABOVE NUMBERED CONTRACT/ ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103 (b).		
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF: CC I.83, "CHANGES"		
	D. OTHER (specify type of modification and authority)		
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input checked="" type="checkbox"/> is required to sign this document and return <u>original</u> copies to the issuing office.			
14. DESCRIPTION OF AMENDMENT/ MODIFICATION (Organized by UCF section headings, including solicitation/ contract subject matter where feasible.) The following change is made to the above numbered contract for Lake Pontchartrain, Louisiana and Vicinity, High Level Plan, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Robert E. Lee Blvd., West Bank; Mirabeau Avenue to Leon C. Simon Blvd., East Bank Floodwall, Orleans Parish, Louisiana deleting one concrete monolith on the west side of the canal at pumping station #4 from approximately Sta. 100+84.14 to Sta. 101+12.35.			
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.			
15A. NAME AND TITLE OF SIGNER (Type or print) B & K CONSTRUCTION CO. INC. H. B. KENYON, PRESIDENT		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) Chester Ashley, Administrative Contracting Officer	
15B. CONTRACTOR/ OFFEROR  (Signature of Person Authorized to sign)	15C. DATE SIGNED 2/26/96	16B. UNITED STATES OF AMERICA BY  (Signature of Contracting Officer)	16C. DATE SIGNED 2-29-96

APR 2 1996

APR 10 1996
*2nd flrst
kmt*

14. Description of Amendment/ Modification (Cont.)

CHANGES TO THE BIDDING SCHEDULE: The schedule of Contract Items, Descriptions, Estimated Quantities, Units, Unit Prices, and estimated Amounts is modified as follows:

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Estimated Amount</u>	<u>Amount of Change</u>
0014	Reinforced Concrete Floodwall	LS	--	\$1,482,731.00	\$1,482,731.00	(-) \$428.96

CHANGES TO THE CONTRACT SPECIFICATIONS: The contract specifications are changed as follows.

(a) Page C2F-4, para. C2F-4.3. At the end of the paragraph add the following: "Posts shall be attached to uncapped sheet piling using 1/2 in diameter X 4 inch long bolts with washers conforming to C5A-4.2.4. Bolts shall be equally spaced with the top and bottom bolts 3 inches from the top and bottom of the sheetpiling respectively. Posts attached to the sheetpiling shall be 10 feet long.

(b) Page C5A-4, para. C5A-5.2. In the paragraph title after "Floodwall", add "and at Joints between Concrete I-Wall and Uncapped Sheet Pile."

CHANGES TO THE CONTRACT DRAWINGS: The contract drawings are changed as follows:

Delete drawings 13, 17, 18, 32, 49, 50, and 51 of 73 in their entirety FILE NO. H-4-40295, and substitute with drawings 13, 17, 18, 32, 49, 50, and 51 of 73.41 of 73, FILE NO. H-4-40295, dated November 1995.

CHANGES TO THE CONTRACT PRICE: The contract price is decreased by \$428.96.

CHANGES TO THE CONTRACT TIME: The contract time remains unchanged.

It is further understood and agreed that this adjustment constitutes compensation in full on behalf of the contractor, its subcontractors and suppliers for all costs and markups directly or indirectly attributable to the changes ordered, for all delays, impacts and extended overhead related thereto, and for performance of the change within the time frame stated.

PRICE NEGOTIATION MEMORANDUM

Lake Pontchartrain, Louisiana and Vicinity, High Level Plan,
London Avenue Outfall Canal, Parallel Protection,
Mirabeau Avenue to Robert E. Lee Blvd., West Bank;
Mirabeau Avenue to Leon C. Simon Blvd., East Bank Floodwall, Orleans Parish, Louisiana
Contract Number DACW29-94-C-0079,
CIN 09
B & K Construction Co., Inc.

1. **CONTRACT DESCRIPTION.** The subject contract was awarded on 11 July 1994 in the amount of \$4,554,500.00. The contract consists of clearing selective demolition; cutting existing steel sheet piling; pulling, cleaning and delivering existing steel sheet piling; driving new steel sheet piling; construction reinforced concrete I-type floodwalls on existing and new steel piling; concrete slope pavement, driving steel sheet piling under South Central Bell telephone cables and New Orleans Sewerage & Water Board 10-foot relocating Sewerage and Water Board feeder cables; modifying existing utilities; degrading existing levees; placing embankment; fertilizing, seeding, and mulching.

2. DESCRIPTION OF MODIFICATION.

a. **SUMMARY AND NECESSITY FOR CHANGE.** One concrete monolith is deleted from the contract in order to provide access to the pump station renovation work in the near future. Several changes are made to the adjacent monoliths to accomplish this.

b. **REASON FOR OMISSION FROM PLANS AND SPECIFICATIONS.** The request for this change, made by the New Orleans Levee Board, was made after award of the contract.

c. **AUTHORITY FOR MODIFICATION.** This change is issued under the authority provided by Contract Clause I.83, CHANGES.

3. PRICE AND TIME JUSTIFICATION.

a. SUMMARY.

<u>Contractor Proposal</u>	<u>Government Estimate</u>	<u>Negotiated Settlement</u>
\$3,784.62	\$161.87	(\$428.96)

b. **PRICING STRATEGY.** A price analysis was used to evaluate the contractor's proposal using an independent Government Estimate which was prepared based on site specific resources and standard industry practices.

c. PARTICIPANTS. Mr. H. B. Kenyon was the Lead Negotiator for the contractor and Mr. Fidel Perez was the Lead Negotiator for the Government.

d. NEGOTIATION SUMMARY. A request for proposal was made of the contractor on 21 December 1995. The contractor submitted a written proposal on 19 January 1996 in the amount of \$5,731.61 with no increase or decrease in contract time. The Government revised the scope of work and a second request for proposal with these revisions was made of the contractor on 26 January 1995. The contractor submitted a proposal on 6 February 1996 in the amount of \$3,784.62. An independent Government estimate was prepared on 1 February 1996 in the amount of \$161.87 with no increase in contract time. Mr. Perez called Mr. Boone Kenyon on 6 February 1996 and a meeting was set for 7 February 1996. Mr. Perez discussed the contractor's costs which had been prepared by Mr. Blake Andrews of B&K and Mr. Kenyon agreed with Mr. Perez on most of the items. Mr. Kenyon requested a recess to call some of his vendors and examine the labor and equipment closely. Mr. Kenyon submitted a revised proposal in the amount of (\$428.96).

This revised proposal compared favorably with the Government estimate, was considered to be fair and reasonable and was accepted. The contractor also agreed that this modification eliminated all impacts to the contract as a result of this change.

4. APPROPRIATION DATA. Funds have been decreased in the amount of \$428.96 under appropriation 96X3122, BEC2111000NOLML, Lake Ponchartrain, New Orleans East Unit.

SUBMITTED FOR APPROVAL

Date: 12 February 1996


FIDEL PEREZ
Lead Government Negotiator

CELMN-CD-NO

12 Mar 96

MEMORANDUM THRU C/Const Div, ATTN: Contr Admin Br

FOR C/Contr Div

SUBJECT: Contract No. DACW29-94-C-0079, Lake Pontchartrain, Louisiana and Vicinity, High Level Plan, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Robert E. Lee Boulevard, West Bank, Mirabeau Avenue to Leon C. Simon Boulevard, East Bank Floodwall, Orleans Parish, Louisiana

Modification A00007, CIN-09 to the subject contract is forwarded for the contract file.

Enclosure

John S. Martin

CHESTER ASHLEY 3-15-96
Area Engineer
New Orleans Area Office

Fin

MAR 15 1996

Call me 15/11

SF-30

February 27, 1996

MORTON ^{Out}
CELMN-CD-NO-E

Construction Division
New Orleans Area Office

DUHON
CELMN-CD-NO-Q

SUBJECT: Contract DACW29-94-C-0079, Lake Pontchartrain, Louisiana and Vicinity, High Level Plan, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Robert E. Lee Blvd., West Bank; Mirabeau Avenue to Leon C. Simon Blvd., East Bank Floodwall, Orleans Parish, Louisiana Modification A00007, CIN-09



HABBAZ
CELMN-CD-NO

B & K Construction, Incorporated
1905 Highway 59
Mandeville, Louisiana 70448

BERNARD
CELMN-CD-NO

ASHLEY
CELMN-CD-NO

Gentlemen:

Enclosed for your file is the duplicate original of Modification No. A00007, CIN 09 for Contract No. DACW29-95-0079.

Sincerely,

Chester Ashley
Administrative Contracting
Officer

Enclosure

Funding

CHANGE REQUEST

CIN 9

CONTRACT NO. DACW29-94-C-0079

DATE: 13 Feb 96

TITLE/LOCATION: London Ave. Outfall Canal, Parallel Protection

TO: CELMN-PP

FROM (POC): Albert Schick

1. DESCRIPTION OF CHANGE (INCLUDE PLANS, SPECS, & REFERENCES):
One concrete monolith is deleted from the contract to provide access to the pump station renovation work in the near future

2. REASON FOR CHANGE:
The request for change, made by New Orleans Levee Board, was made after award of the contract.

3. AUTHORITY FOR CHANGE: Contract Clause I.83 CHANGES

4. DATE CHANGE DISCOVERED: 26 Jan 96

5. DESIGN ASSISTANCE REQUIRED: None

6. ESTIMATED COST: (428.96) ESTIMATED TIME: -

7. COMMENTS/REMARKS: This change provides a credit to the Govt

8. STATUS OF FUNDS: _____

9. CONST. MGR./DATE: Albert Schick 13 Feb 96 CHG. CAT. _____

FUNDING REQUEST

- 1. Please Program and Commit \$ <428.96> for 2nd QTR, FY 96
- 2. Estimated total contract amount is \$ 4605,838.98 ORG CODE: VD
- 3. Accounting Data: 96X3122 BEC21100 ON OLML ACCTG ELEM: 284

DISTRIBUTION	APPROVAL	DATE	FUNDING STAMP
PROJECT MANAGER (Program Funds)	<u>[C. Ritter]</u>	<u>2.13.96</u>	/
PP-P (Certify Funds)	<u>A. Gunn</u>	<u>2/13/96</u>	
F&A (Commit Funds)			

Program Analyst, POC

Richard T. Hill 2/13/96
 Chief, Construction Division/ Date
 RICHARD T. HILL

CF: ~~CELMN-CD-LA/NO~~ CELMN-PP-P
~~CELMN-PP/CD/ED~~ ~~CELMN-CD-CM~~ CELMN-CD-CS (Schick)

PNM

PNO

PRE NEGOTIATION OBJECTIVES

Lake Pontchartrain, Louisiana and Vicinity, High Level Plan,
London Avenue Outfall Canal, Parallel Protection,
Mirabeau Avenue to Robert E. Lee Blvd., West Bank;
Mirabeau Avenue to Leon C. Simon Blvd., East Bank Floodwall, Orleans Parish, Louisiana
Contract Number DACW29-94-C-0079,
CIN 09
B & K Construction Co., Inc.

1. **CONTRACT DESCRIPTION.** The subject contract was awarded on 11 July 1994 in the amount of \$4,554,500.00. The contract consists of clearing selective demolition; cutting existing steel sheet piling; pulling, cleaning and delivering existing steel sheet piling; driving new steel sheet piling; construction reinforced concrete I-type floodwalls on existing and new steel piling; concrete slope pavement, driving steel sheet piling under South Central Bell telephone cables and New Orleans Sewerage & Water Board 10-foot relocating Sewerage and Water Board feeder cables; modifying existing utilities; degrading existing levees; placing embankment; fertilizing, seeding, and mulching.

2. **PROPOSED MODIFICATION DESCRIPTION:** One concrete monolith is deleted from the contract in order to provide access to the pump station renovation work in the near future. Several changes are made to the adjacent monoliths to accomplish this.

3. **CONTRACTOR PROPOSAL:**

The contractor submitted a proposal on 6 February 1995 in the amount of \$3,784.62.

4. **GOVERNMENT POSITION:** An independent Government Estimate was prepared on 01 February 1996 in the amount of \$161.87.

<u>Contractor Proposal</u>	<u>Government Estimate</u>	<u>Cost Difference</u>
3,784.62	161.87	\$3,622.75

5. COST DIFFERENCES: The contractor's additional costs for materials, equipment and labor are considerably above that of the Government Estimate.

6. OBJECTIVE: The objective of this negotiation is to present the costs differences to the contractor and reach a fair and equitable settlement.



Fidel Perez
Lead Negotiator




Chester Ashley
Administrative Contracting Officer

Gov't Est.

Reasonable Contract Estimate

Project: DACW29-94-C-0079, CIN 09

Description: DELETION OF ONE MONOLITH

Worksheet no.	Description	Estimated Quantity	Unit	Unit Price	Estimated Amount
1	DELETE ONE MONOLITH	1	LS	(\$3,070.06)	(\$3,070.06)
2	TEMPORARY WORK	1	LS	\$3,231.93	\$3,231.93
Total:					\$161.87
		Estimator: FP	7P	Date: 1/16/96	
		Checker:		Date:	

Reasonable Contract Estimate - Detail Summary Sheet:

Prime Contractor

Project:
 DACW29-84-C-0079, CIN 09
 DELETION OF ONE MONOLITH

Bid Item		Equip	Mob & Demob	Labor	Mat'ls	Supply	Sub Total	Dist 21.34%	Total Cost	Unit Cost	Amount	
Designation	Qty	Unit										
DELETE ONE MONOLITH	1	LS	(\$228.00)		(\$1,169.49)	(\$1,132.73)		(\$2,530.22)	(\$539.84)	(\$3,070.06)	(\$3,070.06)	(\$3,070.06)
TEMPORARY WORK	1	LS	\$261.40		\$860.44	\$1,541.79		\$2,663.63	\$568.30	\$3,231.93	\$3,231.93	\$3,231.93
Overhead	10.00%											
Profit	8.68%											
Bond	1.50%											
Total:	21.34%											
Totals			\$33.40		(\$309.05)	\$409.06		\$133.41	\$28.46	\$161.87		\$161.87

Reasonable Contract Estimate Worksheet - Equipment and Labor

Project:
 DACW29-94-C-0079, CIN 09
 DELETE ONE MONOLITH

Unit of Equipment	No.	Hours	Rate	Amount
Chevy Pickup '91	-1	8	7.50	(60.00)
Crane, LS	-1	8	21.00	(168.00)
Subtotal:				(228.00)
Mobilization and Demobilization:				
Small Tools:	0.00%	of labor:		(0.00)
Total Equipment Cost:				(228.00)
Labor	No.	Hours	Rate	Amount
Foreman	-1	4	25.00	(100.00)
Carpenter	-2	6	20.73	(248.81)
Laborer	-3	8	10.56	(253.34)
Concrete Finisher	-3	4	18.51	(222.10)
Operator	-1	8	16.25	(130.03)
Steel Rodman	-3	4	17.93	(215.21)
Total Labor Cost:				(1,169.49)
Total equipment and labor:				(1,397.49)
Remarks:		Date:	Estimator:	FP
			Checker:	

Reasonable Contract Estimate Worksheet - Material and Supplies

Project:
 DACW29-94-C-0079, CIN 09
 DELETE ONE MONOLITH

Material	Unit	Quantity	Price	Amount
CONCRETE	CY	(17.00)	40.00	(680.00)
REBARS	LBS	(761.00)	0.20	(152.20)
1/2" X 36 NEOPRENE	FT	(11.50)	18.00	(207.00)
Sales Tax			9.00%	(93.53)
Total				(1,132.73)
Supplies	Unit	Quantity	Price	Amount
9 % Tax				
Total Supplies Cost				
Total Material and Supplies:				(1,132.73)
Remarks:		Date:	Estimator:	FP
			Checker:	

Reasonable Contract Estimate Worksheet - Equipment and Labor

Project:
 DACW29-94-C-0079, CIN 09
 TEMPORARY WORK

Unit of Equipment	No.	Hours	Rate	Amount
DOZER, KOMATSU D37P	1	4	22.00	88.00
BACKHOE, CASE 580	1	8	12.30	98.40
WELDING MACHINE	1	0.5	150.00	75.00
Subtotal:				261.40
Mobilization and Demobilization:				
Small Tools:	0.00%	of labor:		0.00
Total Equipment Cost:				261.40
Labor	No.	Hours	Rate	Amount
FOREMAN	1	8	22.00	176.00
CARPENTER	2	6	20.73	248.76
WELDER	1	4	17.93	71.72
LABORER	2	8	10.56	168.96
PEO	1	12	16.25	195.00
Total Labor Cost:				860.44
Total equipment and labor:				1121.84
Remarks:			Date:	Estimator: FP
				Checker:

Reasonable Contract Estimate Worksheet - Material and Supplies

Project:
 DACW29-94-C-0079, CIN 09
 TEMPORARY WORK

Material	Unit	Quantity	Price	Amount
1/4" NEOPRENE, 3' X 14'	1	2	300.00	600.00
1/2 X 6 FB, A-36 W/ 9/16 HOLES PUNCHED	1	6	50.00	300.00
RAMNEK FILLER	1	3	75.00	225.00
SHEETMETAL, 18 GA,	EA	4	30.00	120.00
REINFORCING CORNER U-BAR, #6	EA	22	8.00	176.00
Sales Tax			8.50%	120.79
Total				1,541.79
Supplies	Unit	Quantity	Price	Amount
Total Supplies Cost				
Total Material and Supplies:				1,541.79
Remarks:		Date:	Estimator:	FP
			Checker:	

Wage Rate Calculations

Project:
 DACW29-94-C-0079, CIN 09
 DELETION OF ONE MONOLITH

Location:
 Operational Shifts:

Estimator: F Perez Checker:

Craft Description (a)	Basic hourly rate (b)	Overtime		Sub total (b + d) (e)	Taxes & Ins		Sub total (e + g) (h)	Fringe Benefits (i)	Travel or Subsist (j)	Total Cost (h + i + j) (k)
		Mult of (b) (c)	Amt. (b x c) (d)		% of (e) (f)	Amt. (e x f) (g)				
Carpenter	14.81			14.81	0.40	5.92	20.73			20.73
Laborer	7.54			7.54	0.40	3.02	10.56			10.56
Concrete Finisher	13.22			13.22	0.40	5.29	18.51			18.51
Operator	11.61			11.61	0.40	4.64	16.25			16.25
Pile Driver	12.81			12.81	0.40	5.12	17.93			17.93
Welder	12.81			12.81	0.40	5.12	17.93			17.93

Profit Factor
Prime Contractor

Project: DACW29-94-C-0079, CIN 09
Description: DELETION OF ONE MONOLITH

Estimator: FP
Checker:

Factor	Rate	Weight (0.03-0.012)	Value
1. Degree of Risk	20	0.070	1.40%
2. Relative Difficulty of Work	15	0.070	1.05%
3. Size of Job	15	0.120	1.80%
4. Period of Performance	15	0.030	0.45%
5. Contractor's Investment	5	0.075	0.38%
6. Assistance by Government	5	0.120	0.60%
7. Subcontracting	25	0.120	3.00%
Profit Factor:			8.68%

Reasons for Weights Assigned

1. Average
2. Average
3. Less than \$100,000.00
4. Short duration
5. Average
6. No assistance
7. No Subcontracting

London Ave Cont #3 Mod

B + K's estimate:

- material prices okay

- labor & equipment costs are too high for time. ie w/ labor & equipment shown, const. time should be less

- testing of embankment -

B+K is specifying the testing procedures for compacted fill vs semi-compacted fill actually used. Compacted testing is more expensive & unnecessary

- their concrete credit does not include credit for struc excavation & backfill no longer needed

- 1/4" neoprene

- A-36 painted (coal Tar epoxy)

Proposal

CONTRACT DACW29-94-C-0079
 LAKE PONTCHARTRAIN AND VICINITY
 HIGH LEVEL PLAN, LONDON AVENUE
 OUTFALL CANAL, PARALLEL PROTECTION
 LEON C. SIMON BLVD. FLOODWALL
 ORLEANS PARISH, LOUISIANA
 B & K JOB NO. 9402, RFC NO. 008
 CIN-09

DATE: February 7, 1996

DESCRIPTION: Modify the contract by deleting one concrete I-Wall monolith on the west side of the London Avenue Canal at Pumping Station No. 4 from approximately Station 100+84.14 to Station 101+12.35 WB/L. The modifications include the following additional scope items: (1) compacted fill material; (2) two neoprene rubber sheeting sets; (3) two 18 gauge steel sheet metal sets. Futhermore, the modifications include the following revised scope items: (4) fence posts and attachment changes; (5) drive 28.21' of new sheet piling to elevation 14.0' in lieu of elevation 5.75'; (6) delete one concrete I-Wall monolith.

LABOR	Name	Rate	Rg	Hrs	OT Hrs	Total
Scope Item No. 1	Operator - Foreman	16.00		6.00		96.00
	Survey Rodman	11.00		1.00		11.00
	Laborer	8.00		6.00		48.00
	Laborer	8.00		6.00		48.00
	Laborer	7.54		6.00		45.24
Scope Item No. 2	Carpenter	14.81		4.00		59.24
	Laborer	8.00		4.00		32.00
	Laborer	8.00		4.00		32.00
	Welder/Burner	14.81		2.00		29.62
Scope Item No. 3	Carpenter	14.81		2.00		29.62
	Laborer	8.00		2.00		16.00
	Laborer	8.00		2.00		16.00
Scope Item No. 4		0.00		0.00		0.00
Scope Item No. 5	Operator - Foreman	16.00		-2.00		-32.00
	Laborer	8.00		-2.00		-16.00
	Laborer	8.00		-2.00		-16.00
Sub Total						398.72
PR Tax & Ins @ 56.25%						224.28
TOTAL LABOR						623.00

EQUIPMENT	Description	Rate	Hours	Total
Scope Item No. 1	Komatsu D37P Dozer	20.17	6.00	121.02
	Rammex Compactor	59.70	6.00	358.20
Scope Item No. 2	Isuzu Flatbed Truck	7.21	2.00	14.42
	Case 580 Backhoe	11.98	4.00	47.92
	Generator	0.92	4.00	3.68
	Welding Machine	2.55	1.00	2.55
	Chevy 1/2T Pickup	6.64	2.00	13.28
Scope Item No. 3	Isuzu Flatbed Truck	7.21	1.00	7.21
	Case 580 Backhoe	11.98	1.00	11.98
Scope Item No. 4		0.00	0.00	0.00
Scope Item No. 5	405 Koehring Crane	41.84	-2.00	-83.68
	MKT V5 Vibro Hammer	27.25	-2.00	-54.50
TOTAL EQUIPMENT				442.08

MATERIALS	Description	Price	Qty	Total
Scope Item No. 1	Fill Material(1.8 F)	55.00	3.25	178.75
Scope Item No. 2*	Neoprene Rubber Sht	235.00	2.00	470.00
	Concrete Anchors	4.50	52.00	234.00
	Bolts With Nuts	1.20	26.00	31.20
	* Seal Retaining Bars	37.00	6.00	222.00
	Ramnek (box)	70.00	2.00	140.00
	Oxygen	12.50	1.00	12.50
	Acetylene	4.50	1.00	4.50
Scope Item No. 3	18 Gauge Sht Metal	100.00	2.00	200.00
	#6 U-Bars (LS)	171.00	1.00	171.00
	Ramnek	70.00	1.00	70.00
Scope Item No. 4		0.00	0.00	0.00
Scope Item No. 5		0.00	0.00	0.00
Sub Total				1,733.95
Tax @ 9.00%				156.06
Consumables as % of Labor		3.00%	398.72	11.96
TOTAL MATERIALS				1,901.97

SUBCONTRACTS:		Rate	Unit	Total
Scope Item No. 1	Delta Testing			
-Moisture Density	Trip Charge	9.00	1.00	9.00
Tests of Fill	Field Density Tests	20.00	1.00	20.00
Material				
Scope item No. 2		0.00	0.00	0.00
Scope Item No. 3	Arcadia Rebar (LS)	50.00	1.00	50.00
Scope Item No. 4		0.00	0.00	0.00
Scope Item No. 5		0.00	0.00	0.00
TOTAL SUBCONTRACT				79.00

TOTAL COSTS SUMMARY				
	LABOR			623.00
	EQUIPMENT			442.08
	MATERIALS			1,901.97
	SUBCONTRACT			79.00
			SUBTOTAL	3,046.05

OVERHEAD/PROFIT				
	G & A		13.42%	408.78
			SUBTOTAL	3,454.83
	PROFIT		7.50%	259.11
			SUBTOTAL	3,713.94
Scope Item No. 6				
Bid Item No. 14	\$1,483,159.96 / 358 Monoliths			-4,142.90
=====				
TOTAL COST				-428.96
=====				

9402\RFC008.SS

*DENOTES REVISED ITEMS PER MR. ASHLEY'S LETTER
DATED JANUARY 26, 1996.

ROUTING SLIP - ACTION/SUSPENSE COPY
 - SUSPENSE DATE:

CELMN-CD-NO	INITIAL	DATE
ASHLEY	<i>[Signature]</i>	
BERNARD		
HABBAZ		
TUCKER		
SMITH		
ADAMS		

CELMN-CD-NO-E - OFFICE ENGINEER

MORTON		
PEREZ		
SMILEY		
URBAN		
BRUNO		
HAGAN		
BLACKSTOCK		

CELMN-CD-NO-Q - LWR MISS RIVER & NO-VEN HP

FOGARTY		
GUILLOT		
DAVIS, D.		
CARR		

CELMN-CD-NO-Q - LAKE PONT & CHAL AREA HP

DUHON		
BOUDREAUX		
WAGNER		

CELMN-CD-NO-B - BY BONFOUCA

BY BONFOUCA	RES OFC
MORGAN	
MONTEGUT	
BRAKEL	
DUFRECHOU	
SMALLWOOD	
CLOUATRE	

CELMN-CD-NO-Q - SWP & VICINITY

HINKAMP		
BURGESS, C.		
DERBES		
HUTSON		
SCARABIN		


CELMN-CD-NO-Q - UPR MISS RIVER - W JEFF HP

CRUMHOLT		
LAUTO		
DAVIS, A.		

CONST DIV, CONST MGMT SEC
 FOR THE CONTRACT FILE

NOAO FILE

REMARKS:



CONSTRUCTION COMPANY, INC.

February 6, 1996

Mr. Chester Ashley, Contracting Officer
Department of the Army
New Orleans District Corps of Engineers
P. O. Box 61067
New Orleans, LA 70160-0267

Re: Contract No. DACW 29-94-C0079
London Avenue Outfall Canal
Mirabeau Ave. to Robert E. Lee
B&K Job No. 9402
USACOE CIN 09/B&K RFC 008

Dear Mr. Ashley:

In response to your letter dated January 26, 1996, attached please find our revised estimate to modify the contract by deleting one concrete I-Wall monolith on the west side of the London Avenue Canal at Pumping Station No. 4 from approximately Station 100+84.14 to Station 101+12.35 WB/L.

Please contact me if additional information is required on this matter.

Sincerely,

B & K CONSTRUCTION COMPANY, INC.

Blake Andrews
Project Manager

BA/mw

cc: Mr. Mike Tassin

CA020696

CONTRACT DACW29-94-C-0079
 LAKE PONTCHARTRAIN AND VICINITY
 HIGH LEVEL PLAN, LONDON AVENUE
 OUTFALL CANAL, PARALLEL PROTECTION
 LEON C. SIMON BLVD. FLOODWALL
 ORLEANS PARISH, LOUISIANA
 B & K JOB NO. 9402, RFC NO. 008
 CIN-09

DATE:

February 27, 1996

DESCRIPTION:

Modify the contract by deleting one concrete I-Wall monolith on the west side of the London Avenue Canal at Pumping Station No. 4 from approximately Station 100+84.14 to Station 101+12.35 WB/L. The modifications include the following additional scope items: (1) compacted fill material; (2) two neoprene rubber sheeting sets; (3) two 18 gauge steel sheet metal sets. Furthermore, the modifications include the following revised scope items: (4) fence posts and attachment changes; (5) drive 28.21' of new sheet piling to elevation 14.0' in lieu of elevation 5.75'; (6) delete one concrete I-Wall monolith.

LABOR	Name	Rate	Rg	Hrs	OT	Hrs	Total
Scope Item No. 1	Operator - Foreman	16.00		6.00			96.00
	Survey Rodman	11.00		6.00			66.00
	Laborer	8.00		6.00			48.00
	Laborer	8.00		6.00			48.00
	Laborer	7.54		6.00			45.24
Scope Item No. 2	Carpenter - Foreman	15.81		8.00			126.48
	Carpenter	14.81		8.00			118.48
	Laborer	8.00		8.00			64.00
	Laborer	8.00		8.00			64.00
	Welder/Burner	14.81		8.00			118.48
Scope Item No. 3	Carpenter - Foreman	15.81		2.00			31.62
	Carpenter	14.81		2.00			29.62
	Laborer	8.00		2.00			16.00
	Laborer	8.00		2.00			16.00
Scope Item No. 4		0.00		0.00			0.00
Scope Item No. 5	Operator - Foreman	16.00		-1.00			-16.00
	Laborer	8.00		-1.00			-8.00
	Laborer	8.00		-1.00			-8.00
Sub Total							855.92
PR Tax & Ins @ 56.25%							481.46
TOTAL LABOR							1,337.38

EQUIPMENT	Description	Rate	Hours	Total
Scope Item No. 1	Komatsu D37P Dozer	20.17	6.00	121.02
	Isuzu Flatbed Truck	7.21	2.00	14.42
	Case 580 Backhoe	11.98	2.00	23.96
	Rammex Compactor	59.70	6.00	358.20
	Chevy 1/2T Pickup	6.64	2.00	13.28
Scope Item No. 2	Isuzu Flatbed Truck	7.21	2.00	14.42
	Case 580 Backhoe	11.98	8.00	95.84
	Generator	0.92	8.00	7.36
U.S. Rentals	Welding Machine(day)	159.84	1.00	159.84
	Chevy 1/2T Pickup	6.64	2.00	13.28
Scope Item No. 3	Isuzu Flatbed Truck	7.21	1.00	7.21
	Case 580 Backhoe	11.98	2.00	23.96
	Chevy 1/2T Pickup	6.64	1.00	6.64
Scope Item No. 4		0.00	0.00	0.00
Scope Item No. 5	405 Koehring Crane	41.84	-1.00	-41.84
	MKT V5 Vibro Hammer	27.25	-1.00	-27.25
TOTAL EQUIPMENT				790.34

MATERIALS	Description	Price	Qty	Total
Scope Item No. 1	Fill Material(1.8 F)	55.00	3.25	178.75
Scope Item No. 2 *	Neoprene Rubber Sht	235.00	2.00	470.00
	Concrete Anchors	4.50	52.00	234.00
	Bolts With Nuts	1.20	26.00	31.20
	* Seal Retaining Bars	182.50	6.00	1,095.00
	Ramnek (box)	70.00	2.00	140.00
	Oxygen	12.50	1.00	12.50
	Acetylene	4.50	1.00	4.50
	Welding Rods (lbs)	13.00	1.00	13.00
Scope Item No. 3	18 Gauge Sht Metal	387.50	2.00	775.00
	#6 U-Bars (LS)	171.00	1.00	171.00
	Ramnek	70.00	1.00	70.00
Scope Item No. 4		0.00	0.00	0.00
Scope Item No. 5		0.00	0.00	0.00
Sub Total				3,194.95
Tax @ 9.00%				287.55
Consumables as % of Labor			3.00%	855.92
TOTAL MATERIALS				3,508.17

SUBCONTRACTS:		Rate	Unit	Total
Scope Item No. 1	Delta Testing			
-Moisture Density	Trip Charge	9.00	1.00	9.00
Relationship of	Securing Samples(hr)	19.00	2.00	38.00
Soil	Atterburg Limit Test	45.00	2.00	90.00
	Gradation Test	45.00	2.00	90.00
	Proctor Compaction	100.00	2.00	200.00
-Field Density	Trip Charge	9.00	1.00	9.00
Tests of Fill	Field Density Tests	20.00	9.00	180.00
Material				
Scope item No. 2		0.00	0.00	0.00
Scope Item No. 3	Arcadia Rebar (LS)	50.00	1.00	50.00
Scope Item No. 4	Ace Fence	200.00	1.00	200.00
Scope Item No. 5		0.00	0.00	0.00
TOTAL SUBCONTRACT				866.00

TOTAL COSTS SUMMARY				
	LABOR			1,337.38
	EQUIPMENT			790.34
	MATERIALS			3,508.17
	SUBCONTRACT			866.00
			SUBTOTAL	6,501.89

OVERHEAD/PROFIT				
	G & A		13.42%	872.55
			SUBTOTAL	7,374.44
	PROFIT		7.50%	553.08
			SUBTOTAL	7,927.52
Scope Item No. 6:				
Bid Item No. 14	\$1,483,159.96 / 358 Monoliths			-4,142.90
=====				
TOTAL COST				3,784.62
=====				

9402\RFC008.SS

*DENOTES REVISED ITEMS PER MR. ASHLEY'S LETTER
DATED JANUARY 26, 1996.

ROUTING SLIP - ACTION/SUSPENSE COPY
 - SUSPENSE DATE:

CELMN-CD-NO	INITIAL	DATE
ASHLEY	<i>J</i>	
BERNARD		
HABBAZ		
TUCKER		
SMITH		
ADAMS		

2
3A

CELMN-CD-NO-E - OFFICE ENGINEER	INITIAL	DATE
MORTON		
PEREZ		
SMILEY		
URBAN		
BRUNO		
HAGAN		
BLACKSTOCK		

CELMN-CD-NO-Q - LWR MISS RIVER & NO-VEN HP

FOGARTY		
GOINS		
DAVIS, D.		
CARR		

CELMN-CD-NO-Q - LAKE PONT & CHAL AREA HP

DUHON		
BOUDREAUX		
WAGNER		
SCHICK		

CELMN-CD-NO-B - B BY BONFOUCA RES OFC

MORGAN		
MONTEGUT		
BRAKEL		
DUFRECHOU		
SMALLWOOD		
CLOUATRE		

CELMN-CD-NO-Q - SWP & VICINITY

HINKAMP		
BURGESS, C.		
DERBES		
HUTSON		
SCARABIN		


CELMN-CD-NO-Q - UPR MISS RIVER - W JEFF HP

CRUMHOLT		
LAUTO		
DAVIS, A.		

CONST DIV, CONST MGMT SEC
 FOR THE CONTRACT FILE

NOAO FILE

REMARKS:



CONSTRUCTION COMPANY, INC.

January 19, 1996

Mr. Chester Ashley, Contracting Officer
U.S. Army Corps of Engineers
New Orleans District
P.O. Box 60167
New Orleans, LA 70160-0267

RE: CONTRACT NO. DACW29-94-C-0079
LAKE PONTCHARTRAIN & VICINITY
HIGH LEVEL PLAN, LONDON AVENUE
OUTFALL CANAL, PARALLEL
PROTECTION MIRABEAU AVE TO LEON
C. SIMON BLVD FLOODWALL -
ORLEANS PARISH, LA
B & K JOB NO. 9402

Dear Mr. Ashley:

In response to your letter dated December 21, 1995, attached please find our estimate to modify the contract by deleting one concrete I-Wall monolith on the west side of the London Avenue Canal at Pumping Station No. 4 from approximately Station 100+84.14 to Station 101+12.35 WB/L.

Please contact me if additional information is required on this matter.

Sincerely,
B & K CONSTRUCTION CO., INC.

Blake Andrews/kz

Blake Andrews,
Project Manager

BA/k1

cc: Mr. Mike Tassin

RECEIVED AT
JAN 21 1996
N.O.A.O.

CONTRACT DACW29-94-C-0079
 LAKE PONTCHARTRAIN AND VICINITY
 HIGH LEVEL PLAN, LONDON AVENUE
 OUTFALL CANAL, PARALLEL PROTECTION
 LEON C. SIMON BLVD. FLOODWALL
 ORLEANS PARISH, LOUISIANA
 B & K JOB NO. 9402, RFC NO. 008

January 17, 1996

DESCRIPTION: Modify the contract by deleting one concrete I-Wall monolith on the west side of the London Avenue Canal at Pumping Station No. 4 from approximately Station 100+84.14 to Station 101+12.35 WB/L. The modifications include the following additional scope items: (1) compacted fill material; (2) two neoprene rubber sheeting sets; (3) two 18 gauge steel sheet metal sets. Futhermore, the modifications include the following revised scope items: (4) fence posts and attachment changes; (5) drive 28.21' of new sheet piling to elevation 14.0' in lieu of elevation 5.75'; (6) delete one concrete I-Wall monolith.

LABOR	Name	Rate	Rg Hrs	OT Hrs	Total
Scope Item No. 1	Operator - Foreman	16.00	6.00		96.00
	Survey Rodman	11.00	6.00		66.00
	Laborer	8.00	6.00		48.00
	Laborer	8.00	6.00		48.00
	Laborer	7.54	6.00		45.24
Scope Item No. 2	Carpenter - Foreman	15.81	8.00		126.48
	Carpenter	14.81	8.00		118.48
	Laborer	8.00	8.00		64.00
	Laborer	8.00	8.00		64.00
	Welder/Burner	14.81	8.00		118.48
Scope Item No. 3	Carpenter - Foreman	15.81	2.00		31.62
	Carpenter	14.81	2.00		29.62
	Laborer	8.00	2.00		16.00
	Laborer	8.00	2.00		16.00
Scope Item No. 4		0.00	0.00		0.00
Scope Item No. 5	Operator - Foreman	16.00	-1.00		-16.00
	Laborer	8.00	-1.00		-8.00
	Laborer	8.00	-1.00		-8.00
Sub Total					855.92
PR Tax & Ins @	56.25%				481.46
TOTAL LABOR					1,337.38

EQUIPMENT	Description	Rate	Hours	Total
Scope Item No. 1	Komatsu D37P Dozer	20.17	6.00	121.02
	Isuzu Flatbed Truck	7.21	2.00	14.42
	Case 580 Backhoe	11.98	2.00	23.96
	Rammex Compactor	59.70	6.00	358.20
	Chevy 1/2T Pickup	6.64	2.00	13.28
Scope Item No. 2	Isuzu Flatbed Truck	7.21	2.00	14.42
	Case 580 Backhoe	11.98	8.00	95.84
	Generator	0.92	8.00	7.36
U.S. Rentals	Welding Machine(day)	159.84	1.00	159.84
	Chevy 1/2T Pickup	6.64	2.00	13.28
Scope Item No. 3	Isuzu Flatbed Truck	7.21	1.00	7.21
	Case 580 Backhoe	11.98	2.00	23.96
	Chevy 1/2T Pickup	6.64	1.00	6.64
Scope Item No. 4		0.00	0.00	0.00
Scope Item No. 5	405 Koehring Crane	41.84	-1.00	-41.84
	MKT V5 Vibro Hammer	27.25	-1.00	-27.25
TOTAL EQUIPMENT				790.34

MATERIALS	Description	Price	Qty	Total
Scope Item No. 1	Fill Material(1.8 F)	55.00	3.25	178.75
Scope Item No. 2	Neoprene Rubbber Sht	615.00	2.00	1,230.00
	Concrete Anchors	4.50	52.00	234.00
	Bolts With Nuts	1.20	26.00	31.20
	Seal Retaining Bars	300.00	6.00	1,800.00
	Ramnek (box)	70.00	2.00	140.00
	Oxygen	12.50	1.00	12.50
	Acetylene	4.50	1.00	4.50
	Welding Rods (lbs)	13.00	1.00	13.00
Scope Item No. 3	18 Gauge Sht Metal	387.50	2.00	775.00
	#6 U-Bars (LS)	171.00	1.00	171.00
	Ramnek	70.00	1.00	70.00
Scope Item No. 4		0.00	0.00	0.00
Scope Item No. 5		0.00	0.00	0.00
Sub Total				4,659.95
Tax @ 9.00%				419.40
Consumables as % of Labor			3.00%	855.92
TOTAL MATERIALS				5,105.02

SUBCONTRACTS:		Rate	Unit	Total
Scope Item No. 1	Delta Testing			
-Moisture Density	Trip Charge	9.00	1.00	9.00
Relationship of	Securing Samples(hr)	19.00	2.00	38.00
Soil	Atterburg Limit Test	45.00	2.00	90.00
	Gradation Test	45.00	2.00	90.00
	Proctor Compaction	100.00	2.00	200.00
-Field Density	Trip Charge	9.00	1.00	9.00
Tests of Fill	Field Density Tests	20.00	9.00	180.00
Material				
Scope item No. 2		0.00	0.00	0.00
Scope Item No. 3	Arcadia Rebar (LS)	50.00	1.00	50.00
Scope Item No. 4	Ace Fence	200.00	1.00	200.00
Scope Item No. 5		0.00	0.00	0.00
TOTAL SUBCONTRACT				866.00

TOTAL COSTS SUMMARY			
	LABOR		1,337.38
	EQUIPMENT		790.34
	MATERIALS		5,105.02
	SUBCONTRACT		866.00
		SUBTOTAL	8,098.74

OVERHEAD/PROFIT			
	G & A	13.42%	1,086.85
		SUBTOTAL	9,185.59
	PROFIT	7.50%	688.92
		SUBTOTAL	9,874.51

Bid Item No. 14	\$1,483,159.96 / 358 Monoliths		-4,142.90
=====			
TOTAL COST			5,731.61
=====			

9402\RFC008.SS

Correspondence

January 26, 1996

New Orleans Area Office

SUBJECT: Contract Number DACW29-94-C-0079, Lake Pontchartrain, Louisiana and Vicinity, High Level Plan, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Robert E. Lee Blvd., West Bank; Mirabeau Avenue to Leon C. Simon Blvd., East Bank Floodwall, Orleans Parish, Louisiana, CIN 09

B&K Construction Company, Incorporated
1905 Highway 59
Mandeville, Louisiana 70448

Gentlemen:

This is to advise you of changes in the scope of work for CIN 09. The neoprene cover to protect the exposed three bulb water stops on either side of the deleted monolith is changed from 1/2 inch thick to 1/4 inch thick. Also, the six steel bars holding the neoprene in place is changed from corrosion resistance steel to A-36 steel painted with 8 mils of coal tar epoxy.

Please resubmit your proposal no later than February 7, 1996.

Sincerely,

Chester Ashley
Administrative Contracting Officer

CF:
CELMN-CD-CS
CELMN-CT
Project Engr (Wagner)
Office Engr (Perez) ✓

January 26, 1996

New Orleans Area Office

MORTON
CEL MN-CD-NO-E

SUBJECT: Contract Number DACW29-94-C-0079, Lake Pontchartrain, Louisiana and Vicinity, High Level Plan, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Robert E. Lee Blvd., West Bank; Mirabeau Avenue to Leon C. Simon Blvd., East Bank Floodwall, Orleans Parish, Louisiana, CIN 09

DUHON *out*
CEL MN-CD-NO-Q

HABBAZ *gt*
CEL MN-CD-NC

B&K Construction Company, Incorporated
1905 Highway 59
Mandeville, Louisiana 70448

BERNARD
CEL MN-CD-NC

ASHLEY
CEL MN-CD-NC

Gentlemen:

This is to advise you of changes in the scope of work for CIN 09. The neoprene cover to protect the exposed three bulb water stops on either side of the deleted monolith is changed from 1/2 inch thick to 1/4 inch thick. Also, the six steel bars holding the neoprene in place is changed from corrosion resistance steel to A-36 steel painted with 8 mils of coal tar epoxy.

Please resubmit your proposal no later than February 7, 1996.

Sincerely,

Chester Ashley
Administrative Contracting Officer

CF:
CEL MN-CD-CS
CEL MN-CT
Project Engr (Wagner)
Office Engr (Perez)



DEPARTMENT OF THE ARMY

NEW ORLEANS DISTRICT, CORPS OF ENGINEERS
P.O. BOX 60267
NEW ORLEANS, LOUISIANA 70160-0267

REPLY TO
ATTENTION OF:

January 26, 1996

New Orleans Area Office

SUBJECT: Contract Number DACW29-94-C-0079, Lake Pontchartrain, Louisiana and Vicinity, High Level Plan, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Robert E. Lee Blvd., West Bank; Mirabeau Avenue to Leon C. Simon Blvd., East Bank Floodwall, Orleans Parish, Louisiana, CIN 09

B&K Construction Company, Incorporated
1905 Highway 59
Mandeville, Louisiana 70448

Gentlemen:

This is to advise you of changes in the scope of work for CIN 09. The neoprene cover to protect the exposed three bulb water stops on either side of the deleted monolith is changed from 1/2 inch thick to 1/4 inch thick. Also, the six steel bars holding the neoprene in place is changed from corrosion resistance steel to A-36 steel painted with 8 mils of coal tar epoxy.

Please resubmit your proposal no later than February 7, 1996.

Sincerely,

A handwritten signature in black ink that reads "Chester Ashley".

Chester Ashley
Administrative Contracting Officer

ROUTING SLIP - ACTION/SUSPENSE COPY

- SUSPENSE DATE:

CELMN-CD-NO	INITIAL	DATE
ASHLEY	<i>cf</i>	
BERNARD		
HABBAZ		
TUCKER		
SMITH		
ADAMS		

2

CELMN-CD-NO-E - OFFICE ENGINEER		
MORTON	<i>JJ</i>	
PEREZ		
SMILEY		
URBAN		
BRUNO		
HAGAN		
BLACKSTOCK		

CELMN-CD-NO-Q - LWR MISS RIVER & NO-VEN HP

FOGARTY		
GOINS		
DAVIS, D.		
CARR		

CELMN-CD-NO-Q - LAKE PONT & CHAL AREA HP

DUHON		
BOUDREAUX		
WAGNER		
SCHICK		

CELMN-CD-NO-B - B BY BONFOUCA RES OFC

MORGAN		
MONTEGUT		
BRAKEL		
DUFRECHOU		
SMALLWOOD		
CLOUATRE		

CELMN-CD-NO-Q - SWP & VICINITY

HINKAMP		
BURGESS, C.		
DERBES		
HUTSON		
SCARABIN		

CELMN-CD-NO-Q - UPR MISS RIVER - W JEFF HP

CRUMHOLT		
LAUTO		
DAVIS, A.		

CONST DIV, CONST MGMT SEC
FOR THE CONTRACT FILE

NOAO FILE

REMARKS:


MEMORANDUM THRU C/CONST DIV

FOR CELMN-CD-NO

SUBJECT: Request for Modification, DACW29-94-C-0079, Lake Pontchartrain, Louisiana and Vicinity, High Level Plan, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Leon C. Simon Boulevard Floodwall, Orleans Parish, Louisiana

1. Forwarded is the original request from Engineering Division for modification to subject contract. This change has been assigned CIN 09, and any reference thereto should address this number.
2. The change is to delete one concrete I-Wall monolith on the West side at Pumping Station No. 4 from approximate Sta. 100+84.14 to Sta. 101+12.35 WB/L.
3. Please proceed with the change as requested.

Enclosure


WILLIAM R. MARSALIS
Chief, Contract Admin Br

CF:
CELMN-CD-CS (Guillot)

MEMORANDUM FOR C/ Construction Division

SUBJECT: Lake Pontchartrain, LA & Vicinity, High Level Plan, London Ave. Outfall Canal, Parallel Protection, Mirabeau Ave. to Leon C. Simion, East Bank, Mirabeau Ave. to Robert E. Lee Ave., West Bank, Orleans Parish, LA

1. It is requested that a modification request be issued on the subject project, contract number 94-C-0079.

2. the following information is provided for your use in preparing the modification:

a. Description of Work.

(1) The Change. Eliminate one concrete I-Wall monolith on the west side of the canal at Pumping Station #4 from approximately Sta. 100+84.14 to Sta. 101+12.35 WB/L.

(2) Contract Specifications.

a. Page C2F-4, para. C2F-4.3. At the end of the paragraph, add the following: "Posts shall be attached to uncapped sheet piling using 1/2" \varnothing x 4" bolts with washers conforming to C5A-4.2.4. Bolts shall be equally spaced with the top and bottom bolts 3" from the top of the sheet piling and bottom of the post respectively. Posts attached to sheet piling shall be 10' long."

b. Page C5A-4, para. C5A-5.2. In the paragraph title, after "Floodwall", add "and at Joints between Concrete I-Wall and Uncapped Sheet Pile".

(3) Contract Drawings. Delete dwgs. 13, 17, 18, 32, 49, 50, and 51 of 73 in their entirety and replace with modified dwgs. 13, 17, 18, 32, 49, 50, and 51 of 73

b. Necessity for the Change. By removing the concrete I-Wall and leaving the sheet piling in this area, the Contractor for the Fronting Protection of Pump Station #4 will have easier access to the canal. The concrete portion of the I-Wall will be placed in the later contract.

c. Reason for the Omission from the Plans and Specifications. The necessity for this change was discovered subsequent to award of the contract.

3. The preliminary engineering cost estimate for the change estimated herein is a credit for \$8,000.

CELMN-ED-TM

29 Nov 95

SUBJECT: Lake Pontchartrain, LA & Vicinity, High Level Plan, London Ave. Outfall Canal, Parallel Protection, Mirabeau Ave. to Leon C. Simion, East Bank, Mirabeau Ave. to Robert E. Lee Ave., West Bank, Orleans Parish, LA

4. Point of contact is Angela DeSoto, x2733.


Encls (6 copies)

Dwgs. 13, 17, 18, 32, 49, 50, & 51 of 73

CF:(w/o encls)

CELMN-ED-C

CELMN-PP-P



W. EUGENE TICKNER
Chief, Engineering Division

January 17, 1996

New Orleans Area Office

SUBJECT: DACW29-94-C-0079, Lake Pontchartrain, Louisiana and Vicinity, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Leon C. Simon Boulevard Floodwall, Orleans Parish, Louisiana

B & K Construction Company, Incorporated
1905 Highway 59
Mandeville, Louisiana 70448

Gentlemen:

This confirms the verbal request for proposal on January 17, 1996 by Mr. Fidel Perez of my office to Mr. Blake Andrews of your company to modify the subject contract in accordance with CC I.86, CHANGES. This change eliminates the restoration of the staging area grounds to its original condition and requires that you leave the wooden fence in place.

As agreed, please submit your proposal for this modification by February 1, 1996. The proposal should be broken down in sufficient detail for the analysis of the elements of labor, equipment, materials and supplies, and include appropriate mark-ups and any time deduction required for the deletion of the work.

This is not a notice to proceed with the change. Do not start work under this proposed change until you have been authorized to do so.

The point of contact for this modification is Mr. Fidel Perez at 862-1245.

Sincerely,

CF:
CELMN-CT
Proj Engr (Wagner)
Ofc Engr (Perez)✓

Chester Ashley
Administrative Contracting
Officer

December 21, 1995

WAGNER
CELMN-CD-NO-Q

New Orleans Area Office

SUBJECT: Contract No. DACW29-94-C-0079, Lake Pontchartrain and Vicinity, High Level Plan, London Avenue Outfall Canal, Parallel Protection, Mirabeau Avenue to Leon C. Simon Boulevard Floodwall, Orleans Parish, Louisiana, *CIN 09*

~~DUHON~~ *ISW*
CELMN-CD-NO-Q

HABBAZ
CELMN-CD-NO

BERNARD
CELMN-CD-NO

ASHLEY
CELMN-CD-NO

B & K Construction Company, Incorporated
1905 Highway 59
Mandeville, Louisiana 70448

Gentlemen:

This confirms the verbal request for proposal on December 18, 1995 by Mr. Fidel Perez of my office to Mr. Boone Kenyon of your company to modify the subject contract in accordance with CC I. 86, CHANGES, by deleting one concrete I-Wall monolith on the west side of the London Avenue Canal at Pumping Station No. 4 from approximately Station 100+84.14 to Station 101+12.35 W B/L.

In order to accomplish this change, the following revisions to the plans and specifications are proposed:

a. Delete drawings No. 13, 17, 18, 32, 49, 50 and 51 of 73 and substitute the attached revised drawing No. 13, 17, 18, 32, 49, 50 and 51 of 73.

b. Page C2F-4, Paragraph C2F-4.3. of the contract specifications. At the end of the paragraph, add the following: Posts shall be attached to uncapped sheet piling using 1/2" diameter X4" long bolts with washers conforming to C5A-4.2.4. Bolts shall be equally spaced with the top bottom bolts 3" from the top of the sheet piling and bottom of the post respectively. Posts attached to sheet piling shall be 10 feet long."

c. Page C5A-4, Paragraph C5A-5.2 of the contract specifications. In the paragraph title after "Floodwall", add "and at Joints between Concrete I-Wall and Uncapped Sheet Pile."

As agreed, please submit your proposal for this modification by January 4, 1996. The proposal should be

broken down in sufficient detail for the analysis of the elements of labor, equipment, materials and supplies, and include appropriate mark-ups and any time deduction required for the deletion of the work.

This is not a notice to proceed with the change. Do not start work under this proposed change until you have been authorized to do so.

The point of contact for this modification is Mr. Fidel Perez at 862-1245.

Sincerely,

Chester Ashley
Administrative Contracting
Officer

Attachment

CF:

Ofc Engr (Perez)
Supv Civ Engr (Duhon)