

A0003809

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE PAGE OF PAGES 1 7

2. AMENDMENT/MODIFICATION NO. 0002 3. EFFECTIVE DATE 07/19/95 4. REQUISITION/PURCHASE REQ. NO. ED0000-4193-0145 A 5. PROJECT NO. (if applicable) dk

6. ISSUED BY CODE ISSUE1 7. ADMINISTERED BY (if other than Item 6) CODE ADMIN1 US ARMY ENGR DIST NEW ORLEANS PO BOX 60267 NEW ORLEANS LA 70160-0267 Sheila W. Enclade SC1(504) 862-1514 US ARMY ENGR DIST, NEW ORLEANS ATTN CELMN-CT PO BOX 60267 NEW ORLEANS LA 70160-0267

8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code) CELMN-ED-T F (GEN'L CONST) (1S & 1P) 9A. AMENDMENT OF SOLICITATION NO. DACW29-95-B-0095 9B. DATED (SEE ITEM 11) 06/21/95 10A. MODIFICATION OF CONTRACT/ORDER NO. 10B. DATED (SEE ITEM 13) CODE FACILITY CODE

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers [X] is extended, [] is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (if required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

(X) A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A. B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103 (b). C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF: D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [] is not, [] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) Plans and Specifications covering Lake Ponchartrain, LA. and Vicinity Floodproofing Veterans Boulevard Bridges Over 17th Street Canal, Orleans and Jefferson Parishes, Louisiana, are hereby amended as follows: BID OPENING DATE Bid Opening Date and Time of 1 August 1995, 2:00 P.M., LOCAL TIME AT PLACE OF BID OPENING, remains unchanged.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print) 16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) 15B. CONTRACTOR/OFFEROR 15C. DATE SIGNED 16B. UNITED STATES OF AMERICA 16C. DATE SIGNED (Signature of person authorized to sign) BY (Signature of Contracting Officer)

SECTION 00010, BIDDING SCHEDULE

Delete page 00010-3 in its entirety and substitute revised attached page 00010-3 therefor. Double asterisks (**) denote changes.

SECTION 00800, "SPECIAL CONTRACT REQUIREMENTS"

Delete existing pages 00800-8 and 00800-9 in their entirety and substitute revised attached pages 00800-8 and 00800-9 therefor.

SECTION 01521, "TEMPORARY ROADWAY CONSTRUCTION"

1. Page 01521-1, Paragraph 1. In the sixth (6th) line, add "backfill and temporary paving of the disturbed approach slab areas behind the new abutment caps during construction sequences 2 and 3," after "approaches,".

2. Page 01521-2. Add the following new paragraph after existing paragraph 7.1:

"7.1.1 In the disturbed approach slab areas behind the new abutment caps, the Contractor shall backfill and provide base course material to the required elevation before providing temporary surfacing during phase 2 and 3 construction.".

3. Page 01521-3, Paragraph 9. In the seventh (7th) line, add ", and backfill and temporary paving of the areas specified in paragraph 7.1.1" between "7.4" and the period marking the end of the sentence.

SECTION 01571, "MAINTENANCE OF TRAFFIC DURING CONSTRUCTION"

Page 01571-2, Paragraph 6.1. Add the following to the end of existing paragraph 6.1: "A portion of the barriers (145 barriers/2175 linear feet) will be provided by the Orleans Levee Board, through the Louisiana Department of Transportation and Development. The remainder will be furnished and installed by the Contractor. The Contractor shall provide the equipment and vehicles necessary to load and transport the barriers to the worksite. Upon completion of the work, the Contractor shall return the barriers to the point of origin. The Contractor shall contact Mr. Robert Roth of LADOTD at (504)437-3100 for the location of the concrete barrier stockpile.".

SECTION 02222, "STRUCTURAL EXCAVATION AND BACKFILL"

1. Page 02222-11, Paragraph 9.1. In the third (3rd) line from the top of page 02222-11, add "riprap protection at bridge abutments, geotextile fabrics," after "stockpiling,"
2. Page 02222-11, Paragraph 9.3. In the third (3rd) line of this paragraph, add "and excavation required for permanent roadway pavement" after "plan".

SECTION 02355, "PILE LOAD TESTS"

Page 02355-2, Paragraph 6.2. In the second (2nd) line of this paragraph, add "be" between "shall" and excavated".

SECTION 02411, "STEEL SHEET PILING"

Page 02411-4, Paragraph 8.1.1.1 In third (3rd) line from the top of the page, change "0.5 inches" to "0.335 inches".

SECTION 03301, "CAST-IN-PLACE STRUCTURAL CONCRETE"

Page 03301-23, Paragraph 12.2.1. In the table entitled "BRIDGE STRUCTURE", under the column "STRUCTURE OR PORTION OF STRUCTURE", change "Barriers and ends of bent caps" to "Barriers and all exposed faces of bent caps".

DRAWINGS

Delete Drawings Nos. 12a, 25, 28, 29 and 30 of 79, File No. H-4-40359, in their entirety, and substitute revised attached Drawings Nos. 12a, 25, 28, 29 and 30 of 79, File No. H-4-40359, therefor. Also, please make the following pen-and-ink changes:

1. Drawing No. 12 of 79, File No. H-4-40359. In the "NOTES" located in the bottom middle of the drawing, delete Note 4 in its entirety and substitute the following:

- "4. A GEOTEXTILE FABRIC UNDERLINER IS REQUIRED. THE GEOTEXTILE FABRIC SHALL BE CLASS D AND SHALL MEET THE REQUIREMENTS OF LOUISIANA STANDARD SPECIFICATIONS FOR ROADS AND BRIDGES (LSSRB) SECTION 1019."

2. Drawing No. 16 of 79, File No. H-4-40359. Add the following under the "HP 14x73 PILE SPLICE DETAIL":

"NOTES:

"THE CONTRACTOR MAY USE WEB AND FLANGE GUIDE PLATES AT NO COST TO THE GOVERNMENT.

"ONLY ONE SPLICE PER PILE SHALL BE PERMITTED. SPLICE SHALL BE LOCATED A MINIMUM OF 40 FEET BELOW THE PILE CUTOFF ELEVATION."

3. Drawing No. 19 of 79, File No. H-4-40359.

a. In the "FLOODWALL KEY PLAN", change from "C/L VETERANS BLVD. (SUB-B/L STA. 2+30.00)" to "C/L VETERANS BLVD. STA. 625+79.79".

b. Also in the "FLOODWALL KEY PLAN", add the following note under "PANEL 9": "EXISTING SHEET PILE, REQ'D CAP". Add a leading arrow from this note to Panel 9.

4. Drawing No. 21 of 79, File No. H-4-40359. In the "FLOOD SIDE ELEVATION, I-WALL TO ABUTMENT/BARRIER", change the note leading to the bond cable from "BOND CABLE, SEE NOTE, DWG. 18" to "BOND CABLE, SEE NOTE, DWG. 20".

5. Drawing No. 22 of 79, File No. H-4-40359.

a. In the "SECTION @ JOINT, TYPE I CAP", change the cut section designation from "B-B" to "A-A".

b. In the "SECTION @ JOINT, TYPE II CAP", change the cut section designation from "A-A" to "B-B".

6. Drawing No. 23 of 79, File No. H-4-40359. In the "PLAN" located in the upper left corner of the drawing, change the note in the middle from "SEE DWG. 25 FOR DETAILS" to "SEE DWG. 26 FOR DETAILS".

7. Drawing No. 41 of 79, File No. H-4-40359. In the "REINFORCING BAR SCHEDULE" for "APPROACH SLAB BARRIER TRANSITION", change the total weight from "455 LBS." to " $8 \times 455 = 3,640$ LBS.". In the "REINFORCING BAR SCHEDULE" for "APPROACH SLAB BOLSTER BLOCK", change the total weight from "1,111 LBS." to " $4 \times 811 = 3,244$ LBS.".

8. Drawing No. 66 of 79, File No. H-4-40359. In the table entitled "PILE TEST REQUIREMENTS" located in the far right center of the drawing, change the location "STA. 19+75, 20' RT." to "STA. 19+75, 250' RT.".

SOLICITATION NO. DACW29-95-B-0095

SECTION 00010 - BIDDING SCHEDULE

LAKE PONTCHARTRAIN, LOUISIANA AND VICINITY,
FLOODPROOFING VETERANS BOULEVARD BRIDGES OVER 17TH STREET CANAL,
ORLEANS AND JEFFERSON PARISHES, LOUISIANA

Item No.	Description	Estimated Quantity	Unit	Unit Price	Est. Amt.
0001.	Mobilization and Demobilization	Lump Sum	LS		
0002.	Demolition	Lump Sum	LS		
0003.	Maintenance of Traffic (Including Temporary Signing)	Lump Sum	LS		
** 0004.	Furnish and Deliver 24-Inch Prestressed Concrete Piles	5,635	LF		
** 0005.	Driving 24-Inch Prestressed Concrete Piles	5,365	LF		
** 0006.	Furnish and Deliver Steel H-Piles	2,840	LF		
** 0007.	Driving Steel H-Piles	2,840	LF		
0008.	Class A Concrete	Lump Sum	LS		
0009.	Class AA Concrete	Lump Sum	LS		
0010.	Precast, Prestressed Concrete Girders	Lump Sum	LS		
0011.	Miscellaneous Metalwork	Lump Sum	LS		
0012.	Asphaltic Concrete Pavement	Lump Sum	LS		
0013.	Floodwall Gate Near I-10	Lump Sum	LS		
** 0014.	Steel Sheet Piling	3,220	SF		
0015.	Driving Government Furnished Sheet Piling	Lump Sum	LS		
0016.	Furnish and Drive Test Piles	2	EA		
0017.	Pile Load Tests	2	EA		
0018.	Permanent Pavement Markings	Lump Sum	LS		
0019.	Drainage Structures	Lump Sum	LS		

c. The Contractor's liability for the removal of a vessel wrecked or sunk without fault or negligence is limited to that provided in Sections 15, 19, and 20 of the River and Harbor Act of March 3, 1899 (33 U.S.C.410 et.seq.).

12. IDENTIFICATION OF GOVERNMENT-FURNISHED PROPERTY (FAR 52.245-3 1984 APR).

a. The Government will furnish to the Contractor the property identification in the Schedule to be incorporated or installed into the work or used in performing the contract. The listed property will be furnished f.o.b. railroad cars at the place specified in the contract Schedule or f.o.b. truck at the project site. The Contractor is required to accept delivery, pay any demurrage or detention charges, and unload and transport the property to the job site at its own expense. When the property is delivered, the Contractor shall verify its quantity and condition and acknowledge receipt in writing to the Contracting Officer within 24 hours of delivery any damage to or shortage of the property as received. All such property shall be installed or incorporated into the work at the expense of the Contractor, unless otherwise indicated in this contract.

b. Each item of property to be furnished under this clause shall be identified in the Schedule by quantity, item, and description.

SCHEDULE OF GOVERNMENT FURNISHED PROPERTY.

a. In lieu of the second and third sentences of paragraph a of the Special Contract Requirement entitled "IDENTIFICATION OF GOVERNMENT FURNISHED PROPERTY", the property listed below will be furnished to the Contractor at the East Jefferson Levee District (EJLD) Maintenance Yard located at 1135 Leasan Dr., Kenner, LA. The Government will furnish to the Contractor the property identified in the schedule below:

PROPERTY SCHEDULE

<u>Items</u>	<u>Quantity</u>
Frodingham 1B Steel Sheet Piling 14'-0" Long	28 Sheets

The Contractor is encouraged to visit the property location to obtain more information about the property. Visits of this type shall be coordinated with the New Orleans Area Office.

b. In lieu of the second and third sentences of paragraph a of the Special Contract Requirement entitled "IDENTIFICATION OF GOVERNMENT FURNISHED PROPERTY", the property listed below will be furnished to the Contractor by the Orleans Levee Board through the LADOTD:

PROPERTY SCHEDULE

<u>Items</u>	<u>Quantity</u>
Temporary Concrete Barriers	145 Barriers (2175 Linear Feet)

The Contractor shall contact Mr. Robert Roth of LADOTD at (504)437-3100 for the location of the concrete barrier stockpile.

c. The Contractor shall notify the Contracting Officer five (5) days prior to proceeding to load and transport the Government-furnished property. The Contractor shall provide suitable equipment to load/unload the property at the warehouse. The Contractor shall then transport the property to the job site and unload.

d. The Contractor shall verify the quantity and condition of the property, and acknowledge receipt in writing to the Contracting Officer. In case of damage to the property, the Contractor shall report such damage to the Contracting Officer immediately. The damaged property shall be replaced by the Contractor at no cost to the Government.