


GPS OCX Update

14 October 2010



System Overview



Service Oriented Architecture

....Provides Enhanced Capabilities

- Plan and execute NAVWAR mission
- Additional signals: L5, L1C, L2C*, M-Code
- C2 and Navigation for GPS IIA, IIR, IIR-M, IIF and IIIA
- Robust IA counters emerging cyber-threats
- Improved accuracy inherent in design
- Integrity & Continuity using FAA-Certified WAAS Algorithms
- Operator Automation

...Supports Future Capabilities

- Flexible architecture to accommodate new functional capabilities, evolving CONOPS and additional automation
- Internal SOA enables new GIG / Net Centric Interfaces
- Re-programmable M-Code Receiver
- PSICA infrastructure in Block 1 lays foundation for future integrity requirements

*New signal in Block 1



OCX Will Modernize GPS

▪ GPS control stations

- New Master Control Station (MCS) hardware at Schriever AFB
- New Alternate MCS hardware at Vandenberg AFB
- Test and training simulators
- **New advanced ground antennas**

▪ GPS remote sites

- Upgrade of existing ground antennas
- Addition of modernized monitor station receiver element
- **Upgrade receivers for new signals**

▪ New architecture with the following functionality


- Robust Information Assurance
- TT&C and NAV for on-orbit SVs and for new SV's
- Full modernization – SAASM, M-Code
- New Civil signal monitor & control: L1 C/A, L1C, L2C, L5
- Service Oriented Architecture enables net-centricity and Global Information Grid connectivity
- Early support to Effects Based Ops: Flex Power, Over the Air Re-keying
- **Evolved GPS support to Effects Based Ops: Spot Beam, Crosslink C2**

■ OCX Blocks 1.0 and 2.0


■ Future OCX Blocks



OCX Graceful Growth Path to Full CDD Requirements




OCX Summary Schedule




GPS OCX Block 1 Summary View

GPS OCX BLOCK 1 SUMMARY VIEW



Baseline: IBR Baseline
Status: 8 October 2010



OCX Phase B Program Milestone Status

OCX Milestone	Baseline	Forecast	Actual	Status
Technical Baseline Review	23 Mar 2010		23 Mar 2010	●
Software Iteration 1.2 Start	10 Jun 2010		10 Jun 2010	●
Phase B IBR	20 Aug 2010		20 Aug 2010	●
Block 1 SSR	3 Sep 2010		23 Sep 2010*	●
Block 1 HW PDR	11 Nov 2010	17 Nov 2010*		●
Software Iteration 1.2 Complete	14 Jan 2011	14 Jan 2011		●
Block 1 SBR	31 Jan 2011	31 Jan 2011		●
Block 1 & 2 PDR	1 Apr 2011	1 Apr 2011		●
Block 1 HW CDR	3 Jun 2011	3 Jun 2011		●
Software Iteration 1.3 Complete	29 Aug 2011	29 Aug 2011		●

* Moved to accommodate GPSW's schedule

● Complete ● Forecast On Schedule ● Forecast Late to Baseline, Potential Impacts ● Forecast Late to Baseline, Impacts Likely



Closing on Enterprise Integration

- **Systems Integration Demonstration Plans Resynchronized**
 - Successfully redefined and re-aligned the OCX/GPS IIIA demonstration plan to address the 18-month schedule gap
- **OCX/GPS IIIA Requirements Baseline Established**
 - Established OCX PDR baseline consistent with GPS IIIA CDR baseline
 - Successful dry run of the state vector phase 1 demonstration
- **Working Site Integration and Transition Planning Upfront to Ensure Seamless Transition from AEP/LADO and each Subsequent Delivery**
 - Transition requirements built into the architecture and deployment strategy
 - Completed multiple facilities site surveys and analysis
 - Created OCX-OCS ICD
- **Developed GPS IIIA Launch and Checkout Approach**
 - Enables early GPS IIIA launch with minimal impact to the OCX baseline
 - Significantly reduces OCX/GPS IIIA integration risk
 - Provides long term sustainment capability



Summary

- OCX is responsive to today's system requirements while maintaining a vision and path to future system capabilities
- OCX is off to a solid start and on-track to delivery Block 1 on time
- Enterprise integration is resynchronized and requirement's baselines established
- Upfront site integration and transition planning significantly reduces the risk of backward compatibility and seamless transition

