


August 2012

# Monthly Energy Review



*Independent Statistics & Analysis*  
U.S. Energy Information  
Administration

[www.eia.gov/mer](http://www.eia.gov/mer)

# Monthly Energy Review

The *Monthly Energy Review (MER)* is the U.S. Energy Information Administration's (EIA) primary report of recent and historical energy statistics. Included are statistics on total energy production, consumption, trade, and energy prices; overviews of petroleum, natural gas, coal, electricity, nuclear energy, renewable energy, and international petroleum; carbon dioxide emissions; and data unit conversions.

Release of the MER is in keeping with responsibilities given to EIA in Public Law 95-91 (Department of Energy Organization Act), which states, in part, in Section 205(a)(2):

*“The Administrator shall be responsible for carrying out a central, comprehensive, and unified energy data and information program which will collect, evaluate, assemble, analyze, and disseminate data and information....”*

The MER is intended for use by Members of Congress, Federal and State agencies, energy analysts, and the general public. EIA welcomes suggestions from readers regarding the content of the MER and other EIA publications.

**Related Monthly Publications:** Other monthly EIA reports are *Petroleum Supply Monthly*, *Petroleum Marketing Monthly*, *Natural Gas Monthly*, *Electric Power Monthly*, and *International Petroleum Monthly*. For more information, contact EIA's Office of Communications via email at [infoctr@eia.gov](mailto:infoctr@eia.gov).

## Important Notes About the Data

**Data Displayed:** For tables beginning in 1973, some annual data (usually 1974, 1976-1979, 1981-1984, 1986-1989, and 1991-1994) are not shown in the tables in Portable Document Format (PDF) files; however, all annual data are shown in the Excel and comma-separated values (CSV) files. Also, only two to three years of monthly data are displayed in the PDF files; however, for many series, monthly data beginning with January 1973 are available in the Excel and CSV files.

**Comprehensive Changes:** Each month, most MER tables and figures carry a new month of data, which is usually preliminary (and sometimes estimated or even forecast) and likely to be revised in the succeeding month.

**Annual Data From 1949:** The emphasis of the MER is on recent monthly and annual data trends. Analysts may wish to use the data in this report in conjunction with EIA's *Annual Energy Review (AER)* that offers annual data beginning in 1949 for many of the data series found in the MER. The AER is available at <http://www.eia.gov/totalenergy/data/annual>.

## Electronic Access

The MER is available on EIA's website in a variety of formats at <http://www.eia.gov/totalenergy/data/monthly>.

- Full report and sections: PDF files
- Report tables: PDF files
- Table data (unrounded): Excel and CSV files
- Graphs: PDF files

Note: PDF files display selected annual and monthly data; Excel and CSV files display all available annual and monthly data, often at a greater level of precision than the PDF files.

**Timing of Release:** The MER is posted on the EIA website by the last work day of the month at <http://www.eia.gov/totalenergy/data/monthly>.

# Monthly Energy Review

## August 2012

**U.S. Energy Information Administration**  
Office of Energy Statistics  
U.S. Department of Energy  
Washington, DC 20585

This report was prepared by the U.S. Energy Information Administration (EIA), the statistical and analytical agency within the U.S. Department of Energy. By law, EIA's data, analyses, and forecasts are independent of approval by any other officer or employee of the United States Government. The views in this report therefore should not be construed as representing those of the Department of Energy or other Federal agencies.

# Contacts

The *Monthly Energy Review* is prepared by the U.S. Energy Information Administration, Office of Energy Statistics, Office of Survey Development and Statistical Integration, Integrated Energy Statistics Team, under the direction of Barbara T. Fichman, 202-586-5737 (barbara.fichman@eia.gov). Questions and comments specifically related to the *Monthly Energy Review* may be addressed to Alexander Sun, 202-287-5948 (alexander.sun@eia.gov).

For assistance in acquiring data, please contact EIA's Office of Communications at 202-586-8800 (infoctr@eia.gov). Questions about the collection, processing, or interpretation of the information may be directed to the following subject specialists:

<b>Section 1. Energy Overview</b>	Dianne R. Dunn	202-586-2792 dianne.dunn@eia.gov
<b>Section 2. Energy Consumption by Sector</b>	Dianne R. Dunn	202-586-2792 dianne.dunn@eia.gov
<b>Section 3. Petroleum</b>	Jennifer Barrick	202-586-6254 jennifer.barrick@eia.gov
<b>Section 4. Natural Gas</b>	Amy Sweeney	202-586-2627 amy.sweeney@eia.gov
<b>Section 5. Crude Oil and Natural Gas Resource Development</b>	Robert F. King	202-586-4787 robert.king@eia.gov
<b>Section 6. Coal</b>	Nicholas Paduano	202-287-6326 nicholas.paduano@eia.gov
<b>Section 7. Electricity</b>	Ronald S. Hankey	202-586-2630 ronald.hankey@eia.gov
<b>Section 8. Nuclear Energy</b>	Michael P. Mobilia	202-287-6318 michael.mobilia@eia.gov
<b>Section 9. Energy Prices</b>		
Petroleum	Maureen Klein	202-586-8013 maureen.klein@eia.gov
Natural Gas	Amy Sweeney	202-586-2627 amy.sweeney@eia.gov
Average Retail Prices of Electricity	Charlene Harris-Russell	202-586-2661 charlene.harris-russell@eia.gov
Cost of Fuel at Electric Generating Plants	Rebecca Peterson	202-586-4509 rebecca.peterson@eia.gov
<b>Section 10. Renewable Energy</b>	Fred Mayes	202-586-1508 fred.mayes@eia.gov
<b>Section 11. International Petroleum</b>	Patricia Smith	202-586-6925 patricia.smith@eia.gov
<b>Section 12. Environment</b>	Perry Lindstrom	202-586-0934 perry.lindstrom@eia.gov

# Contents

	<b>Page</b>
Section	1. Energy Overview. . . . . 1
Section	2. Energy Consumption by Sector. . . . . 21
Section	3. Petroleum. . . . . 35
Section	4. Natural Gas. . . . . 67
Section	5. Crude Oil and Natural Gas Resource Development. . . . . 75
Section	6. Coal. . . . . 81
Section	7. Electricity. . . . . 91
Section	8. Nuclear Energy. . . . . 113
Section	9. Energy Prices. . . . . 117
Section	10. Renewable Energy. . . . . 137
Section	11. International Petroleum. . . . . 149
Section	12. Environment. . . . . 159
Appendix	A. British Thermal Unit Conversion Factors. . . . . 173
Appendix	B. Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors. . . . . 185
Glossary	. . . . . 189

# Tables

	Page
<b>Section 1. Energy Overview</b>	
1.1 Primary Energy Overview. . . . .	3
1.2 Primary Energy Production by Source. . . . .	5
1.3 Primary Energy Consumption by Source. . . . .	7
1.4a Primary Energy Imports by Source. . . . .	10
1.4b Primary Energy Exports by Source and Total Net Imports. . . . .	11
1.5 Merchandise Trade Value. . . . .	13
1.6 Cost of Fuels to End Users in Real (1982-1984) Dollars. . . . .	15
1.7 Primary Energy Consumption per Real Dollar of Gross Domestic Product. . . . .	16
1.8 Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy. . . . .	17
1.9 Heating Degree-Days by Census Division. . . . .	18
1.10 Cooling Degree-Days by Census Division. . . . .	19
<b>Section 2. Energy Consumption by Sector</b>	
2.1 Energy Consumption by Sector. . . . .	23
2.2 Residential Sector Energy Consumption. . . . .	25
2.3 Commercial Sector Energy Consumption. . . . .	27
2.4 Industrial Sector Energy Consumption. . . . .	29
2.5 Transportation Sector Energy Consumption. . . . .	31
2.6 Electric Power Sector Energy Consumption. . . . .	33
<b>Section 3. Petroleum</b>	
3.1 Petroleum Overview . . . . .	37
3.2 Refinery and Blender Net Inputs and Net Production. . . . .	39
3.3 Petroleum Trade	
3.3a Overview. . . . .	41
3.3b Imports and Exports by Type. . . . .	43
3.3c Imports From OPEC Countries. . . . .	44
3.3d Imports From Non-OPEC Countries. . . . .	45
3.4 Petroleum Stocks. . . . .	47
3.5 Petroleum Products Supplied by Type. . . . .	49
3.6 Heat Content of Petroleum Products Supplied by Type. . . . .	51
3.7 Petroleum Consumption	
3.7a Residential and Commercial Sectors. . . . .	53
3.7b Industrial Sector. . . . .	54
3.7c Transportation and Electric Power Sectors. . . . .	55
3.8 Heat Content of Petroleum Consumption	
3.8a Residential and Commercial Sectors. . . . .	57
3.8b Industrial Sector. . . . .	58
3.8c Transportation and Electric Power Sectors. . . . .	59
<b>Section 4. Natural Gas</b>	
4.1 Natural Gas Overview. . . . .	69
4.2 Natural Gas Trade by Country . . . . .	70
4.3 Natural Gas Consumption by Sector. . . . .	71
4.4 Natural Gas in Underground Storage. . . . .	72
<b>Section 5. Crude Oil and Natural Gas Resource Development</b>	
5.1 Crude Oil and Natural Gas Drilling Activity Measurements. . . . .	77
5.2 Crude Oil and Natural Gas Exploratory and Development Wells. . . . .	78

# Tables

	Page
<b>Section 6. Coal</b>	
6.1 Coal Overview. . . . .	83
6.2 Coal Consumption by Sector. . . . .	84
6.3 Coal Stocks by Sector. . . . .	85
<b>Section 7. Electricity</b>	
7.1 Electricity Overview. . . . .	93
7.2 Electricity Net Generation	
7.2a Total (All Sectors). . . . .	95
7.2b Electric Power Sector. . . . .	96
7.2c Commercial and Industrial Sectors. . . . .	97
7.3 Consumption of Combustible Fuels for Electricity Generation	
7.3a Total (All Sectors). . . . .	99
7.3b Electric Power Sector. . . . .	100
7.3c Commercial and Industrial Sectors (Selected Fuels). . . . .	101
7.4 Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output	
7.4a Total (All Sectors). . . . .	103
7.4b Electric Power Sector. . . . .	104
7.4c Commercial and Industrial Sectors (Selected Fuels). . . . .	105
7.5 Stocks of Coal and Petroleum: Electric Power Sector. . . . .	107
7.6 Electricity End Use. . . . .	109
<b>Section 8. Nuclear Energy</b>	
8.1 Nuclear Energy Overview. . . . .	115
<b>Section 9. Energy Prices</b>	
9.1 Crude Oil Price Summary. . . . .	119
9.2 F.O.B. Costs of Crude Oil Imports From Selected Countries. . . . .	120
9.3 Landed Costs of Crude Oil Imports From Selected Countries. . . . .	121
9.4 Motor Gasoline Retail Prices, U.S. City Average. . . . .	122
9.5 Refiner Prices of Residual Fuel Oil. . . . .	123
9.6 Refiner Prices of Petroleum Products for Resale. . . . .	124
9.7 Refiner Prices of Petroleum Products to End Users. . . . .	125
9.8 No. 2 Distillate Prices to Residences	
9.8a Northeastern States. . . . .	126
9.8b Selected South Atlantic and Midwestern States. . . . .	127
9.8c Selected Western States and U.S. Average. . . . .	128
9.9 Average Retail Prices of Electricity. . . . .	130
9.10 Cost of Fossil-Fuel Receipts at Electric Generating Plants. . . . .	131
9.11 Natural Gas Prices. . . . .	133
<b>Section 10. Renewable Energy</b>	
10.1 Renewable Energy Production and Consumption by Source. . . . .	139
10.2 Renewable Energy Consumption	
10.2a Residential and Commercial Sectors. . . . .	140
10.2b Industrial and Transportation Sectors. . . . .	141
10.2c Electric Power Sector . . . . .	142
10.3 Fuel Ethanol Overview. . . . .	143
10.4 Biodiesel Overview. . . . .	144

# Tables

Page

## Section 11. International Petroleum

11.1	World Crude Oil Production	
	11.1a OPEC Members. . . . .	152
	11.1b Persian Gulf Nations, Non-OPEC, and World. . . . .	153
11.2	Petroleum Consumption in OECD Countries. . . . .	155
11.3	Petroleum Stocks in OECD Countries. . . . .	157

## Section 12. Environment

12.1	Carbon Dioxide Emissions From Energy Consumption by Source . . . . .	161
12.2	Carbon Dioxide Emissions From Energy Consumption: Residential Sector . . . . .	163
12.3	Carbon Dioxide Emissions From Energy Consumption: Commercial Sector. . . . .	164
12.4	Carbon Dioxide Emissions From Energy Consumption: Industrial Sector. . . . .	165
12.5	Carbon Dioxide Emissions From Energy Consumption: Transportation Sector. . . . .	166
12.6	Carbon Dioxide Emissions From Energy Consumption: Electric Power Sector. . . . .	167
12.7	Carbon Dioxide Emissions From Biomass Energy Consumption . . . . .	168

## Appendix A. British Thermal Unit Conversion Factors

A1.	Approximate Heat Content of Petroleum Products. . . . .	173
A2.	Approximate Heat Content of Petroleum Production, Imports, and Exports. . . . .	174
A3.	Approximate Heat Content of Petroleum Consumption and Biofuels Production. . . . .	175
A4.	Approximate Heat Content of Natural Gas. . . . .	176
A5.	Approximate Heat Content of Coal and Coal Coke. . . . .	177
A6.	Approximate Heat Rates for Electricity, and Heat Content of Electricity. . . . .	178

## Appendix B. Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors

B1.	Metric Conversion Factors. . . . .	186
B2.	Metric Prefixes. . . . .	187
B3.	Other Physical Conversion Factors. . . . .	187



# Figures

	Page
<b>Section 1. Energy Overview</b>	
1.1 Primary Energy Overview. . . . .	2
1.2 Primary Energy Production. . . . .	4
1.3 Primary Energy Consumption. . . . .	6
1.4a Primary Energy Imports and Exports. . . . .	8
1.4b Primary Energy Net Imports. . . . .	9
1.5 Merchandise Trade Value. . . . .	12
1.6 Cost of Fuels to End Users in Real (1982-1984) Dollars. . . . .	14
1.7 Primary Energy Consumption per Real Dollar of Gross Domestic Product. . . . .	16
1.8 Motor Vehicle Fuel Economy. . . . .	17
<b>Section 2. Energy Consumption by Sector</b>	
2.1 Energy Consumption by Sector. . . . .	22
2.2 Residential Sector Energy Consumption. . . . .	24
2.3 Commercial Sector Energy Consumption. . . . .	26
2.4 Industrial Sector Energy Consumption. . . . .	28
2.5 Transportation Sector Energy Consumption. . . . .	30
2.6 Electric Power Sector Energy Consumption. . . . .	32
<b>Section 3. Petroleum</b>	
3.1 Petroleum Overview . . . . .	36
3.2 Refinery and Blender Net Inputs and Net Production. . . . .	38
3.3 Petroleum Trade	
3.3a Overview. . . . .	40
3.3b Imports. . . . .	42
3.4 Petroleum Stocks. . . . .	46
3.5 Petroleum Products Supplied by Type. . . . .	48
3.6 Heat Content of Petroleum Products Supplied by Type. . . . .	50
3.7 Petroleum Consumption by Sector. . . . .	52
3.8 Heat Content of Petroleum Consumption by Sector, Selected Products. . . . .	56
<b>Section 4. Natural Gas</b>	
4.1 Natural Gas. . . . .	68
<b>Section 5. Crude Oil and Natural Gas Resource Development</b>	
5.1 Crude Oil and Natural Gas Resource Development Indicators. . . . .	76
<b>Section 6. Coal</b>	
6.1 Coal. . . . .	82
<b>Section 7. Electricity</b>	
7.1 Electricity Overview. . . . .	92
7.2 Electricity Net Generation. . . . .	94
7.3 Consumption of Selected Combustible Fuels for Electricity Generation. . . . .	98
7.4 Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output. . . . .	102
7.5 Stocks of Coal and Petroleum: Electric Power Sector. . . . .	106
7.6 Electricity End Use. . . . .	108
<b>Section 8. Nuclear Energy</b>	
8.1 Nuclear Energy Overview. . . . .	114

# Figures


	<b>Page</b>
<b>Section 9. Energy Prices</b>	
9.1 Petroleum Prices. . . . .	118
9.2 Average Retail Prices of Electricity. . . . .	129
9.3 Cost of Fossil-Fuel Receipts at Electric Generating Plants. . . . .	129
9.4 Natural Gas Prices. . . . .	132
<b>Section 10. Renewable Energy</b>	
10.1 Renewable Energy Consumption. . . . .	138
<b>Section 11. International Petroleum</b>	
11.1 World Crude Oil Production	
11.1a Overview. . . . .	150
11.1b By Selected Country. . . . .	151
11.2 Petroleum Consumption in OECD Countries. . . . .	154
11.3 Petroleum Stocks in OECD Countries. . . . .	156
<b>Section 12. Environment</b>	
12.1 Carbon Dioxide Emissions From Energy Consumption by Source . . . . .	160
12.2 Carbon Dioxide Emissions From Energy Consumption by Sector. . . . .	162

# 1. Energy Overview


---

**Figure 1.1 Primary Energy Overview**  
(Quadrillion Btu)


Consumption, Production, and Imports, 1973-2011




Consumption, Production, and Imports, Monthly



Overview, May 2012



Net Imports, January-May



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.  
Source: Table 1.1.

**Table 1.1 Primary Energy Overview**  
(Quadrillion Btu)


	Production				Trade			Stock Change and Other <sup>d</sup>	Consumption			
	Fossil Fuels <sup>a</sup>	Nuclear Electric Power	Renewable Energy <sup>b</sup>	Total	Imports	Exports	Net Imports <sup>c</sup>		Fossil Fuels <sup>e</sup>	Nuclear Electric Power	Renewable Energy <sup>b</sup>	Total <sup>f</sup>
1973 Total	58.241	0.910	4.411	63.563	14.613	2.033	12.580	-0.459	70.314	0.910	4.411	75.684
1975 Total	54.733	1.900	4.687	61.320	14.032	2.323	11.709	-1.065	65.357	1.900	4.687	71.965
1980 Total	59.008	2.739	5.428	67.175	15.796	3.695	12.101	-1.210	69.828	2.739	5.428	78.067
1985 Total	57.539	4.076	6.084	67.698	11.781	4.196	7.584	1.110	66.093	4.076	6.084	76.392
1990 Total	58.560	6.104	6.041	70.705	18.817	4.752	14.065	-.284	72.332	6.104	6.041	84.485
1995 Total	57.540	7.075	6.558	71.174	22.260	4.511	17.750	2.105	77.259	7.075	6.560	91.029
1996 Total	58.387	7.087	7.012	72.486	23.702	4.633	19.069	2.468	79.785	7.087	7.014	94.022
1997 Total	58.857	6.597	7.018	72.472	25.215	4.514	20.701	1.429	80.873	6.597	7.016	94.602
1998 Total	59.314	7.068	6.494	72.876	26.581	4.299	22.281	-.140	81.369	7.068	6.493	95.018
1999 Total	57.614	7.610	6.517	71.742	27.252	3.715	23.537	1.372	82.427	7.610	6.516	96.652
2000 Total	57.366	7.862	6.104	71.332	28.973	4.006	24.967	2.515	84.731	7.862	6.106	98.814
2001 Total	58.541	8.029	5.164	71.735	30.157	3.771	26.386	-1.953	82.902	8.029	5.163	96.168
2002 Total	56.837	8.145	5.734	70.716	29.408	3.669	25.739	1.190	83.699	8.145	5.729	97.645
2003 Total	56.099	7.959	5.982	70.040	31.061	4.054	27.007	.931	84.014	7.959	5.983	97.978
2004 Total	55.895	8.222	6.070	70.188	33.544	4.434	29.110	.864	85.819	8.222	6.082	100.162
2005 Total	55.038	8.161	6.229	69.428	34.709	4.560	30.149	.705	85.794	8.161	6.242	100.282
2006 Total	55.968	8.215	6.599	70.782	34.679	4.872	29.806	-.959	84.702	8.215	6.649	99.629
2007 Total	56.409	8.455	6.509	71.373	34.703	5.482	29.221	.702	86.211	8.455	6.523	101.296
2008 Total	57.482	8.427	7.202	73.111	32.992	7.060	25.932	-.231	83.549	8.427	7.186	99.275
2009 Total	56.685	8.356	7.616	72.657	29.706	6.965	22.741	-.839	78.488	8.356	7.600	94.559
2010 January	4.733	.758	.672	6.164	2.516	.590	1.926	R 1.043	7.697	.758	.662	9.132
February	4.445	.682	.610	5.738	2.237	.556	1.681	.794	6.915	.682	.605	8.213
March	5.032	.676	.682	6.389	2.519	.654	1.865	-.049	6.846	.676	.673	8.205
April	4.773	.602	.661	6.036	2.580	.686	1.894	R -.558	6.104	.602	.657	7.372
May	R 4.777	.697	.717	R 6.190	2.578	.704	1.874	R -.387	6.261	.697	.715	7.678
June	4.716	.714	.753	6.183	2.556	.684	1.872	-.048	6.530	.714	.755	8.008
July	4.889	.752	.701	6.341	2.705	.716	1.989	.052	6.920	.752	.701	8.383
August	R 4.988	.748	.662	6.397	2.627	.698	1.929	.118	7.030	.748	.660	8.445
September	4.931	.725	.626	R 6.282	2.431	.675	1.757	-.344	6.345	.725	.622	7.694
October	R 5.006	.656	.646	6.308	2.390	.714	1.676	-.474	6.209	.656	.643	7.509
November	4.898	.655	.682	6.235	2.289	.760	1.529	.033	6.464	.655	.676	7.797
December	5.061	.770	.726	R 6.557	2.447	.797	1.650	1.025	7.732	.770	.720	9.231
Total	R 58.249	8.434	8.136	R 74.820	29.877	8.234	21.643	1.204	81.054	8.434	8.090	97.667
2011 January	5.000	.760	.754	R 6.515	2.607	.832	1.776	1.061	7.843	.760	.739	9.351
February	R 4.528	.677	.717	R 5.922	2.087	.751	1.336	R .873	6.736	.677	.710	8.131
March	R 5.182	.686	.822	R 6.690	2.501	.869	1.631	R .051	6.867	.686	.811	8.373
April	R 4.922	.570	.821	R 6.313	2.378	.852	1.526	R -.294	6.156	.570	.812	7.545
May	R 5.013	.596	.840	R 6.449	2.466	.832	1.634	R -.474	6.166	.596	.835	7.609
June	R 4.937	.682	.828	R 6.447	2.407	.802	1.605	R -.120	6.412	.682	.827	7.932
July	R 4.955	.756	.797	R 6.508	2.493	.833	1.660	R .206	6.814	.756	.787	8.373
August	R 5.204	.746	.746	R 6.695	2.395	.893	1.502	R .186	6.879	.746	.744	8.384
September	R 5.070	.699	.680	R 6.448	2.288	.891	1.397	R -.278	6.184	.699	.673	7.567
October	R 5.292	.662	.711	R 6.665	2.345	.892	1.453	R -.546	6.199	.662	.702	7.573
November	R 5.230	.674	.742	R 6.646	2.269	.900	1.369	R -.264	6.339	.674	.730	7.751
December	R 5.337	.751	.779	R 6.867	2.354	1.008	1.347	R .379	7.064	.751	.766	8.592
Total	R 60.670	8.259	9.236	R 78.165	28.590	10.356	18.234	R .780	79.658	8.259	9.135	97.180
2012 January	R 5.390	.757	.792	R 6.938	2.330	.866	1.464	.297	R 7.162	.757	R .769	R 8.699
February	R 4.967	.667	.705	R 6.339	2.102	R .840	R 1.262	.416	R 6.646	.667	R .694	R 8.017
March	R 5.197	.645	.797	R 6.639	R 2.258	R .967	R 1.291	R -.220	R 6.267	.645	R .788	R 7.710
April	R 4.903	.584	.776	R 6.263	R 2.177	R 1.001	R 1.176	R -.147	R 5.923	.584	.773	R 7.292
May	5.104	.649	.819	6.572	2.352	1.015	1.337	-.233	6.193	.649	.819	7.675
5-Month Total	25.560	3.302	3.890	32.751	11.218	4.688	6.530	.113	32.191	3.302	3.843	39.394
2011 5-Month Total	24.645	3.290	3.954	31.889	12.039	4.137	7.902	1.218	33.767	3.290	3.907	41.009
2010 5-Month Total	23.761	3.415	3.341	30.517	12.430	3.189	9.241	.842	33.824	3.415	3.312	40.600

<sup>a</sup> Coal, natural gas (dry), crude oil, and natural gas plant liquids.  
<sup>b</sup> See Tables 10.1–10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.  
<sup>c</sup> Net imports equal imports minus exports.  
<sup>d</sup> Includes petroleum stock change and adjustments; natural gas net storage withdrawals and balancing item; coal stock change, losses, and unaccounted for; fuel ethanol stock change; and biodiesel stock change and balancing item.  
<sup>e</sup> Coal, coal coke net imports, natural gas, and petroleum.  
<sup>f</sup> Also includes electricity net imports.  
R=Revised.


Notes: • See "Primary Energy," "Primary Energy Production," and "Primary Energy Consumption," in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available data beginning in 1973.  
Sources: • **Production:** Table 1.2. • **Trade:** Tables 1.4a and 1.4b. • **Stock Change and Other:** Calculated as consumption minus production and net imports. • **Consumption:** Table 1.3.

**Figure 1.2 Primary Energy Production**  
(Quadrillion Btu)


Total, 1973-2011




Total, Monthly




By Source, 1973-2011




By Source, Monthly



Total, January-May



By Source, May 2012



<sup>a</sup> Natural gas plant liquids.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.2.

**Table 1.2 Primary Energy Production by Source**  
(Quadrillion Btu)

	Fossil Fuels					Nuclear Electric Power	Renewable Energy <sup>a</sup>						Total
	Coal <sup>b</sup>	Natural Gas (Dry)	Crude Oil <sup>c</sup>	NGPL <sup>d</sup>	Total		Hydro-electric Power <sup>e</sup>	Geo-thermal	Solar/ PV	Wind	Bio-mass	Total	
<b>1973 Total</b> .....	13.992	22.187	19.493	2.569	58.241	0.910	2.861	0.020	NA	NA	1.529	4.411	63.563
<b>1975 Total</b> .....	14.989	19.640	17.729	2.374	54.733	1.900	3.155	.034	NA	NA	1.499	4.687	61.320
<b>1980 Total</b> .....	18.598	19.908	18.249	2.254	59.008	2.739	2.900	.053	NA	NA	2.475	5.428	67.175
<b>1985 Total</b> .....	19.325	16.980	18.992	2.241	57.539	4.076	2.970	.097	(s)	(s)	3.016	6.084	67.698
<b>1990 Total</b> .....	22.488	18.326	15.571	2.175	58.560	6.104	3.046	.171	.059	.029	2.735	6.041	70.705
<b>1995 Total</b> .....	22.130	19.082	13.887	2.442	57.540	7.075	3.205	.152	.069	.033	3.099	6.558	71.174
<b>1996 Total</b> .....	22.790	19.344	13.723	2.530	58.387	7.087	3.590	.163	.070	.033	3.155	7.012	72.486
<b>1997 Total</b> .....	23.310	19.394	13.658	2.495	58.857	6.597	3.640	.167	.070	.034	3.108	7.018	72.472
<b>1998 Total</b> .....	24.045	19.613	13.235	2.420	59.314	7.068	3.297	.168	.069	.031	2.929	6.494	72.876
<b>1999 Total</b> .....	23.295	19.341	12.451	2.528	57.614	7.610	3.268	.171	.068	.046	2.965	6.517	71.742
<b>2000 Total</b> .....	22.735	19.662	12.358	2.611	57.366	7.862	2.811	.164	.066	.057	3.006	6.104	71.332
<b>2001 Total</b> .....	23.547	20.166	12.282	2.547	58.541	8.029	2.242	.164	.064	.070	2.624	5.164	71.735
<b>2002 Total</b> .....	22.732	19.382	12.163	2.559	56.837	8.145	2.689	.171	.063	.105	2.705	5.734	70.716
<b>2003 Total</b> .....	22.094	19.633	12.026	2.346	56.099	7.959	2.825	.175	.062	.115	2.805	5.982	70.040
<b>2004 Total</b> .....	22.852	19.074	11.503	2.466	55.895	8.222	2.690	.178	.063	.142	2.998	6.070	70.188
<b>2005 Total</b> .....	23.185	18.556	10.963	2.334	55.038	8.161	2.703	.181	.063	.178	3.104	6.229	69.428
<b>2006 Total</b> .....	23.790	19.022	10.801	2.356	55.968	8.215	2.869	.181	.068	.264	3.216	6.599	70.782
<b>2007 Total</b> .....	23.493	19.786	10.721	2.409	56.409	8.455	2.446	.186	.076	.341	3.461	6.509	71.373
<b>2008 Total</b> .....	23.851	20.703	10.509	2.419	57.482	8.427	2.511	.192	.089	.546	3.864	7.202	73.111
<b>2009 Total</b> .....	21.624	21.139	11.348	2.574	56.685	8.356	2.669	.200	.098	.721	3.928	7.616	72.657
<b>2010</b>													
January .....	1.743	1.790	.970	.230	4.733	.758	.218	.018	.010	.067	.359	.672	6.164
February .....	1.687	1.648	.900	.210	4.445	.682	.201	.016	.009	.053	.332	.610	5.738
March .....	1.969	1.835	.991	.236	5.032	.676	.204	.018	.010	.084	.366	.682	6.389
April .....	1.848	1.763	.935	.227	4.773	.602	.186	.017	.010	.095	.351	.661	6.036
May .....	1.736	1.832	R .970	.238	R 4.777	.697	.245	.018	.011	.085	.358	.717	R 6.190
June .....	1.802	1.751	.937	.226	4.716	.714	.291	.017	.011	.079	.355	.753	6.183
July .....	1.847	1.859	.956	.227	4.889	.752	.239	.017	.011	.066	.367	.701	6.341
August .....	1.898	1.874	R .980	.236	R 4.988	.748	.196	.018	.011	.065	.371	.662	6.397
September .....	1.897	1.826	.977	.232	4.931	.725	.168	.017	.011	.069	.360	.626	R 6.282
October .....	1.864	1.892	R 1.008	.242	R 5.006	.656	.173	.017	.010	.077	.369	.646	6.308
November .....	1.860	1.833	.969	.235	4.898	.655	.191	.017	.010	.095	.369	.682	6.235
December .....	1.886	1.920	1.012	.242	5.061	.770	.226	.018	.010	.088	.383	.726	R 6.557
<b>Total</b> .....	<b>22.038</b>	<b>21.823</b>	<b>R 11.606</b>	<b>2.781</b>	<b>R 58.249</b>	<b>8.434</b>	<b>2.539</b>	<b>.208</b>	<b>.126</b>	<b>.923</b>	<b>4.341</b>	<b>8.136</b>	<b>R 74.820</b>
<b>2011</b>													
January .....	1.854	E 1.922	E .994	.230	5.000	.760	.255	.020	.012	.084	.383	.754	R 6.515
February .....	1.736	E 1.711	RE .884	.198	R 4.528	.677	.241	.018	.012	.103	.344	.717	R 5.922
March .....	1.958	E 1.963	RE 1.014	.247	R 5.182	.686	.310	.020	.013	.103	.377	.822	R 6.690
April .....	1.789	E 1.925	RE .969	.238	R 4.922	.570	.309	.018	.013	.121	.359	.821	R 6.313
May .....	1.755	E 1.988	RE 1.017	.253	R 5.013	.596	.323	.019	.014	.114	.371	.840	R 6.449
June .....	1.798	E 1.923	RE .976	.240	R 4.937	.682	.315	.019	.014	.106	.375	.828	R 6.447
July .....	1.733	E 1.987	RE .985	.250	R 4.955	.756	.308	.019	.014	.072	.384	.797	R 6.508
August .....	1.933	E 1.994	RE 1.026	.251	R 5.204	.746	.257	.019	.014	.072	.384	.746	R 6.695
September .....	1.903	E 1.952	RE .978	.237	R 5.070	.699	.210	.018	.013	.067	.371	.680	R 6.448
October .....	1.915	E 2.052	RE 1.066	.259	R 5.292	.662	.195	.019	.014	.104	.379	.711	R 6.665
November .....	1.904	E 2.014	RE 1.053	.258	R 5.230	.674	.209	.019	.012	.121	.382	.742	R 6.646
December .....	1.903	E 2.075	RE 1.091	.268	R 5.337	.751	.241	.019	.013	.102	.403	.779	R 6.867
<b>Total</b> .....	<b>22.181</b>	<b>E 23.506</b>	<b>RE 12.055</b>	<b>2.928</b>	<b>R 60.670</b>	<b>8.259</b>	<b>3.171</b>	<b>.226</b>	<b>.158</b>	<b>1.168</b>	<b>4.511</b>	<b>9.236</b>	<b>R 78.165</b>
<b>2012</b>													
January .....	1.924	RE 2.087	RE 1.108	.271	R 5.390	.757	.233	.019	.015	.135	.389	.792	R 6.938
February .....	1.737	RE 1.930	RE 1.045	.255	R 4.967	.667	.203	.018	.015	.108	.362	.705	R 6.339
March .....	1.735	RE 2.061	RE 1.131	.271	R 5.197	.645	.256	.019	.016	.132	.372	.797	R 6.639
April .....	1.552	RE 2.004	RE 1.084	.263	R 4.903	.584	.261	.018	.017	.123	.357	.776	R 6.263
May .....	1.634	E 2.072	E 1.127	.271	5.104	.649	.283	.019	.019	.121	.377	.819	6.572
<b>5-Month Total</b> ...	<b>8.583</b>	<b>E 10.154</b>	<b>E 5.494</b>	<b>1.329</b>	<b>25.560</b>	<b>3.302</b>	<b>1.237</b>	<b>.095</b>	<b>.082</b>	<b>.619</b>	<b>1.857</b>	<b>3.890</b>	<b>32.751</b>
<b>2011 5-Month Total</b> ...	<b>9.092</b>	<b>E 9.509</b>	<b>E 4.879</b>	<b>1.166</b>	<b>24.645</b>	<b>3.290</b>	<b>1.437</b>	<b>.095</b>	<b>.064</b>	<b>.525</b>	<b>1.833</b>	<b>3.954</b>	<b>31.889</b>
<b>2010 5-Month Total</b> ...	<b>8.983</b>	<b>8.868</b>	<b>4.767</b>	<b>1.142</b>	<b>23.761</b>	<b>3.415</b>	<b>1.054</b>	<b>.086</b>	<b>.051</b>	<b>.384</b>	<b>1.766</b>	<b>3.341</b>	<b>30.517</b>

<sup>a</sup> Most data are estimates. See Tables 10.1-10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.

<sup>b</sup> Beginning in 1989, includes waste coal supplied. Beginning in 2001, also includes a small amount of refuse recovery. See Table 6.1.

<sup>c</sup> Includes lease condensate.

<sup>d</sup> Natural gas plant liquids.

<sup>e</sup> Conventional hydroelectric power.

R=Revised. E=Estimate. NA=Not available. (s)=Less than 0.5 trillion Btu.


Notes: • See "Primary Energy Production" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available data beginning in 1973.


Sources: • **Coal:** Tables 6.1 and A5. • **Natural Gas (Dry):** Tables 4.1 and A4. • **Crude Oil and Natural Gas Plant Liquids:** Tables 3.1 and A2. • **Nuclear Electric Power:** Tables 7.2a and A6 ("Nuclear Plants" heat rate). • **Renewable Energy:** Table 10.1.

**Figure 1.3 Primary Energy Consumption**  
(Quadrillion Btu)


Total, 1973-2011




Total, Monthly




By Source,<sup>a</sup> 1973-2011




By Source,<sup>a</sup> Monthly



Total, January-May



By Source,<sup>a</sup> May 2012



<sup>a</sup> Small quantities of net imports of coal coke and electricity are not shown.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.  
Source: Table 1.3.



**Table 1.3 Primary Energy Consumption by Source**  
(Quadrillion Btu)

	Fossil Fuels				Nuclear Electric Power	Renewable Energy <sup>a</sup>						Total <sup>f</sup>
	Coal	Natural Gas <sup>b</sup>	Petro-leum <sup>c</sup>	Total <sup>d</sup>		Hydro-electric Power <sup>e</sup>	Geo-thermal	Solar/PV	Wind	Bio-mass	Total	
1973 Total	12.971	22.512	34.837	70.314	0.910	2.861	0.020	NA	NA	1.529	4.411	75.684
1975 Total	12.663	19.948	32.732	65.357	1.900	3.155	.034	NA	NA	1.499	4.687	71.965
1980 Total	15.423	20.235	34.205	69.828	2.739	2.900	.053	NA	NA	2.475	5.428	78.067
1985 Total	17.478	17.703	30.925	66.093	4.076	2.970	.097	(s)	(s)	3.016	6.084	76.392
1990 Total	19.173	19.603	33.552	72.332	6.104	3.046	.171	.059	.029	2.735	6.041	84.485
1995 Total	20.089	22.671	34.438	77.259	7.075	3.205	.152	.069	.033	3.101	6.560	91.029
1996 Total	21.002	23.085	35.675	79.785	7.087	3.590	.163	.070	.033	3.157	7.014	94.022
1997 Total	21.445	23.223	36.159	80.873	6.597	3.640	.167	.070	.034	3.105	7.016	94.602
1998 Total	21.656	22.830	36.816	81.369	7.068	3.297	.168	.069	.031	2.927	6.493	95.018
1999 Total	21.623	22.909	37.838	82.427	7.610	3.268	.171	.068	.046	2.963	6.516	96.652
2000 Total	22.580	23.824	38.262	84.731	7.862	2.811	.164	.066	.057	3.008	6.106	98.814
2001 Total	21.914	22.773	38.186	82.902	8.029	2.242	.164	.064	.070	2.622	5.163	96.168
2002 Total	21.904	23.510	38.224	83.699	8.145	2.689	.171	.063	.105	2.701	5.729	97.645
2003 Total	22.321	22.831	38.811	84.014	7.959	2.825	.175	.062	.115	2.807	5.983	97.978
2004 Total	22.466	22.923	40.292	85.819	8.222	2.690	.178	.063	.142	3.010	6.082	100.162
2005 Total	22.797	22.565	40.388	85.794	8.161	2.703	.181	.063	.178	3.117	6.242	100.282
2006 Total	22.447	22.239	39.955	84.702	8.215	2.869	.181	.068	.264	3.267	6.649	99.629
2007 Total	22.749	23.663	39.774	86.211	8.455	2.446	.186	.076	.341	3.474	6.523	101.296
2008 Total	22.385	23.843	37.280	83.549	8.427	2.511	.192	.089	.546	3.849	7.186	99.275
2009 Total	19.692	23.416	35.403	78.488	8.356	2.669	.200	.098	.721	3.912	7.600	94.559
<b>2010 Total</b>	<b>20.794</b>	<b>24.256</b>	<b>36.010</b>	<b>81.054</b>	<b>8.434</b>	<b>2.539</b>	<b>.208</b>	<b>.126</b>	<b>.923</b>	<b>4.294</b>	<b>8.090</b>	<b>97.667</b>
2010 January	1.914	2.841	2.947	7.697	.758	.218	.018	.010	.067	.349	.662	9.132
February	1.706	2.507	2.698	6.915	.682	.201	.016	.009	.053	.326	.605	8.213
March	1.635	2.160	3.048	6.846	.676	.204	.018	.010	.084	.357	.673	8.205
April	1.444	1.700	2.960	6.104	.602	.186	.017	.010	.095	.348	.657	7.372
May	1.618	1.622	3.020	6.261	.697	.245	.018	.011	.085	.356	.715	7.678
June	1.844	1.656	3.029	6.530	.714	.291	.017	.011	.079	.357	.755	8.008
July	1.995	1.836	3.089	6.920	.752	.239	.017	.011	.066	.368	.701	8.383
August	1.991	1.890	3.148	7.030	.748	.196	.018	.011	.065	.370	.660	8.445
September	1.693	1.644	3.008	6.345	.725	.168	.017	.011	.069	.357	.622	7.694
October	1.519	1.671	3.020	6.209	.656	.173	.017	.010	.077	.366	.643	7.509
November	1.561	1.986	2.923	6.464	.655	.191	.017	.010	.095	.363	.676	7.797
December	1.876	2.741	3.120	7.732	.770	.226	.018	.010	.088	.377	.720	9.231
<b>2011 Total</b>	<b>19.565</b>	<b>24.799</b>	<b>35.283</b>	<b>79.658</b>	<b>8.259</b>	<b>3.171</b>	<b>.226</b>	<b>.158</b>	<b>1.168</b>	<b>4.411</b>	<b>9.135</b>	<b>97.180</b>
2011 January	1.879	2.933	3.030	7.843	.760	.255	.020	.012	.084	.367	.739	9.351
February	1.552	2.482	2.701	6.736	.677	.241	.018	.012	.103	.337	.710	8.131
March	1.534	2.269	3.062	6.867	.686	.310	.020	.013	.103	.366	.811	8.373
April	1.416	1.861	2.878	6.156	.570	.309	.018	.013	.121	.351	.812	7.545
May	1.545	1.696	2.923	6.166	.596	.323	.019	.014	.114	.365	.835	7.609
June	1.752	1.680	2.979	6.412	.682	.315	.019	.014	.106	.374	.827	7.932
July	1.945	1.910	2.959	6.814	.756	.308	.019	.014	.072	.374	.787	8.373
August	1.908	1.908	3.059	6.879	.746	.257	.019	.014	.072	.382	.744	8.384
September	1.604	1.671	2.908	6.184	.699	.210	.018	.013	.067	.365	.673	7.567
October	1.467	1.779	2.953	6.199	.662	.195	.019	.014	.104	.370	.702	7.573
November	1.417	2.045	2.879	6.339	.674	.209	.019	.012	.121	.370	.730	7.751
December	1.547	2.564	2.951	7.064	.751	.241	.019	.013	.102	.390	.766	8.592
<b>2012 5-Month Total</b>	<b>6.515</b>	<b>11.337</b>	<b>14.327</b>	<b>32.191</b>	<b>3.302</b>	<b>1.237</b>	<b>.095</b>	<b>.082</b>	<b>.619</b>	<b>1.810</b>	<b>3.843</b>	<b>39.394</b>
<b>2011 5-Month Total</b>	<b>7.926</b>	<b>11.242</b>	<b>14.594</b>	<b>33.767</b>	<b>3.290</b>	<b>1.437</b>	<b>.095</b>	<b>.064</b>	<b>.525</b>	<b>1.786</b>	<b>3.907</b>	<b>41.009</b>
<b>2010 5-Month Total</b>	<b>8.316</b>	<b>10.832</b>	<b>14.672</b>	<b>33.824</b>	<b>3.415</b>	<b>1.054</b>	<b>.086</b>	<b>.051</b>	<b>.384</b>	<b>1.737</b>	<b>3.312</b>	<b>40.600</b>

<sup>a</sup> Most data are estimates. See Tables 10.1–10.2c for notes on series components and estimation; and see Note, "Renewable Energy Production and Consumption," at end of Section 10.

<sup>b</sup> Natural gas only; excludes supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>c</sup> Petroleum products supplied, including natural gas plant liquids and crude oil burned as fuel. Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass."

<sup>d</sup> Includes coal coke net imports. See Tables 1.4a and 1.4b.

<sup>e</sup> Conventional hydroelectric power.

<sup>f</sup> Includes coal coke net imports and electricity net imports, which are not

separately displayed. See Tables 1.4a and 1.4b.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy Consumption" in Glossary.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available data beginning in 1973.


Sources: • Coal: Tables 6.1 and A5. • Natural Gas: Tables 4.1 and A4.

• Petroleum: Table 3.6. • Nuclear Electric Power: Tables 7.2a and A6


("Nuclear Plants" heat rate). • Renewable Energy: Table 10.1. • Net Imports of Coal Coke and Electricity: Tables 1.4a and 1.4b.

**Figure 1.4a Primary Energy Imports and Exports**  
(Quadrillion Btu)


Total Imports and Exports, 1973-2011




Total Imports and Exports, Monthly




Imports by Source, 1973-2011




Imports by Source, Monthly



Exports by Source, 1973-2011



Exports by Major Source, Monthly




<sup>a</sup> Coal, coal coke, biofuels, and electricity.

<sup>b</sup> Includes coal coke.


Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.  
Sources: Tables 1.4a and 1.4b.

**Figure 1.4b Primary Energy Net Imports**  
(Quadrillion Btu, Except as noted)


Total, 1973-2011




Total, Monthly




By Major Source, 1973-2011




By Major Source, Monthly



By Major Source, May 2012



As Share of Consumption, January-May



<sup>a</sup> Crude oil and lease condensate. Includes imports into the Strategic Petroleum Reserve, which began in 1977.

<sup>b</sup> Petroleum products, unfinished oils, pentanes plus, and gasoline

blending components. Does not include biofuels.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Sources: Tables 1.3, 1.4a, and 1.4b.

**Table 1.4a Primary Energy Imports by Source**  
(Quadrillion Btu)

	Imports								
	Coal	Coal Coke	Natural Gas	Petroleum			Biofuels <sup>c</sup>	Electricity	Total
				Crude Oil <sup>a</sup>	Petroleum Products <sup>b</sup>	Total			
<b>1973 Total</b> .....	<b>0.003</b>	<b>0.027</b>	<b>1.060</b>	<b>6.887</b>	<b>6.578</b>	<b>13.466</b>	<b>NA</b>	<b>0.057</b>	<b>14.613</b>
1975 Total .....	.024	.045	.978	8.721	4.227	12.948	NA	.038	14.032
1980 Total .....	.030	.016	1.006	11.195	3.463	14.658	NA	.085	15.796
1985 Total .....	.049	.014	.952	6.814	3.796	10.609	NA	.157	11.781
1990 Total .....	.067	.019	1.551	12.766	4.351	17.117	NA	.063	18.817
1995 Total .....	.237	.095	2.901	15.669	3.211	18.881	.001	.146	22.260
1996 Total .....	.203	.063	3.002	16.341	3.943	20.284	.001	.148	23.702
1997 Total .....	.187	.078	3.063	17.876	3.864	21.740	(s)	.147	25.215
1998 Total .....	.218	.095	3.225	18.916	3.992	22.908	(s)	.135	26.581
1999 Total .....	.227	.080	3.664	18.935	4.198	23.133	(s)	.147	27.252
2000 Total .....	.313	.094	3.869	19.783	4.749	24.531	(s)	.166	28.973
2001 Total .....	.495	.063	4.068	20.348	5.051	25.398	.002	.131	30.157
2002 Total .....	.422	.080	4.104	19.920	4.754	24.674	.002	.125	29.408
2003 Total .....	.626	.068	4.042	21.060	5.159	26.219	.002	.104	31.061
2004 Total .....	.682	.170	4.365	22.082	6.114	28.197	.013	.117	33.544
2005 Total .....	.762	.088	4.450	22.091	7.157	29.248	.012	.150	34.709
2006 Total .....	.906	.101	4.291	22.085	7.084	29.169	.066	.146	34.679
2007 Total .....	.909	.061	4.723	21.914	6.868	28.781	.054	.175	34.703
2008 Total .....	.855	.089	4.084	21.448	6.237	27.685	.084	.195	32.992
2009 Total .....	.566	.009	3.845	19.699	5.383	25.082	.026	.178	29.706
<b>2010</b> January .....	.042	.001	.394	1.577	.483	2.060	.001	.018	2.516
February .....	.031	.005	.332	1.469	.384	1.853	(s)	.015	2.237
March .....	.047	.003	.327	1.734	.393	2.127	.001	.015	2.519
April .....	.045	.001	.306	1.747	.466	2.214	(s)	.013	2.580
May .....	.037	.005	.305	1.793	.428	2.221	.001	.010	2.578
June .....	.044	.005	.289	1.784	.419	2.203	(s)	.014	2.556
July .....	.035	.003	.337	1.844	.472	2.316	(s)	.015	2.705
August .....	.043	.003	.313	1.772	.484	2.256	(s)	.012	2.627
September .....	.040	.002	.289	1.658	.432	2.090	(s)	.010	2.431
October .....	.044	.001	.302	1.585	.448	2.034	(s)	.009	2.390
November .....	.037	(s)	.280	1.563	.400	1.963	(s)	.009	2.289
December .....	.039	(s)	.361	1.614	.420	2.034	(s)	.013	2.447
<b>Total</b> .....	<b>.484</b>	<b>.030</b>	<b>3.834</b>	<b>20.140</b>	<b>5.231</b>	<b>25.371</b>	<b>.004</b>	<b>.154</b>	<b>29.877</b>
<b>2011</b> January .....	.025	.001	.380	1.689	.497	2.186	(s)	.015	2.607
February .....	.021	.002	.316	1.348	.387	1.735	(s)	.013	2.087
March .....	.038	.004	.322	1.682	.441	2.123	(s)	.014	2.501
April .....	.028	.001	.285	1.570	.479	2.050	(s)	.013	2.378
May .....	.033	.004	.277	1.674	.462	2.135	(s)	.017	2.466
June .....	.024	.004	.272	1.666	.424	2.090	.001	.015	2.407
July .....	.030	.003	.300	1.734	.404	2.138	.001	.021	2.493
August .....	.039	.005	.286	1.680	.364	2.044	.002	.019	2.395
September .....	.021	.003	.260	1.623	.365	1.988	.003	.014	2.288
October .....	.023	.002	.288	1.681	.337	2.018	.002	.013	2.345
November .....	.020	.002	.254	1.591	.388	1.979	.002	.012	2.269
December .....	.024	.004	.303	1.623	.383	2.006	.004	.015	2.354
<b>Total</b> .....	<b>.327</b>	<b>.035</b>	<b>3.542</b>	<b>19.561</b>	<b>4.930</b>	<b>24.491</b>	<b>.016</b>	<b>.178</b>	<b>28.590</b>
<b>2012</b> January .....	.020	.003	.288	1.596	.408	2.005	(s)	.014	2.330
February .....	.013	.002	<sup>R</sup> .276	1.491	.307	1.798	(s)	.012	2.102
March .....	.017	.004	<sup>R</sup> .272	1.633	.316	1.949	.002	.014	<sup>R</sup> 2.258
April .....	.016	.007	<sup>R</sup> .249	1.548	.339	1.887	.001	.017	<sup>R</sup> 2.177
May .....	.025	.004	.263	1.659	.381	2.040	.002	.019	2.352
<b>5-Month Total</b> .....	<b>.091</b>	<b>.020</b>	<b>1.348</b>	<b>7.927</b>	<b>1.751</b>	<b>9.678</b>	<b>.005</b>	<b>.077</b>	<b>11.218</b>
<b>2011 5-Month Total</b> .....	<b>.146</b>	<b>.012</b>	<b>1.581</b>	<b>7.963</b>	<b>2.266</b>	<b>10.229</b>	<b>.001</b>	<b>.071</b>	<b>12.039</b>
<b>2010 5-Month Total</b> .....	<b>.202</b>	<b>.015</b>	<b>1.664</b>	<b>8.320</b>	<b>2.155</b>	<b>10.475</b>	<b>.002</b>	<b>.072</b>	<b>12.430</b>

<sup>a</sup> Crude oil and lease condensate. Includes imports into the Strategic Petroleum Reserve, which began in 1977.

<sup>b</sup> Petroleum products, unfinished oils, pentanes plus, and gasoline blending components. Does not include biofuels.

<sup>c</sup> Fuel ethanol (minus denaturant) and biodiesel.

<sup>R</sup>=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See "Primary Energy" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all

available data beginning in 1973.

Sources: • **Coal:** Tables 6.1 and A5. • **Coal Coke: 1973-1975**—U.S. Department of the Interior, Bureau of Mines, *Minerals Yearbook*, "Coke and Coal Chemicals" chapter. **1976-1980**—U.S. Energy Information Administration (EIA), *Energy Data Report*, "Coke and Coal Chemicals," annual reports. **1981 forward**—EIA, *Quarterly Coal Report*, quarterly reports and Table A5. • **Natural Gas:** Tables 4.1 and A4. • **Crude Oil and Petroleum Products:** Tables 3.3b, 10.3, 10.4, and A2. • **Biofuels:** Tables 10.3, 10.4 and A3. • **Electricity:** Tables 7.1 and A6.

**Table 1.4b Primary Energy Exports by Source and Total Net Imports**  
(Quadrillion Btu)

	Exports									Net Imports <sup>a</sup>
	Coal	Coal Coke	Natural Gas	Petroleum			Biofuels <sup>d</sup>	Electricity	Total	
				Crude Oil <sup>b</sup>	Petroleum Products <sup>c</sup>	Total				
<b>1973 Total</b> .....	1.425	0.035	0.079	0.004	0.482	0.486	NA	0.009	2.033	12.580
<b>1975 Total</b> .....	1.761	.032	.074	.012	.427	.439	NA	.017	2.323	11.709
<b>1980 Total</b> .....	2.421	.051	.049	.609	.551	1.160	NA	.014	3.695	12.101
<b>1985 Total</b> .....	2.438	.028	.056	.432	1.225	1.657	NA	.017	4.196	7.584
<b>1990 Total</b> .....	2.772	.014	.087	.230	1.594	1.824	NA	.055	4.752	14.065
<b>1995 Total</b> .....	2.318	.034	.156	.200	1.791	1.991	NA	.012	4.511	17.750
<b>1996 Total</b> .....	2.368	.040	.155	.233	1.825	2.059	NA	.011	4.633	19.069
<b>1997 Total</b> .....	2.193	.031	.159	.228	1.872	2.100	NA	.031	4.514	20.701
<b>1998 Total</b> .....	2.092	.028	.161	.233	1.740	1.972	NA	.047	4.299	22.281
<b>1999 Total</b> .....	1.525	.022	.164	.250	1.705	1.955	NA	.049	3.715	23.537
<b>2000 Total</b> .....	1.528	.028	.245	.106	2.048	2.154	NA	.051	4.006	24.967
<b>2001 Total</b> .....	1.265	.033	.377	.043	1.996	2.039	(s)	.056	3.771	26.386
<b>2002 Total</b> .....	1.032	.020	.520	.019	2.023	2.042	(s)	.054	3.669	25.739
<b>2003 Total</b> .....	1.117	.018	.686	.026	2.124	2.151	.001	.082	4.054	27.007
<b>2004 Total</b> .....	1.253	.033	.862	.057	2.151	2.208	.001	.078	4.434	29.110
<b>2005 Total</b> .....	1.273	.043	.735	.067	2.374	2.442	.001	.065	4.560	30.149
<b>2006 Total</b> .....	1.264	.040	.730	.052	2.699	2.751	.004	.083	4.872	29.806
<b>2007 Total</b> .....	1.507	.036	.830	.058	2.949	3.007	.035	.069	5.482	29.221
<b>2008 Total</b> .....	2.071	.049	.972	.061	3.739	3.800	.086	.083	7.060	25.932
<b>2009 Total</b> .....	1.515	.032	1.082	.093	4.147	4.240	.034	.062	6.965	22.741
<b>2010</b>										
January .....	.151	.006	.094	.006	.327	.332	.003	.004	.590	1.926
February .....	.138	.001	.089	.009	.312	.321	.003	.003	.556	1.681
March .....	.169	(s)	.100	.008	.366	.374	.006	.004	.654	1.865
April .....	.189	.001	.077	.006	.404	.411	.005	.004	.686	1.894
May .....	.186	.003	.086	.007	.414	.420	.003	.006	.704	1.874
June .....	.190	.004	.091	.005	.385	.391	.003	.005	.684	1.872
July .....	.178	.003	.087	.012	.428	.440	.003	.005	.716	1.989
August .....	.180	.002	.085	.006	.415	.421	.004	.006	.698	1.929
September .....	.184	.003	.080	.011	.385	.396	.004	.008	.675	1.757
October .....	.170	.003	.097	.004	.429	.433	.004	.007	.714	1.676
November .....	.180	.006	.125	.006	.433	.439	.004	.006	.760	1.529
December .....	.186	.005	.136	.007	.452	.459	.007	.005	.797	1.650
<b>Total</b> .....	<b>2.101</b>	<b>.036</b>	<b>1.147</b>	<b>.088</b>	<b>4.750</b>	<b>4.838</b>	<b>.046</b>	<b>.065</b>	<b>8.234</b>	<b>21.643</b>
<b>2011</b>										
January .....	.218	.001	.137	.013	.451	.464	.006	.005	.832	1.776
February .....	.212	.002	.126	.005	.395	.400	.005	.005	.751	1.336
March .....	.252	.001	.146	.007	.450	.457	.008	.005	.869	1.631
April .....	.227	.001	.128	.007	.473	.480	.011	.005	.852	1.526
May .....	.232	.002	.133	.007	.448	.454	.007	.004	.832	1.634
June .....	.233	.003	.121	.006	.428	.434	.006	.004	.802	1.605
July .....	.202	.003	.114	.013	.485	.498	.011	.004	.833	1.660
August .....	.241	.001	.112	.006	.525	.531	.005	.003	.893	1.502
September .....	.224	.003	.128	.006	.518	.524	.010	.003	.891	1.397
October .....	.235	.002	.110	.009	.522	.531	.011	.003	.892	1.453
November .....	.226	.004	.129	.011	.513	.524	.013	.004	.900	1.369
December .....	.249	.001	.136	.010	.595	.604	.014	.003	1.008	1.347
<b>Total</b> .....	<b>2.751</b>	<b>.024</b>	<b>1.521</b>	<b>.100</b>	<b>5.801</b>	<b>5.901</b>	<b>.108</b>	<b>.051</b>	<b>10.356</b>	<b>18.234</b>
<b>2012</b>										
January .....	.234	.001	.132	.010	.478	.489	.008	.003	.866	1.464
February .....	.217	.002	.131	.010	.470	.480	.007	.003	R .840	R 1.262
March .....	.284	.002	R .143	.011	.516	.527	.008	.004	R .967	R 1.291
April .....	.321	.001	R .123	.006	.538	.544	.007	.004	R 1.001	R 1.176
May .....	.314	.003	.135	.012	.539	.552	.006	.004	1.015	1.337
<b>5-Month Total</b> .....	<b>1.370</b>	<b>.008</b>	<b>.664</b>	<b>.049</b>	<b>2.542</b>	<b>2.591</b>	<b>.036</b>	<b>.018</b>	<b>4.688</b>	<b>6.530</b>
<b>2011 5-Month Total</b> .....	<b>1.141</b>	<b>.007</b>	<b>.670</b>	<b>.038</b>	<b>2.216</b>	<b>2.255</b>	<b>.038</b>	<b>.026</b>	<b>4.137</b>	<b>7.902</b>
<b>2010 5-Month Total</b> .....	<b>.833</b>	<b>.010</b>	<b>.447</b>	<b>.036</b>	<b>1.822</b>	<b>1.859</b>	<b>.019</b>	<b>.022</b>	<b>3.189</b>	<b>9.241</b>

<sup>a</sup> Net imports equal imports minus exports.

<sup>b</sup> Crude oil and lease condensate.

<sup>c</sup> Petroleum products, unfinished oils, pentanes plus, and gasoline blending components. Does not include biofuels.

<sup>d</sup> Through 2010, data are for biodiesel only. Beginning in 2011, data are for fuel ethanol (minus denaturant) and biodiesel.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.


Notes: • See "Primary Energy" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available data beginning in 1973.


Sources: • **Coal:** Tables 6.1 and A5. • **Coal Coke: 1973-1975—U.S. Department of the Interior, Bureau of Mines, *Minerals Yearbook*, "Coke and Coal Chemicals" chapter. 1976-1980—U.S. Energy Information Administration (EIA), *Energy Data Report*, "Coke and Coal Chemicals," annual reports. 1981 forward—EIA, *Quarterly Coal Report*, quarterly reports and Table A5. • **Natural Gas:** Tables 4.1 and A4. • **Crude Oil and Petroleum Products:** Tables 3.3b, 10.4, and A2. • **Biofuels:** Tables 10.3, 10.4 and A3. • **Electricity:** Tables 7.1 and A6.**

**Figure 1.5 Merchandise Trade Value**  
(Billion Dollars<sup>a</sup>)


Imports and Exports, 1974-2011




Imports and Exports, Monthly



Trade Balance, 1974-2011



Trade Balance, Monthly



<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
<http://www.eia.gov/totalenergy/data/monthly/#summary>.  
Source: Table 1.5.

**Table 1.5 Merchandise Trade Value**  
(Million Dollars<sup>a</sup>)

	Petroleum <sup>b</sup>			Energy <sup>c</sup>			Non-Energy Balance	Total Merchandise		
	Exports	Imports	Balance	Exports	Imports	Balance		Exports	Imports	Balance
1974 Total .....	792	24,668	-23,876	3,444	25,454	-22,010	18,126	99,437	103,321	-3,884
1975 Total .....	907	25,197	-24,289	4,470	26,476	-22,006	31,557	108,856	99,305	9,551
1980 Total .....	2,833	78,637	-75,803	7,982	82,924	-74,942	55,246	225,566	245,262	-19,696
1985 Total .....	4,707	50,475	-45,768	9,971	53,917	-43,946	-73,765	218,815	336,526	-117,712
1990 Total .....	6,901	61,583	-54,682	12,233	64,661	-52,428	-50,068	393,592	496,088	-102,496
1995 Total .....	6,321	54,368	-48,047	10,358	59,109	-48,751	-110,050	584,742	743,543	-158,801
1996 Total .....	7,984	72,022	-64,038	12,181	78,086	-65,905	-104,309	625,075	795,289	-170,214
1997 Total .....	8,592	71,152	-62,560	12,682	78,277	-65,595	-114,927	689,182	869,704	-180,522
1998 Total .....	6,574	50,264	-43,690	10,251	57,323	-47,072	-182,686	682,138	911,896	-229,758
1999 Total .....	7,118	67,173	-60,055	9,880	75,803	-65,923	-262,898	695,797	1,024,618	-328,821
2000 Total .....	10,192	119,251	-109,059	13,179	135,367	-122,188	-313,916	781,918	1,218,022	-436,104
2001 Total .....	8,868	102,747	-93,879	12,494	121,923	-109,429	-302,470	729,100	1,140,999	-411,899
2002 Total .....	8,569	102,663	-94,094	11,541	115,748	-104,207	-364,056	693,103	1,161,366	-468,263
2003 Total .....	10,209	132,433	-122,224	13,768	153,298	-139,530	-392,820	724,771	1,257,121	-532,350
2004 Total .....	13,130	179,266	-166,136	18,642	206,660	-188,018	-462,912	818,775	1,469,704	-650,930
2005 Total .....	19,155	250,068	-230,913	26,488	289,723	-263,235	-504,242	905,978	1,673,455	-767,477
2006 Total .....	28,171	299,714	-271,543	34,711	332,500	-297,789	-519,515	1,036,635	1,853,938	-817,304
2007 Total .....	33,293	327,620	-294,327	41,725	364,987	-323,262	-485,501	1,148,199	1,956,962	-808,763
2008 Total .....	61,695	449,847	-388,152	76,075	491,885	-415,810	-400,389	1,287,442	2,103,641	-816,199
2009 Total .....	44,509	251,833	-207,324	54,536	271,739	-217,203	-286,379	1,056,043	1,559,625	-503,582
<b>2010</b> January .....	4,083	25,234	-21,151	5,236	28,075	-22,839	-21,285	92,601	136,725	-44,124
February .....	4,003	23,666	-19,663	5,115	26,018	-20,903	-19,141	93,854	133,898	-40,044
March .....	5,348	28,549	-23,201	6,667	30,613	-23,946	-23,271	110,511	157,728	-47,217
April .....	5,680	30,016	-24,336	6,970	31,657	-24,687	-26,034	102,443	153,163	-50,721
May .....	5,484	28,733	-23,249	6,887	30,369	-23,482	-27,165	105,477	156,124	-50,647
June .....	4,798	29,011	-24,213	6,170	30,698	-24,528	-36,592	107,202	168,321	-61,120
July .....	5,505	29,218	-23,713	6,760	31,113	-24,353	-35,451	104,057	163,861	-59,804
August .....	5,346	30,130	-24,784	6,744	31,907	-25,163	-38,957	106,846	170,966	-64,120
September .....	5,482	27,479	-21,997	6,802	28,992	-22,190	-37,244	107,644	167,078	-59,434
October .....	6,084	25,556	-19,472	7,318	27,056	-19,738	-33,397	117,104	170,239	-53,135
November .....	6,272	25,982	-19,710	7,610	27,363	-19,753	-35,966	113,046	168,765	-55,719
December .....	6,694	29,892	-23,198	8,182	31,107	-22,925	-25,888	117,480	166,293	-48,813
<b>Total .....</b>	<b>64,778</b>	<b>333,465</b>	<b>-268,687</b>	<b>80,460</b>	<b>354,968</b>	<b>-274,508</b>	<b>-360,389</b>	<b>1,278,263</b>	<b>1,913,160</b>	<b>-634,897</b>
<b>2011</b> January .....	7,446	33,050	-25,604	9,275	35,010	-25,735	-31,134	110,179	167,048	-56,869
February .....	6,604	27,551	-20,947	8,291	29,062	-20,771	-25,897	109,647	156,315	-46,668
March .....	7,841	37,096	-29,255	9,958	38,763	-28,805	-25,442	131,728	185,975	-54,247
April .....	9,016	36,457	-27,441	11,059	37,803	-26,744	-27,589	123,959	178,293	-54,333
May .....	8,767	41,002	-32,235	10,795	42,470	-31,675	-33,171	124,107	188,953	-64,846
June .....	8,032	40,872	-32,840	10,039	42,305	-32,266	-36,274	123,039	191,579	-68,540
July .....	9,069	38,622	-29,553	10,902	40,224	-29,322	-37,702	120,239	187,263	-67,024
August .....	9,912	39,063	-29,151	11,940	40,732	-28,792	-40,896	126,633	196,321	-69,688
September .....	9,202	36,467	-27,265	11,141	37,741	-26,600	-35,855	127,107	189,562	-62,455
October .....	9,573	33,467	-23,894	11,410	34,857	-23,447	-37,306	131,058	191,811	-60,753
November .....	9,533	35,665	-26,132	11,401	36,821	-25,420	-38,944	125,899	190,263	-64,364
December .....	10,501	36,831	-26,330	12,353	38,083	-25,730	-31,876	126,837	184,443	-57,606
<b>Total .....</b>	<b>105,499</b>	<b>436,145</b>	<b>-330,646</b>	<b>128,564</b>	<b>453,872</b>	<b>-325,308</b>	<b>-402,084</b>	<b>1,480,432</b>	<b>2,207,824</b>	<b>-727,392</b>
<b>2012</b> January .....	8,730	37,044	-28,314	10,606	38,290	-27,684	-37,519	118,209	183,411	-65,203
February .....	8,605	31,171	-22,566	10,124	32,250	-22,126	-26,181	123,428	171,735	-48,307
March .....	9,709	37,933	-28,224	11,552	38,937	-27,385	-29,974	139,965	197,324	-57,359
April .....	10,152	38,129	-27,977	12,057	39,043	-26,986	-35,179	127,411	189,577	-62,165
May .....	10,056	37,835	-27,779	11,858	38,829	-26,971	<sup>R</sup> -39,590	<sup>R</sup> 131,735	<sup>R</sup> 198,296	<sup>R</sup> -66,561
June .....	9,228	35,043	-25,815	11,100	35,910	-24,810	-34,147	132,871	191,828	-58,957
<b>6-Month Total .....</b>	<b>56,480</b>	<b>217,155</b>	<b>-160,675</b>	<b>67,297</b>	<b>223,259</b>	<b>-155,962</b>	<b>-202,590</b>	<b>773,619</b>	<b>1,132,171</b>	<b>-358,553</b>
<b>2011 6-Month Total .....</b>	<b>47,706</b>	<b>216,028</b>	<b>-168,322</b>	<b>59,417</b>	<b>225,413</b>	<b>-165,996</b>	<b>-179,507</b>	<b>722,659</b>	<b>1,068,161</b>	<b>-345,502</b>
<b>2010 6-Month Total .....</b>	<b>29,396</b>	<b>165,209</b>	<b>-135,813</b>	<b>37,045</b>	<b>177,430</b>	<b>-140,385</b>	<b>-153,488</b>	<b>612,087</b>	<b>905,960</b>	<b>-293,872</b>

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> Crude oil, petroleum preparations, liquefied propane and butane, and other mineral fuels.

<sup>c</sup> Petroleum, coal, natural gas, and electricity.

<sup>R</sup>=Revised.

Notes: • Monthly data are not adjusted for seasonal variations. • See Note, "Merchandise Trade Value," at end of section. • Totals may not equal sum of


components due to independent rounding. • The U.S. import statistics reflect both government and nongovernment imports of merchandise from foreign countries into the U.S. customs territory, which comprises the 50 States, the District of Columbia, Puerto Rico, and the Virgin Islands.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available data beginning in 1974.


Sources: See end of section.

**Figure 1.6 Cost of Fuels to End Users in Real (1982-1984) Dollars**


Costs, 1973-2011




Costs, May 2012




Residential Electricity,<sup>a</sup> Monthly




Motor Gasoline,<sup>a</sup> Monthly



Residential Heating Oil,<sup>b</sup> Monthly



Residential Natural Gas,<sup>a</sup> Monthly



<sup>a</sup> Includes taxes.

<sup>b</sup> Excludes taxes.

Note: See "Real Dollars" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.

Source: Table 1.6.



**Table 1.6 Cost of Fuels to End Users in Real (1982-1984) Dollars**

	Consumer Price Index, All Urban Consumers <sup>a</sup>	Motor Gasoline <sup>b</sup>		Residential Heating Oil <sup>c</sup>		Residential Natural Gas <sup>b</sup>		Residential Electricity <sup>b</sup>	
	Index 1982-1984=100	Dollars per Gallon	Dollars per Million Btu	Dollars per Gallon	Dollars per Million Btu	Dollars per Thousand Cubic Feet	Dollars per Million Btu	Cents per Kilowatt-hour	Dollars per Million Btu
<b>1973 Average</b> .....	<b>44.4</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>2.91</b>	<b>2.85</b>	<b>5.6</b>	<b>16.50</b>
<b>1975 Average</b> .....	<b>53.8</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>3.18</b>	<b>3.12</b>	<b>6.5</b>	<b>19.07</b>
<b>1980 Average</b> .....	<b>82.4</b>	<b>1.482</b>	<b>11.85</b>	<b>1.182</b>	<b>8.52</b>	<b>4.47</b>	<b>4.36</b>	<b>6.6</b>	<b>19.21</b>
<b>1985 Average</b> .....	<b>107.6</b>	<b>1.112</b>	<b>8.89</b>	<b>0.979</b>	<b>7.06</b>	<b>5.69</b>	<b>5.52</b>	<b>6.87</b>	<b>20.13</b>
<b>1990 Average</b> .....	<b>130.7</b>	<b>0.931</b>	<b>7.44</b>	<b>0.813</b>	<b>5.86</b>	<b>4.44</b>	<b>4.31</b>	<b>5.99</b>	<b>17.56</b>
<b>1995 Average</b> .....	<b>152.4</b>	<b>0.791</b>	<b>6.37</b>	<b>0.569</b>	<b>4.10</b>	<b>3.98</b>	<b>3.87</b>	<b>5.51</b>	<b>16.15</b>
<b>1996 Average</b> .....	<b>156.9</b>	<b>0.821</b>	<b>6.61</b>	<b>0.630</b>	<b>4.54</b>	<b>4.04</b>	<b>3.94</b>	<b>5.33</b>	<b>15.62</b>
<b>1997 Average</b> .....	<b>160.5</b>	<b>0.804</b>	<b>6.48</b>	<b>0.613</b>	<b>4.42</b>	<b>4.32</b>	<b>4.21</b>	<b>5.25</b>	<b>15.39</b>
<b>1998 Average</b> .....	<b>163.0</b>	<b>0.684</b>	<b>5.51</b>	<b>0.523</b>	<b>3.77</b>	<b>4.18</b>	<b>4.05</b>	<b>5.07</b>	<b>14.85</b>
<b>1999 Average</b> .....	<b>166.6</b>	<b>0.733</b>	<b>5.91</b>	<b>0.526</b>	<b>3.79</b>	<b>4.02</b>	<b>3.91</b>	<b>4.90</b>	<b>14.36</b>
<b>2000 Average</b> .....	<b>172.2</b>	<b>0.908</b>	<b>7.32</b>	<b>0.761</b>	<b>5.49</b>	<b>4.51</b>	<b>4.39</b>	<b>4.79</b>	<b>14.02</b>
<b>2001 Average</b> .....	<b>177.1</b>	<b>0.864</b>	<b>6.97</b>	<b>0.706</b>	<b>5.09</b>	<b>5.44</b>	<b>5.28</b>	<b>4.84</b>	<b>14.20</b>
<b>2002 Average</b> .....	<b>179.9</b>	<b>0.801</b>	<b>6.46</b>	<b>0.628</b>	<b>4.52</b>	<b>4.39</b>	<b>4.28</b>	<b>4.69</b>	<b>13.75</b>
<b>2003 Average</b> .....	<b>184.0</b>	<b>0.890</b>	<b>7.18</b>	<b>0.736</b>	<b>5.31</b>	<b>5.23</b>	<b>5.09</b>	<b>4.74</b>	<b>13.89</b>
<b>2004 Average</b> .....	<b>188.9</b>	<b>1.018</b>	<b>8.20</b>	<b>0.819</b>	<b>5.91</b>	<b>5.69</b>	<b>5.55</b>	<b>4.74</b>	<b>13.89</b>
<b>2005 Average</b> .....	<b>195.3</b>	<b>1.197</b>	<b>9.64</b>	<b>1.051</b>	<b>7.58</b>	<b>6.50</b>	<b>6.33</b>	<b>4.84</b>	<b>14.18</b>
<b>2006 Average</b> .....	<b>201.6</b>	<b>1.307</b>	<b>10.52</b>	<b>1.173</b>	<b>8.46</b>	<b>6.81</b>	<b>6.63</b>	<b>5.16</b>	<b>15.12</b>
<b>2007 Average</b> .....	<b>207.342</b>	<b>1.374</b>	<b>11.06</b>	<b>1.250</b>	<b>9.01</b>	<b>6.31</b>	<b>6.14</b>	<b>5.14</b>	<b>15.05</b>
<b>2008 Average</b> .....	<b>215.303</b>	<b>1.541</b>	<b>12.40</b>	<b>1.495</b>	<b>10.78</b>	<b>6.45</b>	<b>6.28</b>	<b>5.23</b>	<b>15.33</b>
<b>2009 Average</b> .....	<b>214.537</b>	<b>1.119</b>	<b>9.01</b>	<b>1.112</b>	<b>8.02</b>	<b>5.66</b>	<b>5.52</b>	<b>5.37</b>	<b>15.72</b>
<b>2010 January</b> .....	<b>216.687</b>	<b>1.282</b>	<b>10.32</b>	<b>1.275</b>	<b>9.19</b>	<b>4.87</b>	<b>4.76</b>	<b>4.84</b>	<b>14.19</b>
February .....	216.741	1.250	10.06	1.226	8.84	4.93	4.82	5.02	14.73
March .....	217.631	1.300	10.46	1.267	9.13	5.05	4.93	5.10	14.96
April .....	218.009	1.333	10.73	1.278	9.22	5.49	5.37	5.37	15.74
May .....	218.178	1.336	10.75	1.248	9.00	6.01	5.88	5.46	16.00
June .....	218.965	1.277	10.28	1.203	8.68	6.82	6.66	5.46	16.01
July .....	218.011	1.277	10.27	1.185	8.55	7.44	7.27	5.52	16.19
August .....	218.312	1.280	10.31	1.190	8.58	7.63	7.46	5.51	16.15
September .....	218.439	1.261	10.15	1.209	8.72	7.16	7.00	5.47	16.03
October .....	218.711	1.300	10.46	1.278	9.21	6.11	5.98	5.42	15.89
November .....	218.803	1.325	10.66	1.337	9.64	4.97	4.86	5.31	15.66
December .....	219.179	1.383	11.13	1.409	10.16	4.51	4.41	5.05	14.79
<b>Average</b> .....	<b>218.056</b>	<b>1.301</b>	<b>10.47</b>	<b>1.283</b>	<b>9.25</b>	<b>5.22</b>	<b>5.11</b>	<b>5.29</b>	<b>15.51</b>
<b>2011 January</b> .....	<b>220.223</b>	<b>1.425</b>	<b>11.47</b>	<b>1.476</b>	<b>10.64</b>	<b>4.45</b>	<b>4.35</b>	<b>4.97</b>	<b>14.57</b>
February .....	221.309	1.453	11.69	1.540	11.11	4.52	4.42	5.02	14.73
March .....	223.467	1.608	12.95	NA	NA	4.56	4.46	5.19	15.20
April .....	224.906	1.718	13.83	NA	NA	4.91	4.80	5.22	15.31
May .....	225.964	1.762	14.18	NA	NA	5.37	5.25	5.32	15.58
June .....	225.722	1.663	13.38	NA	NA	6.27	6.13	5.34	15.65
July .....	225.922	1.639	13.19	NA	NA	6.88	6.72	5.38	15.77
August .....	226.545	1.624	13.07	NA	NA	7.07	6.91	5.36	15.72
September .....	226.889	1.615	13.00	NA	NA	6.65	6.50	5.40	15.82
October .....	226.421	1.555	12.52	NA	NA	5.50	5.38	5.36	15.70
November .....	226.230	1.536	12.36	NA	NA	4.68	4.57	5.25	15.39
December .....	225.672	1.475	11.87	NA	NA	4.29	4.20	5.10	14.96
<b>Average</b> .....	<b>224.939</b>	<b>1.590</b>	<b>12.80</b>	<b>NA</b>	<b>NA</b>	<b>4.81</b>	<b>4.70</b>	<b>5.25</b>	<b>15.37</b>
<b>2012 January</b> .....	<b>226.665</b>	<b>1.521</b>	<b>12.24</b>	<b>NA</b>	<b>NA</b>	<b>4.21</b>	<b>4.12</b>	<b>5.04</b>	<b>14.78</b>
February .....	227.663	1.591	12.81	NA	NA	4.13	4.04	5.07	14.87
March .....	229.392	1.708	13.75	NA	NA	4.52	4.41	5.13	15.03
April .....	230.085	1.728	13.91	NA	NA	4.67	4.57	5.19	15.22
May .....	229.815	1.670	13.45	NA	NA	<sup>R</sup> 5.30	<sup>R</sup> 5.19	<sup>R</sup> 5.21	<sup>R</sup> 15.27
June .....	229.478	1.570	12.63	NA	NA	NA	NA	NA	NA
July .....	229.104	1.529	12.30	NA	NA	NA	NA	NA	NA

<sup>a</sup> Data are U.S. city averages for all items, and are not seasonally adjusted.

<sup>b</sup> Includes taxes.

<sup>c</sup> Excludes taxes.

R=Revised. NA=Not available.


Notes: • See "Real Dollars" in Glossary. • Fuel costs are calculated by using the Urban Consumer Price Index (CPI) developed by the Bureau of Labor Statistics. • Annual averages may not equal average of months due to independent rounding. • Geographic coverage is the 50 States and the District of

Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#summary> for all available data beginning in 1973.

Sources: • **Fuel Prices:** Tables 9.4 (All Types), 9.8c, 9.9, and 9.11, adjusted by the CPI. • **Consumer Price Index, All Urban Consumers:** U.S. Department of Labor, Bureau of Labor Statistics, series ID CUUR0000SA0. • **Conversion Factors:** Tables A1, A3, A4, and A6.

**Figure 1.7 Primary Energy Consumption per Real Dollar of Gross Domestic Product, 1973-2011**  
(Thousand Btu per Chained (2005) Dollar)



Note: See "Real Dollars" in Glossary.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.  
Source: Table 1.7.


**Table 1.7 Primary Energy Consumption per Real Dollar of Gross Domestic Product**

	Energy Consumption			Gross Domestic Product (GDP)	Energy Consumption per Real Dollar of GDP		
	Petroleum and Natural Gas	Other Energy <sup>a</sup>	Total		Petroleum and Natural Gas	Other Energy <sup>a</sup>	Total
	Quadrillion Btu				Billion Chained (2005) Dollars	Thousand Btu per Chained (2005) Dollar	
1973 Year .....	57.350	18.334	75.684	4,912.8	11.67	3.73	15.41
1974 Year .....	55.186	18.776	73.962	4,885.7	11.30	3.84	15.14
1975 Year .....	52.680	19.284	71.965	4,875.4	10.81	3.96	14.76
1976 Year .....	55.523	20.452	75.975	5,136.9	10.81	3.98	14.79
1977 Year .....	57.054	20.907	77.961	5,373.1	10.62	3.89	14.51
1978 Year .....	57.963	21.987	79.950	5,672.8	10.22	3.88	14.09
1979 Year .....	57.788	23.070	80.859	5,850.1	9.88	3.94	13.82
1980 Year .....	54.440	23.627	78.067	5,834.0	9.33	4.05	13.38
1981 Year .....	51.680	24.426	76.106	5,982.1	8.64	4.08	12.72
1982 Year .....	48.588	24.511	73.099	5,865.9	8.28	4.18	12.46
1983 Year .....	47.273	25.698	72.971	6,130.9	7.71	4.19	11.90
1984 Year .....	49.447	27.185	76.632	6,571.5	7.52	4.14	11.66
1985 Year .....	48.628	27.764	76.392	6,843.4	7.11	4.06	11.16
1986 Year .....	48.790	27.857	76.647	7,080.5	6.89	3.93	10.83
1987 Year .....	50.504	28.551	79.054	7,307.0	6.91	3.91	10.82
1988 Year .....	52.671	30.038	82.709	7,607.4	6.92	3.95	10.87
1989 Year .....	53.811	30.975	84.786	7,879.2	6.83	3.93	10.76
1990 Year .....	53.155	31.330	84.485	8,027.1	6.62	3.90	10.52
1991 Year .....	52.879	31.559	84.438	8,008.3	6.60	3.94	10.54
1992 Year .....	54.239	31.544	85.783	8,280.0	6.55	3.81	10.36
1993 Year .....	54.973	32.450	87.424	8,516.2	6.46	3.81	10.27
1994 Year .....	56.289	32.803	89.091	8,863.1	6.35	3.70	10.05
1995 Year .....	57.110	33.920	91.029	9,086.0	6.29	3.73	10.02
1996 Year .....	58.760	35.262	94.022	9,425.8	6.23	3.74	9.97
1997 Year .....	59.382	35.221	94.602	9,845.9	6.03	3.58	9.61
1998 Year .....	59.646	35.372	95.018	10,274.7	5.81	3.44	9.25
1999 Year .....	60.747	35.905	96.652	10,770.7	5.64	3.33	8.97
2000 Year .....	62.086	36.729	98.814	11,216.4	5.54	3.27	8.81
2001 Year .....	60.958	35.210	96.168	11,337.5	5.38	3.11	8.48
2002 Year .....	61.734	35.911	97.645	11,543.1	5.35	3.11	8.46
2003 Year .....	61.642	36.336	97.978	11,836.4	5.21	3.07	8.28
2004 Year .....	63.215	36.947	100.162	12,246.9	5.16	3.02	8.18
2005 Year .....	62.953	37.328	100.282	12,623.0	4.99	2.96	7.94
2006 Year .....	62.194	37.435	99.629	12,958.5	4.80	2.89	7.69
2007 Year .....	63.437	37.859	101.296	13,206.4	4.80	2.87	7.67
2008 Year .....	61.123	38.152	99.275	13,161.9	4.64	2.90	7.54
2009 Year .....	58.819	35.740	94.559	R 12,757.9	R 4.61	R 2.80	R 7.41
2010 Year .....	60.266	37.401	97.667	R 13,063.0	R 4.61	R 2.86	R 7.48
2011 Year .....	60.081	37.099	97.180	R 13,299.1	R 4.52	R 2.79	R 7.31

<sup>a</sup> Coal, coal coke net imports, nuclear electric power, renewable energy, and electricity net imports.  
R=Revised.  
Notes: • See "Primary Energy Consumption" and "Real Dollars" in Glossary.  
• Totals may not equal sum of components due to independent rounding.  
• Geographic coverage is the 50 States and the District of

Columbia.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.  
Sources: • **Energy Consumption:** Table 1.3. • **Gross Domestic Product:** U.S. Department of Commerce, Bureau of Economic Analysis, National Income and Product Accounts (July 27, 2012), Table 1.1.6.

**Figure 1.8 Motor Vehicle Fuel Economy, 1973-2008**  
(Miles per Gallon)



<sup>a</sup> Motorcycles are included through 1989.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.  
Source: Table 1.8.

**Table 1.8 Motor Vehicle Mileage, Fuel Consumption, and Fuel Economy**

	Passenger Cars <sup>a</sup>			Vans, Pickup Trucks, and Sport Utility Vehicles <sup>b</sup>			Heavy-Duty Trucks <sup>c</sup>			All Motor Vehicles <sup>d</sup>		
	Mileage (miles per vehicle)	Fuel Consumption (gallons per vehicle)	Fuel Economy (miles per gallon)	Mileage (miles per vehicle)	Fuel Consumption (gallons per vehicle)	Fuel Economy (miles per gallon)	Mileage (miles per vehicle)	Fuel Consumption (gallons per vehicle)	Fuel Economy (miles per gallon)	Mileage (miles per vehicle)	Fuel Consumption (gallons per vehicle)	Fuel Economy (miles per gallon)
1973	9,884	737	13.4	9,779	931	10.5	15,370	2,775	5.5	10,099	850	11.9
1974	9,221	677	13.6	9,452	862	11.0	14,995	2,708	5.5	9,493	788	12.0
1975	9,309	665	14.0	9,829	934	10.5	15,167	2,722	5.6	9,627	790	12.2
1976	9,418	681	13.8	10,127	934	10.8	15,438	2,764	5.6	9,774	806	12.1
1977	9,517	676	14.1	10,607	947	11.2	16,700	3,002	5.6	9,978	814	12.3
1978	9,500	665	14.3	10,968	948	11.6	18,045	3,263	5.5	10,077	816	12.4
1979	9,062	620	14.6	10,802	905	11.9	18,502	3,380	5.5	9,722	776	12.5
1980	8,813	551	16.0	10,437	854	12.2	18,736	3,447	5.4	9,458	712	13.3
1981	8,873	538	16.5	10,244	819	12.5	19,016	3,565	5.3	9,477	697	13.6
1982	9,050	535	16.9	10,276	762	13.5	19,931	3,647	5.5	9,644	686	14.1
1983	9,118	534	17.1	10,497	767	13.7	21,083	3,769	5.6	9,760	686	14.2
1984	9,248	530	17.4	11,151	797	14.0	22,550	3,967	5.7	10,017	691	14.5
1985	9,419	538	17.5	10,506	735	14.3	20,597	3,570	5.8	10,020	685	14.6
1986	9,464	543	17.4	10,764	738	14.6	22,143	3,821	5.8	10,143	692	14.7
1987	9,720	539	18.0	11,114	744	14.9	23,349	3,937	5.9	10,453	694	15.1
1988	9,972	531	18.8	11,465	745	15.4	22,485	3,736	6.0	10,721	688	15.6
1989	<sup>a</sup> 10,157	<sup>a</sup> 533	<sup>a</sup> 19.0	11,676	724	16.1	22,926	3,776	6.1	10,932	688	15.9
1990	10,504	520	20.2	11,902	738	16.1	23,603	3,953	6.0	11,107	677	16.4
1991	10,571	501	21.1	12,245	721	17.0	24,229	4,047	6.0	11,294	669	16.9
1992	10,857	517	21.0	12,381	717	17.3	25,373	4,210	6.0	11,558	683	16.9
1993	10,804	527	20.5	12,430	714	17.4	26,262	4,309	6.1	11,595	693	16.7
1994	10,992	531	20.7	12,156	701	17.3	25,838	4,202	6.1	11,683	698	16.7
1995	11,203	530	21.1	12,018	694	17.3	26,514	4,315	6.1	11,793	700	16.8
1996	11,330	534	21.2	11,811	685	17.2	26,092	4,221	6.2	11,813	700	16.9
1997	11,581	539	21.5	12,115	703	17.2	27,032	4,218	6.4	12,107	711	17.0
1998	11,754	544	21.6	12,173	707	17.2	25,397	4,135	6.1	12,211	721	16.9
1999	11,848	553	21.4	11,957	701	17.0	26,014	4,352	6.0	12,206	732	16.7
2000	11,976	547	21.9	11,672	669	17.4	25,617	4,391	5.8	12,164	720	16.9
2001	11,831	534	22.1	11,204	636	17.6	26,602	4,477	5.9	11,887	695	17.1
2002	12,202	555	22.0	11,364	650	17.5	27,071	4,642	5.8	12,171	719	16.9
2003	12,325	556	22.2	11,287	697	16.2	28,093	4,215	6.7	12,208	718	17.0
2004	12,460	553	22.5	11,184	690	16.2	27,023	4,057	6.7	12,200	714	17.1
2005	12,510	567	22.1	10,920	617	17.7	26,235	4,385	6.0	12,082	706	17.1
2006	12,485	554	22.5	10,920	612	17.8	25,231	4,304	5.9	12,017	698	17.2
2007	12,304	547	22.5	10,962	609	18.0	25,152	4,275	5.9	11,920	693	17.2
2008 <sup>P</sup>	11,788	522	22.6	10,951	605	18.1	25,254	4,075	6.2	11,619	667	17.4

<sup>a</sup> Through 1989, includes motorcycles.  
<sup>b</sup> Includes a small number of trucks with 2 axles and 4 tires, such as step vans.  
<sup>c</sup> Single-unit trucks with 2 axles and 6 or more tires, and combination trucks.  
<sup>d</sup> Includes buses and motorcycles, which are not shown separately.  
P=Preliminary.  
Note: Geographic coverage is the 50 States and the District of Columbia.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#summary>.  
Sources: • **Passenger Cars, 1990-1994:** U.S. Department of Transportation, Bureau of Transportation Statistics, *National Transportation Statistics 1998*, Table 4-13. • **All Other Data:** • **1973-1994**—Federal Highway Administration (FHWA), *Highway Statistics Summary to 1995*, Table VM-201A. • **1995 forward**—FHWA, *Highway Statistics*, annual reports, Table VM-1.

**Table 1.9 Heating Degree-Days by Census Division**

Census Divisions	July				
	Normal <sup>a</sup>	2011	2012	Percent Change	
				Normal to 2012	2011 to 2012
<b>New England</b> Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, Vermont .....	11	4	5	NM	NM
<b>Middle Atlantic</b> New Jersey, New York, Pennsylvania .....	6	0	1	NM	NM
<b>East North Central</b> Illinois, Indiana, Michigan, Ohio, Wisconsin .....	9	1	0	NM	NM
<b>West North Central</b> Iowa, Kansas, Minnesota, Missouri, Nebraska, North Dakota, South Dakota .....	15	2	1	NM	NM
<b>South Atlantic</b> Delaware, Florida, Georgia, Maryland and the District of Columbia, North Carolina, South Carolina, Virginia, West Virginia .....	0	0	0	NM	NM
<b>East South Central</b> Alabama, Kentucky, Mississippi, Tennessee .....	0	0	0	NM	NM
<b>West South Central</b> Arkansas, Louisiana, Oklahoma, Texas .....	0	0	0	NM	NM
<b>Mountain</b> Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Utah, Wyoming .....	19	1	0	NM	NM
<b>Pacific<sup>b</sup></b> California, Oregon, Washington .....	24	21	11	NM	NM
<b>U.S. Average<sup>b</sup></b> .....	<b>9</b>	<b>4</b>	<b>2</b>	<b>NM</b>	<b>NM</b>

<sup>a</sup> "Normal" is based on calculations of data from 1971 through 2000.

<sup>b</sup> Excludes Alaska and Hawaii.

NM=Not meaningful (because "Normal" is less than 100 or ratio is incalculable).

Notes: Degree-days are relative measurements of outdoor air temperature used as an index for heating and cooling energy requirements. Heating degree-days are the number of degrees that the daily average temperature falls below 65° F. Cooling degree-days are the number of degrees that the daily average temperature rises above 65° F. The daily average temperature is the mean of the maximum and minimum temperatures in a 24-hour period. For example, a weather station recording an average daily temperature of 40° F would report 25 heating degree-days for that day (and 0 cooling degree-days). If a weather station recorded an average daily temperature of 78° F, cooling degree-days for that station would be 13 (and 0 heating degree days).

Web Pages: • See <http://www.eia.gov/totalenergy/data/monthly/#summary>

for current data. • See <http://www.eia.gov/totalenergy/data/annual/#summary> for historical data.

Sources: There are several degree-day databases maintained by the National Oceanic and Atmospheric Administration. The information published here is developed by the National Weather Service Climate Prediction Center, Camp Springs, MD. The data are available weekly with monthly summaries and are based on mean daily temperatures recorded at about 200 major weather stations around the country. The temperature information recorded at those weather stations is used to calculate statewide degree-day averages based on population. The State figures are then aggregated into Census Divisions and into the national average. The population weights currently used represent resident State population data estimated for the 2000 Census by the U.S. Department of Commerce, Bureau of the Census. The data provided here are available sooner than the Historical Climatology Series 5-1 (heating degree-days) developed by the National Climatic Data Center, Asheville, NC, which compiles data from some 8,000 weather stations.

**Table 1.10 Cooling Degree-Days by Census Division**

Census Divisions	July					Cumulative January through July				
	Normal <sup>a</sup>	2011	2012	Percent Change		Normal <sup>a</sup>	2011	2012	Percent Change	
				Normal to 2012	2011 to 2012				Normal to 2012	2011 to 2012
<b>New England</b> Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, Vermont .....	180	255	247	37	-3	249	376	366	47	-3
<b>Middle Atlantic</b> New Jersey, New York, Pennsylvania .....	247	352	349	41	-1	387	581	561	45	-3
<b>East North Central</b> Illinois, Indiana, Michigan, Ohio, Wisconsin .....	245	385	414	69	8	443	626	725	64	16
<b>West North Central</b> Iowa, Kansas, Minnesota, Missouri, Nebraska, North Dakota, South Dakota .....	308	437	470	53	8	574	749	863	50	15
<b>South Atlantic</b> Delaware, Florida, Georgia, Maryland and the District of Columbia, North Carolina, South Carolina, Virginia, West Virginia .....	425	509	499	17	-2	1,105	1,413	1,329	20	-6
<b>East South Central</b> Alabama, Kentucky, Mississippi, Tennessee .....	412	494	500	21	1	901	1,175	1,166	29	-1
<b>West South Central</b> Arkansas, Louisiana, Oklahoma, Texas .....	545	677	595	9	-12	1,404	1,904	1,754	25	-8
<b>Mountain</b> Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Utah, Wyoming .....	341	374	387	13	3	715	718	867	21	21
<b>Pacific<sup>b</sup></b> California, Oregon, Washington .....	188	203	207	10	2	344	281	327	-5	16
<b>U.S. Average<sup>b</sup></b> .....	<b>321</b>	<b>411</b>	<b>408</b>	<b>27</b>	<b>-1</b>	<b>697</b>	<b>892</b>	<b>896</b>	<b>29</b>	(s)

<sup>a</sup> "Normal" is based on calculations of data from 1971 through 2000.

<sup>b</sup> Excludes Alaska and Hawaii.

(s)=Less than 0.5 percent and greater than -0.5 percent.

Notes: Degree-days are relative measurements of outdoor air temperature used as an index for heating and cooling energy requirements. Cooling degree-days are the number of degrees that the daily average temperature rises above 65° F. Heating degree-days are the number of degrees that the daily average temperature falls below 65° F. The daily average temperature is the mean of the maximum and minimum temperatures in a 24-hour period. For example, if a weather station recorded an average daily temperature of 78° F, cooling degree-days for that station would be 13 (and 0 heating degree-days). A weather station recording an average daily temperature of 40° F would report 25 heating degree-days for that day (and 0 cooling degree-days).

Web Pages: • See <http://www.eia.gov/totalenergy/data/monthly/#summary> for current data. • See <http://www.eia.gov/totalenergy/data/annual/#summary>

for historical data.

Sources: There are several degree-day databases maintained by the National Oceanic and Atmospheric Administration. The information published here is developed by the National Weather Service Climate Prediction Center, Camp Springs, MD. The data are available weekly with monthly summaries and are based on mean daily temperatures recorded at about 200 major weather stations around the country. The temperature information recorded at those weather stations is used to calculate statewide degree-day averages based on population. The State figures are then aggregated into Census Divisions and into the national average. The population weights currently used represent resident State population data estimated for the 2000 Census by the U.S. Department of Commerce, Bureau of the Census. The data provided here are available sooner than the Historical Climatology Series 5-2 (cooling degree-days) developed by the National Climatic Data Center, Asheville, NC, which compiles data from some 8,000 weather stations.

## Energy Overview

**Note. Merchandise Trade Value.** Imports data presented are based on the customs values. Those values do not include insurance and freight and are consequently lower than the cost, insurance, and freight (CIF) values, which are also reported by the Bureau of the Census. All exports data, and imports data prior to 1981, are on a free alongside ship (f.a.s.) basis.

“Balance” is exports minus imports; a positive balance indicates a surplus trade value and a negative balance indicates a deficit trade value. “Energy” includes mineral fuels, lubricants, and related material. “Non-Energy Balance” and “Total Merchandise” include foreign exports (i.e., re-exports) and nonmonetary gold and U.S. Department of Defense Grant-Aid shipments. The “Non-Energy Balance” is calculated by subtracting the “Energy” from the “Total Merchandise Balance.”

“Imports” consist of government and nongovernment shipments of merchandise into the 50 States, the District of Columbia, Puerto Rico, the U.S. Virgin Islands, and the U.S. Foreign Trade Zones. They reflect the total arrival from foreign countries of merchandise that immediately entered consumption channels, warehouses, the Foreign Trade Zones, or the Strategic Petroleum Reserve. They exclude shipments between the United States, Puerto Rico, and U.S. possessions, shipments to U.S. Armed Forces and diplomatic missions abroad for their own use, U.S. goods returned to the United States by its Armed Forces, and in-transit shipments.

### Table 1.5 Sources

U.S. Department of Commerce, Bureau of the Census, Foreign Trade Division:

#### Petroleum Exports

1974–1987: “U.S. Exports,” FT-410, December issues.  
1988 and 1989: “Report on U.S. Merchandise Trade,” Final Revisions.  
1990–1992: “U.S. Merchandise Trade,” Final Report.  
1993–2007: “U.S. International Trade in Goods and Services,” Annual Revision.

2008 forward: “U.S. International Trade in Goods and Services,” FT-900, monthly.

#### Petroleum Imports

1974–1987: “U.S. Merchandise Trade,” FT-900, December issues, 1975-1988.  
1988 and 1989: “Report on U.S. Merchandise Trade,” Final Revisions.  
1990–1993: “U.S. Merchandise Trade,” Final Report.  
1994–2007: “U.S. International Trade in Goods and Services,” Annual Revision.  
2008 forward: “U.S. International Trade in Goods and Services,” FT-900, monthly.

#### Energy Exports and Imports

1974–1987: U.S. merchandise trade press releases and database printouts for adjustments.  
1988: January–July, monthly FT-900 supplement, 1989 issues. August–December, monthly FT-900, 1989 issues.  
1989: Monthly FT-900, 1990 issues.  
1990–1992: “U.S. Merchandise Trade,” Final Report.  
1993–2007: “U.S. International Trade in Goods and Services,” Annual Revision.  
2008 forward: “U.S. International Trade in Goods and Services,” FT-900, monthly.

#### Petroleum, Energy, and Non-Energy Balances

Calculated by the U.S. Energy Information Administration.

#### Total Merchandise


1974–1987: U.S. merchandise trade press releases and database printouts for adjustments.  
1988: “Report on U.S. Merchandise Trade, 1988 Final Revisions,” August 18, 1989.  
1989: “Report on U.S. Merchandise Trade, 1989 Revisions,” July 10, 1990.  
1990: “U.S. Merchandise Trade, 1990 Final Report,” May 10, 1991, and “U.S. Merchandise Trade, December 1992,” February 18, 1993, page 3.  
1991: “U.S. Merchandise Trade, 1992 Final Report,” May 12, 1993.  
1992–2007: “U.S. International Trade in Goods and Services,” Annual Revision.  
2008 forward: “U.S. International Trade in Goods and Services,” FT-900, monthly.

## **2. Energy Consumption by Sector**


---

**Figure 2.1 Energy Consumption by Sector**  
(Quadrillion Btu)


Total Consumption by End-Use Sector, 1973-2011



Total Consumption by End-Use Sector, Monthly



By Sector, May 2012



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.  
Source: Table 2.1.



**Table 2.1 Energy Consumption by Sector**  
(Trillion Btu)

	End-Use Sectors								Electric Power Sector <sup>c,d</sup>	Balancing Item <sup>g</sup>	Primary Total <sup>h</sup>
	Residential		Commercial <sup>a</sup>		Industrial <sup>b</sup>		Transportation				
	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>	Primary <sup>e</sup>	Total <sup>f</sup>			
<b>1973 Total</b> .....	8,225	14,897	4,423	9,543	24,720	32,623	18,577	18,613	19,731	7	75,684
<b>1975 Total</b> .....	7,990	14,813	4,059	9,492	21,434	29,413	18,210	18,245	20,270	1	71,965
<b>1980 Total</b> .....	7,439	15,753	4,105	10,578	22,595	32,039	19,659	19,697	24,269	-1	78,067
<b>1985 Total</b> .....	7,148	16,041	3,732	11,451	19,443	28,816	20,041	20,088	26,032	-4	76,392
<b>1990 Total</b> .....	6,557	16,945	3,896	13,320	21,180	31,810	22,366	22,420	30,495	-9	84,485
<b>1995 Total</b> .....	6,936	18,519	4,101	14,690	22,719	33,971	23,791	23,846	33,479	3	91,029
<b>1996 Total</b> .....	7,467	19,504	4,273	15,172	23,410	34,904	24,383	24,437	34,485	4	94,022
<b>1997 Total</b> .....	7,033	18,965	4,295	15,681	23,686	35,200	24,695	24,750	34,886	6	94,602
<b>1998 Total</b> .....	6,413	18,955	4,005	15,968	23,177	34,843	25,201	25,256	36,225	-3	95,018
<b>1999 Total</b> .....	6,775	19,557	4,053	16,376	22,950	34,764	25,891	25,949	36,976	6	96,652
<b>2000 Total</b> .....	7,159	20,425	4,278	17,175	22,824	34,664	26,489	26,548	38,062	2	98,814
<b>2001 Total</b> .....	6,868	20,042	4,084	17,137	21,794	32,720	26,213	26,275	37,215	-6	96,168
<b>2002 Total</b> .....	6,912	20,791	4,132	17,345	21,799	32,662	26,781	26,842	38,016	5	97,645
<b>2003 Total</b> .....	7,211	21,110	4,283	17,343	21,503	32,532	26,920	26,994	38,062	-1	97,978
<b>2004 Total</b> .....	6,993	21,093	4,232	17,659	22,412	33,520	27,817	27,895	38,713	-6	100,162
<b>2005 Total</b> .....	6,909	21,626	4,051	17,857	21,411	32,446	28,272	28,353	39,638	(s)	100,282
<b>2006 Total</b> .....	6,168	20,688	3,747	17,711	21,536	32,401	28,751	28,830	39,428	(s)	99,629
<b>2007 Total</b> .....	6,598	21,531	3,922	18,255	21,370	32,394	29,029	29,117	40,377	-1	101,296
<b>2008 Total</b> .....	6,817	21,596	4,073	18,381	20,480	31,290	27,925	28,008	39,978	(s)	99,275
<b>2009 Total</b> .....	6,619	21,064	4,061	17,899	18,813	28,525	26,989	27,071	38,077	(s)	94,559
<b>2010 January</b> .....	1,142	2,691	617	1,752	1,695	2,487	2,190	2,198	3,484	4	9,132
February .....	985	2,250	548	1,585	1,601	2,365	2,004	2,012	3,073	1	8,213
March .....	737	1,887	419	1,465	1,752	2,557	2,290	2,297	3,008	-1	8,205
April .....	439	1,347	277	1,307	1,624	2,435	2,280	2,286	2,755	-2	7,372
May .....	328	1,386	226	1,410	1,612	2,527	2,349	2,356	3,163	(s)	7,678
June .....	268	1,659	198	1,501	1,608	2,517	2,320	2,328	3,611	2	8,008
July .....	240	1,889	182	1,546	1,618	2,532	2,404	2,411	3,934	4	8,383
August .....	232	1,855	186	1,547	1,707	2,633	2,399	2,406	3,917	4	8,445
September .....	237	1,494	189	1,390	1,671	2,512	2,291	2,298	3,306	(s)	7,694
October .....	343	1,331	256	1,364	1,644	2,482	2,327	2,333	2,942	-1	7,509
November .....	599	1,597	364	1,451	1,671	2,523	2,221	2,228	2,944	-1	7,797
December .....	1,054	2,476	579	1,761	1,802	2,679	2,307	2,314	3,488	1	9,231
<b>Total</b> .....	<b>6,603</b>	<b>21,862</b>	<b>4,039</b>	<b>18,078</b>	<b>20,003</b>	<b>30,250</b>	<b>27,384</b>	<b>27,466</b>	<b>39,626</b>	<b>11</b>	<b>97,667</b>
<b>2011 January</b> .....	1,174	2,692	636	1,766	1,837	2,665	2,220	2,227	3,483	1	9,351
February .....	953	2,179	531	1,540	1,600	2,364	2,042	2,049	3,006	-1	8,131
March .....	774	1,886	448	1,544	1,787	2,642	2,297	2,304	3,070	-3	8,373
April .....	480	1,478	298	1,359	1,622	2,462	2,242	2,249	2,905	-2	7,545
May .....	329	1,396	221	1,387	1,633	2,515	2,306	2,312	3,121	-1	7,609
June .....	261	1,621	193	1,462	1,639	2,533	2,308	2,315	3,530	1	7,932
July .....	239	1,925	185	1,569	1,616	2,552	2,316	2,323	4,012	5	8,373
August .....	250	1,863	202	1,548	1,695	2,614	2,349	2,356	3,885	3	8,384
September .....	263	1,488	211	1,382	1,629	2,459	2,232	2,238	3,232	-1	7,567
October .....	382	1,364	293	1,411	1,675	2,536	2,257	2,264	2,967	-2	7,573
November .....	594	1,589	367	1,434	1,699	2,549	2,175	2,181	2,919	-3	7,751
December .....	885	2,132	504	1,621	1,736	2,581	2,253	2,260	3,215	-3	8,592
<b>Total</b> .....	<b>6,583</b>	<b>21,616</b>	<b>4,089</b>	<b>18,020</b>	<b>20,169</b>	<b>30,471</b>	<b>26,998</b>	<b>27,078</b>	<b>39,346</b>	<b>-5</b>	<b>97,180</b>
<b>2012 January</b> .....	1,008	2,323	R 559	1,652	R 1,778	R 2,596	R 2,124	R 2,131	3,232	-2	R 8,699
February .....	848	1,954	484	1,499	R 1,687	R 2,484	2,077	R 2,084	2,924	-3	R 8,017
March .....	R 574	R 1,598	R 347	R 1,396	R 1,653	R 2,484	R 2,231	R 2,238	2,911	-5	R 7,710
April .....	R 424	R 1,332	R 280	R 1,314	R 1,612	R 2,438	R 2,209	R 2,215	2,775	-7	R 7,292
May .....	309	1,394	218	1,403	1,657	2,568	2,308	2,314	3,188	-4	7,675
<b>5-Month Total</b> .....	<b>3,163</b>	<b>8,600</b>	<b>1,888</b>	<b>7,265</b>	<b>8,386</b>	<b>12,569</b>	<b>10,949</b>	<b>10,982</b>	<b>15,029</b>	<b>-22</b>	<b>39,394</b>
<b>2011 5-Month Total</b> .....	<b>3,709</b>	<b>9,630</b>	<b>2,134</b>	<b>7,596</b>	<b>8,480</b>	<b>12,648</b>	<b>11,107</b>	<b>11,141</b>	<b>15,585</b>	<b>-6</b>	<b>41,009</b>
<b>2010 5-Month Total</b> .....	<b>3,632</b>	<b>9,561</b>	<b>2,086</b>	<b>7,518</b>	<b>8,283</b>	<b>12,371</b>	<b>11,113</b>	<b>11,148</b>	<b>15,484</b>	<b>2</b>	<b>40,600</b>

<sup>a</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>d</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

<sup>e</sup> See "Primary Energy Consumption" in Glossary.

<sup>f</sup> Total energy consumption in the end-use sectors consists of primary energy consumption, electricity retail sales, and electrical system energy losses. See Note 2, "Electrical System Energy Losses," at end of section.

<sup>g</sup> A balancing item. The sum of primary consumption in the five energy-use sectors equals the sum of total consumption in the four end-use sectors. However, total energy consumption does not equal the sum of the sectoral components due to the use of sector-specific conversion factors for coal and natural gas.

<sup>h</sup> Primary energy consumption total. See Table 1.3.

R=Revised. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.


Notes: • See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 1, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> for all available data beginning in 1973.


Sources: Tables 1.3 and 2.2–2.6.

**Figure 2.2 Residential Sector Energy Consumption**  
(Quadrillion Btu)


By Major Source, 1973-2011




By Major Source, Monthly



Total, January-May



By Major Source, May 2012



<sup>a</sup> Electricity retail sales.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.  
Source: Table 2.2.

**Table 2.2 Residential Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>									Electricity Retail Sales <sup>d</sup>	Electrical System Energy Losses <sup>e</sup>	Total
	Fossil Fuels				Renewable Energy <sup>b</sup>				Total Primary			
	Coal	Natural Gas <sup>c</sup>	Petroleum	Total	Geo-thermal	Solar/PV	Bio-mass	Total				
<b>1973 Total</b> .....	94	4,977	2,800	7,871	NA	NA	354	354	8,225	1,976	4,696	14,897
<b>1975 Total</b> .....	63	5,023	2,479	7,564	NA	NA	425	425	7,990	2,007	4,817	14,813
<b>1980 Total</b> .....	31	4,825	1,734	6,589	NA	NA	850	850	7,439	2,448	5,866	15,753
<b>1985 Total</b> .....	39	4,534	1,565	6,138	NA	NA	1,010	1,010	7,148	2,709	6,184	16,041
<b>1990 Total</b> .....	31	4,491	1,394	5,916	6	56	580	641	6,557	3,153	7,235	16,945
<b>1995 Total</b> .....	17	4,954	1,374	6,345	7	64	520	591	6,936	3,557	8,026	18,519
<b>1996 Total</b> .....	17	5,354	1,484	6,854	7	65	540	612	7,467	3,694	8,344	19,504
<b>1997 Total</b> .....	16	5,093	1,422	6,531	8	64	430	502	7,033	3,671	8,261	18,965
<b>1998 Total</b> .....	12	4,646	1,304	5,962	8	64	380	452	6,413	3,856	8,686	18,955
<b>1999 Total</b> .....	14	4,835	1,465	6,314	9	63	390	461	6,775	3,906	8,875	19,557
<b>2000 Total</b> .....	11	5,105	1,554	6,670	9	61	420	489	7,159	4,069	9,197	20,425
<b>2001 Total</b> .....	12	4,889	1,529	6,430	9	59	370	438	6,868	4,100	9,074	20,042
<b>2002 Total</b> .....	12	4,995	1,457	6,464	10	57	380	448	6,912	4,317	9,562	20,791
<b>2003 Total</b> .....	12	5,209	1,519	6,741	13	57	400	470	7,211	4,353	9,546	21,110
<b>2004 Total</b> .....	11	4,981	1,520	6,513	14	57	410	481	6,993	4,408	9,691	21,093
<b>2005 Total</b> .....	8	4,946	1,451	6,406	16	58	430	504	6,909	4,638	10,079	21,626
<b>2006 Total</b> .....	6	4,476	1,224	5,706	18	63	380	462	6,168	4,611	9,909	20,688
<b>2007 Total</b> .....	8	4,835	1,254	6,097	22	70	410	502	6,598	4,750	10,182	21,531
<b>2008 Total</b> .....	8	5,010	1,243	6,261	26	80	450	557	6,817	4,708	10,071	21,596
<b>2009 Total</b> .....	8	4,883	1,176	6,067	33	89	430	552	6,619	4,656	9,789	21,064
<b>2010 January</b> .....	1	953	140	1,094	3	10	36	48	1,142	503	1,045	2,691
February .....	1	812	128	941	3	9	32	44	985	419	846	2,250
March .....	1	592	96	689	3	10	36	48	737	381	768	1,887
April .....	(s)	320	72	392	3	9	35	47	439	300	608	1,347
May .....	(s)	201	78	280	3	10	36	48	328	324	734	1,386
June .....	1	137	83	221	3	9	35	47	268	435	956	1,659
July .....	1	114	78	192	3	10	36	48	240	528	1,121	1,889
August .....	1	109	74	183	3	10	36	48	232	526	1,098	1,855
September .....	(s)	120	70	190	3	9	35	47	237	425	832	1,494
October .....	1	206	88	294	3	10	36	48	343	330	658	1,331
November .....	1	456	96	552	3	9	35	47	599	318	680	1,597
December .....	1	865	140	1,006	3	10	36	48	1,054	444	978	2,476
<b>Total</b> .....	7	4,883	1,142	6,032	37	114	420	571	6,603	4,933	10,326	21,862
<b>2011 January</b> .....	1	993	129	1,122	3	12	37	52	1,174	494	1,023	2,692
February .....	1	787	118	906	3	11	33	47	953	412	814	2,179
March .....	1	619	102	722	3	12	37	52	774	358	754	1,886
April .....	(s)	356	73	430	3	12	35	50	480	321	677	1,478
May .....	(s)	212	64	277	3	12	37	52	329	334	733	1,396
June .....	(s)	136	74	211	3	12	35	50	261	430	931	1,621
July .....	(s)	114	73	187	3	12	37	52	239	528	1,158	1,925
August .....	(s)	112	86	198	3	12	37	52	250	524	1,089	1,863
September .....	(s)	124	89	213	3	12	35	50	263	419	806	1,488
October .....	(s)	234	96	330	3	12	37	52	382	323	659	1,364
November .....	(s)	439	104	544	3	12	35	50	594	318	678	1,589
December .....	(s)	702	131	834	3	12	37	52	885	396	851	2,132
<b>Total</b> .....	6	4,828	1,139	5,973	40	140	430	610	6,583	4,858	10,176	21,616
<b>2012 January</b> .....	1	818	135	954	3	14	36	54	1,008	432	884	2,323
February .....	1	682	115	797	3	13	34	51	848	369	737	1,954
March .....	(s)	<sup>R</sup> 416	103	<sup>R</sup> 520	3	14	36	54	<sup>R</sup> 574	339	685	<sup>R</sup> 1,598
April .....	1	<sup>R</sup> 289	82	<sup>R</sup> 372	3	14	35	52	<sup>R</sup> 424	302	606	<sup>R</sup> 1,332
May .....	(s)	168	86	255	3	14	36	54	309	343	741	1,394
<b>5-Month Total</b> .....	3	2,373	522	2,897	16	70	179	265	3,163	1,785	3,653	8,600
<b>2011 5-Month Total</b> .....	3	2,968	486	3,457	16	58	178	252	3,709	1,919	4,002	9,630
<b>2010 5-Month Total</b> .....	3	2,878	514	3,395	15	47	174	236	3,632	1,928	4,001	9,561

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> Data are estimates. See Table 10.2a for notes on series components.

<sup>c</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>d</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>e</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total

electricity retail sales. See Note 2, "Electrical System Energy Losses," at end of section.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • See Note 1, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding.


• Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> for all available data beginning in 1973.


Sources: Tables 2.6, 3.8a, 4.3, 6.2, 7.6, 10.2a, A4, A5, and A6.

**Figure 2.3 Commercial Sector Energy Consumption**  
(Quadrillion Btu)


By Major Source, 1973-2011




By Major Source, Monthly



Total, January-May



By Major Source, May 2012



<sup>a</sup> Electricity retail sales.  
Web Page: <http://www.eia.doe.gov/emeu/mer/consump.html>.  
Source: Table 2.3.

**Table 2.3 Commercial Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>										Electricity Retail Sales <sup>f</sup>	Electrical System Energy Losses <sup>g</sup>	Total	
	Fossil Fuels				Renewable Energy <sup>b</sup>									
	Coal	Natural Gas <sup>c</sup>	Petroleum <sup>d</sup>	Total	Hydroelectric Power <sup>e</sup>	Geothermal	Solar/PV	Wind	Biomass	Total				Total Primary
<b>1973 Total</b> .....	160	2,649	1,607	4,416	NA	NA	NA	NA	7	7	4,423	1,517	3,604	9,543
<b>1975 Total</b> .....	147	2,558	1,346	4,051	NA	NA	NA	NA	8	8	4,059	1,598	3,835	9,492
<b>1980 Total</b> .....	115	2,651	1,318	4,084	NA	NA	NA	NA	21	21	4,105	1,906	4,567	10,578
<b>1985 Total</b> .....	137	2,488	1,083	3,708	NA	NA	NA	NA	24	24	3,732	2,351	5,368	11,451
<b>1990 Total</b> .....	124	2,682	991	3,798	1	3	—	—	94	98	3,896	2,860	6,564	13,320
<b>1995 Total</b> .....	117	3,096	769	3,982	1	5	—	—	113	118	4,101	3,252	7,338	14,690
<b>1996 Total</b> .....	122	3,226	790	4,138	1	5	—	—	129	135	4,273	3,344	7,555	15,172
<b>1997 Total</b> .....	129	3,285	743	4,157	1	6	—	—	131	138	4,295	3,503	7,883	15,681
<b>1998 Total</b> .....	93	3,083	702	3,878	1	7	—	—	118	127	4,005	3,678	8,285	15,968
<b>1999 Total</b> .....	103	3,115	707	3,925	1	7	—	—	121	129	4,053	3,766	8,557	16,376
<b>2000 Total</b> .....	92	3,252	807	4,150	1	8	—	—	119	128	4,278	3,956	8,942	17,175
<b>2001 Total</b> .....	97	3,097	790	3,984	1	8	—	—	92	101	4,084	4,062	8,990	17,137
<b>2002 Total</b> .....	90	3,212	726	4,028	(s)	9	—	—	95	104	4,132	4,110	9,104	17,345
<b>2003 Total</b> .....	82	3,261	827	4,170	1	11	—	—	101	113	4,283	4,090	8,969	17,343
<b>2004 Total</b> .....	103	3,201	809	4,113	1	12	—	—	105	118	4,232	4,198	9,229	17,659
<b>2005 Total</b> .....	97	3,073	761	3,932	1	14	—	—	105	120	4,051	4,351	9,455	17,857
<b>2006 Total</b> .....	65	2,902	663	3,629	1	14	—	—	103	118	3,747	4,435	9,529	17,711
<b>2007 Total</b> .....	70	3,085	649	3,805	1	14	—	—	103	118	3,922	4,560	9,773	18,255
<b>2008 Total</b> .....	69	3,228	651	3,948	1	15	(s)	—	109	125	4,073	4,558	9,749	18,381
<b>2009 Total</b> .....	63	3,187	682	3,932	1	17	(s)	(s)	112	129	4,061	4,460	9,378	17,899
<b>2010</b>														
January .....	8	509	89	606	(s)	2	(s)	(s)	9	11	617	369	766	1,752
February .....	7	450	81	538	(s)	1	(s)	(s)	8	10	548	344	694	1,585
March .....	6	344	58	407	(s)	2	(s)	(s)	9	11	419	347	699	1,465
April .....	4	220	43	266	(s)	2	(s)	(s)	9	11	277	340	689	1,307
May .....	4	164	46	214	(s)	2	(s)	(s)	10	12	226	362	822	1,410
June .....	4	132	51	187	(s)	2	(s)	(s)	9	11	198	407	896	1,501
July .....	4	123	44	171	(s)	2	(s)	(s)	9	11	182	436	927	1,546
August .....	4	129	41	175	(s)	2	(s)	(s)	10	11	186	441	920	1,547
September .....	4	135	39	178	(s)	2	(s)	(s)	9	11	189	406	795	1,390
October .....	5	189	52	245	(s)	2	(s)	(s)	9	11	256	370	738	1,364
November .....	5	292	56	353	(s)	2	(s)	(s)	9	10	364	346	741	1,451
December .....	6	477	85	568	(s)	2	(s)	(s)	9	11	579	369	813	1,761
<b>Total</b> .....	<b>60</b>	<b>3,164</b>	<b>685</b>	<b>3,908</b>	<b>1</b>	<b>19</b>	<b>(s)</b>	<b>(s)</b>	<b>111</b>	<b>130</b>	<b>4,039</b>	<b>4,539</b>	<b>9,501</b>	<b>18,078</b>
<b>2011</b>														
January .....	7	540	78	625	(s)	2	(s)	(s)	9	11	636	368	762	1,766
February .....	6	442	72	521	(s)	2	(s)	(s)	9	10	531	339	670	1,540
March .....	6	372	60	437	(s)	2	(s)	(s)	9	11	448	353	742	1,544
April .....	4	241	43	287	(s)	2	(s)	(s)	9	10	298	341	720	1,359
May .....	4	171	34	210	(s)	2	(s)	(s)	9	11	221	365	802	1,387
June .....	4	135	43	182	(s)	2	(s)	(s)	9	11	193	401	868	1,462
July .....	3	129	42	174	(s)	2	(s)	(s)	9	11	185	434	950	1,569
August .....	3	136	52	191	(s)	2	(s)	(s)	9	11	202	437	908	1,548
September .....	3	144	54	201	(s)	2	(s)	(s)	9	11	211	401	770	1,382
October .....	3	220	59	282	(s)	2	(s)	(s)	9	11	293	367	751	1,411
November .....	4	288	64	356	(s)	2	(s)	(s)	9	11	367	340	726	1,434
December .....	4	406	82	493	(s)	2	(s)	(s)	10	11	504	355	762	1,621
<b>Total</b> .....	<b>51</b>	<b>3,225</b>	<b>683</b>	<b>3,959</b>	<b>1</b>	<b>20</b>	<b>(s)</b>	<b>(s)</b>	<b>110</b>	<b>131</b>	<b>4,089</b>	<b>4,501</b>	<b>9,429</b>	<b>18,020</b>
<b>2012</b>														
January .....	5	457	87	549	(s)	2	(s)	(s)	9	11	<sup>R</sup> 559	359	734	1,652
February .....	4	399	71	474	(s)	2	(s)	(s)	9	10	484	339	676	1,499
March .....	4	<sup>R</sup> 268	64	<sup>R</sup> 336	(s)	2	(s)	(s)	9	11	<sup>R</sup> 347	347	702	<sup>R</sup> 1,396
April .....	4	<sup>R</sup> 216	49	<sup>R</sup> 269	(s)	2	(s)	(s)	9	11	<sup>R</sup> 280	344	691	<sup>R</sup> 1,314
May .....	3	153	50	207	(s)	2	(s)	(s)	9	11	218	375	810	1,403
<b>5-Month Total</b> .....	<b>20</b>	<b>1,494</b>	<b>321</b>	<b>1,835</b>	<b>(s)</b>	<b>8</b>	<b>(s)</b>	<b>(s)</b>	<b>45</b>	<b>54</b>	<b>1,888</b>	<b>1,763</b>	<b>3,613</b>	<b>7,265</b>
<b>2011 5-Month Total</b> .....	<b>27</b>	<b>1,767</b>	<b>287</b>	<b>2,080</b>	<b>1</b>	<b>8</b>	<b>(s)</b>	<b>(s)</b>	<b>45</b>	<b>54</b>	<b>2,134</b>	<b>1,766</b>	<b>3,696</b>	<b>7,596</b>
<b>2010 5-Month Total</b> .....	<b>28</b>	<b>1,687</b>	<b>317</b>	<b>2,031</b>	<b>(s)</b>	<b>8</b>	<b>(s)</b>	<b>(s)</b>	<b>46</b>	<b>54</b>	<b>2,086</b>	<b>1,763</b>	<b>3,670</b>	<b>7,518</b>

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> Most data are estimates. See Table 10.2a for notes on series components and estimation.

<sup>c</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>d</sup> Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass."

<sup>e</sup> Conventional hydroelectric power.

<sup>f</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>g</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total

electricity retail sales. See Note 2, "Electrical System Energy Losses," at end of section.

<sup>R</sup>=Revised. NA=Not available. —=No data reported. (s)=Less than 0.5 trillion Btu.


Notes: • The commercial sector includes commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 1, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> for all available data beginning in 1973.


Sources: Tables 2.6, 3.8a, 4.3, 6.2, 7.6, 10.2a, A4, A5, and A6.

**Figure 2.4 Industrial Sector Energy Consumption**  
(Quadrillion Btu)


By Major Source, 1973-2011




By Major Source, Monthly



Total, January-May



By Major Source, May 2012



<sup>a</sup> Electricity retail sales.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.  
Source: Table 2.4.

**Table 2.4 Industrial Sector Energy Consumption**  
(Trillion Btu)


	Primary Consumption <sup>a</sup>										Total Primary	Elec- tricity Retail Sales <sup>g</sup>	Electrical System Energy Losses <sup>h</sup>	Total <sup>e</sup>	
	Fossil Fuels				Renewable Energy <sup>b</sup>										
	Coal	Natural Gas <sup>c</sup>	Petro- leum <sup>d</sup>	Total <sup>e</sup>	Hydro- electric Power <sup>f</sup>	Geo- thermal	Solar/ PV	Wind	Bio- mass	Total					
<b>1973 Total</b> .....	4,057	10,388	9,083	23,521	35	NA	NA	NA	1,165	1,200	24,720	2,341	5,562	32,623	
<b>1975 Total</b> .....	3,667	8,532	8,127	20,339	32	NA	NA	NA	1,063	1,096	21,434	2,346	5,632	29,413	
<b>1980 Total</b> .....	3,155	8,333	9,509	20,962	33	NA	NA	NA	1,600	1,633	22,595	2,781	6,664	32,039	
<b>1985 Total</b> .....	2,760	7,032	7,714	17,492	33	NA	NA	NA	1,918	1,951	19,443	2,855	6,518	28,816	
<b>1990 Total</b> .....	2,756	8,451	8,251	19,463	31	2	-	-	1,684	1,717	21,180	3,226	7,404	31,810	
<b>1995 Total</b> .....	2,488	9,592	8,586	20,727	55	3	-	-	1,934	1,992	22,719	3,455	7,796	33,971	
<b>1996 Total</b> .....	2,434	9,901	9,019	21,377	61	3	-	-	1,969	2,033	23,410	3,527	7,968	34,904	
<b>1997 Total</b> .....	2,395	9,933	9,255	21,629	58	3	-	-	1,996	2,057	23,686	3,542	7,972	35,200	
<b>1998 Total</b> .....	2,335	9,763	9,082	21,248	55	3	-	-	1,872	1,929	23,177	3,587	8,079	34,843	
<b>1999 Total</b> .....	2,227	9,375	9,356	21,016	49	4	-	-	1,882	1,934	22,950	3,611	8,203	34,764	
<b>2000 Total</b> .....	2,256	9,500	9,075	20,896	42	4	-	-	1,881	1,928	22,824	3,631	8,208	34,664	
<b>2001 Total</b> .....	2,192	8,676	9,178	20,075	33	5	-	-	1,681	1,719	21,794	3,400	7,526	32,720	
<b>2002 Total</b> .....	2,019	8,832	9,168	20,079	39	5	-	-	1,676	1,720	21,799	3,379	7,484	32,662	
<b>2003 Total</b> .....	2,041	8,488	9,197	19,777	43	3	-	-	1,679	1,726	21,503	3,454	7,575	32,532	
<b>2004 Total</b> .....	2,047	8,550	9,825	20,559	33	4	-	-	1,817	1,853	22,412	3,473	7,635	33,520	
<b>2005 Total</b> .....	1,954	7,907	9,633	19,538	32	4	-	-	1,837	1,873	21,411	3,477	7,557	32,446	
<b>2006 Total</b> .....	1,914	7,861	9,770	19,606	29	4	-	-	1,897	1,930	21,536	3,451	7,415	32,401	
<b>2007 Total</b> .....	1,865	8,074	9,451	19,414	16	5	-	-	1,936	1,956	21,370	3,507	7,517	32,394	
<b>2008 Total</b> .....	1,796	8,083	8,511	18,431	17	5	-	-	2,028	2,049	20,480	3,444	7,365	31,290	
<b>2009 Total</b> .....	1,396	7,609	7,816	16,797	18	4	-	-	1,994	2,016	18,813	3,130	6,582	28,525	
<b>2010</b>															
January .....	126	737	648	1,508	2	(s)	(s)	-	185	187	1,695	258	535	2,487	
February .....	130	681	614	1,429	2	(s)	(s)	-	170	172	1,601	253	511	2,365	
March .....	136	695	728	1,562	2	(s)	(s)	-	188	190	1,752	267	538	2,557	
April .....	130	630	680	1,441	2	(s)	(s)	-	181	183	1,624	268	543	2,435	
May .....	131	638	655	1,427	2	(s)	(s)	-	183	185	1,612	280	635	2,527	
June .....	130	619	675	1,424	1	(s)	(s)	-	182	183	1,608	284	625	2,517	
July .....	132	631	665	1,429	1	(s)	(s)	-	188	190	1,618	292	621	2,532	
August .....	134	635	745	1,515	1	(s)	(s)	-	190	191	1,707	300	626	2,633	
September .....	136	630	718	1,484	1	(s)	(s)	-	185	187	1,671	284	557	2,512	
October .....	132	647	675	1,452	1	(s)	(s)	-	190	192	1,644	280	559	2,482	
November .....	134	672	679	1,479	1	(s)	(s)	-	190	191	1,671	272	581	2,523	
December .....	138	742	728	1,602	1	(s)	(s)	-	198	199	1,802	274	604	2,679	
<b>Total</b> .....	<b>1,590</b>	<b>7,959</b>	<b>8,210</b>	<b>17,753</b>	<b>16</b>	<b>4</b>	<b>(s)</b>	<b>(s)</b>	<b>2,230</b>	<b>2,250</b>	<b>20,003</b>	<b>3,313</b>	<b>6,934</b>	<b>30,250</b>	
<b>2011</b>															
January .....	132	764	742	1,638	1	(s)	(s)	(s)	197	199	1,837	270	558	2,665	
February .....	128	690	604	1,422	2	(s)	(s)	(s)	176	178	1,600	257	508	2,364	
March .....	134	721	738	1,595	2	(s)	(s)	(s)	190	192	1,787	276	580	2,642	
April .....	120	675	643	1,438	2	(s)	(s)	(s)	182	185	1,622	270	569	2,462	
May .....	125	674	645	1,446	2	(s)	(s)	(s)	185	187	1,633	275	606	2,515	
June .....	124	641	680	1,447	1	(s)	(s)	(s)	190	192	1,639	282	611	2,533	
July .....	121	651	651	1,423	1	(s)	(s)	(s)	192	194	1,616	293	642	2,552	
August .....	126	663	709	1,502	1	(s)	(s)	(s)	191	192	1,695	299	620	2,614	
September .....	126	655	658	1,440	1	(s)	(s)	(s)	187	188	1,629	284	546	2,459	
October .....	126	684	675	1,485	1	(s)	(s)	(s)	189	190	1,675	283	578	2,536	
November .....	125	705	677	1,505	1	(s)	(s)	(s)	192	194	1,699	271	579	2,549	
December .....	130	758	642	1,532	2	(s)	(s)	(s)	202	204	1,736	268	576	2,581	
<b>Total</b> .....	<b>1,518</b>	<b>8,282</b>	<b>8,064</b>	<b>17,874</b>	<b>18</b>	<b>4</b>	<b>(s)</b>	<b>(s)</b>	<b>2,273</b>	<b>2,295</b>	<b>20,169</b>	<b>3,329</b>	<b>6,973</b>	<b>30,471</b>	
<b>2012</b>															
January .....	121	767	<sup>R</sup> 689	<sup>R</sup> 1,579	2	(s)	(s)	(s)	197	199	<sup>R</sup> 1,778	268	549	<sup>R</sup> 2,596	
February .....	121	723	<sup>R</sup> 659	<sup>R</sup> 1,503	2	(s)	(s)	(s)	183	185	<sup>R</sup> 1,687	266	531	<sup>R</sup> 2,484	
March .....	125	<sup>R</sup> 708	<sup>R</sup> 630	<sup>R</sup> 1,466	2	(s)	(s)	(s)	184	186	<sup>R</sup> 1,653	275	556	<sup>R</sup> 2,484	
April .....	129	<sup>R</sup> 679	<sup>R</sup> 617	<sup>R</sup> 1,432	2	(s)	(s)	(s)	178	180	<sup>R</sup> 1,612	274	552	<sup>R</sup> 2,438	
May .....	124	675	666	1,467	2	(s)	(s)	(s)	188	190	1,657	288	622	2,568	
<b>5-Month Total</b> .....	<b>620</b>	<b>3,552</b>	<b>3,262</b>	<b>7,446</b>	<b>9</b>	<b>2</b>	<b>(s)</b>	<b>(s)</b>	<b>930</b>	<b>940</b>	<b>8,386</b>	<b>1,372</b>	<b>2,810</b>	<b>12,569</b>	
<b>2011 5-Month Total</b> .....	<b>639</b>	<b>3,523</b>	<b>3,372</b>	<b>7,539</b>	<b>9</b>	<b>2</b>	<b>(s)</b>	<b>(s)</b>	<b>930</b>	<b>941</b>	<b>8,480</b>	<b>1,348</b>	<b>2,820</b>	<b>12,648</b>	
<b>2010 5-Month Total</b> .....	<b>654</b>	<b>3,382</b>	<b>3,326</b>	<b>7,366</b>	<b>8</b>	<b>2</b>	<b>(s)</b>	<b>-</b>	<b>907</b>	<b>917</b>	<b>8,283</b>	<b>1,326</b>	<b>2,762</b>	<b>12,371</b>	

<sup>a</sup> See "Primary Energy Consumption" in Glossary.  
<sup>b</sup> Most data are estimates. See Table 10.2b for notes on series components and estimation.  
<sup>c</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.  
<sup>d</sup> Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass."  
<sup>e</sup> Includes coal coke net imports, which are not separately displayed. See Tables 1.4a and 1.4b.  
<sup>f</sup> Conventional hydroelectric power.  
<sup>g</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.  
<sup>h</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are


allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Note 2, "Electrical System Energy Losses," at end of section.  
<sup>R</sup>=Revised. <sup>NA</sup>=Not available. <sup>-</sup>=No data reported. <sup>(s)</sup>=Less than 0.5 trillion Btu.  
Notes: • The industrial sector includes industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • See Note 1, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> for all available data beginning in 1973.  
Sources: Tables 1.4a, 1.4b, 2.6, 3.8b, 4.3, 6.2, 7.6, 10.2b, A4, A5, and A6.

**Figure 2.5 Transportation Sector Energy Consumption**  
(Quadrillion Btu)


By Major Source, 1973-2011




By Major Source, Monthly



Total, January-May



Total, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.  
Source: Table 2.5.



**Table 2.5 Transportation Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>					Total Primary	Electricity Retail Sales <sup>e</sup>	Electrical System Energy Losses <sup>f</sup>	Total
	Fossil Fuels				Renewable Energy <sup>b</sup>				
	Coal	Natural Gas <sup>c</sup>	Petroleum <sup>d</sup>	Total	Biomass				
<b>1973 Total</b> .....	<b>3</b>	<b>743</b>	<b>17,832</b>	<b>18,577</b>	<b>NA</b>	<b>18,577</b>	<b>11</b>	<b>25</b>	<b>18,613</b>
<b>1975 Total</b> .....	<b>1</b>	<b>595</b>	<b>17,615</b>	<b>18,210</b>	<b>NA</b>	<b>18,210</b>	<b>10</b>	<b>24</b>	<b>18,245</b>
<b>1980 Total</b> .....	(9)	<b>650</b>	<b>19,009</b>	<b>19,659</b>	<b>NA</b>	<b>19,659</b>	<b>11</b>	<b>27</b>	<b>19,697</b>
<b>1985 Total</b> .....	(9)	<b>519</b>	<b>19,472</b>	<b>19,992</b>	<b>50</b>	<b>20,041</b>	<b>14</b>	<b>32</b>	<b>20,088</b>
<b>1990 Total</b> .....	(9)	<b>680</b>	<b>21,626</b>	<b>22,306</b>	<b>60</b>	<b>22,366</b>	<b>16</b>	<b>37</b>	<b>22,420</b>
<b>1995 Total</b> .....	(9)	<b>724</b>	<b>22,955</b>	<b>23,679</b>	<b>112</b>	<b>23,791</b>	<b>17</b>	<b>38</b>	<b>23,846</b>
<b>1996 Total</b> .....	(9)	<b>737</b>	<b>23,565</b>	<b>24,302</b>	<b>81</b>	<b>24,383</b>	<b>17</b>	<b>38</b>	<b>24,437</b>
<b>1997 Total</b> .....	(9)	<b>780</b>	<b>23,813</b>	<b>24,593</b>	<b>102</b>	<b>24,695</b>	<b>17</b>	<b>38</b>	<b>24,750</b>
<b>1998 Total</b> .....	(9)	<b>666</b>	<b>24,422</b>	<b>25,088</b>	<b>113</b>	<b>25,201</b>	<b>17</b>	<b>38</b>	<b>25,256</b>
<b>1999 Total</b> .....	(9)	<b>675</b>	<b>25,098</b>	<b>25,774</b>	<b>118</b>	<b>25,891</b>	<b>17</b>	<b>40</b>	<b>25,949</b>
<b>2000 Total</b> .....	(9)	<b>672</b>	<b>25,682</b>	<b>26,354</b>	<b>135</b>	<b>26,489</b>	<b>18</b>	<b>42</b>	<b>26,548</b>
<b>2001 Total</b> .....	(9)	<b>658</b>	<b>25,412</b>	<b>26,070</b>	<b>142</b>	<b>26,213</b>	<b>20</b>	<b>43</b>	<b>26,275</b>
<b>2002 Total</b> .....	(9)	<b>699</b>	<b>25,913</b>	<b>26,612</b>	<b>170</b>	<b>26,781</b>	<b>19</b>	<b>42</b>	<b>26,842</b>
<b>2003 Total</b> .....	(9)	<b>627</b>	<b>26,063</b>	<b>26,690</b>	<b>230</b>	<b>26,920</b>	<b>23</b>	<b>51</b>	<b>26,994</b>
<b>2004 Total</b> .....	(9)	<b>602</b>	<b>26,925</b>	<b>27,527</b>	<b>290</b>	<b>27,817</b>	<b>25</b>	<b>54</b>	<b>27,895</b>
<b>2005 Total</b> .....	(9)	<b>624</b>	<b>27,309</b>	<b>27,933</b>	<b>339</b>	<b>28,272</b>	<b>26</b>	<b>56</b>	<b>28,353</b>
<b>2006 Total</b> .....	(9)	<b>625</b>	<b>27,651</b>	<b>28,276</b>	<b>475</b>	<b>28,751</b>	<b>25</b>	<b>54</b>	<b>28,830</b>
<b>2007 Total</b> .....	(9)	<b>663</b>	<b>27,763</b>	<b>28,427</b>	<b>602</b>	<b>29,029</b>	<b>28</b>	<b>60</b>	<b>29,117</b>
<b>2008 Total</b> .....	(9)	<b>692</b>	<b>26,407</b>	<b>27,099</b>	<b>826</b>	<b>27,925</b>	<b>26</b>	<b>56</b>	<b>28,008</b>
<b>2009 Total</b> .....	(9)	<b>715</b>	<b>25,339</b>	<b>26,054</b>	<b>935</b>	<b>26,989</b>	<b>27</b>	<b>56</b>	<b>27,071</b>
<b>2010 January</b> .....	(9)	<b>84</b>	<b>2,025</b>	<b>2,109</b>	<b>81</b>	<b>2,190</b>	<b>2</b>	<b>5</b>	<b>2,198</b>
February .....	(9)	<b>74</b>	<b>1,851</b>	<b>1,926</b>	<b>79</b>	<b>2,004</b>	<b>2</b>	<b>5</b>	<b>2,012</b>
March .....	(9)	<b>64</b>	<b>2,141</b>	<b>2,205</b>	<b>85</b>	<b>2,290</b>	<b>2</b>	<b>5</b>	<b>2,297</b>
April .....	(9)	<b>50</b>	<b>2,142</b>	<b>2,193</b>	<b>87</b>	<b>2,280</b>	<b>2</b>	<b>4</b>	<b>2,286</b>
May .....	(9)	<b>48</b>	<b>2,209</b>	<b>2,257</b>	<b>92</b>	<b>2,349</b>	<b>2</b>	<b>5</b>	<b>2,356</b>
June .....	(9)	<b>49</b>	<b>2,179</b>	<b>2,228</b>	<b>93</b>	<b>2,320</b>	<b>2</b>	<b>5</b>	<b>2,328</b>
July .....	(9)	<b>54</b>	<b>2,256</b>	<b>2,310</b>	<b>94</b>	<b>2,404</b>	<b>2</b>	<b>5</b>	<b>2,411</b>
August .....	(9)	<b>56</b>	<b>2,250</b>	<b>2,306</b>	<b>94</b>	<b>2,399</b>	<b>2</b>	<b>4</b>	<b>2,406</b>
September .....	(9)	<b>48</b>	<b>2,153</b>	<b>2,202</b>	<b>90</b>	<b>2,291</b>	<b>2</b>	<b>4</b>	<b>2,298</b>
October .....	(9)	<b>49</b>	<b>2,184</b>	<b>2,233</b>	<b>94</b>	<b>2,327</b>	<b>2</b>	<b>4</b>	<b>2,333</b>
November .....	(9)	<b>59</b>	<b>2,072</b>	<b>2,131</b>	<b>91</b>	<b>2,221</b>	<b>2</b>	<b>4</b>	<b>2,228</b>
December .....	(9)	<b>81</b>	<b>2,132</b>	<b>2,213</b>	<b>94</b>	<b>2,307</b>	<b>2</b>	<b>5</b>	<b>2,314</b>
<b>Total</b> .....	(9)	<b>716</b>	<b>25,595</b>	<b>26,310</b>	<b>1,074</b>	<b>27,384</b>	<b>26</b>	<b>55</b>	<b>27,466</b>
<b>2011 January</b> .....	(9)	<b>86</b>	<b>2,048</b>	<b>2,133</b>	<b>86</b>	<b>2,220</b>	<b>2</b>	<b>5</b>	<b>2,227</b>
February .....	(9)	<b>73</b>	<b>1,884</b>	<b>1,957</b>	<b>85</b>	<b>2,042</b>	<b>2</b>	<b>4</b>	<b>2,049</b>
March .....	(9)	<b>67</b>	<b>2,137</b>	<b>2,204</b>	<b>93</b>	<b>2,297</b>	<b>2</b>	<b>5</b>	<b>2,304</b>
April .....	(9)	<b>55</b>	<b>2,096</b>	<b>2,152</b>	<b>91</b>	<b>2,242</b>	<b>2</b>	<b>4</b>	<b>2,249</b>
May .....	(9)	<b>51</b>	<b>2,156</b>	<b>2,207</b>	<b>99</b>	<b>2,306</b>	<b>2</b>	<b>5</b>	<b>2,312</b>
June .....	(9)	<b>50</b>	<b>2,156</b>	<b>2,207</b>	<b>102</b>	<b>2,308</b>	<b>2</b>	<b>5</b>	<b>2,315</b>
July .....	(9)	<b>57</b>	<b>2,163</b>	<b>2,220</b>	<b>96</b>	<b>2,316</b>	<b>2</b>	<b>5</b>	<b>2,323</b>
August .....	(9)	<b>57</b>	<b>2,187</b>	<b>2,244</b>	<b>106</b>	<b>2,349</b>	<b>2</b>	<b>4</b>	<b>2,356</b>
September .....	(9)	<b>50</b>	<b>2,085</b>	<b>2,135</b>	<b>97</b>	<b>2,232</b>	<b>2</b>	<b>4</b>	<b>2,238</b>
October .....	(9)	<b>53</b>	<b>2,104</b>	<b>2,157</b>	<b>100</b>	<b>2,257</b>	<b>2</b>	<b>4</b>	<b>2,264</b>
November .....	(9)	<b>61</b>	<b>2,017</b>	<b>2,077</b>	<b>98</b>	<b>2,175</b>	<b>2</b>	<b>4</b>	<b>2,181</b>
December .....	(9)	<b>75</b>	<b>2,076</b>	<b>2,151</b>	<b>102</b>	<b>2,253</b>	<b>2</b>	<b>5</b>	<b>2,260</b>
<b>Total</b> .....	(9)	<b>734</b>	<b>25,110</b>	<b>25,843</b>	<b>1,154</b>	<b>26,998</b>	<b>26</b>	<b>54</b>	<b>27,078</b>
<b>2012 January</b> .....	(9)	<b>81</b>	<sup>R</sup> 1,957	<b>2,038</b>	<sup>R</sup> 86	<sup>R</sup> 2,124	<b>2</b>	<b>5</b>	<sup>R</sup> 2,131
February .....	(9)	<b>74</b>	<sup>R</sup> 1,914	<sup>R</sup> 1,988	<sup>R</sup> 89	<sup>R</sup> 2,077	<b>2</b>	<b>4</b>	<sup>R</sup> 2,084
March .....	(9)	<b>64</b>	<sup>R</sup> 2,070	<sup>R</sup> 2,134	<sup>R</sup> 98	<sup>R</sup> 2,231	<b>2</b>	<b>4</b>	<sup>R</sup> 2,238
April .....	(9)	<b>59</b>	<sup>R</sup> 2,052	<sup>R</sup> 2,111	<sup>R</sup> 98	<sup>R</sup> 2,209	<b>2</b>	<b>4</b>	<sup>R</sup> 2,215
May .....	(9)	<b>56</b>	<b>2,145</b>	<b>2,201</b>	<b>107</b>	<b>2,308</b>	<b>2</b>	<b>5</b>	<b>2,314</b>
<b>5-Month Total</b> .....	(9)	<b>334</b>	<b>10,138</b>	<b>10,472</b>	<b>477</b>	<b>10,949</b>	<b>11</b>	<b>22</b>	<b>10,982</b>
<b>2011 5-Month Total</b> .....	(9)	<b>331</b>	<b>10,322</b>	<b>10,653</b>	<b>454</b>	<b>11,107</b>	<b>11</b>	<b>23</b>	<b>11,141</b>
<b>2010 5-Month Total</b> .....	(9)	<b>320</b>	<b>10,369</b>	<b>10,689</b>	<b>424</b>	<b>11,113</b>	<b>11</b>	<b>23</b>	<b>11,148</b>

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> Data are estimates. See Table 10.2b for notes on series components.

<sup>c</sup> Natural gas only; does not include supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>d</sup> Does not include biofuels that have been blended with petroleum—biofuels are included in "Biomass."

<sup>e</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>f</sup> Total losses are calculated as the primary energy consumed by the electric power sector minus the energy content of electricity retail sales. Total losses are allocated to the end-use sectors in proportion to each sector's share of total

electricity retail sales. See Note 2, "Electrical System Energy Losses," at end of section.

<sup>g</sup> Beginning in 1978, the small amounts of coal consumed for transportation are reported as industrial sector consumption.

R=Revised. NA=Not available.

Notes: • See Note 1, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding.


• Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> for all available data beginning in 1973.


Sources: Tables 2.6, 3.8c, 4.3, 6.2, 7.6, 10.2b, A4, A5, and A6.

**Figure 2.6 Electric Power Sector Energy Consumption**  
(Quadrillion Btu)


Total, 1973-2011




Total, Monthly




By Major Source, 1973-2011




By Major Source, Monthly



Total, January-May



By Major Source, May 2012



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#consumption>.  
Source: Table 2.6.

**Table 2.6 Electric Power Sector Energy Consumption**  
(Trillion Btu)

	Primary Consumption <sup>a</sup>												Elec- tricity Net Imports	Total Primary
	Fossil Fuels				Nuclear Electric Power	Renewable Energy <sup>b</sup>								
	Coal	Natural Gas <sup>c</sup>	Petro- leum	Total		Hydro- electric Power <sup>d</sup>	Geo- thermal	Solar/ PV	Wind	Bio- mass	Total			
<b>1973 Total</b> .....	8,658	3,748	3,515	15,921	910	2,827	20	NA	NA	3	2,851	49	19,731	
<b>1975 Total</b> .....	8,786	3,240	3,166	15,191	1,900	3,122	34	NA	NA	2	3,158	21	20,270	
<b>1980 Total</b> .....	12,123	3,778	2,634	18,534	2,739	2,867	53	NA	NA	4	2,925	71	24,269	
<b>1985 Total</b> .....	14,542	3,135	1,090	18,767	4,076	2,937	97	(s)	(s)	14	3,049	140	26,032	
<b>1990 Total<sup>e</sup></b> .....	16,261	3,309	1,289	20,859	6,104	3,014	161	4	29	317	3,524	8	30,495	
<b>1995 Total</b> .....	17,466	4,302	755	22,523	7,075	3,149	138	5	33	422	3,747	134	33,479	
<b>1996 Total</b> .....	18,429	3,862	817	23,109	7,087	3,528	148	5	33	438	4,153	137	34,485	
<b>1997 Total</b> .....	18,905	4,126	927	23,957	6,597	3,581	150	5	34	446	4,216	116	34,886	
<b>1998 Total</b> .....	19,216	4,675	1,306	25,197	7,068	3,241	151	5	31	444	3,872	88	36,225	
<b>1999 Total</b> .....	19,279	4,902	1,211	25,393	7,610	3,218	152	5	46	453	3,874	99	36,976	
<b>2000 Total</b> .....	20,220	5,293	1,144	26,658	7,862	2,768	144	5	57	453	3,427	115	38,062	
<b>2001 Total</b> .....	19,614	5,458	1,277	26,348	8,029	2,209	142	6	70	337	2,763	75	37,215	
<b>2002 Total</b> .....	19,783	5,767	961	26,511	8,145	2,650	147	6	105	380	3,288	72	38,016	
<b>2003 Total</b> .....	20,185	5,246	1,205	26,636	7,959	2,781	148	5	115	397	3,445	22	38,062	
<b>2004 Total</b> .....	20,305	5,595	1,212	27,112	8,222	2,656	148	6	142	388	3,340	39	38,713	
<b>2005 Total</b> .....	20,737	6,015	1,235	27,986	8,161	2,670	147	6	178	406	3,406	85	39,638	
<b>2006 Total</b> .....	20,462	6,375	648	27,485	8,215	2,839	145	5	264	412	3,665	63	39,428	
<b>2007 Total</b> .....	20,808	7,005	657	28,470	8,455	2,430	145	6	341	423	3,345	107	40,377	
<b>2008 Total</b> .....	20,513	6,829	468	27,810	8,427	2,494	146	9	546	435	3,630	112	39,978	
<b>2009 Total</b> .....	18,225	7,022	390	25,638	8,356	2,650	146	9	721	441	3,967	116	38,077	
<b>2010</b>														
January .....	1,775	557	45	2,377	758	217	13	(s)	67	39	335	14	3,484	
February .....	1,568	489	23	2,080	682	199	11	(s)	53	36	300	12	3,073	
March .....	1,494	466	25	1,984	676	202	13	1	84	39	338	10	3,008	
April .....	1,312	480	23	1,815	602	184	12	1	95	36	329	9	2,755	
May .....	1,483	570	31	2,084	697	243	13	1	85	36	378	5	3,163	
June .....	1,708	719	41	2,468	714	290	12	2	79	39	421	9	3,611	
July .....	1,855	914	46	2,815	752	238	12	2	66	40	358	10	3,934	
August .....	1,849	961	37	2,847	748	195	13	2	65	41	315	6	3,917	
September .....	1,554	709	28	2,291	725	168	12	1	69	38	288	2	3,306	
October .....	1,383	581	22	1,986	656	171	12	1	77	37	298	1	2,942	
November .....	1,423	506	21	1,950	655	190	12	1	95	39	337	3	2,944	
December .....	1,731	575	36	2,341	770	225	13	(s)	88	41	367	9	3,488	
<b>Total</b> .....	<b>19,133</b>	<b>7,527</b>	<b>378</b>	<b>27,039</b>	<b>8,434</b>	<b>2,521</b>	<b>148</b>	<b>12</b>	<b>923</b>	<b>459</b>	<b>4,064</b>	<b>89</b>	<b>39,626</b>	
<b>2011</b>														
January .....	1,737	552	33	2,323	760	254	14	(s)	84	38	391	9	3,483	
February .....	1,417	491	23	1,931	677	239	13	1	103	35	390	8	3,006	
March .....	1,395	491	26	1,912	686	308	14	1	103	38	463	8	3,070	
April .....	1,293	535	23	1,851	570	307	13	2	121	33	476	7	2,905	
May .....	1,416	589	22	2,027	596	321	14	2	113	35	486	12	3,121	
June .....	1,621	718	25	2,364	682	313	13	2	106	38	473	11	3,530	
July .....	1,816	959	31	2,805	756	307	13	2	72	40	434	16	4,012	
August .....	1,776	940	25	2,741	746	256	13	2	72	39	383	16	3,885	
September .....	1,475	699	22	2,196	699	209	13	2	67	37	327	10	3,232	
October .....	1,339	589	19	1,946	662	194	14	2	104	36	349	10	2,967	
November .....	1,289	553	17	1,860	674	207	13	1	120	36	377	8	2,919	
December .....	1,413	624	20	2,057	751	239	14	1	102	39	396	12	3,215	
<b>Total</b> .....	<b>17,986</b>	<b>7,740</b>	<b>288</b>	<b>26,014</b>	<b>8,259</b>	<b>3,153</b>	<b>163</b>	<b>18</b>	<b>1,168</b>	<b>444</b>	<b>4,945</b>	<b>127</b>	<b>39,346</b>	
<b>2012</b>														
January .....	1,360	663	21	2,045	757	232	14	1	135	38	420	11	3,232	
February .....	1,210	661	17	1,888	667	201	13	1	108	35	359	9	2,924	
March .....	1,108	692	15	1,816	645	255	14	2	132	37	440	10	2,911	
April .....	995	737	14	1,746	584	259	13	3	123	33	432	13	2,775	
May .....	1,217	834	16	2,067	649	281	14	4	121	36	457	15	3,188	
<b>5-Month Total</b> .....	<b>5,890</b>	<b>3,588</b>	<b>84</b>	<b>9,563</b>	<b>3,302</b>	<b>1,228</b>	<b>69</b>	<b>11</b>	<b>619</b>	<b>180</b>	<b>2,106</b>	<b>58</b>	<b>15,029</b>	
<b>2011 5-Month Total</b> .....	<b>7,258</b>	<b>2,659</b>	<b>127</b>	<b>10,044</b>	<b>3,290</b>	<b>1,428</b>	<b>69</b>	<b>6</b>	<b>525</b>	<b>179</b>	<b>2,206</b>	<b>45</b>	<b>15,585</b>	
<b>2010 5-Month Total</b> .....	<b>7,631</b>	<b>2,561</b>	<b>147</b>	<b>10,340</b>	<b>3,415</b>	<b>1,045</b>	<b>62</b>	<b>4</b>	<b>384</b>	<b>186</b>	<b>1,680</b>	<b>50</b>	<b>15,484</b>	

<sup>a</sup> See "Primary Energy Consumption" in Glossary.

<sup>b</sup> See Table 10.2c for notes on series components.

<sup>c</sup> Natural gas only; excludes the estimated portion of supplemental gaseous fuels. See Note 3, "Supplemental Gaseous Fuels," at end of Section 4.

<sup>d</sup> Conventional hydroelectric power.

<sup>e</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for fuels consumed to produce electricity and useful thermal

output. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • See Note 1, "Energy Consumption Data and Surveys," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#consumption> for all available data beginning in 1973.

Sources: Tables 3.8c, 4.3, 6.2, 7.1, 7.2b, 10.2c, A4, A5, and A6.

## Energy Consumption by Sector

**Note 1. Energy Consumption Data and Surveys.** Most of the data in this section of the Monthly Energy Review (MER) are developed from a group of energy-related surveys, typically called "supply surveys," conducted by the U.S. Energy Information Administration (EIA). Supply surveys are directed to suppliers and marketers of specific energy sources. They measure the quantities of specific energy sources produced, or the quantities supplied to the market, or both. The data obtained from EIA's supply surveys are integrated to yield the summary consumption statistics published in this section (and in Section 1) of the MER.

Users of EIA's energy consumption statistics should be aware of a second group of energy-related surveys, typically called "consumption surveys." Consumption surveys gather information on the types of energy consumed by end users of energy, along with the characteristics of those end users that can be associated with energy use. For example, the Manufacturing Energy Consumption Survey belongs to the consumption survey group because it collects information directly from end users (the manufacturing establishments). There are important differences between the supply and consumption surveys that need to be taken into account in any analysis that uses both data sources. For information on

those differences, see Energy Consumption by End-Use Sector, A Comparison of Measures by Consumption and Supply Surveys, DOE/EIA-0533, U.S. Energy Information Administration, Washington, DC, April 6, 1990.


**Note 2. Electrical System Energy Losses.** Electrical system energy losses are calculated as the difference between total primary consumption by the electric power sector (see Table 2.6) and the total energy content of electricity retail sales (see Tables 7.6 and A6). Most of these losses occur at steam-electric power plants (conventional and nuclear) in the conversion of heat energy into mechanical energy to turn electric generators. The loss is a thermodynamically necessary feature of the steam-electric cycle. Part of the energy input-to-output losses is a result of imputing fossil energy equivalent inputs for hydroelectric and other energy sources, since there is no generally accepted practice for measuring those thermal conversion rates. In addition to conversion losses, other losses include power plant use of electricity, transmission and distribution of electricity from power plants to end-use consumers (also called "line losses"), and unaccounted for electricity. Total losses are allocated to the end-use sectors in proportion to each sector's share of total electricity sales. Overall, about two thirds of total energy input is lost in conversion. Currently, of electricity generated, approximately 5 percent is lost in plant use and 7 percent is lost in transmission and distribution.

## **3. Petroleum**


---

**Figure 3.1 Petroleum Overview**  
(Million Barrels per Day)


Overview, January-July




Overview, 1973-2011




Total Field Production, 1973-2011



Crude Oil<sup>b</sup> Field Production, 1973-2011



Total Field Production,<sup>a</sup> Monthly



<sup>a</sup> Crude oil, including lease condensate, and natural gas plant liquids field production.  
<sup>b</sup> Includes lease condensate.

<sup>c</sup> United States excluding Alaska and Hawaii.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
Source: Table 3.1.

**Table 3.1 Petroleum Overview**  
(Thousand Barrels per Day)

	Field Production <sup>a</sup>					Renewable Fuels and Oxygenates <sup>g</sup>	Processing Gain <sup>h</sup>	Trade			Stock Change <sup>k</sup>	Adjustments <sup>c,l</sup>	Petroleum Products Supplied
	Crude Oil <sup>b,c</sup>			NGPL <sup>e,f</sup>	Total <sup>c</sup>			Imports <sup>i</sup>	Exports <sup>f</sup>	Net Imports <sup>i</sup>			
	48 States <sup>d</sup>	Alaska	Total										
1973 Average	9,010	198	9,208	1,738	10,946	NA	453	6,256	231	6,025	135	18	17,308
1975 Average	8,183	191	8,375	1,633	10,007	NA	460	6,056	209	5,846	32	41	16,322
1980 Average	6,980	1,617	8,597	1,573	10,170	NA	597	6,909	544	6,365	140	64	17,056
1985 Average	7,146	1,825	8,971	1,609	10,581	NA	557	5,067	781	4,286	-103	200	15,726
1990 Average	5,582	1,773	7,355	1,559	8,914	NA	683	8,018	857	7,161	107	338	16,988
1995 Average	5,076	1,484	6,560	1,762	8,322	NA	774	8,835	949	7,886	-246	496	17,725
1996 Average	5,071	1,393	6,465	1,830	8,295	NA	837	9,478	981	8,498	-151	528	18,309
1997 Average	5,156	1,296	6,452	1,817	8,269	NA	850	10,162	1,003	9,158	143	487	18,620
1998 Average	5,077	1,175	6,252	1,759	8,011	NA	886	10,708	945	9,764	239	495	18,917
1999 Average	4,832	1,050	5,881	1,850	7,731	NA	886	10,852	940	9,912	-422	567	19,519
2000 Average	4,851	970	5,822	1,911	7,733	NA	948	11,459	1,040	10,419	-69	532	19,701
2001 Average	4,839	963	5,801	1,868	7,670	NA	903	11,871	971	10,900	325	501	19,649
2002 Average	4,761	984	5,746	1,880	7,626	NA	957	11,530	984	10,546	-105	527	19,761
2003 Average	4,706	974	5,681	1,719	7,400	NA	974	12,264	1,027	11,238	56	478	20,034
2004 Average	4,510	908	5,419	1,809	7,228	NA	1,051	13,145	1,048	12,097	209	564	20,731
2005 Average	4,314	864	5,178	1,717	6,895	NA	989	13,714	1,165	12,549	145	513	20,802
2006 Average	4,361	741	5,102	1,739	6,841	NA	994	13,707	1,317	12,390	60	522	20,687
2007 Average	4,342	722	5,064	1,783	6,847	NA	996	13,468	1,433	12,036	-148	653	20,680
2008 Average	4,268	683	4,950	1,784	6,734	NA	993	12,915	1,802	11,114	195	852	19,498
2009 Average	4,715	645	5,361	1,910	7,270	746	979	11,691	2,024	9,667	109	218	18,771
2010 January	4,756	640	R 5,396	2,017	R 7,413	846	961	11,300	1,897	9,404	309	336	18,652
February	4,908	635	R 5,543	2,043	R 7,587	874	1,060	11,230	2,034	9,197	-46	R 87	18,850
March	R 4,867	646	R 5,513	2,076	R 7,589	895	1,064	11,621	2,149	9,472	77	R 156	19,099
April	R 4,736	640	R 5,376	2,061	R 7,437	878	1,028	12,526	2,432	10,093	762	R 370	19,044
May	R 4,825	571	R 5,397	2,091	R 7,487	893	1,069	12,141	2,399	9,742	661	R 336	18,866
June	R 4,853	534	R 5,387	2,046	R 7,433	905	1,085	12,444	2,304	10,140	373	347	19,537
July	R 4,773	545	R 5,318	1,994	R 7,311	906	1,109	12,675	2,516	10,159	440	275	19,319
August	R 4,910	538	R 5,449	2,071	R 7,519	911	1,123	12,356	2,410	9,946	214	R 376	19,662
September	R 5,001	614	R 5,614	2,104	R 7,718	915	1,062	11,823	2,345	9,478	-23	R 243	19,438
October	R 4,986	618	R 5,604	2,125	R 7,729	924	1,012	11,142	2,480	8,662	-451	R 195	18,974
November	R 4,962	606	R 5,568	2,136	R 7,704	967	1,051	11,096	2,598	8,498	-667	R 90	18,977
December	R 4,998	632	R 5,630	2,124	R 7,754	961	1,187	11,132	2,644	8,488	-1,068	R 263	19,722
Average	4,881	601	5,482	2,074	7,556	907	1,068	11,793	2,353	9,441	49	R 257	19,180
2011 January	RE 5,050	E 479	RE 5,529	2,022	RE 7,551	957	1,067	11,954	2,687	9,266	318	R 598	19,121
February	RE 4,831	E 611	RE 5,442	1,920	RE 7,362	941	980	10,503	2,575	7,929	-1,069	R 588	18,869
March	RE 5,010	E 631	RE 5,641	2,168	RE 7,809	956	1,027	11,593	2,660	8,933	-126	R 397	19,248
April	RE 4,965	E 606	RE 5,571	2,157	RE 7,728	941	1,001	11,592	2,903	8,689	218	R 472	18,613
May	RE 5,055	E 601	RE 5,657	2,222	RE 7,879	934	1,083	11,669	2,642	9,028	926	R 365	18,363
June	RE 5,058	E 553	RE 5,612	2,176	RE 7,788	945	1,101	11,794	2,607	9,187	96	R 353	19,277
July	RE 5,012	E 468	RE 5,480	2,193	RE 7,673	936	1,125	11,667	2,919	8,748	399	R 473	18,555
August	RE 5,162	E 544	RE 5,705	2,201	RE 7,906	958	1,132	11,145	3,071	8,074	-623	R 460	19,153
September	RE 5,037	E 585	RE 5,622	2,145	RE 7,767	937	1,132	11,209	3,158	8,051	-659	R 250	18,795
October	RE 5,346	E 585	RE 5,930	2,274	RE 8,205	944	1,106	10,994	3,104	7,890	-359	R 59	18,563
November	RE 5,461	E 593	RE 6,054	2,342	RE 8,396	992	1,117	11,166	3,182	7,985	65	R 310	18,734
December	RE 5,457	E 611	RE 6,069	2,351	RE 8,420	1,003	1,135	10,957	3,549	7,407	-654	R 119	18,738
Average	RE 5,123	E 572	RE 5,694	2,183	RE 7,877	954	1,085	11,360	2,924	8,436	-115	R 369	18,835
2012 January	RE 5,550	E 612	RE 6,162	2,376	RE 8,538	R 1,021	1,053	10,944	2,839	8,104	R 655	R 219	R 18,280
February	RE 5,628	E 582	RE 6,210	2,388	RE 8,599	R 1,012	1,068	10,464	2,980	7,484	R -228	R 369	R 18,760
March	RE 5,721	E 567	RE 6,288	2,375	RE 8,663	R 994	1,023	10,610	3,064	7,547	R 409	R 394	R 18,213
April	RE 5,677	E 552	RE 6,230	2,382	RE 8,612	R 1,001	1,047	10,634	3,263	7,370	R -18	R 281	R 18,330
May	RE 5,718	RE 547	RE 6,265	R 2,376	RE 8,641	R 1,018	R 1,089	R 11,132	R 3,194	R 7,939	R 524	R 545	R 18,707
June	E 5,740	E 496	E 6,236	E 2,288	E 8,524	E 940	E 1,143	E 11,326	E 2,935	E 8,391	E 387	E 514	E 19,125
July	E 5,865	E 420	E 6,285	E 2,087	E 8,372	E 873	E 1,146	E 10,895	E 2,880	E 8,015	E 184	E 654	E 18,876
7-Month Average	E 5,701	E 539	E 6,240	E 2,324	E 8,564	E 980	E 1,081	E 10,860	E 3,022	E 7,839	E 279	E 426	E 18,611
2011 7-Month Average	E 4,999	E 564	E 5,563	2,125	E 7,688	944	1,056	11,552	2,715	8,837	125	462	18,863
2010 7-Month Average	4,816	601	5,417	2,047	7,464	885	1,053	11,997	2,249	9,748	372	274	19,053

<sup>a</sup> Crude oil production on leases, and natural gas liquids (liquefied petroleum gases, pentanes plus, and a small amount of finished petroleum products) production at natural gas processing plants. Excludes what was previously classified as "Field Production" of finished motor gasoline, motor gasoline blending components, and other hydrocarbons and oxygenates; these are now included in "Adjustments."

<sup>b</sup> Includes lease condensate.

<sup>c</sup> Data for crude oil production, total field production, and adjustments are revised monthly going back as far as the data year of the U.S. Energy Information Administration's (EIA) last published *Petroleum Supply Annual (PSA)*—these revisions are released at the same time as EIA's *Petroleum Supply Monthly*. Once a year, data for these series are revised going back as far as 10 years—these revisions are released at the same time as the PSA.

<sup>d</sup> United States excluding Alaska and Hawaii.

<sup>e</sup> Natural gas plant liquids.

<sup>f</sup> See Note 6, "Petroleum Data Discrepancies," at end of section.

<sup>g</sup> Renewable fuels and oxygenate plant net production.

<sup>h</sup> Refinery and blender net production minus refinery and blender net inputs. See Table 3.2.

<sup>i</sup> Includes Strategic Petroleum Reserve imports. See Table 3.3b.

<sup>j</sup> Net imports equal imports minus exports.

<sup>k</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase. The current month stock change estimate is based on the change from the previous month's estimate, rather than the stocks values shown in Table 3.4. Includes crude oil stocks in the Strategic Petroleum Reserve, but excludes distillate fuel oil stocks in the Northeast Heating Oil Reserve. See Table 3.4. Also see Note 4, "Petroleum New Stock Basis," at end of section.

<sup>l</sup> An adjustment for crude oil, hydrogen, oxygenates, renewable fuels, other hydrocarbons, motor gasoline blending components, finished motor gasoline, and distillate fuel oil. See EIA, *Petroleum Supply Monthly*, Appendix B, "PSM Explanatory Notes," for further information.

R=Revised. E=Estimate. NA=Not available.


Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.


Sources: See end of section.

**Figure 3.2 Refinery and Blender Net Inputs and Net Production**  
(Million Barrels per Day)


Net Inputs and Net Production, 1973-2011




Net Inputs and Net Production, Monthly




Net Production, Selected Products, 1973-2011



Net Production, Selected Products, Monthly



Net Production, Selected Products



<sup>a</sup> Includes lease condensate.

<sup>b</sup> Natural gas plant liquids and other liquids.

<sup>c</sup> Beginning in 1993, includes fuel ethanol blended into motor gasoline.

<sup>d</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>e</sup> Beginning in 2005, includes kerosene-type jet fuel only.

<sup>f</sup> Includes propylene.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Source: Table 3.2.



**Table 3.2 Refinery and Blender Net Inputs and Net Production**  
(Thousand Barrels per Day)


	Refinery and Blender Net Inputs <sup>a</sup>				Refinery and Blender Net Production <sup>b</sup>							
	Crude Oil <sup>d</sup>	NGPL <sup>e</sup>	Other Liquids <sup>f</sup>	Total	Distillate Fuel Oil <sup>g</sup>	Jet Fuel <sup>h</sup>	LPG <sup>c</sup>		Motor Gasoline <sup>i</sup>	Residual Fuel Oil	Other Products <sup>k</sup>	Total
							Propane <sup>j</sup>	Total				
1973 Average	12,431	815	155	13,401	2,820	859	271	375	6,527	971	2,301	13,854
1975 Average	12,442	710	72	13,225	2,653	871	234	311	6,518	1,235	2,097	13,685
1980 Average	13,481	462	81	14,025	2,661	999	269	330	6,492	1,580	2,559	14,622
1985 Average	12,002	509	681	13,192	2,686	1,189	295	391	6,419	882	2,183	13,750
1990 Average	13,409	467	713	14,589	2,925	1,488	404	499	6,959	950	2,452	15,272
1995 Average	13,973	471	775	15,220	3,155	1,416	503	654	7,459	788	2,522	15,994
1996 Average	14,195	450	843	15,487	3,316	1,515	520	662	7,565	726	2,541	16,324
1997 Average	14,662	416	832	15,909	3,392	1,554	565	691	7,743	708	2,671	16,759
1998 Average	14,889	403	853	16,144	3,424	1,526	550	674	7,892	762	2,753	17,030
1999 Average	14,804	372	927	16,103	3,399	1,565	569	684	7,934	698	2,709	16,989
2000 Average	15,067	380	849	16,295	3,580	1,606	583	705	7,951	696	2,705	17,243
2001 Average	15,128	429	825	16,382	3,695	1,530	556	667	8,022	721	2,651	17,285
2002 Average	14,947	429	941	16,316	3,592	1,514	572	671	8,183	601	2,712	17,273
2003 Average	15,304	419	791	16,513	3,707	1,488	570	658	8,194	660	2,780	17,487
2004 Average	15,475	422	866	16,762	3,814	1,547	584	645	8,265	655	2,887	17,814
2005 Average	15,220	441	1,149	16,811	3,954	1,546	540	573	8,318	628	2,782	17,800
2006 Average	15,242	501	1,238	16,981	4,040	1,481	543	627	8,364	635	2,827	17,975
2007 Average	15,156	505	1,337	16,999	4,133	1,448	562	655	8,358	673	2,728	17,994
2008 Average	14,648	485	2,019	17,153	4,294	1,493	519	630	8,548	620	2,561	18,146
2009 Average	14,336	485	2,082	16,904	4,048	1,396	537	623	8,786	598	2,431	17,882
2010 January	13,666	503	1,501	15,670	3,551	1,338	531	480	8,348	633	2,281	16,631
February	13,950	402	1,654	16,005	3,658	1,340	562	540	8,510	632	2,385	17,065
March	14,314	413	2,166	16,893	3,835	1,379	575	726	8,913	581	2,523	17,957
April	15,131	374	2,135	17,640	4,156	1,470	585	850	9,062	598	2,531	18,668
May	15,215	399	2,348	17,963	4,375	1,449	571	857	9,113	615	2,622	19,031
June	15,382	397	2,349	18,127	4,408	1,495	572	870	9,211	559	2,670	19,212
July	15,519	384	2,595	18,498	4,425	1,542	574	860	9,500	576	2,704	19,607
August	15,110	390	2,607	18,107	4,404	1,463	552	778	9,426	554	2,605	19,230
September	14,740	443	2,294	17,477	4,341	1,404	551	614	9,143	588	2,449	18,539
October	14,000	504	2,517	17,021	4,315	1,317	526	501	9,049	528	2,323	18,033
November	14,637	531	2,223	17,391	4,503	1,394	543	390	9,134	564	2,457	18,442
December	14,976	563	2,185	17,724	4,670	1,417	572	430	9,252	595	2,547	18,911
Average	14,724	442	2,219	17,385	4,223	1,418	560	659	9,059	585	2,509	18,452
2011 January	14,446	543	1,732	16,721	4,305	1,362	560	439	8,671	552	2,459	17,788
February	13,745	517	2,229	16,491	4,032	1,298	513	490	8,793	529	2,329	17,471
March	14,453	454	2,183	17,090	4,284	1,435	525	632	8,824	519	2,424	18,117
April	14,302	452	2,494	17,248	4,187	1,422	540	773	8,931	535	2,402	18,249
May	14,776	427	2,457	17,660	4,277	1,483	561	805	9,142	557	2,477	18,742
June	15,365	443	2,440	18,248	4,469	1,568	566	840	9,286	553	2,632	19,349
July	15,617	417	2,247	18,281	4,655	1,550	557	814	9,165	562	2,659	19,405
August	15,592	437	2,353	18,382	4,667	1,543	550	784	9,265	604	2,652	19,514
September	15,269	494	2,092	17,855	4,574	1,553	569	608	9,132	516	2,604	18,987
October	14,543	524	2,252	17,318	4,534	1,375	541	494	8,953	529	2,540	18,425
November	14,958	597	2,110	17,665	4,903	1,341	564	384	9,125	516	2,512	18,781
December	14,841	566	2,263	17,670	4,919	1,449	566	372	9,118	482	2,464	18,805
Average	14,833	489	2,237	17,559	4,487	1,449	551	620	9,035	538	2,514	18,643
2012 January	14,415	513	1,633	16,561	4,498	1,437	518	414	8,427	495	2,343	17,613
February	14,659	531	1,618	16,809	4,416	1,401	532	492	8,645	547	2,375	17,876
March	14,545	445	2,022	17,012	4,262	1,412	545	685	8,753	577	2,347	18,035
April	14,614	443	2,215	17,272	4,330	1,433	558	833	8,763	525	2,436	18,319
May	15,177	429	2,228	17,833	4,537	1,468	569	856	8,952	509	2,601	18,922
June	15,636	424	2,368	18,429	4,670	1,587	574	843	9,119	558	2,795	19,572
July	15,653	427	2,184	18,264	4,687	1,620	567	815	8,895	496	2,897	19,410
7-Month Average	14,958	459	2,040	17,457	4,486	1,480	564	706	8,793	529	2,543	18,538
2011 7-Month Average	14,684	464	2,253	17,401	4,319	1,447	546	686	8,974	544	2,485	18,456
2010 7-Month Average	14,746	411	2,112	17,268	4,062	1,431	567	742	8,956	599	2,532	18,322

<sup>a</sup> See "Refinery and Blender Net Inputs," in Glossary.  
<sup>b</sup> See "Refinery and Blender Net Production," in Glossary.  
<sup>c</sup> Liquefied petroleum gases.  
<sup>d</sup> Includes lease condensate.  
<sup>e</sup> Natural gas plant liquids (liquefied petroleum gases and pentanes plus).  
<sup>f</sup> Unfinished oils (net), other hydrocarbons, and hydrogen. Beginning in 1981, also includes aviation and motor gasoline blending components (net). Beginning in 1993, also includes oxygenates (net), including fuel ethanol. Beginning in 2009, also includes renewable diesel fuel (including biodiesel).  
<sup>g</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.  
<sup>h</sup> Through 2004, includes kerosene-type and naphtha-type jet fuel. Beginning in 2005, includes kerosene-type jet fuel only; naphtha-type jet fuel is included in "Other Products."  
<sup>i</sup> Includes propylene.  
<sup>j</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.


<sup>k</sup> Asphalt and road oil, finished aviation gasoline, kerosene, lubricants, petrochemical feedstocks, petroleum coke, special naphthas, still gas, waxes, and miscellaneous products. Beginning in 2005, also includes naphtha-type jet fuel.  
R=Revised. E=Estimate. F=Forecast.  
Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.  
Sources: • 1973-1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • 1976-1980: U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • 1981-2010: EIA, *Petroleum Supply Annual*, annual reports. • 2011 and 2012: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.

### Figure 3.3a Petroleum Trade: Overview


Overview, May 2012




Imports From OPEC and Persian Gulf as Share of Total Imports, 1973-2011




Imports From OPEC and Persian Gulf as Share of Total Imports, January-May



Net Imports as Share of Products Supplied, 1973-2011



Net Imports as Share of Products Supplied, January-July



Note: OPEC=Organization of the Petroleum Exporting Countries.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
 Source: Table 3.3a.

**Table 3.3a Petroleum Trade: Overview**

	Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>	Imports	Exports	Net Imports	Products Supplied	As Share of Products Supplied				As Share of Total Imports	
							Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>	Imports	Net Imports	Imports From Persian Gulf <sup>a</sup>	Imports From OPEC <sup>b</sup>
							Thousand Barrels per Day					
<b>1973 Average</b> .....	848	2,993	6,256	231	6,025	17,308	4.9	17.3	36.1	34.8	13.6	47.8
<b>1975 Average</b> .....	1,165	3,601	6,056	209	5,846	16,322	7.1	22.1	37.1	35.8	19.2	59.5
<b>1980 Average</b> .....	1,519	4,300	6,909	544	6,365	17,056	8.9	25.2	40.5	37.3	22.0	62.2
<b>1985 Average</b> .....	311	1,830	5,067	781	4,286	15,726	2.0	11.6	32.2	27.3	6.1	36.1
<b>1990 Average</b> .....	1,966	4,296	8,018	857	7,161	16,988	11.6	25.3	47.2	42.2	24.5	53.6
<b>1995 Average</b> .....	1,573	4,002	8,835	949	7,886	17,725	8.9	22.6	49.8	44.5	17.8	45.3
<b>1996 Average</b> .....	1,604	4,211	9,478	981	8,498	18,309	8.8	23.0	51.8	46.4	16.9	44.4
<b>1997 Average</b> .....	1,755	4,569	10,162	1,003	9,158	18,620	9.4	24.5	54.6	49.2	17.3	45.0
<b>1998 Average</b> .....	2,136	4,905	10,708	945	9,764	18,917	11.3	25.9	56.6	51.6	19.9	45.8
<b>1999 Average</b> .....	2,464	4,953	10,852	940	9,912	19,519	12.6	25.4	55.6	50.8	22.7	45.6
<b>2000 Average</b> .....	2,488	5,203	11,459	1,040	10,419	19,701	12.6	26.4	58.2	52.9	21.7	45.4
<b>2001 Average</b> .....	2,761	5,528	11,871	971	10,900	19,649	14.1	28.1	60.4	55.5	23.3	46.6
<b>2002 Average</b> .....	2,269	4,605	11,530	984	10,546	19,761	11.5	23.3	58.3	53.4	19.7	39.9
<b>2003 Average</b> .....	2,501	5,162	12,264	1,027	11,238	20,034	12.5	25.8	61.2	56.1	20.4	42.1
<b>2004 Average</b> .....	2,493	5,701	13,145	1,048	12,097	20,731	12.0	27.5	63.4	58.4	19.0	43.4
<b>2005 Average</b> .....	2,334	5,587	13,714	1,165	12,549	20,802	11.2	26.9	65.9	60.3	17.0	40.7
<b>2006 Average</b> .....	2,211	5,517	13,707	1,317	12,390	20,687	10.7	26.7	66.3	59.9	16.1	40.2
<b>2007 Average</b> .....	2,163	5,980	13,468	1,433	12,036	20,680	10.5	28.9	65.1	58.2	16.1	44.4
<b>2008 Average</b> .....	2,370	5,954	12,915	1,802	11,114	19,498	12.2	30.5	66.2	57.0	18.4	46.1
<b>2009 Average</b> .....	1,689	4,776	11,691	2,024	9,667	18,771	9.0	25.4	62.3	51.5	14.4	40.9
<b>2010 January</b> .....	1,563	4,554	11,300	1,897	9,404	18,652	8.4	24.4	60.6	50.4	13.8	40.3
February .....	1,666	4,659	11,230	2,034	9,197	18,850	8.8	24.7	59.6	48.8	14.8	41.5
March .....	1,842	5,084	11,621	2,149	9,472	19,099	9.6	26.6	60.8	49.6	15.9	43.7
April .....	2,026	5,376	12,526	2,432	10,093	19,044	10.6	28.2	65.8	53.0	16.2	42.9
May .....	1,724	5,055	12,141	2,399	9,742	18,866	9.1	26.8	64.4	51.6	14.2	41.6
June .....	1,972	5,297	12,444	2,304	10,140	19,537	10.1	27.1	63.7	51.9	15.8	42.6
July .....	1,679	5,178	12,675	2,516	10,159	19,319	8.7	26.8	65.6	52.6	13.2	40.8
August .....	1,663	5,117	12,356	2,410	9,946	19,662	8.5	26.0	62.8	50.6	13.5	41.4
September .....	1,698	5,111	11,823	2,345	9,478	19,438	8.7	26.3	60.8	48.8	14.4	43.2
October .....	1,490	4,305	11,142	2,480	8,662	18,974	7.9	22.7	58.7	45.7	13.4	38.6
November .....	1,662	4,525	11,096	2,598	8,498	18,977	8.8	23.8	58.5	44.8	15.0	40.8
December .....	1,564	4,614	11,132	2,644	8,488	19,722	7.9	23.4	56.4	43.0	14.0	41.4
<b>Average</b> .....	<b>1,711</b>	<b>4,906</b>	<b>11,793</b>	<b>2,353</b>	<b>9,441</b>	<b>19,180</b>	<b>8.9</b>	<b>25.6</b>	<b>61.5</b>	<b>49.2</b>	<b>14.5</b>	<b>41.6</b>
<b>2011 January</b> .....	1,719	4,872	11,954	2,687	9,266	19,121	9.0	25.5	62.5	48.5	14.4	40.8
February .....	1,495	4,504	10,503	2,575	7,929	18,869	7.9	23.9	55.7	42.0	14.2	42.9
March .....	1,651	4,588	11,593	2,660	8,933	19,248	8.6	23.8	60.2	46.4	14.2	39.6
April .....	1,704	4,509	11,592	2,903	8,689	18,613	9.2	24.2	62.3	46.7	14.7	38.9
May .....	1,829	4,572	11,669	2,642	9,028	18,363	10.0	24.9	63.5	49.2	15.7	39.2
June .....	2,033	4,883	11,794	2,607	9,187	19,277	10.5	25.3	61.2	47.7	17.2	41.4
July .....	2,167	4,928	11,667	2,919	8,748	18,555	11.7	26.6	62.9	47.1	18.6	42.2
August .....	1,910	4,648	11,145	3,071	8,074	19,153	10.0	24.3	58.2	42.2	17.1	41.7
September .....	2,039	4,326	11,209	3,158	8,051	18,795	10.8	23.0	59.6	42.8	18.2	38.6
October .....	1,904	4,267	10,994	3,104	7,890	18,563	10.3	23.0	59.2	42.5	17.3	38.8
November .....	1,944	4,219	11,166	3,182	7,985	18,734	10.4	22.5	59.6	42.6	17.4	37.8
December .....	1,921	4,085	10,957	3,549	7,407	18,738	10.3	21.8	58.5	39.5	17.5	37.3
<b>Average</b> .....	<b>1,862</b>	<b>4,534</b>	<b>11,360</b>	<b>2,924</b>	<b>8,436</b>	<b>18,835</b>	<b>9.9</b>	<b>24.1</b>	<b>60.3</b>	<b>44.8</b>	<b>16.4</b>	<b>39.9</b>
<b>2012 January</b> .....	2,208	4,203	10,944	2,839	8,104	18,280	12.1	23.0	59.9	44.3	20.2	38.4
February .....	1,948	3,986	10,464	2,980	7,484	18,760	10.4	21.2	55.8	39.9	18.6	38.1
March .....	2,222	4,314	10,610	3,064	7,547	18,213	12.2	23.7	58.3	41.4	20.9	40.7
April .....	2,228	4,394	10,634	3,263	7,370	18,330	12.2	24.0	58.0	40.2	21.0	41.3
May .....	2,250	4,672	11,132	3,194	7,939	18,707	13.7	25.0	59.5	42.4	23.0	42.0
June .....	NA	NA	11,326	2,935	8,391	19,125	NA	NA	59.2	43.9	NA	NA
July .....	NA	NA	10,895	2,880	8,015	18,876	NA	NA	57.7	42.5	NA	NA
<b>7-Month Average</b> .....	<b>NA</b>	<b>NA</b>	<b>10,860</b>	<b>3,022</b>	<b>7,839</b>	<b>18,611</b>	<b>NA</b>	<b>NA</b>	<b>58.4</b>	<b>42.1</b>	<b>NA</b>	<b>NA</b>
<b>2011 7-Month Average</b> .....	<b>1,804</b>	<b>4,696</b>	<b>11,552</b>	<b>2,715</b>	<b>8,837</b>	<b>18,863</b>	<b>9.6</b>	<b>24.9</b>	<b>61.2</b>	<b>46.9</b>	<b>15.6</b>	<b>40.7</b>
<b>2010 7-Month Average</b> .....	<b>1,781</b>	<b>5,031</b>	<b>11,997</b>	<b>2,249</b>	<b>9,748</b>	<b>19,053</b>	<b>9.3</b>	<b>26.4</b>	<b>63.0</b>	<b>51.2</b>	<b>14.8</b>	<b>41.9</b>

<sup>a</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).

<sup>b</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. See Table 3.3c for notes on which countries are included in the data.

R=Revised. E=Estimate. NA=Not available.  
Notes: • Readers of this table may be interested in a feature article, "Measuring Dependence on Imported Oil," that was published in the August 1995 *Monthly Energy Review*. See [http://www.eia.gov/totalenergy/data/monthly/pdf/historical/imported\\_oil.pdf](http://www.eia.gov/totalenergy/data/monthly/pdf/historical/imported_oil.pdf).

• Beginning in October 1977, data include Strategic Petroleum Reserve imports. See Table 3.3b. • Annual averages may not equal averages of months due to independent rounding. • U.S. geographic coverage is the 50 States and the


District of Columbia. U.S. exports include shipments to U.S. territories, and imports include receipts from U.S. territories.

Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.


Sources: • **1973-1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976-1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981-2010:** EIA, *Petroleum Supply Annual*, annual reports. • **2011 and 2012:** EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

**Figure 3.3b Petroleum Trade: Imports**  
(Million Barrels per Day)


Overview, 1973-2011




Crude Oil and Petroleum Products, January-July




OPEC and Non-OPEC, 1973-2011




OPEC and Non-OPEC



From Selected OPEC Countries, May 2012



From Selected Non-OPEC Countries, May 2012



Note: OPEC=Organization of the Petroleum Exporting Countries.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
Sources: Tables 3.3b-3.3d.

**Table 3.3b Petroleum Trade: Imports and Exports by Type**  
(Thousand Barrels per Day)

	Imports										Exports		
	Crude Oil <sup>a</sup>		Distillate Fuel Oil	Jet Fuel <sup>e</sup>	LPG <sup>b</sup>		Motor Gasoline <sup>g</sup>	Residual Fuel Oil	Other <sup>h</sup>	Total	Crude Oil <sup>a</sup>	Petroleum Products	Total
	SPR <sup>c,d</sup>	Total			Propane <sup>f</sup>	Total							
1973 Average	--	3,244	392	212	71	132	134	1,853	290	6,256	2	229	231
1975 Average	--	4,105	155	133	60	112	184	1,223	144	6,056	6	204	209
1980 Average	44	5,263	142	80	69	216	140	939	130	6,909	287	258	544
1985 Average	118	3,201	200	39	67	187	381	510	550	5,067	204	577	781
1990 Average	27	5,894	278	108	115	188	342	504	705	8,018	109	748	857
1995 Average	--	7,230	193	106	102	146	265	187	708	8,835	95	855	949
1996 Average	--	7,508	230	111	119	166	336	248	879	9,478	110	871	981
1997 Average	--	8,225	228	91	113	169	309	194	945	10,162	108	896	1,003
1998 Average	--	8,706	210	124	137	194	311	275	888	10,708	110	835	945
1999 Average	8	8,731	250	128	122	182	382	237	943	10,852	118	822	940
2000 Average	8	9,071	295	162	161	215	427	352	938	11,459	50	990	1,040
2001 Average	11	9,328	344	148	145	206	454	295	1,095	11,871	20	951	971
2002 Average	16	9,140	267	107	145	183	498	249	1,085	11,530	9	975	984
2003 Average	--	9,665	333	109	168	225	518	327	1,087	12,264	12	1,014	1,027
2004 Average	77	10,088	325	127	209	263	496	426	1,419	13,145	27	1,021	1,048
2005 Average	52	10,126	329	190	233	328	603	530	1,609	13,714	32	1,133	1,165
2006 Average	8	10,118	365	186	228	332	475	350	1,881	13,707	25	1,292	1,317
2007 Average	7	10,031	304	217	182	247	413	372	1,885	13,468	27	1,405	1,433
2008 Average	19	9,783	213	103	185	253	302	349	1,913	12,915	29	1,773	1,802
2009 Average	56	9,013	225	81	147	182	223	331	1,635	11,691	44	1,980	2,024
<b>2010</b>													
January	--	8,492	462	131	192	225	179	376	1,435	11,300	33	1,864	1,897
February	--	8,761	293	75	217	242	196	382	1,282	11,230	58	1,976	2,034
March	--	9,341	179	79	137	155	120	376	1,370	11,621	45	2,104	2,149
April	--	9,726	220	88	79	102	178	480	1,732	12,526	37	2,396	2,432
May	--	9,655	189	81	82	108	107	404	1,599	12,141	36	2,363	2,399
June	--	9,927	237	114	73	113	163	283	1,607	12,444	31	2,273	2,304
July	--	9,932	170	113	56	104	114	400	1,841	12,675	69	2,447	2,516
August	--	9,543	246	103	62	107	129	330	1,899	12,356	36	2,374	2,410
September	--	9,229	189	122	85	124	130	367	1,662	11,823	61	2,283	2,345
October	--	8,540	163	94	131	165	86	337	1,758	11,142	23	2,457	2,480
November	--	8,699	178	101	132	165	117	345	1,491	11,096	32	2,567	2,598
December	--	8,695	219	73	214	231	99	315	1,501	11,132	40	2,604	2,644
<b>Average</b>	--	<b>9,213</b>	<b>228</b>	<b>98</b>	<b>121</b>	<b>153</b>	<b>134</b>	<b>366</b>	<b>1,600</b>	<b>11,793</b>	<b>42</b>	<b>2,311</b>	<b>2,353</b>
<b>2011</b>													
January	--	9,069	326	65	172	204	103	456	1,733	11,954	72	2,616	2,687
February	--	8,013	206	68	172	199	119	428	1,471	10,503	30	2,544	2,575
March	--	9,033	190	65	136	165	135	468	1,538	11,593	36	2,623	2,660
April	--	8,715	186	80	94	113	138	519	1,842	11,592	41	2,862	2,903
May	--	8,988	167	91	73	100	137	299	1,887	11,669	37	2,605	2,642
June	--	9,247	126	82	58	85	130	371	1,753	11,794	36	2,571	2,607
July	--	9,310	153	95	61	84	92	246	1,686	11,667	73	2,846	2,919
August	--	9,021	148	66	72	100	106	229	1,474	11,145	34	3,037	3,071
September	--	9,006	177	58	107	130	99	276	1,463	11,209	35	3,123	3,158
October	--	9,029	127	61	93	116	66	282	1,314	10,994	51	3,054	3,104
November	--	8,826	133	72	107	127	74	340	1,594	11,166	64	3,118	3,182
December	--	8,716	174	21	149	174	60	333	1,478	10,957	53	3,496	3,549
<b>Average</b>	--	<b>8,921</b>	<b>176</b>	<b>69</b>	<b>108</b>	<b>133</b>	<b>105</b>	<b>353</b>	<b>1,603</b>	<b>11,360</b>	<b>47</b>	<b>2,877</b>	<b>2,924</b>
<b>2012</b>													
January	--	8,572	156	6	145	168	99	305	1,637	10,944	56	2,783	2,839
February	--	8,558	142	41	125	155	46	226	1,296	10,464	59	2,921	2,980
March	--	8,767	136	5	108	136	91	271	1,205	10,610	60	3,004	3,064
April	--	8,591	98	56	102	129	53	240	1,466	10,634	32	3,231	3,263
May	--	<sup>R</sup> 8,909	<sup>R</sup> 111	<sup>R</sup> 49	<sup>R</sup> 172	<sup>R</sup> 218	<sup>R</sup> 60	<sup>R</sup> 251	<sup>R</sup> 1,534	<sup>R</sup> 11,132	<sup>R</sup> 69	<sup>R</sup> 3,124	<sup>R</sup> 3,194
June	--	<sup>E</sup> 9,081	<sup>E</sup> 77	<sup>E</sup> 15	<sup>E</sup> 70	NA	<sup>E</sup> 61	<sup>E</sup> 281	NA	<sup>E</sup> 11,326	<sup>E</sup> 39	<sup>E</sup> 2,896	<sup>E</sup> 2,935
July	--	<sup>E</sup> 8,874	<sup>E</sup> 96	<sup>E</sup> 31	<sup>E</sup> 86	NA	<sup>E</sup> 48	<sup>E</sup> 243	NA	<sup>E</sup> 10,895	<sup>E</sup> 40	<sup>E</sup> 2,841	<sup>E</sup> 2,880
<b>7-Month Average</b>	--	<b><sup>E</sup>8,766</b>	<b><sup>E</sup>117</b>	<b><sup>E</sup>29</b>	<b><sup>E</sup>116</b>	<b>NA</b>	<b><sup>E</sup>66</b>	<b><sup>E</sup>260</b>	<b>NA</b>	<b><sup>E</sup>10,860</b>	<b><sup>E</sup>51</b>	<b><sup>E</sup>2,971</b>	<b><sup>E</sup>3,022</b>
<b>2011 7-Month Average</b>	--	<b>8,923</b>	<b>194</b>	<b>78</b>	<b>109</b>	<b>135</b>	<b>122</b>	<b>397</b>	<b>1,704</b>	<b>11,552</b>	<b>47</b>	<b>2,668</b>	<b>2,715</b>
<b>2010 7-Month Average</b>	--	<b>9,410</b>	<b>249</b>	<b>97</b>	<b>118</b>	<b>149</b>	<b>150</b>	<b>386</b>	<b>1,555</b>	<b>11,997</b>	<b>44</b>	<b>2,205</b>	<b>2,249</b>

<sup>a</sup> Includes lease condensate.  
<sup>b</sup> Liquefied petroleum gases.  
<sup>c</sup> "SPR" is the Strategic Petroleum Reserve, which began in October 1977. Through 2003, includes crude oil imports by SPR only; beginning in 2004, includes crude oil imports by SPR, and crude oil imports into SPR by others.  
<sup>d</sup> See Note 6, "Petroleum Data Discrepancies," at end of section.  
<sup>e</sup> Through 2004, includes kerosene-type and naphtha-type jet fuel. Beginning in 2005, includes kerosene-type jet fuel only; naphtha-type jet fuel is included in "Other."  
<sup>f</sup> Includes propylene.  
<sup>g</sup> Finished motor gasoline. Through 1980, also includes motor gasoline blending components.  
<sup>h</sup> Asphalt and road oil, finished aviation gasoline, gasoline blending components, kerosene, lubricants, pentanes plus, petrochemical feedstocks, petroleum coke, special naphthas, unfinished oils, waxes, other hydrocarbons and oxygenates, and miscellaneous products. Beginning in 2005, also includes

naphtha-type jet fuel.  
R=Revised. E=Estimate. NA=Not available. -- =Not applicable. -- =No data reported.  
Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.  
Sources: • **1973-1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976-1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981-2010:** EIA, *Petroleum Supply Annual*, annual reports. • **2011 and 2012:** EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

**Table 3.3c Petroleum Trade: Imports From OPEC Countries**  
(Thousand Barrels per Day)

	Algeria	Angola <sup>a</sup>	Ecuador <sup>b</sup>	Iraq	Kuwait <sup>c</sup>	Libya	Nigeria	Saudi Arabia <sup>c</sup>	Venezuela	Other <sup>d</sup>	Total OPEC
1973 Average	136	(a)	48	4	47	164	459	486	1,135	514	2,993
1975 Average	282	(a)	57	2	16	232	762	715	702	832	3,601
1980 Average	488	(a)	27	28	27	554	857	1,261	481	577	4,300
1985 Average	187	(a)	67	46	21	4	293	168	605	439	1,830
1990 Average	280	(a)	49	518	86	0	800	1,339	1,025	199	4,296
1995 Average	234	(a)	(b)	0	218	0	627	1,344	1,480	98	4,002
1996 Average	256	(a)	(b)	1	236	0	617	1,363	1,676	62	4,211
1997 Average	285	(a)	(b)	89	253	0	698	1,407	1,773	64	4,569
1998 Average	290	(a)	(b)	336	301	0	696	1,491	1,719	73	4,905
1999 Average	259	(a)	(b)	725	248	0	657	1,478	1,493	93	4,953
2000 Average	225	(a)	(b)	620	272	0	896	1,572	1,546	72	5,203
2001 Average	278	(a)	(b)	795	250	0	885	1,662	1,553	105	5,528
2002 Average	264	(a)	(b)	459	228	0	621	1,552	1,398	83	4,605
2003 Average	382	(a)	(b)	481	220	0	867	1,774	1,376	61	5,162
2004 Average	452	(a)	(b)	656	250	20	1,140	1,558	1,554	70	5,701
2005 Average	478	(a)	(b)	531	243	56	1,166	1,537	1,529	47	5,587
2006 Average	657	(a)	(b)	553	185	87	1,114	1,463	1,419	38	5,517
2007 Average	670	508	(b)	484	181	117	1,134	1,485	1,361	39	5,980
2008 Average	548	513	221	627	210	103	988	1,529	1,189	26	5,954
2009 Average	493	460	185	450	182	79	809	1,004	1,063	50	4,776
2010 January	498	280	215	523	77	40	1,048	963	911	—	4,554
February	498	360	152	540	228	40	932	898	1,010	—	4,659
March	455	502	183	475	218	79	962	1,149	1,061	—	5,084
April	464	509	225	490	278	142	1,060	1,257	951	—	5,376
May	518	448	182	394	225	39	1,026	1,097	1,117	10	5,055
June	550	425	245	630	217	98	1,108	1,125	899	—	5,297
July	518	374	239	430	189	110	1,174	1,053	1,084	7	5,178
August	565	484	276	281	251	123	985	1,132	1,022	—	5,117
September	543	417	229	422	172	43	1,174	1,093	1,008	10	5,111
October	451	324	203	143	215	36	872	1,131	930	—	4,305
November	572	276	194	340	170	23	856	1,152	942	—	4,525
December	484	319	192	336	125	66	1,070	1,093	917	9	4,614
Average	510	393	212	415	197	70	1,023	1,096	988	3	4,906
2011 January	565	316	178	470	147	57	1,007	1,102	1,030	—	4,872
February	394	370	242	263	118	35	978	1,114	989	—	4,504
March	500	280	146	382	161	31	913	1,108	1,067	—	4,588
April	466	277	142	519	78	(s)	922	1,107	997	—	4,509
May	400	356	134	407	200	(s)	854	1,203	999	19	4,572
June	293	373	219	559	238	35	853	1,169	1,077	68	4,883
July	354	407	172	596	228	—	884	1,326	943	18	4,928
August	298	331	309	637	165	1	892	1,075	906	32	4,648
September	291	304	305	404	145	2	580	1,479	806	11	4,326
October	173	424	178	490	278	2	690	1,120	894	17	4,267
November	260	355	181	395	302	10	703	1,222	764	26	4,219
December	297	357	106	380	231	9	534	1,310	860	—	4,085
Average	358	346	192	460	191	15	817	1,195	944	16	4,534
2012 January	269	370	100	390	352	5	504	1,423	750	41	4,203
February	256	230	244	271	252	29	353	1,420	931	—	3,986
March	325	175	174	386	462	60	374	1,374	984	—	4,314
April	259	253	201	395	235	68	483	1,589	904	7	4,394
May	303	256	199	675	407	65	428	1,471	861	7	4,672
5-Month Average	283	257	183	426	344	46	429	1,455	885	11	4,318
2011 5-Month Average	466	319	167	410	142	24	934	1,127	1,017	4	4,612
2010 5-Month Average	487	420	192	483	204	68	1,007	1,075	1,010	2	4,948

<sup>a</sup> Angola joined OPEC in January 2007. For 1973-2006, Angola is included in "Total Non-OPEC" on Table 3.3d.

<sup>b</sup> Ecuador was a member of OPEC from 1973-1992, and rejoined OPEC in November 2007. For 1993-2007, Ecuador is included in "Total Non-OPEC" on Table 3.3d.

<sup>c</sup> Imports from the Neutral Zone are reported as originating in either Saudi Arabia or Kuwait depending on the country reported to U.S. Customs.

<sup>d</sup> For all years, includes Iran, Qatar, and United Arab Emirates. For 1973-2008, also includes Indonesia; and for 1975-1994, also includes Gabon.

—=No data reported. (s)=Less than 500 barrels per day.

Notes: • See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. Petroleum imports not classified as "OPEC" on this table are included on Table 3.3d. • The country of origin for petroleum products may not be the country of origin for the crude oil from which the products were produced. For example,

refined products imported from West European refining areas may have been produced from Middle East crude oil. • Includes imports for the Strategic Petroleum Reserve, which began in October 1977. • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 States and the District of Columbia.

Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.

Sources: • 1973-1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • 1976-1980: U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • 1981-2010: EIA, *Petroleum Supply Annual*, annual reports. • 2011 and 2012: EIA, *Petroleum Supply Monthly*, monthly reports.

**Table 3.3d Petroleum Trade: Imports From Non-OPEC Countries**  
(Thousand Barrels per Day)

	Brazil	Canada	Colombia	Mexico	Nether-lands	Norway	Russia <sup>a</sup>	United Kingdom	U.S. Virgin Islands	Other	Total Non-OPEC
1973 Average .....	9	1,325	9	16	53	1	26	15	329	1,480	3,263
1975 Average .....	5	846	9	71	19	17	14	14	406	1,052	2,454
1980 Average .....	3	455	4	533	2	144	1	176	388	903	2,609
1985 Average .....	61	770	23	816	58	32	8	310	247	913	3,237
1990 Average .....	49	934	182	755	55	102	45	189	282	1,128	3,721
1995 Average .....	8	1,332	219	1,068	15	273	25	383	278	1,233	4,833
1996 Average .....	9	1,424	234	1,244	19	313	25	308	313	1,377	5,267
1997 Average .....	5	1,563	271	1,385	25	309	13	226	300	1,495	5,593
1998 Average .....	26	1,598	354	1,351	31	236	24	250	293	1,640	5,803
1999 Average .....	26	1,539	468	1,324	27	304	89	365	280	1,478	5,899
2000 Average .....	51	1,807	342	1,373	30	343	72	366	291	1,581	6,257
2001 Average .....	82	1,828	296	1,440	43	341	90	324	268	1,631	6,343
2002 Average .....	116	1,971	260	1,547	66	393	210	478	236	1,649	6,925
2003 Average .....	108	2,072	195	1,623	87	270	254	440	288	1,766	7,103
2004 Average .....	104	2,138	176	1,665	101	244	298	380	330	2,008	7,444
2005 Average .....	156	2,181	196	1,662	151	233	410	396	328	2,413	8,127
2006 Average .....	193	2,353	155	1,705	174	196	369	272	328	2,446	8,190
2007 Average .....	200	2,455	155	1,532	128	142	414	277	346	1,839	7,489
2008 Average .....	258	2,493	200	1,302	168	102	465	236	320	1,416	6,961
2009 Average .....	309	2,479	276	1,210	140	108	563	245	277	1,307	6,915
<b>2010</b> January .....	353	2,596	322	1,133	116	126	463	282	298	1,057	6,747
February .....	226	2,491	386	1,137	126	99	423	413	196	1,074	6,571
March .....	306	2,505	251	1,306	136	59	494	267	235	977	6,538
April .....	318	2,472	423	1,282	89	166	587	304	331	1,178	7,149
May .....	319	2,528	315	1,428	108	119	719	176	195	1,180	7,087
June .....	308	2,717	407	1,211	87	52	760	269	246	1,090	7,146
July .....	332	2,549	404	1,289	207	119	719	351	239	1,287	7,497
August .....	251	2,489	372	1,282	137	57	786	266	301	1,298	7,239
September .....	181	2,479	363	1,254	45	62	648	178	302	1,200	6,712
October .....	169	2,347	422	1,347	108	111	655	152	270	1,255	6,837
November .....	198	2,513	492	1,363	57	79	561	187	234	886	6,571
December .....	295	2,736	231	1,365	71	26	514	236	191	855	6,518
<b>Average .....</b>	<b>272</b>	<b>2,535</b>	<b>365</b>	<b>1,284</b>	<b>108</b>	<b>89</b>	<b>612</b>	<b>256</b>	<b>253</b>	<b>1,112</b>	<b>6,887</b>
<b>2011</b> January .....	274	2,826	332	1,366	101	85	531	155	276	1,136	7,082
February .....	177	2,831	211	1,104	129	69	437	110	182	749	5,999
March .....	161	2,666	399	1,319	91	156	690	197	149	1,177	7,005
April .....	227	2,625	516	1,077	133	167	704	187	179	1,267	7,083
May .....	282	2,481	433	1,286	128	101	677	233	194	1,283	7,097
June .....	285	2,524	309	1,222	175	93	689	146	151	1,319	6,911
July .....	329	2,626	415	1,197	80	58	562	175	192	1,105	6,739
August .....	228	2,637	395	1,185	81	87	585	125	185	988	6,497
September .....	188	2,829	529	1,192	64	97	592	124	189	1,079	6,883
October .....	187	2,692	578	1,177	23	180	687	150	151	903	6,727
November .....	234	2,815	424	1,256	96	174	737	125	177	910	6,948
December .....	404	2,932	508	1,064	101	88	552	162	214	846	6,872
<b>Average .....</b>	<b>249</b>	<b>2,706</b>	<b>422</b>	<b>1,205</b>	<b>100</b>	<b>113</b>	<b>621</b>	<b>158</b>	<b>187</b>	<b>1,065</b>	<b>6,825</b>
<b>2012</b> January .....	321	3,008	431	1,114	101	46	572	168	96	884	6,740
February .....	286	3,048	472	1,081	92	163	288	127	28	894	6,478
March .....	356	2,931	482	1,004	143	87	326	187	1	779	6,296
April .....	237	2,931	472	1,002	84	51	388	204	12	858	6,239
May .....	215	3,018	430	996	121	95	550	143	2	891	6,460
<b>5-Month Average .....</b>	<b>283</b>	<b>2,987</b>	<b>457</b>	<b>1,039</b>	<b>109</b>	<b>88</b>	<b>427</b>	<b>166</b>	<b>28</b>	<b>860</b>	<b>6,444</b>
<b>2011 5-Month Average .....</b>	<b>225</b>	<b>2,683</b>	<b>381</b>	<b>1,234</b>	<b>116</b>	<b>116</b>	<b>610</b>	<b>178</b>	<b>196</b>	<b>1,129</b>	<b>6,869</b>
<b>2010 5-Month Average .....</b>	<b>306</b>	<b>2,519</b>	<b>338</b>	<b>1,260</b>	<b>115</b>	<b>114</b>	<b>539</b>	<b>286</b>	<b>252</b>	<b>1,093</b>	<b>6,821</b>

<sup>a</sup> Through 1992, may include imports from republics other than Russia in the former U.S.S.R. See "Union of Soviet Socialist Republics (U.S.S.R.," in Glossary.

Notes: • See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary for membership. Petroleum imports not classified as "OPEC" on Table 3.3c are included on this table. • The country of origin for petroleum products may not be the country of origin for the crude oil from which the products were produced. For example, refined products imported from West European refining areas may have been produced from Middle East crude oil. • Includes imports for the Strategic Petroleum Reserve, which began in October 1977. • Totals may not equal sum of components due to independent rounding. • U.S. geographic


coverage is the 50 States and the District of Columbia.

Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.


Sources: • **1973-1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976-1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981-2010:** EIA, *Petroleum Supply Annual*, annual reports. • **2011 and 2012:** EIA, *Petroleum Supply Monthly*, monthly reports.

**Figure 3.4 Petroleum Stocks**  
(Billion Barrels, Except as Noted)


Overview, 1973-2011




Overview, Monthly




Total Stocks (Crude Oil and Petroleum Products)



SPR and Non-SPR Crude Oil Stocks, 1973-2011



Selected Products



<sup>a</sup> Includes propylene.

<sup>b</sup> Includes kerosene-type jet fuel only.

Notes: • SPR=Strategic Petroleum Reserve. • Stocks are at end of

period.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Source: Table 3.4.



**Table 3.4 Petroleum Stocks**  
(Million Barrels)

	Crude Oil <sup>a</sup>			Distillate Fuel Oil <sup>f,g</sup>	Jet Fuel <sup>h</sup>	LPG <sup>b</sup>		Motor Gasoline <sup>f,j</sup>	Residual Fuel Oil <sup>f</sup>	Other <sup>k</sup>	Total <sup>f</sup>
	SPR <sup>c</sup>	Non-SPR <sup>d,e,f</sup>	Total <sup>e,f</sup>			Propane <sup>f,i</sup>	Total <sup>f</sup>				
1973 Year	--	242	242	196	29	65	99	209	53	179	1,008
1975 Year	--	271	271	209	30	82	125	235	74	188	1,133
1980 Year	108	358	466	205	42	65	120	261	92	205	1,392
1985 Year	493	321	814	144	40	39	74	223	50	174	1,519
1990 Year	586	323	908	132	52	49	98	220	49	162	1,621
1995 Year	592	303	895	130	40	43	93	202	37	165	1,563
1996 Year	566	284	850	127	40	43	86	195	46	164	1,507
1997 Year	563	305	868	138	44	44	89	210	40	169	1,560
1998 Year	571	324	895	156	45	65	115	216	45	176	1,647
1999 Year	567	284	852	125	41	43	89	193	36	157	1,493
2000 Year	541	286	826	118	45	41	83	196	36	164	1,468
2001 Year	550	312	862	145	42	66	121	210	41	166	1,586
2002 Year	599	278	877	134	39	53	106	209	31	152	1,548
2003 Year	638	269	907	137	39	50	94	207	38	147	1,568
2004 Year	676	286	961	126	40	55	104	218	42	153	1,645
2005 Year	685	324	1,008	136	42	57	109	208	37	157	1,698
2006 Year	689	312	1,001	144	39	62	113	212	42	169	1,720
2007 Year	697	286	983	134	39	52	96	218	39	156	1,665
2008 Year	702	326	1,028	146	38	55	113	214	36	162	1,737
2009 Year	727	325	1,052	166	43	50	102	223	37	153	1,776
2010 January	727	337	1,063	164	44	35	80	232	40	162	1,786
February	727	343	1,070	155	44	28	70	235	41	170	1,785
March	727	359	1,086	147	42	28	73	225	41	174	1,787
April	727	363	1,090	145	44	35	89	220	44	178	1,810
May	727	362	1,089	150	45	42	105	218	46	178	1,830
June	727	365	1,092	158	45	49	120	216	43	169	1,842
July	727	358	1,084	167	47	55	130	220	41	166	1,855
August	727	359	1,086	170	47	59	139	221	39	159	1,862
September	727	363	1,089	167	47	61	141	219	40	158	1,861
October	727	368	1,094	162	44	61	138	210	41	158	1,847
November	727	352	1,079	162	44	61	131	213	41	158	1,827
December	727	333	1,060	164	43	49	108	219	41	158	1,794
2011 January	727	347	1,074	162	41	35	85	235	39	166	1,803
February	727	350	1,077	154	39	26	71	229	35	168	1,773
March	727	363	1,089	149	40	24	69	215	37	171	1,770
April	727	369	1,096	143	39	28	80	205	39	175	1,776
May	727	370	1,096	145	41	34	92	214	37	180	1,805
June	727	358	1,085	144	42	40	105	215	37	179	1,808
July	718	348	1,066	158	44	47	119	217	37	178	1,820
August	696	349	1,046	157	43	52	130	212	39	173	1,801
September	696	332	1,028	154	46	57	132	216	35	170	1,781
October	696	339	1,035	143	46	60	133	208	37	169	1,770
November	696	338	1,034	144	42	59	125	221	39	167	1,772
December	696	331	1,027	150	42	55	111	224	34	164	1,751
2012 January	696	340	1,036	149	42	48	101	235	34	R 175	R 1,772
February	696	347	1,043	139	41	43	96	231	36	R 179	R 1,765
March	696	368	1,064	134	39	45	102	219	36	R 184	R 1,778
April	696	377	1,073	125	40	50	116	211	34	R 179	R 1,777
May	696	R 386	R 1,082	R 122	40	R 56	R 133	R 205	R 33	R 179	R 1,794
June	E 696	E 382	E 1,078	E 119	E 38	E 63	RF 148	E 206	E 35	RE 172	E 1,795
July	E 696	E 371	E 1,067	E 124	E 40	E 68	F 161	E 207	E 35	E 167	E 1,801

<sup>a</sup> Includes lease condensate.

<sup>b</sup> Liquefied petroleum gases.

<sup>c</sup> "SPR" is the Strategic Petroleum Reserve, which began in October 1977. Crude oil stocks in the SPR include non-U.S. stocks held under foreign or commercial storage agreements.

<sup>d</sup> All crude oil stocks other than those in "SPR."

<sup>e</sup> Beginning in 1981, includes stocks of Alaskan crude oil in transit. See Note 5, "Stocks of Alaskan Crude Oil," at end of section.

<sup>f</sup> See Note 4, "Petroleum New Stock Basis," at end of section.

<sup>g</sup> Excludes stocks in the Northeast Heating Oil Reserve. Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>h</sup> Through 2004, includes kerosene-type and naphtha-type jet fuel. Beginning in 2005, includes kerosene-type jet fuel only; naphtha-type jet fuel is included in "Other."

<sup>i</sup> Includes propylene.

<sup>j</sup> Includes finished motor gasoline and motor gasoline blending components; excludes oxygenates.

<sup>k</sup> Asphalt and road oil, aviation gasoline, aviation gasoline blending

components, kerosene, lubricants, pentanes plus, petrochemical feedstocks, petroleum coke, special naphthas, unfinished oils, waxes, miscellaneous products, oxygenates, renewable fuels, and other hydrocarbons. Beginning in 2005, also includes naphtha-type jet fuel.

R=Revised. E=Estimate. F=Forecast. -- =Not applicable.


Notes: • Stocks are at end of period. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.


Sources: • 1973-1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • 1976-1980: U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • 1981-2010: EIA, *Petroleum Supply Annual*, annual reports. • 2011 and 2012: EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.

**Figure 3.5 Petroleum Products Supplied by Type**  
(Million Barrels per Day)


Total and Motor Gasoline, 1973-2011




Total, January-July




Selected Products, 1973-2011



Selected Products, Monthly



Selected Products



<sup>a</sup> Beginning in 1993, includes fuel ethanol blended into motor gasoline.  
<sup>b</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.  
<sup>c</sup> Beginning in 2005, includes kerosene-type jet fuel only.

<sup>d</sup> Includes propylene.  
 Note: SPR=Strategic Petroleum Reserve.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.  
 Source: Table 3.5.

**Table 3.5 Petroleum Products Supplied by Type**  
(Thousand Barrels per Day)

	Asphalt and Road Oil	Aviation Gasoline	Distillate Fuel Oil <sup>b</sup>	Jet Fuel <sup>c</sup>	Kerosene	LPG <sup>a</sup>		Lubricants	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total
						Propane <sup>d</sup>	Total						
1973 Average	522	45	3,092	1,059	216	872	1,449	162	6,674	261	2,822	1,005	17,308
1975 Average	419	39	2,851	1,001	159	783	1,333	137	6,675	247	2,462	1,001	16,322
1980 Average	396	35	2,866	1,068	158	754	1,469	159	6,579	237	2,508	1,581	17,056
1985 Average	425	27	2,868	1,218	114	883	1,599	145	6,831	264	1,202	1,032	15,726
1990 Average	483	24	3,021	1,522	43	917	1,556	164	7,235	339	1,229	1,373	16,988
1995 Average	486	21	3,207	1,514	54	1,096	1,899	156	7,789	365	852	1,381	17,725
1996 Average	484	20	3,365	1,578	62	1,136	2,012	151	7,891	379	848	1,518	18,309
1997 Average	505	22	3,435	1,599	66	1,170	2,038	160	8,017	377	797	1,605	18,620
1998 Average	521	19	3,461	1,622	78	1,120	1,952	168	8,253	447	887	1,508	18,917
1999 Average	547	21	3,572	1,673	73	1,246	2,195	169	8,431	477	830	1,532	19,519
2000 Average	525	20	3,722	1,725	67	1,235	2,231	166	8,472	406	909	1,458	19,701
2001 Average	519	19	3,847	1,655	72	1,142	2,044	153	8,610	437	811	1,481	19,649
2002 Average	512	18	3,776	1,614	43	1,248	2,163	151	8,848	463	700	1,474	19,761
2003 Average	503	16	3,927	1,578	55	1,215	2,074	140	8,935	455	772	1,579	20,034
2004 Average	537	17	4,058	1,630	64	1,276	2,132	141	9,105	524	865	1,657	20,731
2005 Average	546	19	4,118	1,679	70	1,229	2,030	141	9,159	515	920	1,605	20,802
2006 Average	521	18	4,169	1,633	54	1,215	2,052	137	9,253	522	689	1,640	20,687
2007 Average	494	17	4,196	1,622	32	1,235	2,085	142	9,286	490	723	1,593	20,680
2008 Average	417	15	3,945	1,539	14	1,154	1,954	131	8,989	464	622	1,408	19,498
2009 Average	360	14	3,631	1,393	18	1,160	2,051	118	8,997	427	511	1,251	18,771
<b>2010</b> January	203	10	3,701	1,344	15	1,638	2,644	116	8,520	268	615	1,218	18,652
February	249	10	3,854	1,343	34	1,526	2,531	137	8,579	334	515	1,263	18,850
March	264	14	3,835	1,443	11	1,193	2,225	138	8,793	425	531	1,421	19,099
April	331	17	3,759	1,410	7	916	1,843	132	9,108	385	590	1,463	19,044
May	378	15	3,639	1,446	11	891	1,878	128	9,162	339	519	1,351	18,866
June	517	18	3,743	1,543	16	901	1,938	155	9,311	411	500	1,386	19,537
July	470	20	3,544	1,494	19	915	1,978	141	9,301	385	595	1,373	19,319
August	537	14	3,830	1,486	9	973	2,025	129	9,255	434	476	1,467	19,662
September	463	20	3,886	1,457	8	1,040	2,084	136	9,112	433	513	1,326	19,438
October	434	15	3,773	1,430	15	1,135	2,126	127	9,016	335	489	1,215	18,974
November	295	11	3,873	1,396	46	1,168	2,141	125	8,816	389	552	1,333	18,977
December	204	12	4,176	1,383	50	1,634	2,677	113	8,911	371	525	1,301	19,722
<b>Average</b>	<b>362</b>	<b>15</b>	<b>3,800</b>	<b>1,432</b>	<b>20</b>	<b>1,160</b>	<b>2,173</b>	<b>131</b>	<b>8,993</b>	<b>376</b>	<b>535</b>	<b>1,343</b>	<b>19,180</b>
<b>2011</b> January	224	14	3,968	1,355	17	1,652	2,660	136	8,412	363	623	1,349	19,121
February	248	13	3,871	1,343	47	1,423	2,406	121	8,648	282	627	1,264	18,869
March	280	19	3,993	1,389	25	1,189	2,291	148	8,750	339	547	1,468	19,248
April	314	7	3,689	1,451	9	933	1,916	131	8,762	352	600	1,381	18,613
May	354	18	3,657	1,429	(s)	934	1,994	120	8,784	415	478	1,114	18,363
June	455	17	3,903	1,545	4	889	1,938	119	9,046	386	471	1,394	19,277
July	463	18	3,452	1,466	9	918	1,929	112	8,960	361	316	1,470	18,555
August	543	18	3,959	1,555	5	974	1,987	134	8,907	452	319	1,274	19,153
September	462	13	3,929	1,417	13	979	2,035	126	8,753	360	482	1,207	18,795
October	424	16	3,944	1,370	-4	1,147	2,140	107	8,623	410	402	1,132	18,563
November	298	12	4,055	1,427	10	1,236	2,235	124	8,527	361	395	1,291	18,734
December	191	10	3,782	1,354	12	1,400	2,525	112	8,659	313	519	1,261	18,738
<b>Average</b>	<b>355</b>	<b>15</b>	<b>3,849</b>	<b>1,425</b>	<b>12</b>	<b>1,138</b>	<b>2,171</b>	<b>124</b>	<b>8,736</b>	<b>367</b>	<b>480</b>	<b>1,300</b>	<b>18,835</b>
<b>2012</b> January	216	12	R 3,823	1,313	2	1,406	2,463	129	8,187	367	420	1,349	R 18,280
February	218	11	R 3,980	1,350	23	1,343	2,421	139	8,622	297	394	1,306	R 18,760
March	236	14	R 3,706	1,382	2	1,134	2,226	111	8,633	323	416	1,163	R 18,213
April	329	14	R 3,704	1,359	3	986	2,069	122	8,817	338	408	1,166	R 18,330
May	R 378	R 17	R 3,745	R 1,409	R 1	R 1,095	R 2,152	R 116	R 8,996	R 376	R 294	R 1,224	R 18,707
June	F 492	F 15	E 3,685	E 1,580	RF 6	E 1,047	F 1,984	F 127	E 8,917	F 397	E 307	RE 1,614	E 19,125
July	F 482	F 18	E 3,527	E 1,492	F 2	E 1,091	F 2,007	F 130	E 8,759	F 358	E 326	E 1,776	E 18,876
<b>7-Month Average</b>	<b>E 336</b>	<b>E 14</b>	<b>E 3,737</b>	<b>E 1,412</b>	<b>E 5</b>	<b>E 1,157</b>	<b>E 2,188</b>	<b>E 124</b>	<b>E 8,704</b>	<b>E 351</b>	<b>E 366</b>	<b>E 1,372</b>	<b>E 18,611</b>
<b>2011 7-Month Average</b>	<b>335</b>	<b>15</b>	<b>3,789</b>	<b>1,426</b>	<b>16</b>	<b>1,132</b>	<b>2,161</b>	<b>127</b>	<b>8,766</b>	<b>358</b>	<b>522</b>	<b>1,349</b>	<b>18,863</b>
<b>2010 7-Month Average</b>	<b>345</b>	<b>15</b>	<b>3,723</b>	<b>1,433</b>	<b>16</b>	<b>1,137</b>	<b>2,145</b>	<b>135</b>	<b>8,971</b>	<b>364</b>	<b>553</b>	<b>1,354</b>	<b>19,053</b>

<sup>a</sup> Liquefied petroleum gases.  
<sup>b</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.  
<sup>c</sup> Through 2004, includes kerosene-type and naphtha-type jet fuel. Beginning in 2005, includes kerosene-type jet fuel only; naphtha-type jet fuel is included in "Other."  
<sup>d</sup> Includes propylene.  
<sup>e</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.  
<sup>f</sup> Pentanes plus, petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.  
R=Revised. E=Estimate. F=Forecast. (s)=Less than 500 barrels per day and greater than -500 barrels per day.


Notes: • Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a-3.8c. • See Note 7, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.


Sources: • **1973-1975:** Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports. • **1976-1980:** U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports. • **1981-2010:** EIA, *Petroleum Supply Annual*, annual reports. • **2011 and 2012:** EIA, *Petroleum Supply Monthly*, monthly reports; and, for the current two months, *Weekly Petroleum Status Report* data system, Short-Term Integrated Forecasting System, and *Monthly Energy Review* data system calculations.

**Figure 3.6 Heat Content of Petroleum Products Supplied by Type**  
(Quadrillion Btu)


Total, 1973-2011



Total



By Product, July 2012



<sup>a</sup> Includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>b</sup> Includes kerosene-type jet fuel only.

<sup>c</sup> Includes fuel ethanol blended into motor gasoline.

<sup>d</sup> All petroleum products not shown above.

(s)=Less than 0.0005 quadrillion Btu.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Source: Table 3.6.

**Table 3.6 Heat Content of Petroleum Products Supplied by Type**  
(Trillion Btu)

	Asphalt and Road Oil	Aviation Gasoline	Distillate Fuel Oil <sup>b</sup>	Jet Fuel <sup>c</sup>	Kerosene	LPG <sup>a</sup>		Lubricants	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total
						Propane <sup>d</sup>	Total						
<b>1973 Total</b> .....	1,264	83	6,575	2,167	447	1,221	1,981	359	12,797	573	6,477	2,114	34,837
<b>1975 Total</b> .....	1,014	71	6,061	2,047	329	1,097	1,807	304	12,798	542	5,649	2,109	32,732
<b>1980 Total</b> .....	962	64	6,110	2,190	329	1,059	1,976	354	12,648	522	5,772	3,278	34,205
<b>1985 Total</b> .....	1,029	50	6,098	2,497	236	1,236	2,103	322	13,098	582	2,759	2,152	30,925
<b>1990 Total</b> .....	1,170	45	6,422	3,129	88	1,284	2,059	362	13,872	745	2,820	2,839	33,552
<b>1995 Total</b> .....	1,178	40	6,818	3,132	112	1,534	2,512	346	14,825	802	1,955	2,837	34,556
<b>1996 Total</b> .....	1,176	37	7,175	3,274	128	1,594	2,660	335	15,064	837	1,952	3,121	35,759
<b>1997 Total</b> .....	1,224	40	7,304	3,308	136	1,638	2,690	354	15,254	829	1,828	3,298	36,265
<b>1998 Total</b> .....	1,263	35	7,359	3,357	162	1,568	2,575	371	15,701	982	2,036	3,093	36,934
<b>1999 Total</b> .....	1,324	39	7,595	3,462	151	1,745	2,897	375	16,036	1,048	1,905	3,129	37,960
<b>2000 Total</b> .....	1,276	36	7,935	3,580	140	1,734	2,945	369	16,155	895	2,091	2,979	38,402
<b>2001 Total</b> .....	1,257	35	8,179	3,426	150	1,598	2,697	338	16,373	961	1,861	3,056	38,333
<b>2002 Total</b> .....	1,240	34	8,028	3,340	90	1,747	2,852	334	16,819	1,018	1,605	3,040	38,400
<b>2003 Total</b> .....	1,220	30	8,349	3,265	113	1,701	2,748	309	16,981	1,000	1,772	3,264	39,051
<b>2004 Total</b> .....	1,304	31	8,652	3,383	133	1,791	2,824	313	17,379	1,156	1,990	3,428	40,593
<b>2005 Total</b> .....	1,323	35	8,755	3,475	144	1,721	2,682	312	17,444	1,133	2,111	3,318	40,732
<b>2006 Total</b> .....	1,261	33	8,864	3,379	111	1,701	2,700	303	17,622	1,148	1,581	3,416	40,420
<b>2007 Total</b> .....	1,197	32	8,921	3,358	67	1,729	2,733	313	17,689	1,077	1,659	3,313	40,358
<b>2008 Total</b> .....	1,012	28	8,411	3,193	30	1,620	2,574	291	17,168	1,022	1,432	2,941	38,101
<b>2009 Total</b> .....	873	27	7,720	2,883	36	1,624	2,664	262	17,135	938	1,173	2,611	36,321
<b>2010 January</b> .....	42	2	668	236	3	195	294	22	1,378	50	120	215	3,029
February .....	46	1	629	213	5	164	255	23	1,253	56	91	202	2,776
March .....	54	2	692	254	2	142	246	26	1,422	79	103	252	3,134
April .....	66	3	657	240	1	105	198	24	1,426	70	111	251	3,046
May .....	78	2	657	254	2	106	207	24	1,482	63	101	240	3,111
June .....	103	3	654	263	3	104	206	28	1,458	74	94	237	3,122
July .....	97	3	640	263	3	109	217	27	1,504	72	116	242	3,183
August .....	110	2	692	261	2	116	220	24	1,497	81	93	259	3,241
September .....	92	3	679	248	1	120	219	25	1,426	78	97	227	3,097
October .....	89	2	681	251	3	135	233	24	1,458	63	95	215	3,114
November .....	59	2	677	238	8	134	228	23	1,380	70	104	227	3,014
December .....	42	2	754	243	9	194	298	21	1,441	69	102	233	3,214
<b>Total</b> .....	<b>878</b>	<b>27</b>	<b>8,080</b>	<b>2,963</b>	<b>41</b>	<b>1,624</b>	<b>2,821</b>	<b>291</b>	<b>17,127</b>	<b>826</b>	<b>1,228</b>	<b>2,800</b>	<b>37,082</b>
<b>2011 January</b> .....	46	2	717	238	3	196	295	26	1,361	68	121	239	3,116
February .....	46	2	631	213	7	153	241	20	1,263	48	110	202	2,784
March .....	58	3	721	244	4	141	251	28	1,415	63	107	259	3,152
April .....	63	1	645	247	1	107	201	24	1,372	64	113	234	2,965
May .....	73	3	660	251	(s)	111	216	23	1,421	78	93	199	3,017
June .....	91	3	682	263	1	102	204	22	1,416	70	89	236	3,075
July .....	95	3	623	258	2	109	209	21	1,449	67	62	260	3,049
August .....	112	3	715	273	1	116	217	25	1,441	84	62	227	3,160
September .....	92	2	687	241	2	113	215	23	1,370	65	91	208	2,996
October .....	87	3	712	241	-1	136	234	20	1,395	77	78	201	3,047
November .....	59	2	709	243	2	142	235	23	1,335	65	74	222	2,968
December .....	39	2	683	238	2	167	278	21	1,401	58	101	224	3,047
<b>Total</b> .....	<b>860</b>	<b>27</b>	<b>8,184</b>	<b>2,950</b>	<b>25</b>	<b>1,594</b>	<b>2,796</b>	<b>275</b>	<b>16,639</b>	<b>807</b>	<b>1,102</b>	<b>2,712</b>	<b>36,376</b>
<b>2012 January</b> .....	44	2	<sup>R</sup> 690	231	(s)	167	270	24	1,324	69	82	238	<sup>R</sup> 2,975
February .....	42	2	<sup>R</sup> 672	222	4	149	250	24	1,305	52	72	219	<sup>R</sup> 2,863
March .....	49	2	<sup>R</sup> 669	243	(s)	135	245	21	1,396	60	81	209	<sup>R</sup> 2,976
April .....	65	2	<sup>R</sup> 647	231	1	113	219	22	1,380	61	77	201	<sup>R</sup> 2,907
May .....	<sup>R</sup> 78	<sup>R</sup> 3	<sup>R</sup> 676	<sup>R</sup> 248	<sup>R</sup> (s)	<sup>R</sup> 130	<sup>R</sup> 237	<sup>R</sup> 22	<sup>R</sup> 1,455	<sup>R</sup> 70	<sup>R</sup> 57	<sup>R</sup> 217	<sup>R</sup> 3,063
June .....	<sup>F</sup> 98	<sup>F</sup> 2	<sup>E</sup> 644	<sup>E</sup> 269	<sup>F</sup> 1	<sup>E</sup> 120	<sup>F</sup> 210	<sup>F</sup> 23	<sup>E</sup> 1,396	<sup>F</sup> 72	<sup>E</sup> 58	<sup>E</sup> 263	<sup>E</sup> 3,036
July .....	<sup>F</sup> 99	<sup>F</sup> 3	<sup>E</sup> 637	<sup>E</sup> 262	<sup>F</sup> (s)	<sup>E</sup> 130	<sup>F</sup> 220	<sup>F</sup> 24	<sup>E</sup> 1,417	<sup>F</sup> 67	<sup>E</sup> 64	<sup>E</sup> 304	<sup>E</sup> 3,096
<b>7-Month Total</b> .....	<sup>E</sup> 475	<sup>E</sup> 16	<sup>E</sup> 4,636	<sup>E</sup> 1,705	<sup>E</sup> 6	<sup>E</sup> 945	<sup>E</sup> 1,650	<sup>E</sup> 161	<sup>E</sup> 9,674	<sup>E</sup> 451	<sup>E</sup> 490	<sup>E</sup> 1,651	<sup>E</sup> 20,916
<b>2011 7-Month Total</b> .....	471	16	4,679	1,714	19	920	1,617	163	9,697	457	695	1,630	21,158
<b>2010 7-Month Total</b> .....	485	16	4,597	1,722	19	925	1,623	174	9,924	465	737	1,640	21,401

<sup>a</sup> Liquefied petroleum gases.

<sup>b</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>c</sup> Through 2004, includes kerosene-type and naphtha-type jet fuel. Beginning in 2005, includes kerosene-type jet fuel only; naphtha-type jet fuel is included in "Other."

<sup>d</sup> Includes propylene.

<sup>e</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>f</sup> Pentanes plus, petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned

as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

R=Revised. E=Estimate. F=Forecast. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.


Notes: • Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a-3.8c. • See Note 7, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Pages: • For all available data beginning in 1973, see <http://www.eia.gov/totalenergy/data/monthly/#petroleum>. • For related information, see <http://www.eia.gov/petroleum/>.


Sources: See end of section.

**Figure 3.7 Petroleum Consumption by Sector**  
(Million Barrels per Day)


By Sector, 1973-2011




By Sector, May 2012




Residential and Commercial Sectors,<sup>a</sup> Selected Products, May 2012




Industrial Sector,<sup>a</sup> Selected Products, May 2012



Transportation Sector, Selected Products, May 2012



Electric Power Sector, May 2012



<sup>a</sup> Includes combined-heat-and-power plants and a small number of electricity-only plants.

<sup>b</sup> Liquefied petroleum gases.

<sup>c</sup> Includes fuel ethanol blended into motor gasoline.

<sup>d</sup> Includes renewable diesel fuel (including biodiesel) blended into

distillate fuel oil.

<sup>e</sup> Includes kerosene-type jet fuel only.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 3.7a–3.7c.

**Table 3.7a Petroleum Consumption: Residential and Commercial Sectors**  
(Thousand Barrels per Day)

	Residential Sector				Commercial Sector <sup>a</sup>						
	Distillate Fuel Oil	Kero-sene	Liquefied Petroleum Gases	Total	Distillate Fuel Oil	Kero-sene	Liquefied Petroleum Gases	Motor Gasoline <sup>b</sup>	Petro-leum Coke	Residual Fuel Oil	Total
1973 Average .....	942	110	407	1,459	303	31	105	45	NA	290	774
1975 Average .....	850	78	365	1,293	276	24	92	46	NA	214	653
1980 Average .....	617	51	222	890	243	20	63	56	NA	245	626
1985 Average .....	514	77	224	815	297	16	68	50	NA	99	530
1990 Average .....	460	31	252	742	252	6	73	58	0	100	489
1995 Average .....	426	36	282	743	225	11	78	10	(s)	62	385
1996 Average .....	434	43	334	811	227	10	87	14	(s)	60	397
1997 Average .....	411	45	325	781	209	12	86	22	(s)	48	378
1998 Average .....	363	52	303	718	202	15	84	20	(s)	37	358
1999 Average .....	389	54	376	819	206	13	100	15	(s)	32	366
2000 Average .....	424	46	395	865	230	14	107	23	(s)	40	415
2001 Average .....	427	46	375	849	239	15	102	20	(s)	30	406
2002 Average .....	404	29	384	817	209	8	101	24	(s)	35	376
2003 Average .....	425	34	389	848	226	9	112	32	(s)	48	428
2004 Average .....	433	41	364	839	221	10	108	23	(s)	53	416
2005 Average .....	402	40	366	809	210	10	94	24	(s)	50	389
2006 Average .....	335	32	318	685	189	7	88	26	(s)	33	343
2007 Average .....	342	21	345	708	181	4	87	32	(s)	33	337
2008 Average .....	314	10	394	718	174	2	113	24	(s)	32	345
2009 Average .....	283	13	391	687	194	2	99	28	(s)	33	357
2010 January .....	460	10	461	931	324	2	122	28	(s)	57	532
February .....	471	24	441	936	332	4	116	28	(s)	58	538
March .....	270	8	388	666	190	1	102	28	(s)	33	356
April .....	196	5	321	521	138	1	85	29	(s)	24	277
May .....	207	8	327	542	146	1	86	30	0	25	289
June .....	244	11	338	593	172	2	89	30	0	30	323
July .....	189	13	345	547	133	2	91	30	0	23	280
August .....	169	7	353	528	119	1	93	30	(s)	21	264
September .....	157	6	363	526	111	1	96	29	(s)	19	256
October .....	233	10	370	614	164	2	98	29	(s)	29	322
November .....	271	32	373	676	190	5	99	29	(s)	33	356
December .....	432	35	466	934	304	6	123	29	(s)	53	516
Average .....	274	14	379	667	193	2	100	29	(s)	34	358
2011 January .....	395	12	464	870	278	2	122	27	(s)	45	475
February .....	414	33	419	866	291	5	111	28	(s)	47	483
March .....	282	18	399	699	199	3	105	28	(s)	32	368
April .....	195	6	334	534	137	1	88	28	0	22	277
May .....	128	(s)	347	476	90	(s)	92	28	0	15	225
June .....	199	3	338	540	140	1	89	29	0	23	282
July .....	178	6	336	520	125	1	89	29	0	20	264
August .....	243	4	346	593	171	1	91	29	0	28	320
September .....	266	9	355	630	187	1	94	28	0	30	341
October .....	289	-3	373	659	203	(s)	99	28	0	33	362
November .....	331	7	389	728	233	1	103	28	(s)	38	403
December .....	428	8	440	876	301	1	116	28	(s)	49	496
Average .....	278	9	378	665	196	1	100	28	(s)	32	357
2012 January .....	463	1	429	893	326	(s)	113	26	(s)	53	519
February .....	389	16	422	827	274	3	111	28	(s)	44	460
March .....	316	1	388	705	222	(s)	102	28	(s)	36	389
April .....	231	2	361	594	163	(s)	95	29	(s)	26	313
May .....	229	(s)	375	605	161	(s)	99	29	0	26	316
5-Month Average .....	325	4	395	724	229	1	104	28	(s)	37	399
2011 5-Month Average .....	281	14	392	687	198	2	104	28	(s)	32	364
2010 5-Month Average .....	319	11	387	716	224	2	102	29	(s)	39	396

<sup>a</sup> Commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

NA=Not available. (s)=Less than 500 barrels per day and greater than -500 barrels per day.

Notes: • Data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is

an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. • See Note 7, "Petroleum Products Supplied and Petroleum Consumption," at end of section.

• Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> for all available data beginning in 1973.

Sources: See end of section.

**Table 3.7b Petroleum Consumption: Industrial Sector**  
(Thousand Barrels per Day)

	Industrial Sector <sup>a</sup>									
	Asphalt and Road Oil	Distillate Fuel Oil	Kerosene	Liquefied Petroleum Gases	Lubricants	Motor Gasoline <sup>b</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>c</sup>	Total
1973 Average .....	522	691	75	902	88	133	254	809	1,005	4,479
1975 Average .....	419	630	58	844	68	116	246	658	1,001	4,038
1980 Average .....	396	621	87	1,172	82	82	234	586	1,581	4,842
1985 Average .....	425	526	21	1,285	75	114	261	326	1,032	4,065
1990 Average .....	483	541	6	1,215	84	97	325	179	1,373	4,304
1995 Average .....	486	532	7	1,527	80	105	328	147	1,381	4,594
1996 Average .....	484	557	9	1,580	78	105	343	146	1,518	4,819
1997 Average .....	505	566	9	1,617	82	111	331	127	1,605	4,953
1998 Average .....	521	570	11	1,553	86	105	390	100	1,508	4,844
1999 Average .....	547	558	6	1,709	87	80	426	90	1,532	5,035
2000 Average .....	525	563	8	1,720	86	79	361	105	1,458	4,903
2001 Average .....	519	611	11	1,557	79	155	390	89	1,481	4,892
2002 Average .....	512	566	7	1,668	78	163	383	83	1,474	4,934
2003 Average .....	503	534	12	1,561	72	171	375	96	1,579	4,903
2004 Average .....	537	570	14	1,646	73	195	423	108	1,657	5,222
2005 Average .....	546	594	19	1,549	72	187	404	123	1,605	5,100
2006 Average .....	521	594	14	1,627	71	198	425	104	1,640	5,193
2007 Average .....	494	595	6	1,637	73	161	412	84	1,593	5,056
2008 Average .....	417	599	2	1,419	67	131	394	86	1,408	4,523
2009 Average .....	360	521	2	1,541	61	128	363	46	1,251	4,274
<b>2010</b> January .....	203	484	3	2,036	60	140	201	59	1,218	4,403
February .....	249	531	6	1,949	70	141	264	55	1,263	4,528
March .....	264	686	2	1,714	71	144	356	54	1,421	4,712
April .....	331	623	1	1,419	68	149	323	61	1,463	4,438
May .....	378	472	2	1,446	66	150	274	51	1,351	4,190
June .....	517	427	3	1,492	80	153	333	43	1,386	4,433
July .....	470	331	3	1,523	73	153	303	53	1,373	4,282
August .....	537	544	2	1,559	66	152	370	42	1,467	4,738
September .....	463	701	1	1,604	70	150	371	51	1,326	4,738
October .....	434	548	3	1,637	66	148	279	51	1,215	4,380
November .....	295	664	8	1,648	64	145	339	57	1,333	4,533
December .....	204	700	9	2,061	58	146	307	51	1,301	4,838
<b>Average</b> .....	<b>362</b>	<b>559</b>	<b>4</b>	<b>1,673</b>	<b>68</b>	<b>148</b>	<b>310</b>	<b>52</b>	<b>1,343</b>	<b>4,519</b>
<b>2011</b> January .....	224	749	3	2,049	70	138	283	64	1,349	4,928
February .....	248	585	8	1,853	62	142	215	65	1,264	4,442
March .....	280	755	5	1,764	76	144	266	57	1,468	4,814
April .....	314	544	2	1,475	68	144	304	63	1,381	4,295
May .....	354	553	(s)	1,536	62	144	366	50	1,114	4,177
June .....	455	568	1	1,492	61	148	324	48	1,394	4,492
July .....	463	257	2	1,486	57	147	286	30	1,470	4,197
August .....	543	523	1	1,530	69	146	388	30	1,274	4,505
September .....	462	578	2	1,567	65	144	297	49	1,207	4,371
October .....	424	575	-1	1,648	55	141	362	42	1,132	4,378
November .....	298	696	2	1,721	64	140	320	39	1,291	4,571
December .....	191	434	2	1,945	58	142	261	52	1,261	4,346
<b>Average</b> .....	<b>355</b>	<b>568</b>	<b>2</b>	<b>1,672</b>	<b>64</b>	<b>143</b>	<b>307</b>	<b>49</b>	<b>1,300</b>	<b>4,460</b>
<b>2012</b> January .....	216	<sup>R</sup> 580	(s)	1,896	66	134	311	40	1,349	<sup>R</sup> 4,593
February .....	218	<sup>R</sup> 749	4	1,864	71	141	250	38	1,306	<sup>R</sup> 4,642
March .....	236	<sup>R</sup> 525	(s)	1,715	57	142	289	41	1,163	<sup>R</sup> 4,168
April .....	329	<sup>R</sup> 517	1	1,594	63	145	311	41	1,166	<sup>R</sup> 4,165
May .....	378	496	(s)	1,657	59	148	344	29	1,224	4,336
<b>5-Month Average</b> .....	<b>276</b>	<b>571</b>	<b>1</b>	<b>1,745</b>	<b>63</b>	<b>142</b>	<b>302</b>	<b>38</b>	<b>1,242</b>	<b>4,379</b>
<b>2011 5-Month Average</b> .....	<b>284</b>	<b>639</b>	<b>3</b>	<b>1,735</b>	<b>68</b>	<b>142</b>	<b>288</b>	<b>60</b>	<b>1,316</b>	<b>4,534</b>
<b>2010 5-Month Average</b> .....	<b>285</b>	<b>559</b>	<b>3</b>	<b>1,710</b>	<b>67</b>	<b>145</b>	<b>284</b>	<b>56</b>	<b>1,344</b>	<b>4,453</b>

<sup>a</sup> Industrial sector fuel use, including that at industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>b</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>c</sup> Pentanes plus, petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

R=Revised. (s)=Less than 500 barrels per day and greater than -500 barrels per

day.

Notes: • Data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. • See Note 7, "Petroleum Products Supplied and Petroleum Consumption," at end of section.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> for all available data beginning in 1973.

Sources: See end of section.



**Table 3.7c Petroleum Consumption: Transportation and Electric Power Sectors**  
(Thousand Barrels per Day)

	Transportation Sector							Electric Power Sector <sup>a</sup>				
	Aviation Gasoline	Distillate Fuel Oil <sup>b</sup>	Jet Fuel <sup>c</sup>	Liquefied Petroleum Gases	Lubricants	Motor Gasoline <sup>d</sup>	Residual Fuel Oil	Total	Distillate Fuel Oil <sup>e</sup>	Petroleum Coke	Residual Fuel Oil <sup>f</sup>	Total
1973 Average	45	1,045	1,042	35	74	6,496	317	9,054	129	7	1,406	1,542
1975 Average	39	998	992	31	70	6,512	310	8,951	107	1	1,280	1,388
1980 Average	35	1,311	1,062	13	77	6,441	608	9,546	79	2	1,069	1,151
1985 Average	27	1,491	1,218	21	71	6,667	342	9,838	40	3	435	478
1990 Average	24	1,722	1,522	16	80	7,080	443	10,888	45	14	507	566
1995 Average	21	1,973	1,514	13	76	7,674	397	11,668	51	37	247	334
1996 Average	20	2,096	1,578	11	73	7,772	370	11,921	51	36	273	360
1997 Average	22	2,198	1,599	10	78	7,883	310	12,099	52	46	311	410
1998 Average	19	2,263	1,622	13	81	8,128	294	12,420	64	56	456	576
1999 Average	21	2,352	1,673	10	82	8,336	290	12,765	66	51	418	535
2000 Average	20	2,422	1,725	8	81	8,370	386	13,012	82	45	378	505
2001 Average	19	2,489	1,655	10	74	8,435	255	12,938	80	47	437	564
2002 Average	18	2,536	1,614	10	73	8,662	295	13,208	60	80	287	427
2003 Average	16	2,665	1,578	12	68	8,733	249	13,321	76	79	379	534
2004 Average	17	2,783	1,630	14	69	8,887	321	13,720	52	101	382	535
2005 Average	19	2,858	1,679	20	68	8,948	365	13,957	54	111	382	547
2006 Average	18	3,017	1,633	20	67	9,029	395	14,178	35	97	157	289
2007 Average	17	3,037	1,622	16	69	9,093	433	14,287	42	78	173	293
2008 Average	15	2,824	1,539	29	64	8,834	400	13,704	34	70	104	209
2009 Average	14	2,600	1,393	20	57	8,840	353	13,279	33	63	79	175
2010 January	10	2,353	1,344	26	57	8,352	407	12,547	79	67	93	239
February	10	2,490	1,343	24	66	8,411	364	12,709	30	69	38	138
March	14	2,663	1,443	22	67	8,620	403	13,231	24	69	41	134
April	17	2,779	1,410	18	64	8,929	465	13,682	23	62	40	125
May	15	2,781	1,446	18	62	8,983	377	13,681	33	64	66	164
June	18	2,858	1,543	19	75	9,128	322	13,963	41	78	105	224
July	20	2,848	1,494	19	69	9,118	399	13,966	42	81	120	244
August	14	2,963	1,486	20	63	9,074	315	13,934	34	63	98	196
September	20	2,888	1,457	20	66	8,933	381	13,766	29	62	61	153
October	15	2,803	1,430	21	62	8,839	371	13,540	25	56	37	118
November	11	2,719	1,396	21	60	8,643	427	13,277	30	50	35	114
December	12	2,679	1,383	26	55	8,736	355	13,245	60	63	67	189
Average	15	2,737	1,432	21	64	8,816	382	13,466	38	65	67	170
2011 January	14	2,507	1,355	26	66	8,247	457	12,672	40	81	57	177
February	13	2,550	1,343	23	59	8,478	478	12,944	31	67	36	134
March	19	2,730	1,389	22	72	8,578	420	13,230	27	73	38	137
April	7	2,782	1,451	19	64	8,590	468	13,381	31	49	46	126
May	18	2,857	1,429	19	58	8,612	372	13,365	29	49	41	119
June	17	2,964	1,545	19	58	8,868	356	13,826	32	62	44	138
July	18	2,855	1,466	19	54	8,784	214	13,410	37	75	52	163
August	18	2,995	1,555	19	65	8,732	215	13,600	26	65	45	135
September	13	2,871	1,417	20	61	8,581	369	13,331	25	63	34	123
October	16	2,854	1,370	21	52	8,453	295	13,061	22	48	32	102
November	12	2,771	1,427	22	60	8,359	286	12,937	23	40	32	96
December	10	2,593	1,354	24	55	8,489	387	12,912	26	51	31	109
Average	15	2,779	1,425	21	60	8,565	359	13,223	29	60	41	130
2012 January	12	<sup>R</sup> 2,430	1,313	24	62	8,026	293	<sup>R</sup> 12,161	24	55	34	114
February	11	<sup>R</sup> 2,546	1,350	23	67	8,452	284	<sup>R</sup> 12,734	22	47	27	96
March	14	<sup>R</sup> 2,625	1,382	22	54	8,463	310	<sup>R</sup> 12,869	18	34	29	81
April	14	<sup>R</sup> 2,769	1,359	20	59	8,644	313	<sup>R</sup> 13,179	24	27	28	79
May	17	2,831	1,409	21	56	8,819	211	13,364	27	32	29	88
5-Month Average	14	2,641	1,363	22	60	8,480	282	12,861	23	39	29	92
2011 5-Month Average	14	2,687	1,394	22	64	8,501	438	13,120	31	64	44	139
2010 5-Month Average	13	2,615	1,398	21	63	8,662	403	13,176	38	66	56	161

<sup>a</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>b</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>c</sup> Through 2004, includes kerosene-type and naphtha-type jet fuel. Beginning in 2005, includes kerosene-type jet fuel only; naphtha-type jet fuel is included in "Industrial Sector, Other" on Table 3.7b.

<sup>d</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>e</sup> Fuel oil nos. 1, 2, and 4. Through 2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>f</sup> Fuel oil nos. 5 and 6. Through 2000, electric utility data also include a small amount of fuel oil no. 4.

R=Revised.


Notes: • Transportation sector data are estimates. • For total petroleum consumption by all sectors, see petroleum products supplied data in Table 3.5. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. • See Note 7, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> for all available data beginning in 1973.


Sources: See end of section.

**Figure 3.8 Heat Content of Petroleum Consumption by Sector, Selected Products**  
(Quadrillion Btu)


Residential and Commercial Sectors,<sup>a</sup> 1973-2011




Residential and Commercial Sectors,<sup>a</sup> Monthly




Industrial Sector,<sup>a</sup> 1973-2011




Industrial Sector,<sup>a</sup> Monthly



Transportation Sector, 1973-2011



Transportation Sector, Monthly



<sup>a</sup> Includes combined-heat-and-power plants and a small number of electricity-only plants.

<sup>b</sup> Liquefied petroleum gases.

<sup>c</sup> Beginning in 1993, includes fuel ethanol blended into motor gasoline.

<sup>d</sup> Beginning in 2009, includes renewable diesel fuel (including bio-

diesel) blended into distillate fuel oil.

<sup>e</sup> Beginning in 2005, includes kerosene-type jet fuel only.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#petroleum>.

Sources: Tables 3.8a–3.8c.

**Table 3.8a Heat Content of Petroleum Consumption: Residential and Commercial Sectors**  
(Trillion Btu)

	Residential Sector				Commercial Sector <sup>a</sup>						
	Distillate Fuel Oil	Kerosene	Liquefied Petroleum Gases	Total	Distillate Fuel Oil	Kerosene	Liquefied Petroleum Gases	Motor Gasoline <sup>b</sup>	Petroleum Coke	Residual Fuel Oil	Total
<b>1973 Total</b> .....	2,003	227	570	2,800	644	65	147	87	NA	665	1,607
<b>1975 Total</b> .....	1,807	161	512	2,479	587	49	129	89	NA	492	1,346
<b>1980 Total</b> .....	1,316	107	311	1,734	518	41	88	107	NA	565	1,318
<b>1985 Total</b> .....	1,092	159	314	1,565	631	33	95	96	NA	228	1,083
<b>1990 Total</b> .....	978	64	352	1,394	536	12	102	111	0	230	991
<b>1995 Total</b> .....	905	74	395	1,374	479	22	109	18	(s)	141	769
<b>1996 Total</b> .....	926	89	469	1,484	483	21	122	27	(s)	137	790
<b>1997 Total</b> .....	874	93	455	1,422	444	25	120	43	(s)	111	743
<b>1998 Total</b> .....	772	108	424	1,304	429	31	118	39	(s)	85	702
<b>1999 Total</b> .....	828	111	526	1,465	438	27	140	28	(s)	73	707
<b>2000 Total</b> .....	905	95	555	1,554	491	30	150	45	(s)	92	807
<b>2001 Total</b> .....	908	95	526	1,529	508	31	143	37	(s)	70	790
<b>2002 Total</b> .....	860	60	537	1,457	444	16	141	45	(s)	80	726
<b>2003 Total</b> .....	905	70	544	1,519	481	19	157	60	(s)	111	828
<b>2004 Total</b> .....	924	85	512	1,520	470	20	152	45	(s)	122	810
<b>2005 Total</b> .....	854	84	513	1,451	447	22	131	46	(s)	116	762
<b>2006 Total</b> .....	712	66	446	1,224	401	15	123	49	(s)	75	664
<b>2007 Total</b> .....	726	44	484	1,254	384	9	121	61	(s)	75	651
<b>2008 Total</b> .....	669	21	553	1,243	372	4	158	46	(s)	73	653
<b>2009 Total</b> .....	602	28	547	1,176	413	4	139	53	(s)	76	685
<b>2010</b>											
January .....	83	2	55	140	58	(s)	14	4	(s)	11	89
February .....	77	4	47	128	54	1	13	4	(s)	10	82
March .....	49	1	46	96	34	(s)	12	5	(s)	6	58
April .....	34	1	37	72	24	(s)	10	5	(s)	5	43
May .....	37	1	39	78	26	(s)	10	5	0	5	47
June .....	43	2	39	83	30	(s)	10	5	0	6	51
July .....	34	2	41	78	24	(s)	11	5	0	5	45
August .....	31	1	42	74	21	(s)	11	5	(s)	4	42
September .....	27	1	42	70	19	(s)	11	5	(s)	4	39
October .....	42	2	44	88	30	(s)	12	5	(s)	6	52
November .....	47	6	43	96	33	1	11	4	(s)	6	56
December .....	78	6	55	140	55	1	15	5	(s)	10	86
<b>Total</b> .....	<b>583</b>	<b>29</b>	<b>530</b>	<b>1,142</b>	<b>410</b>	<b>5</b>	<b>140</b>	<b>55</b>	<b>(s)</b>	<b>77</b>	<b>688</b>
<b>2011</b>											
January .....	71	2	55	129	50	(s)	15	4	(s)	9	78
February .....	68	5	45	118	48	1	12	4	(s)	8	73
March .....	51	3	47	102	36	1	13	5	(s)	6	60
April .....	34	1	38	73	24	(s)	10	4	0	4	43
May .....	23	(s)	41	64	16	(s)	11	5	0	3	35
June .....	35	1	39	74	24	(s)	10	5	0	4	44
July .....	32	1	40	73	23	(s)	11	5	0	4	42
August .....	44	1	41	86	31	(s)	11	5	0	5	52
September .....	47	2	41	89	33	(s)	11	4	0	6	54
October .....	52	(s)	44	96	37	(s)	12	5	0	6	59
November .....	58	1	45	104	41	(s)	12	4	(s)	7	64
December .....	77	1	52	131	54	(s)	14	5	(s)	9	82
<b>Total</b> .....	<b>592</b>	<b>18</b>	<b>530</b>	<b>1,139</b>	<b>417</b>	<b>3</b>	<b>140</b>	<b>54</b>	<b>(s)</b>	<b>73</b>	<b>686</b>
<b>2012</b>											
January .....	84	(s)	51	135	59	(s)	13	4	(s)	10	87
February .....	66	3	47	115	46	(s)	12	4	(s)	8	71
March .....	57	(s)	46	103	40	(s)	12	5	(s)	7	64
April .....	40	(s)	41	82	28	(s)	11	4	(s)	5	49
May .....	41	(s)	45	86	29	(s)	12	5	0	5	51
<b>5-Month Total</b> .....	<b>288</b>	<b>4</b>	<b>230</b>	<b>522</b>	<b>203</b>	<b>1</b>	<b>61</b>	<b>22</b>	<b>(s)</b>	<b>35</b>	<b>322</b>
<b>2011 5-Month Total</b> .....	<b>247</b>	<b>12</b>	<b>227</b>	<b>486</b>	<b>174</b>	<b>2</b>	<b>60</b>	<b>22</b>	<b>(s)</b>	<b>30</b>	<b>288</b>
<b>2010 5-Month Total</b> .....	<b>280</b>	<b>9</b>	<b>224</b>	<b>514</b>	<b>197</b>	<b>2</b>	<b>59</b>	<b>23</b>	<b>(s)</b>	<b>37</b>	<b>318</b>

<sup>a</sup> Commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

NA=Not available. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption

and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c.

• See Note 7, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> for all available data beginning in 1973.

Sources: See end of section.

**Table 3.8b Heat Content of Petroleum Consumption: Industrial Sector**  
(Trillion Btu)

	Industrial Sector <sup>a</sup>									
	Asphalt and Road Oil	Distillate Fuel Oil	Kerosene	Liquefied Petroleum Gases	Lubricants	Motor Gasoline <sup>b</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>c</sup>	Total
<b>1973 Total</b> .....	1,264	1,469	156	1,215	195	255	558	1,858	2,114	9,083
<b>1975 Total</b> .....	1,014	1,339	119	1,123	149	223	540	1,509	2,109	8,127
<b>1980 Total</b> .....	962	1,324	181	1,559	182	158	516	1,349	3,278	9,509
<b>1985 Total</b> .....	1,029	1,119	44	1,664	166	218	575	748	2,152	7,714
<b>1990 Total</b> .....	1,170	1,150	12	1,582	186	185	714	411	2,839	8,251
<b>1995 Total</b> .....	1,178	1,131	15	1,990	178	200	721	337	2,837	8,588
<b>1996 Total</b> .....	1,176	1,187	18	2,054	173	200	757	335	3,121	9,020
<b>1997 Total</b> .....	1,224	1,203	19	2,100	182	212	727	291	3,298	9,256
<b>1998 Total</b> .....	1,263	1,211	22	2,016	191	199	858	230	3,093	9,083
<b>1999 Total</b> .....	1,324	1,187	13	2,217	193	152	936	207	3,129	9,357
<b>2000 Total</b> .....	1,276	1,200	16	2,228	190	150	796	241	2,979	9,076
<b>2001 Total</b> .....	1,257	1,300	23	2,014	174	295	858	203	3,056	9,181
<b>2002 Total</b> .....	1,240	1,204	14	2,160	172	309	842	190	3,040	9,171
<b>2003 Total</b> .....	1,220	1,136	24	2,030	159	324	825	220	3,264	9,202
<b>2004 Total</b> .....	1,304	1,214	28	2,141	161	372	934	249	3,428	9,831
<b>2005 Total</b> .....	1,323	1,264	39	2,009	160	356	889	281	3,318	9,640
<b>2006 Total</b> .....	1,261	1,263	30	2,104	156	376	934	239	3,416	9,780
<b>2007 Total</b> .....	1,197	1,265	13	2,106	161	306	906	193	3,313	9,461
<b>2008 Total</b> .....	1,012	1,277	4	1,823	150	250	868	198	2,941	8,523
<b>2009 Total</b> .....	873	1,107	4	1,950	135	244	799	106	2,611	7,829
<b>2010 January</b> .....	42	87	(s)	222	11	23	38	11	215	650
February .....	46	87	1	193	12	21	45	10	202	615
March .....	54	124	(s)	186	13	23	67	11	252	730
April .....	66	109	(s)	149	12	23	58	11	251	681
May .....	78	85	(s)	156	12	24	51	10	240	657
June .....	103	75	(s)	154	14	24	60	8	237	676
July .....	97	60	1	163	14	25	57	10	242	667
August .....	110	98	(s)	165	12	25	69	8	259	747
September .....	92	123	(s)	164	13	23	67	10	227	719
October .....	89	99	(s)	175	12	24	52	10	215	676
November .....	59	116	1	171	12	23	61	11	227	680
December .....	42	126	2	225	11	24	57	10	233	729
<b>Total</b> .....	<b>878</b>	<b>1,188</b>	<b>7</b>	<b>2,121</b>	<b>149</b>	<b>281</b>	<b>682</b>	<b>120</b>	<b>2,800</b>	<b>8,227</b>
<b>2011 January</b> .....	46	135	1	222	13	22	53	13	239	744
February .....	46	95	1	182	11	21	36	11	202	605
March .....	58	136	1	188	14	23	50	11	259	740
April .....	63	95	(s)	151	12	23	55	12	234	644
May .....	73	100	(s)	162	12	23	68	10	199	647
June .....	91	99	(s)	153	11	23	59	9	236	681
July .....	95	46	(s)	156	11	24	53	6	260	652
August .....	112	94	(s)	163	13	24	72	6	227	711
September .....	92	101	(s)	161	12	22	54	9	208	660
October .....	87	104	(s)	176	10	23	68	8	201	676
November .....	59	122	(s)	176	12	22	58	7	222	678
December .....	39	78	(s)	209	11	23	49	10	224	643
<b>Total</b> .....	<b>860</b>	<b>1,207</b>	<b>4</b>	<b>2,097</b>	<b>141</b>	<b>273</b>	<b>674</b>	<b>113</b>	<b>2,712</b>	<b>8,081</b>
<b>2012 January</b> .....	44	<sup>R</sup> 105	(s)	203	12	22	58	8	238	<sup>R</sup> 691
February .....	42	<sup>R</sup> 127	1	188	13	21	44	7	219	<sup>R</sup> 661
March .....	49	<sup>R</sup> 95	(s)	184	11	23	54	8	209	<sup>R</sup> 632
April .....	65	<sup>R</sup> 90	(s)	164	11	23	56	8	201	<sup>R</sup> 619
May .....	78	90	(s)	178	11	24	64	6	217	667
<b>5-Month Total</b> .....	<b>278</b>	<b>506</b>	<b>1</b>	<b>917</b>	<b>58</b>	<b>113</b>	<b>276</b>	<b>36</b>	<b>1,085</b>	<b>3,269</b>
<b>2011 5-Month Total</b> .....	<b>285</b>	<b>562</b>	<b>3</b>	<b>904</b>	<b>62</b>	<b>112</b>	<b>262</b>	<b>57</b>	<b>1,133</b>	<b>3,379</b>
<b>2010 5-Month Total</b> .....	<b>286</b>	<b>492</b>	<b>2</b>	<b>905</b>	<b>61</b>	<b>114</b>	<b>258</b>	<b>53</b>	<b>1,161</b>	<b>3,332</b>

<sup>a</sup> Industrial sector fuel use, including that at industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>b</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>c</sup> Pentanes plus, petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

<sup>R</sup>=Revised. (s)=Less than 0.5 trillion Btu and greater than -0.5 trillion Btu.

Notes: • Data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c.

• See Note 7, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> for all available data beginning in 1973.

Sources: See end of section.

**Table 3.8c Heat Content of Petroleum Consumption: Transportation and Electric Power Sectors (Trillion Btu)**

	Transportation Sector								Electric Power Sector <sup>a</sup>			
	Aviation Gasoline	Distillate Fuel Oil <sup>b</sup>	Jet Fuel <sup>c</sup>	Liquefied Petroleum Gases	Lubricants	Motor Gasoline <sup>d</sup>	Residual Fuel Oil	Total	Distillate Fuel Oil <sup>e</sup>	Petroleum Coke	Residual Fuel Oil <sup>f</sup>	Total
<b>1973 Total</b> .....	83	2,222	2,131	49	163	12,455	727	17,832	273	15	3,226	3,515
<b>1975 Total</b> .....	71	2,121	2,029	43	155	12,485	711	17,615	226	2	2,937	3,166
<b>1980 Total</b> .....	64	2,795	2,179	18	172	12,383	1,398	19,009	169	5	2,459	2,634
<b>1985 Total</b> .....	50	3,170	2,497	30	156	12,784	786	19,472	85	7	998	1,090
<b>1990 Total</b> .....	45	3,661	3,129	23	176	13,575	1,016	21,626	97	30	1,163	1,289
<b>1995 Total</b> .....	40	4,195	3,132	18	168	14,607	911	23,070	108	81	566	755
<b>1996 Total</b> .....	37	4,469	3,274	16	163	14,837	851	23,648	109	80	628	817
<b>1997 Total</b> .....	40	4,672	3,308	14	172	14,999	712	23,918	111	102	715	927
<b>1998 Total</b> .....	35	4,812	3,357	18	180	15,463	674	24,538	136	124	1,047	1,306
<b>1999 Total</b> .....	39	5,001	3,462	14	182	15,855	665	25,219	140	112	959	1,211
<b>2000 Total</b> .....	36	5,165	3,580	12	179	15,960	888	25,820	175	99	871	1,144
<b>2001 Total</b> .....	35	5,292	3,426	14	164	16,041	586	25,557	171	103	1,003	1,277
<b>2002 Total</b> .....	34	5,392	3,340	14	162	16,465	677	26,085	127	175	659	961
<b>2003 Total</b> .....	30	5,666	3,265	17	150	16,597	571	26,297	161	175	869	1,205
<b>2004 Total</b> .....	31	5,932	3,383	19	152	16,962	740	27,219	111	222	879	1,212
<b>2005 Total</b> .....	35	6,076	3,475	28	151	17,043	837	27,645	115	243	876	1,235
<b>2006 Total</b> .....	33	6,414	3,379	27	147	17,197	906	28,105	74	214	361	648
<b>2007 Total</b> .....	32	6,457	3,358	22	152	17,321	994	28,335	89	171	397	657
<b>2008 Total</b> .....	28	6,020	3,193	40	141	16,872	920	27,214	73	154	240	468
<b>2009 Total</b> .....	27	5,528	2,883	28	127	16,837	810	26,240	70	139	181	390
<b>2010 January</b> .....	2	425	236	3	11	1,351	79	2,107	14	12	18	45
February .....	1	406	213	3	11	1,229	64	1,928	5	12	7	23
March .....	2	481	254	3	13	1,394	79	2,225	4	13	8	25
April .....	3	486	240	2	12	1,398	88	2,227	4	11	8	23
May .....	2	502	254	2	12	1,453	73	2,299	6	12	13	31
June .....	3	499	263	2	14	1,429	61	2,270	7	14	20	41
July .....	3	514	263	2	13	1,475	78	2,348	8	15	23	46
August .....	2	535	261	2	12	1,468	61	2,342	6	12	19	37
September .....	3	505	248	2	12	1,398	72	2,240	5	11	12	28
October .....	2	506	251	2	12	1,430	72	2,276	4	10	7	22
November .....	2	475	238	2	11	1,353	80	2,161	5	9	7	21
December .....	2	484	243	3	10	1,413	69	2,224	11	12	13	36
<b>Total</b> .....	<b>27</b>	<b>5,818</b>	<b>2,963</b>	<b>29</b>	<b>141</b>	<b>16,791</b>	<b>877</b>	<b>26,646</b>	<b>80</b>	<b>144</b>	<b>154</b>	<b>378</b>
<b>2011 January</b> .....	2	453	238	3	12	1,334	89	2,132	7	15	11	33
February .....	2	416	213	2	10	1,239	84	1,966	5	11	6	23
March .....	3	493	244	3	14	1,388	82	2,226	5	14	7	26
April .....	1	486	247	2	12	1,345	88	2,181	5	9	9	23
May .....	3	516	251	2	11	1,393	73	2,249	5	9	8	22
June .....	3	518	263	2	10	1,388	67	2,251	6	11	8	25
July .....	3	516	258	2	10	1,421	42	2,251	7	14	10	31
August .....	3	541	273	2	12	1,412	42	2,286	5	12	9	25
September .....	2	502	241	2	11	1,343	70	2,171	4	11	6	22
October .....	3	515	241	2	10	1,367	58	2,196	4	9	6	19
November .....	2	484	243	2	11	1,309	54	2,105	4	7	6	17
December .....	2	468	238	3	10	1,373	75	2,170	5	10	6	20
<b>Total</b> .....	<b>27</b>	<b>5,908</b>	<b>2,950</b>	<b>29</b>	<b>133</b>	<b>16,312</b>	<b>823</b>	<b>26,182</b>	<b>62</b>	<b>132</b>	<b>94</b>	<b>288</b>
<b>2012 January</b> .....	2	<sup>R</sup> 439	231	3	12	1,298	57	<sup>R</sup> 2,042	4	10	7	21
February .....	2	<sup>R</sup> 430	222	3	12	1,279	52	<sup>R</sup> 1,999	4	8	5	17
March .....	2	<sup>R</sup> 474	243	3	10	1,369	60	<sup>R</sup> 2,161	3	6	6	15
April .....	2	<sup>R</sup> 484	231	2	11	1,353	59	<sup>R</sup> 2,142	4	5	5	14
May .....	3	511	248	2	11	1,427	41	2,242	5	6	6	16
<b>5-Month Total</b> .....	<b>10</b>	<b>2,338</b>	<b>1,174</b>	<b>13</b>	<b>55</b>	<b>6,726</b>	<b>269</b>	<b>10,586</b>	<b>21</b>	<b>36</b>	<b>28</b>	<b>84</b>
<b>2011 5-Month Total</b> .....	<b>11</b>	<b>2,364</b>	<b>1,194</b>	<b>13</b>	<b>58</b>	<b>6,698</b>	<b>416</b>	<b>10,753</b>	<b>28</b>	<b>58</b>	<b>41</b>	<b>127</b>
<b>2010 5-Month Total</b> .....	<b>10</b>	<b>2,300</b>	<b>1,197</b>	<b>12</b>	<b>58</b>	<b>6,825</b>	<b>383</b>	<b>10,785</b>	<b>34</b>	<b>60</b>	<b>53</b>	<b>147</b>

<sup>a</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>b</sup> Beginning in 2009, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>c</sup> Through 2004, includes kerosene-type and naphtha-type jet fuel. Beginning in 2005, includes kerosene-type jet fuel only; naphtha-type jet fuel is included in "Industrial Sector Other" on Table 3.8b.

<sup>d</sup> Finished motor gasoline. Beginning in 1993, also includes fuel ethanol blended into motor gasoline.

<sup>e</sup> Fuel oil nos. 1, 2, and 4. Through 2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>f</sup> Fuel oil nos. 5 and 6. Through 2000, electric utility data also include a small

amount of fuel oil no. 4.

<sup>R</sup>=Revised.

Notes: • Transportation sector data are estimates. • For total heat content of petroleum consumption by all sectors, see data for heat content of petroleum products supplied in Table 3.6. Petroleum products supplied is an approximation of petroleum consumption and is synonymous with the term "petroleum consumption" in Tables 3.7a–3.8c. • See Note 7, "Petroleum Products Supplied and Petroleum Consumption," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#petroleum> for all available data beginning in 1973.

Sources: See end of section.

## Petroleum

**Note 1. Petroleum Survey Respondents.** The U.S. Energy Information Administration (EIA) uses a number of sources and methods to maintain the survey respondent lists. On a regular basis, survey managers review such industry publications as the *Oil & Gas Journal* and *Oil Daily* for information on facilities or companies starting up or closing down operations. Those sources are augmented by articles in newspapers, communications from respondents indicating changes in status, and information received from survey systems.

To supplement routine frames maintenance and to provide more thorough coverage, a comprehensive frames investigation is conducted every 3 years. This investigation results in the reassessment and recompilation of the complete frame for each survey. The effort also includes the evaluation of the impact of potential frame changes on the historical time series of data from these respondents. The results of this frame study are usually implemented in January to provide a full year under the same frame.

In 1991, EIA conducted a frame identifier survey of companies that produce, blend, store, or import oxygenates. A summary of the results from the identification survey was published in the *Weekly Petroleum Status Report* dated February 12, 1992, and in the February 1992 issue of the *Petroleum Supply Monthly (PSM)*. In order to continue to provide relevant information about U.S. and regional gasoline supply, EIA conducted a second frame identifier survey of those companies during 1992. As a result, numerous respondents were added to the monthly surveys effective in January 1993. See PSM, Appendix B, "Frame."

**Note 2. Motor Gasoline.** Beginning in January 1981, EIA expanded its universe to include non-refinery blenders and separated blending components from finished motor gasoline as a reporting category. Also, survey forms were modified to describe refinery operations more accurately.

Beginning with the reporting of January 1993 data, EIA made adjustments to the product supplied series for finished motor gasoline. It was recognized that motor gasoline statistics published by EIA through 1992 were underreported because the reporting system was (1) not collecting all fuel ethanol blending, and (2) there was a misreporting of motor gasoline blending components that were blended into finished gasoline. The adjustments are incorporated into EIA's data beginning in January 1993. To facilitate data analysis across the 1992–1993 period, EIA prepared a table of 1992 data adjusted according to the 1993 basis. See *Petroleum Supply Monthly*, March 1993, Table H3.

**Note 3. Distillate and Residual Fuel Oils.** The requirement to report crude oil in pipelines or burned on leases as either distillate or residual fuel oil was eliminated. Prior to January 1981, the refinery input of unfinished oils typically exceeded the available supply of unfinished oils.

That discrepancy was assumed to be due to the redesignation of distillate and residual fuel oils received as such but used as unfinished oil inputs by the receiving refinery. The imbalance between supply and disposition of unfinished oils would then be subtracted from the production of distillate and residual fuel oils. Two-thirds of that difference was subtracted from distillate and one-third from residual. Beginning in January 1981, EIA modified its survey forms to account for redesignated product and discontinued the above-mentioned adjustment.

Prior to 1983, crude oil burned on leases and used at pipeline pump stations was reported as either distillate or residual fuel oil and was included as product supplied for these products.

**Note 4. Petroleum New Stock Basis.** In January 1975, 1979, 1981, and 1983, numerous respondents were added to bulk terminal and pipeline surveys, affecting subsequent stocks reported and stock change calculations. Using the expanded coverage (new basis), the end-of-year stocks, in million barrels, would have been:

Crude Oil: 1982—645 (Total) and 351 (Non-SPR).

Distillate Fuel Oil: 1974—224; 1980—205; and 1982—186.

Jet Fuel (Total): 1974—30; 1980—42; and 1982—39.

Liquefied Petroleum Gases: 1974—113; 1978—136; 1980—128; and 1982—102.

Propane and Propylene: 1978—86; 1980—69; and 1982—57.

Motor Gasoline (Total): 1974—225; 1980—263; 1982—244.

Residual Fuel Oil: 1974—75; 1980—91; and 1982—69.

Total Petroleum: 1974—1,121; 1980—1,425; and 1982—1,461.

Stock change calculations beginning in 1975, 1979, 1981, and 1983 were made by using new basis stock levels.

In January 1984, changes were made in the reporting of natural gas liquids. As a result, unfractionated stream is now reported on a component basis (ethane, propane, normal butane, isobutane, and pentanes plus). This change affects stocks reported and stock change calculations. Under the new basis, 1983 end-of-year stocks, in million barrels, would have been 108 for liquefied petroleum gases, and 55 for propane and propylene.

In January 1993, changes were made in the monthly surveys to begin collecting bulk terminal and pipeline stocks of oxygenates. This change affected stocks reported and stock change calculations. However, a new basis stock level was not calculated for 1992 end-of-year stocks.

**Note 5. Stocks of Alaskan Crude Oil.** Stocks of Alaskan crude oil in transit were included for the first time in January 1981. The major impact of this change is on the reporting of stock change calculations. Using the expanded coverage (new basis), 1980 end-of-year stocks, in million barrels, would have been 488 (Total) and 380 (Non-SPR).

**Note 6. Petroleum Data Discrepancies.** Due to differences internal to EIA data processing systems, some small discrepancies exist between data in the *Monthly Energy Review* and the *Petroleum Supply Annual (PSA)* and *Petroleum Supply Monthly (PSM)*. The data that have discrepancies are footnoted in Section 3 tables. The corresponding PSA/PSM values, in thousand barrels per day, are: Natural Gas Plant Liquids Production, 1976: 1,603; Total Exports, 1979: 472; Petroleum Products Exports, 1979: 237; and SPR Crude Oil Imports, 1978: 162.

**Note 7. Petroleum Products Supplied and Petroleum Consumption.** Total petroleum products supplied is the sum of the products supplied for each petroleum product, crude oil, unfinished oils, and gasoline blending components. For each of these except crude oil, product supplied is calculated by adding refinery production, natural gas plant liquids production, new supply of other liquids, imports, and stock withdrawals, and subtracting stock additions, refinery inputs, and exports. Crude oil product supplied is the sum of crude oil burned on leases and at pipeline pump stations as reported on Form EIA-813, "Monthly Crude Oil Report." Prior to 1983, crude oil burned on leases and used at pipeline pump stations was reported as either distillate or residual fuel oil and was included as product supplied for these products. Petroleum product supplied (see Tables 3.5 and 3.6) is an approximation of petroleum consumption and is synonymous with the term "Petroleum Consumption" in Tables 3.7a–3.8c.

### Table 3.1 Sources

1973–1975: Bureau of Mines, Mineral Industry Surveys, *Petroleum Statement, Annual*, annual reports.

1976–1980: U.S. Energy Information Administration (EIA), Energy Data Reports, *Petroleum Statement, Annual*, annual reports.

1981–2009: EIA, *Petroleum Supply Annual (PSA)*, annual reports.

2010 forward: EIA, PSA, annual report; *Petroleum Supply Monthly*, monthly reports; revisions to crude oil production, total field production, and adjustments (based on crude oil production data from: State government agencies; U.S. Department of the Interior, Bureau of Safety and Environmental Enforcement, and predecessor agencies; and Form EIA-182, "Domestic Crude Oil First Purchase Report"); and, for the current two months, *Weekly Petroleum Status Report* data system and *Monthly Energy Review* data system calculations.

### Table 3.6 Sources

#### Asphalt and Road Oil, Aviation Gasoline, Distillate Fuel Oil, Kerosene, Propane, Lubricants, Petroleum Coke, and Residual Fuel Oil

Product supplied data in thousand barrels per day for these petroleum products are from Table 3.5, and are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1.

#### Jet Fuel

Product supplied data in thousand barrels per day for kerosene-type jet fuel and, through 2004, naphtha-type jet fuel are from the U.S. Energy Information Administration's (EIA) *Petroleum Supply Annual (PSA)*, *Petroleum Supply Monthly (PSM)*, and earlier publications (see sources for Table 3.5). These data are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total jet fuel product supplied is the sum of the data in trillion Btu for kerosene-type and naphtha-type jet fuel.

#### Liquefied Petroleum Gases (LPG) Total

Prior to the current two months, product supplied data in thousand barrels per day for the component products of LPG (ethane/ethylene, propane/propylene, normal butane/butylene, and isobutane/isobutylene) are from the PSA, PSM, and earlier publications (see sources for Table 3.5). These data are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total LPG product supplied is the sum of the data in trillion Btu for the LPG component products.

For the current two months, product supplied data in thousand barrels per day for total LPG are from Table 3.5, and are converted to trillion Btu by multiplying by the LPG heat content factors in Table A3.

#### Motor Gasoline

Product supplied data in thousand barrels per day for motor gasoline are from Table 3.5, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

#### Other Petroleum Products

Prior to the current two months, product supplied data in thousand barrels per day for "other" petroleum products are from the PSA, PSM, and earlier publications (see sources for Table 3.5). "Other" petroleum products include pentanes plus, petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products; beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components; beginning in 1983, also includes crude oil burned as fuel; and beginning in 2005, also includes naphtha-type jet fuel. These data are converted to trillion Btu by multiplying by the appropriate heat content factors in MER Table A1. Total "Other"

petroleum product supplied is the sum of the data in trillion Btu for the individual products.

For the current two months, total “Other” petroleum products supplied is calculated by first estimating total petroleum products supplied (product supplied data in thousand barrels per day for total petroleum from Table 3.5 are converted to trillion Btu by multiplying by the total petroleum consumption heat content factor in Table A3), and then subtracting data in trillion Btu (from Table 3.6) for asphalt and road oil, aviation gasoline, distillate fuel oil, jet fuel, kerosene, total LPG, lubricants, motor gasoline, petroleum coke, and residual fuel oil.

### **Total Petroleum**

Total petroleum products supplied is the sum of the data in trillion Btu for the products (except “Propane”) shown in Table 3.6.

### **Tables 3.7a–3.7c Sources**

Petroleum consumption data in these tables are derived from data for “petroleum products supplied” from the following sources:

1973–1975: U.S. Department of the Interior, Bureau of Mines, *Mineral Industry Surveys*, “Petroleum Statement, Annual.”

1976–1980: U.S. Energy Information Administration’s (EIA), *Energy Data Reports*, “Petroleum Statement, Annual.”

1981–2010: EIA, *Petroleum Supply Annual*.

2011 and 2012: EIA, *Petroleum Supply Monthly*.

Energy-use allocation procedures by individual product are as follows:

#### **Asphalt and Road Oil**

All consumption of asphalt and road oil is assigned to the industrial sector.

#### **Aviation Gasoline**

All consumption of aviation gasoline is assigned to the transportation sector.

#### **Distillate Fuel Oil**

Distillate fuel oil consumption is assigned to the sectors as follows:

#### **Distillate Fuel Oil Consumed by the Electric Power Sector**

See sources for Table 7.4b. For 1973–1979, electric utility consumption of distillate fuel oil is assumed to be the amount of petroleum (minus small amounts of kerosene and kerosene-type jet fuel deliveries) consumed in gas turbine and internal combustion plants. For 1980–2000, electric utility consumption of distillate fuel oil is assumed to be the amount of light oil (fuel oil nos. 1 and 2, plus small amounts of kerosene and jet fuel) consumed.

#### **Distillate Fuel Oil Consumed by the End-Use Sectors, Annually**

The aggregate end-use amount is total distillate fuel oil supplied minus the amount consumed by the electric power sector. The end-use total consumed annually is allocated to the individual end-use sectors (residential, commercial, industrial, and transportation) in proportion to each sector’s share of sales as reported in EIA’s *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-0535), which is based primarily on data collected by Form EIA-821, “Annual Fuel Oil and Kerosene Sales Report” (previously Form EIA-172). Shares for the current year are based on the most recent Sales report.

Following are notes on the individual sector groupings:

Since 1979, the residential sector sales total is directly from the Sales reports. Prior to 1979, each year’s sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares.

Since 1979, the commercial sector sales total is directly from the Sales reports. Prior to 1979, each year’s sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares.

Since 1979, the industrial sector sales total is the sum of the sales for industrial, farm, oil company, off-highway diesel, and all other uses. Prior to 1979, each year’s sales subtotal of the heating plus industrial category is split into residential, commercial, and industrial (including farm) in proportion to the 1979 shares, and this estimated industrial portion is added to oil company, off-highway diesel, and all other uses.

The transportation sector sales total is the sum of the sales for railroad, vessel bunkering, on-highway diesel, and military uses for all years.

#### **Distillate Fuel Oil Consumed by the End-Use Sectors, Monthly**

Residential sector and commercial sector monthly consumption is estimated by allocating the annual estimates, which are described above, into the months in proportion to each month’s share of the year’s sales of No. 2 heating oil. (For each month of the current year, the residential and commercial consumption increase from the same month in the previous year is based on the percent increase in that month’s No. 2 heating oil sales from the same month in the previous year.) The years’ No. 2 heating oil sales totals are from the following sources: for 1973–1980, the Ethyl Corporation, *Monthly Report of Heating Oil Sales*; for 1981 and 1982, the American Petroleum Institute, *Monthly Report of Heating Oil Sales*; and for 1983 forward, EIA, Form EIA-782A, “Refiners’/Gas Plant Operators’ Monthly Petroleum



Product Sales Report," No. 2 Fuel Oil Sales to End Users and for Resale.

The transportation highway use portion is allocated into the months in proportion to each month's share of the year's total sales for highway use as reported by the Federal Highway Administration's Table MF-25, "Private and Commercial Highway Use of Special Fuels by Months." After 1993, the sales-for-highway-use data are no longer available as a monthly series; the 1993 data are used for allocating succeeding year's totals into months.

A distillate fuel oil "balance" is calculated as total distillate fuel oil supplied minus the amount consumed by the electric power sector, residential sector, commercial sector, and for highway use.

Industrial sector monthly consumption is estimated by multiplying each month's distillate fuel oil "balance" by the annual industrial consumption share of the annual distillate fuel oil "balance."

Total transportation sector monthly consumption is estimated as total distillate fuel oil supplied minus the amount consumed by the residential, commercial, industrial, and electric power sectors.

### **Jet Fuel**

Through 1982, small amounts of kerosene-type jet fuel were consumed by the electric power sector. Kerosene-type jet fuel deliveries to the electric power sector as reported on Form FERC-423 (formerly Form FPC-423) were used as estimates of this consumption. Through 2004, all remaining jet fuel (kerosene-type and naphtha-type) is consumed by the transportation sector. Beginning in 2005, kerosene-type jet fuel is consumed by the transportation sector, while naphtha-type jet fuel is classified under "Other Petroleum Products," which is assigned to the industrial sector.

### **Kerosene**

Kerosene product supplied is allocated to the individual end-use sectors (residential, commercial, and industrial) in proportion to each sector's share of sales as reported in EIA's *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-0535), which is based primarily on data collected by Form EIA-821, "Annual Fuel Oil and Kerosene Sales Report" (previously Form EIA-172).

Since 1979, the residential sector sales total is directly from the Sales reports. Prior to 1979, each year's sales category called "heating" is allocated to the residential, commercial, and industrial sectors in proportion to the 1979 shares.

Since 1979, the commercial sector sales total is directly from the Sales reports. Prior to 1979, each year's sales category called "heating" is allocated to the residential,

commercial, and industrial sectors in proportion to the 1979 shares.

Since 1979, the industrial sector sales total is the sum of the sales for industrial, farm, and all other uses. Prior to 1979, each year's sales category called "heating" is allocated to the residential, commercial and industrial sectors in proportion to the 1979 shares, and the estimated industrial (including farm) portion is added to all other uses.

### **Liquefied Petroleum Gases (LPG)**

The annual shares of LPG's total consumption that are estimated to be used by each sector are applied to each month's total LPG consumption to create monthly sector consumption estimates. The annual sector shares are calculated as described below.

Sales of LPG to the residential and commercial sectors combined are converted from thousand gallons per year to thousand barrels per year and are assumed to be the annual consumption of LPG by the combined sectors. Since 2003, residential sector LPG consumption is assumed to equal propane retail sales, with the remainder of the combined residential and commercial LPG consumption being assigned to the commercial sector. Prior to 2003, residential sector LPG consumption is based on the average of the State residential shares for 2003–2008, with the remainder of the combined residential and commercial LPG consumption being assigned to the commercial sector.

The quantity of LPG sold each year for consumption in internal combustion engines is allocated between the transportation and industrial sectors on the basis of data for special fuels used on highways published by the U.S. Department of Transportation, Federal Highway Administration, in *Highway Statistics*. The allocations of LPG sold for internal combustion engine use to the transportation sector range from a low of 20 percent (in 2001) to a high of 78 percent (in 2008).

LPG consumed annually by the industrial sector is estimated as the difference between LPG total product supplied and the sum of the estimated LPG consumption by the residential, commercial, and transportation sectors. The industrial sector LPG consumption includes LPG used by chemical plants as raw materials or solvents and used in the production of synthetic rubber; refinery fuel use; use as synthetic natural gas feedstock and use in secondary recovery projects; all farm use; LPG sold to gas utility companies for distribution through the mains; and a portion of the use of LPG as an internal combustion engine fuel.

Sources of the annual sales data for creating annual energy shares are:

1973–1982: EIA's "Sales of Liquefied Petroleum Gases and Ethane" reports, based primarily on data collected by Form EIA-174, "Sales of Liquefied Petroleum Gases."

1983: End-use consumption estimates for 1983 are based on 1982 end-use consumption because the collection of data under Form EIA-174 was discontinued after data year 1982. 1984 forward: American Petroleum Institute (API), "Sales of Natural Gas Liquids and Liquefied Refinery Gases," which is based on an LPG sales survey jointly sponsored by API, the Gas Processors Association, and the National Liquefied Petroleum Gas Association. EIA adjusts the data to remove quantities of pentanes plus and to estimate withheld values.

### **Lubricants**

The consumption of lubricants is allocated to the industrial and transportation sectors for all months according to proportions developed from annual sales of lubricants to the two sectors from U.S. Department of Commerce, Bureau of the Census, *Current Industrial Reports*, "Sales of Lubricating and Industrial Oils and Greases." The 1973 shares are applied to 1973 and 1974; the 1975 shares are applied to 1975 and 1976; and the 1977 shares are applied to 1977 forward.

### **Motor Gasoline**

The total monthly consumption of motor gasoline is allocated to the sectors in proportion to aggregations of annual sales categories created on the basis of the U.S. Department of Transportation, Federal Highway Administration, *Highway Statistics*, Tables MF-21, MF-24, and MF-25, as follows:

Commercial sales are the sum of sales for public non-highway use and miscellaneous and unclassified uses.

Industrial sales are the sum of sales for agriculture, construction, and industrial and commercial use as classified in the *Highway Statistics*.

Transportation sales are the sum of sales for highway use (minus the sales of special fuels, which are primarily diesel fuel and are accounted for in the transportation sector of distillate fuel) and sales for marine use.

### **Petroleum Coke**

Portions of petroleum coke are consumed by the electric power sector (see sources for Table 7.4b) and the commercial sector (see sources for Table 7.4c). The remaining petroleum coke is assigned to the industrial sector.

### **Residual Fuel Oil**

Residual fuel oil consumption is assigned to the sectors as follows:

#### **Residual Fuel Oil Consumed by the Electric Power Sector**

See sources for Table 7.4b. For 1973–1979, electric utility consumption of residual fuel oil is assumed to be the amount of petroleum consumed in steam-electric power plants. For 1980–2000, electric utility consumption of residual fuel oil is assumed to be the amount of heavy oil (fuel oil nos. 4, 5, and 6) consumed.

#### **Residual Fuel Oil Consumed by the End-Use Sectors, Annually**

The aggregate end-use amount is total residual fuel oil supplied minus the amount consumed by the electric power sector. The end-use total consumed annually is allocated to the individual end-use sectors (commercial, industrial, and transportation) in proportion to each sector's share of sales as reported in EIA's *Fuel Oil and Kerosene Sales (Sales)* report series (DOE/EIA-535), which is based primarily on data collected by Form EIA-821, "Annual Fuel Oil and Kerosene Sales Report" (previously Form EIA-172). Shares for the current year are based on the most recent Sales report.

Following are notes on the individual sector groupings:

Since 1979, commercial sales data are directly from the Sales reports. Prior to 1979, each year's sales subtotal of the heating plus industrial category is allocated to the commercial and industrial sectors in proportion to the 1979 shares.

Since 1979, industrial sales data are the sum of sales for industrial, oil company, and all other uses. Prior to 1979, each year's sales subtotal of the heating plus industrial category is allocated to the commercial and industrial sectors in proportion to the 1979 shares, and the estimated industrial portion is added to oil company and all other uses.

Transportation sales are the sum of sales for railroad, vessel bunkering, and military uses for all years.

#### **Residual Fuel Oil Consumed by the End-Use Sectors, Monthly**

Commercial sector monthly consumption is estimated by allocating the annual estimates, which are described above, into the months in proportion to each month's share of the year's sales of No. 2 heating oil. (For each month of the current year, the consumption increase from the same month in the previous year is based on the percent increase in that month's No. 2 heating oil sales from the same month in the previous year.) The years' No. 2 heating oil sales totals are from the following sources: for 1973–1980, the Ethyl Corporation, *Monthly Report of Heating Oil Sales*; for 1981 and 1982, the American Petroleum Institute, *Monthly Report of Heating Oil Sales*; and for 1983 forward, EIA, Form EIA-782A, "Refiners'/Gas Plant Operators' Monthly Petroleum Product Sales Report," No. 2 Fuel Oil Sales to End Users and for Resale.

A residual fuel oil "balance" is calculated as total residual fuel oil supplied minus the amount consumed by the electric power sector, commercial sector, and by industrial combined-heat-and-power plants (see sources for Table 7.4c).

Transportation sector monthly consumption is estimated by multiplying each month's residual fuel oil "balance" by the annual transportation consumption share of the annual residual fuel oil "balance."

Total industrial sector monthly consumption is estimated as total residual fuel oil supplied minus the amount consumed by the commercial, transportation, and electric power sectors.

#### **Other Petroleum Products**

Consumption of all remaining petroleum products is assigned to the industrial sector. Other petroleum products include pentanes plus, petrochemical feedstocks, special naphthas, still gas (refinery gas), waxes, and miscellaneous products. Beginning in 1981, also includes negative barrels per day of distillate and residual fuel oil reclassified as unfinished oils, and other products (from both primary and secondary supply) reclassified as gasoline blending components. Beginning in 1983, also includes crude oil burned as fuel. Beginning in 2005, also includes naphtha-type jet fuel.

#### **Table 3.8a Sources**

##### **Distillate Fuel Oil, Kerosene, Petroleum Coke, and Residual Fuel Oil**

Residential and/or commercial sector consumption data in thousand barrels per day for these petroleum products are from Table 3.7a, and are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1.

##### **Liquefied Petroleum Gases (LPG)**

Residential and commercial sector consumption data in thousand barrels per day for LPG are from Table 3.7a, and are converted to trillion Btu by multiplying by the propane heat content factor in Table A1.

##### **Motor Gasoline**

Commercial sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7a, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

##### **Total Petroleum**

Residential sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Residential Sector" in Table 3.8a. Commercial sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under "Commercial Sector" in Table 3.8a.

#### **Table 3.8b Sources**

##### **Asphalt and Road Oil, Distillate Fuel Oil, Kerosene, Lubricants, Petroleum Coke, and Residual Fuel Oil**

Industrial sector consumption data in thousand barrels per day for these petroleum products are from Table 3.7b, and are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1.

##### **Liquefied Petroleum Gases (LPG)**

Industrial sector consumption data for LPG are calculated by subtracting LPG consumption data in trillion Btu for the residential (Table 3.8a), commercial (Table 3.8a), and transportation (Table 3.8c) sectors from total LPG consumption (Table 3.6).

##### **Motor Gasoline**

Industrial sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7b, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

##### **Other Petroleum Products**

Industrial sector "Other" petroleum data are equal to the "Other" petroleum data in Table 3.6.

##### **Total Petroleum**

Industrial sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown in Table 3.8b.

#### **Table 3.8c Sources**

##### **Aviation Gasoline, Distillate Fuel Oil, Lubricants, Petroleum Coke, and Residual Fuel Oil**

Transportation and/or electric power sector consumption data in thousand barrels per day for these petroleum products are from Table 3.7c, and are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1.

##### **Jet Fuel**

Transportation sector consumption data in thousand barrels per day for kerosene-type jet fuel and, through 2004, naphtha-type jet fuel (see sources for Table 3.7c) are converted to trillion Btu by multiplying by the appropriate heat content factors in Table A1. Total transportation sector jet fuel consumption is the sum of the data in trillion Btu for kerosene-type and naphtha-type jet fuel.

##### **Liquefied Petroleum Gases (LPG)**

Transportation sector consumption data in thousand barrels per day for LPG are from Table 3.7c, and are converted to trillion Btu by multiplying by the propane heat content factor in Table A1.

**Motor Gasoline**

Transportation sector consumption data in thousand barrels per day for motor gasoline are from Table 3.7c, and are converted to trillion Btu by multiplying by the motor gasoline heat content factors in Table A3.

**Total Petroleum**


Transportation sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under “Transportation Sector” in Table 3.8c. Electric power sector total petroleum consumption is the sum of the data in trillion Btu for the petroleum products shown under “Electric Power Sector” in Table 3.8c.

## 4. Natural Gas


---

**Figure 4.1 Natural Gas**  
(Trillion Cubic Feet)


Overview, 1973-2011




Overview, Monthly




Consumption by Sector, 1973-2011




Consumption by Sector, Monthly



Underground Storage, End of Year, 1973-2011



Underground Storage, End of Month



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#naturalgas>.  
Sources: Tables 4.1, 4.3, and 4.4.

**Table 4.1 Natural Gas Overview**  
(Billion Cubic Feet)

	Gross Withdrawals <sup>a</sup>	Marketed Production (Wet) <sup>b</sup>	Extraction Loss <sup>c</sup>	Dry Gas Production <sup>d</sup>	Supplemental Gaseous Fuels <sup>e</sup>	Trade			Net Storage Withdrawals <sup>f</sup>	Balancing Item <sup>g</sup>	Consumption <sup>h</sup>
						Imports	Exports	Net Imports			
<b>1973 Total</b> .....	24,067	22,648	917	21,731	NA	1,033	77	956	-442	-196	22,049
<b>1975 Total</b> .....	21,104	20,109	872	19,236	NA	953	73	880	-344	-235	19,538
<b>1980 Total</b> .....	21,870	20,180	777	19,403	155	985	49	936	23	-640	19,877
<b>1985 Total</b> .....	19,607	17,270	816	16,454	126	950	55	894	235	-428	17,281
<b>1990 Total</b> .....	21,523	18,594	784	17,810	123	1,532	86	1,447	-513	307	19,174
<b>1995 Total</b> .....	23,744	19,506	908	18,599	110	2,841	154	2,687	415	396	22,207
<b>1996 Total</b> .....	24,114	19,812	958	18,854	109	2,937	153	2,784	2	860	22,609
<b>1997 Total</b> .....	24,213	19,866	964	18,902	103	2,994	157	2,837	24	871	22,737
<b>1998 Total</b> .....	24,108	19,961	938	19,024	102	3,152	159	2,993	-530	657	22,246
<b>1999 Total</b> .....	23,823	19,805	973	18,832	98	3,586	163	3,422	172	-119	22,405
<b>2000 Total</b> .....	24,174	20,198	1,016	19,182	90	3,782	244	3,538	829	-306	23,333
<b>2001 Total</b> .....	24,501	20,570	954	19,616	86	3,977	373	3,604	-1,166	99	22,239
<b>2002 Total</b> .....	23,941	19,885	957	18,928	68	4,015	516	3,499	467	65	23,027
<b>2003 Total</b> .....	24,119	19,974	876	19,099	68	3,944	680	3,264	-197	44	22,277
<b>2004 Total</b> .....	23,970	19,517	927	18,591	60	4,259	854	3,404	-114	461	22,403
<b>2005 Total</b> .....	23,457	18,927	876	18,051	64	4,341	729	3,612	52	236	22,014
<b>2006 Total</b> .....	23,535	19,410	906	18,504	66	4,186	724	3,462	-436	103	21,699
<b>2007 Total</b> .....	24,664	20,196	930	19,266	63	4,608	822	3,785	192	-203	23,104
<b>2008 Total</b> .....	25,636	21,112	953	20,159	61	3,984	963	3,021	34	2	23,277
<b>2009 Total</b> .....	26,057	21,648	1,024	20,624	65	3,751	1,072	2,679	-355	-103	22,910
<b>2010 January</b> .....	2,224	1,838	88	1,750	5	385	94	291	822	-86	2,783
February .....	2,057	1,692	81	1,611	5	324	88	236	628	-24	2,456
March .....	2,296	1,884	90	1,794	5	319	100	219	34	65	2,117
April .....	2,187	1,810	86	1,723	5	298	76	223	-364	80	1,667
May .....	2,231	1,881	90	1,791	5	298	86	212	-416	-2	1,591
June .....	2,134	1,797	86	1,712	5	282	90	192	-326	41	1,624
July .....	2,221	1,908	91	1,817	6	329	86	243	-231	-35	1,800
August .....	2,241	1,924	92	1,832	6	305	84	221	-190	-15	1,853
September .....	2,251	1,874	89	1,785	5	282	79	202	-363	-16	1,612
October .....	2,343	1,942	93	1,849	6	295	96	199	-360	-54	1,639
November .....	2,266	1,882	90	1,792	5	273	124	150	77	-78	1,947
December .....	2,388	1,971	94	1,877	6	352	135	217	675	-89	2,685
<b>Total</b> .....	<b>26,836</b>	<b>22,402</b>	<b>1,070</b>	<b>21,332</b>	<b>65</b>	<b>3,741</b>	<b>1,137</b>	<b>2,604</b>	<b>-13</b>	<b>-213</b>	<b>23,775</b>
<b>2011 January</b> .....	2,309	E 1,972	92	E 1,880	6	371	136	235	799	-44	2,876
February .....	2,109	E 1,752	79	E 1,674	5	308	125	183	584	-12	2,434
March .....	2,423	E 2,020	99	E 1,921	6	314	145	170	145	-16	2,226
April .....	2,363	E 1,979	95	E 1,884	5	278	127	152	-212	-2	1,826
May .....	2,420	E 2,046	101	E 1,945	3	271	132	139	-398	-26	1,663
June .....	2,330	E 1,977	95	E 1,881	5	265	120	146	-340	-42	1,649
July .....	2,344	E 2,044	99	E 1,944	5	293	113	179	-244	-11	1,874
August .....	2,371	E 2,051	99	E 1,951	5	279	111	168	-244	-8	1,872
September .....	2,371	E 2,005	95	E 1,910	5	253	127	127	-398	-3	1,640
October .....	2,496	E 2,112	104	E 2,008	5	281	110	171	-385	-53	1,746
November .....	2,483	E 2,074	104	E 1,971	5	247	128	120	-37	-52	2,006
December .....	2,557	E 2,138	107	E 2,031	6	295	134	161	384	-66	2,515
<b>Total</b> .....	<b>28,576</b>	<b>E 24,170</b>	<b>1,169</b>	<b>E 23,000</b>	<b>61</b>	<b>3,456</b>	<b>1,507</b>	<b>1,949</b>	<b>-348</b>	<b>-336</b>	<b>24,326</b>
<b>2012 January</b> .....	2,575	RE 2,150	109	RE 2,042	6	281	130	150	545	R -11	R 2,731
February .....	2,380	RE 1,991	102	RE 1,889	5	R 269	130	R 139	459	R -5	R 2,488
March .....	2,539	RE 2,125	109	RE 2,016	6	R 265	141	R 124	-39	R 1	R 2,107
April .....	R 2,447	RE 2,066	105	RE 1,961	5	R 243	R 122	R 121	-137	R -7	R 1,942
May .....	2,527	E 2,135	108	E 2,028	4	257	134	123	-283	-21	1,850
<b>5-Month Total</b> .....	<b>12,467</b>	<b>E 10,468</b>	<b>533</b>	<b>E 9,936</b>	<b>26</b>	<b>1,315</b>	<b>658</b>	<b>657</b>	<b>545</b>	<b>-44</b>	<b>11,119</b>
<b>2011 5-Month Total</b> .....	<b>11,625</b>	<b>E 9,770</b>	<b>466</b>	<b>E 9,304</b>	<b>25</b>	<b>1,542</b>	<b>665</b>	<b>878</b>	<b>918</b>	<b>-100</b>	<b>11,025</b>
<b>2010 5-Month Total</b> .....	<b>10,994</b>	<b>9,104</b>	<b>435</b>	<b>8,669</b>	<b>26</b>	<b>1,624</b>	<b>443</b>	<b>1,181</b>	<b>704</b>	<b>33</b>	<b>10,614</b>

<sup>a</sup> Gas withdrawn from natural gas and crude oil wells; excludes lease condensate.

<sup>b</sup> Gross withdrawals minus repressuring, nonhydrocarbon gases removed, and vented and flared. See Note 1, "Natural Gas Production," at end of section.

<sup>c</sup> See Note 2, "Natural Gas Extraction Loss," at end of section.

<sup>d</sup> Marketed production (wet) minus extraction loss.

<sup>e</sup> See Note 3, "Supplemental Gaseous Fuels," at end of section.

<sup>f</sup> Net withdrawals from underground storage. For 1980-2010, also includes net withdrawals of liquefied natural gas in above-ground tanks. See Note 4, "Natural Gas Storage," at end of section.

<sup>g</sup> See Note 5, "Natural Gas Balancing Item," at end of section. Since 1980, excludes transit shipments that cross the U.S.-Canada border (i.e., natural gas delivered to its destination via the other country).

<sup>h</sup> See Note 6, "Natural Gas Consumption," at end of section.

<sup>i</sup> May include unknown quantities of nonhydrocarbon gases.

<sup>j</sup> For 1989-1992, a small amount of consumption at independent power producers may be counted in both "Other Industrial" and "Electric Power Sector" on Table 4.3. See Note 7, "Natural Gas Consumption, 1989-1992," at end of section.

R=Revised. E=Estimate. NA=Not available.

Notes: • See Note 8, "Natural Gas Adjustments, 1993-2000," at end of section.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> for all available data beginning in 1973.

Sources: • Imports and Exports: Table 4.2. • Consumption: Table 4.3.

• Balancing Item: Calculated as consumption minus dry gas production, supplemental gaseous fuels, net imports, and net storage withdrawals. • All Other Data: 1973-2006—U.S. Energy Information Administration (EIA), *Natural Gas Annual*, annual reports. 2007 forward—EIA, *Natural Gas Monthly*, July 2012, Table 1.

**Table 4.2 Natural Gas Trade by Country**  
(Billion Cubic Feet)

	Imports									Exports				
	Algeria <sup>a</sup>	Canada <sup>b</sup>	Egypt <sup>a</sup>	Mexico <sup>b</sup>	Nigeria <sup>a</sup>	Qatar <sup>a</sup>	Trinidad and Tobago <sup>a</sup>	Other <sup>a,c</sup>	Total	Canada <sup>b</sup>	Japan <sup>a</sup>	Mexico <sup>b</sup>	Other <sup>a,d</sup>	Total
<b>1973 Total</b> .....	3	1,028	0	2	0	0	0	0	1,033	15	48	14	0	77
<b>1975 Total</b> .....	5	948	0	0	0	0	0	0	953	10	53	9	0	73
<b>1980 Total</b> .....	86	797	0	102	0	0	0	0	985	0	45	4	0	49
<b>1985 Total</b> .....	24	926	0	0	0	0	0	0	950	0	53	2	0	55
<b>1990 Total</b> .....	84	1,448	0	0	0	0	0	0	1,532	17	53	16	0	86
<b>1995 Total</b> .....	18	2,816	0	7	0	0	0	0	2,841	28	65	61	0	154
<b>1996 Total</b> .....	35	2,883	0	14	0	0	0	5	2,937	52	68	34	0	153
<b>1997 Total</b> .....	66	2,899	0	17	0	0	0	12	2,994	56	62	38	0	157
<b>1998 Total</b> .....	69	3,052	0	15	0	0	0	17	3,152	40	66	53	0	159
<b>1999 Total</b> .....	76	3,368	0	55	0	20	51	17	3,586	39	64	61	0	163
<b>2000 Total</b> .....	47	3,544	0	12	13	46	99	21	3,782	73	66	106	0	244
<b>2001 Total</b> .....	65	3,729	0	10	38	23	98	14	3,977	167	66	141	0	373
<b>2002 Total</b> .....	27	3,785	0	2	8	35	151	8	4,015	189	63	263	0	516
<b>2003 Total</b> .....	53	3,437	0	0	50	14	378	11	3,944	271	66	343	0	680
<b>2004 Total</b> .....	120	3,607	0	0	12	12	462	46	4,259	395	62	397	0	854
<b>2005 Total</b> .....	97	3,700	73	9	8	3	439	11	4,341	358	65	305	0	729
<b>2006 Total</b> .....	17	3,590	120	13	57	0	389	0	4,186	341	61	322	0	724
<b>2007 Total</b> .....	77	3,783	115	54	95	18	448	18	4,608	482	47	292	2	822
<b>2008 Total</b> .....	0	3,589	55	43	12	3	267	15	3,984	559	39	365	0	963
<b>2009 Total</b> .....	0	3,271	160	28	13	13	236	29	3,751	701	31	338	3	1,072
<b>2010</b>														
January .....	0	327	17	1	0	12	22	6	385	68	2	23	0	94
February .....	0	277	12	1	0	6	16	12	324	60	2	22	3	88
March .....	0	276	9	5	3	1	16	9	319	77	2	21	0	100
April .....	0	252	6	5	9	9	15	3	298	50	4	22	0	76
May .....	0	257	9	4	9	0	16	3	298	55	2	29	0	86
June .....	0	248	6	2	11	0	11	5	282	51	2	34	3	90
July .....	0	291	6	1	5	0	17	8	329	50	4	32	0	86
August .....	0	282	0	1	0	0	17	5	305	49	2	33	0	84
September .....	0	250	6	3	3	0	16	3	282	50	7	23	0	79
October .....	0	257	3	4	2	5	15	9	295	63	2	25	6	96
November .....	0	242	0	(s)	0	9	14	9	273	84	2	30	8	124
December .....	0	322	0	1	0	4	15	9	352	82	3	38	12	135
<b>Total</b> .....	<b>0</b>	<b>3,280</b>	<b>73</b>	<b>30</b>	<b>42</b>	<b>46</b>	<b>190</b>	<b>81</b>	<b>3,741</b>	<b>739</b>	<b>33</b>	<b>333</b>	<b>32</b>	<b>1,137</b>
<b>2011</b>														
January .....	0	331	3	(s)	0	13	16	9	371	85	2	37	13	136
February .....	0	276	6	(s)	0	0	11	15	308	84	2	37	3	125
March .....	0	275	6	(s)	0	14	10	9	314	98	2	41	3	145
April .....	0	245	6	(s)	0	4	11	13	278	76	2	43	6	127
May .....	0	235	3	(s)	0	24	8	0	271	80	3	44	6	132
June .....	0	238	6	(s)	0	5	11	6	265	71	2	47	0	120
July .....	0	272	0	(s)	0	5	13	3	293	64	0	47	3	113
August .....	0	249	0	(s)	2	8	11	9	279	67	2	42	0	111
September .....	0	233	0	(s)	0	4	8	9	253	77	2	39	8	127
October .....	0	250	3	1	0	8	8	12	281	64	0	43	3	110
November .....	0	232	0	(s)	0	3	12	0	247	84	2	39	3	128
December .....	0	269	3	(s)	0	4	10	9	295	87	0	42	5	134
<b>Total</b> .....	<b>0</b>	<b>3,104</b>	<b>35</b>	<b>3</b>	<b>2</b>	<b>91</b>	<b>129</b>	<b>92</b>	<b>3,456</b>	<b>937</b>	<b>18</b>	<b>500</b>	<b>52</b>	<b>1,507</b>
<b>2012</b>														
January .....	0	265	0	(s)	0	4	9	3	281	84	3	40	3	130
February .....	0	<sup>R</sup> 249	3	(s)	0	0	11	6	<sup>R</sup> 269	<sup>R</sup> 87	2	42	0	130
March .....	0	<sup>R</sup> 246	0	(s)	0	4	13	3	<sup>R</sup> 265	93	0	46	3	141
April .....	0	<sup>R</sup> 235	0	(s)	0	4	1	3	<sup>R</sup> 243	77	0	45	0	<sup>R</sup> 122
May .....	0	240	0	(s)	0	6	11	0	257	79	3	52	0	134
<b>5-Month Total</b> .....	<b>0</b>	<b>1,236</b>	<b>3</b>	<b>(s)</b>	<b>0</b>	<b>16</b>	<b>46</b>	<b>14</b>	<b>1,315</b>	<b>419</b>	<b>8</b>	<b>225</b>	<b>6</b>	<b>658</b>
<b>2011 5-Month Total</b> .....	<b>0</b>	<b>1,362</b>	<b>23</b>	<b>1</b>	<b>0</b>	<b>55</b>	<b>56</b>	<b>45</b>	<b>1,542</b>	<b>423</b>	<b>10</b>	<b>201</b>	<b>30</b>	<b>665</b>
<b>2010 5-Month Total</b> .....	<b>0</b>	<b>1,389</b>	<b>52</b>	<b>17</b>	<b>20</b>	<b>28</b>	<b>86</b>	<b>32</b>	<b>1,624</b>	<b>311</b>	<b>12</b>	<b>117</b>	<b>3</b>	<b>443</b>

<sup>a</sup> As liquefied natural gas.

<sup>b</sup> By pipeline, except for very small amounts of liquefied natural gas imported from Canada in 1973, 1977, and 1981 and exported to Mexico beginning in 1998. See Note 9, "Natural Gas Imports and Exports," at end of section.

<sup>c</sup> Australia in 1997-2001 and 2004; Brunei in 2002; Equatorial Guinea in 2007; Indonesia in 1986 and 2000; Malaysia in 1999 and 2002-2005; Norway in 2008 forward; Oman in 2000-2005; Peru in 2010 and 2011; United Arab Emirates in 1996-2000; Yemen in 2010 forward; and Other (unassigned) in 2004.

<sup>d</sup> Brazil in 2010 forward; China in 2011; Chile in 2011; India in 2010 forward; Russia in 2007; South Korea in 2009-2011; Spain in 2010 and 2011; and United Kingdom in 2010 and 2011.

R=Revised. (s)=Less than 500 million cubic feet.

Notes: • See Note 9, "Natural Gas Imports and Exports," at end of section. • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> for all available data beginning in 1973.

Sources: • **1973-1987:** U.S. Energy Information Administration (EIA), Form FPC-14, "Annual Report for Importers and Exporters of Natural Gas." • **1988-2008:** EIA, *Natural Gas Annual*, annual reports. • **2009 forward:** EIA, *Natural Gas Monthly*, July 2012, Tables 4 and 5; and U.S. Department of Energy, Office of Fossil Energy, "Natural Gas Imports and Exports."



**Table 4.3 Natural Gas Consumption by Sector**  
(Billion Cubic Feet)

	End-Use Sectors										Electric Power Sector <sup>f,g</sup>	Total
	Residential	Commercial <sup>a</sup>	Lease and Plant Fuel	Industrial			Transportation					
				CHP <sup>b</sup>	Non-CHP <sup>c</sup>	Total	Total	Pipelines <sup>d</sup> and Distribution <sup>e</sup>	Vehicle Fuel	Total		
<b>1973 Total</b> .....	4,879	2,597	1,496	(h)	8,689	8,689	10,185	728	NA	728	3,660	22,049
<b>1975 Total</b> .....	4,924	2,508	1,396	(h)	6,968	6,968	8,365	583	NA	583	3,158	19,538
<b>1980 Total</b> .....	4,752	2,611	1,026	(h)	7,172	7,172	8,198	635	NA	635	3,682	19,877
<b>1985 Total</b> .....	4,433	2,432	966	(h)	5,901	5,901	6,867	504	NA	504	3,044	17,281
<b>1990 Total</b> .....	4,391	2,623	1,236	1,055	5,963	5,963	7,018	660	(s)	660	3,245	19,174
<b>1995 Total</b> .....	4,850	3,031	1,220	1,258	6,906	6,906	8,164	700	5	705	4,237	22,207
<b>1996 Total</b> .....	5,241	3,158	1,250	1,289	7,146	8,435	9,685	711	6	718	3,807	22,609
<b>1997 Total</b> .....	4,984	3,215	1,203	1,282	7,229	8,511	9,714	751	8	760	4,065	22,737
<b>1998 Total</b> .....	4,520	2,999	1,173	1,355	6,965	8,320	9,493	635	9	645	4,588	22,246
<b>1999 Total</b> .....	4,726	3,045	1,079	1,401	6,678	8,079	9,158	645	12	657	4,820	22,405
<b>2000 Total</b> .....	4,996	3,182	1,151	1,386	6,757	8,142	9,293	642	13	655	5,206	23,333
<b>2001 Total</b> .....	4,771	3,023	1,119	1,310	6,035	7,344	8,463	625	15	640	5,342	22,239
<b>2002 Total</b> .....	4,889	3,144	1,113	1,240	6,287	7,527	8,640	667	15	682	5,672	23,027
<b>2003 Total</b> .....	5,079	3,179	1,122	1,144	6,007	7,150	8,273	591	18	610	5,135	22,277
<b>2004 Total</b> .....	4,869	3,129	1,098	1,191	6,066	7,256	8,354	566	21	587	5,464	22,403
<b>2005 Total</b> .....	4,827	2,999	1,112	1,084	5,518	6,601	7,713	584	23	607	5,869	22,014
<b>2006 Total</b> .....	4,368	2,832	1,142	1,115	5,412	6,527	7,669	584	24	608	6,222	21,699
<b>2007 Total</b> .....	4,722	3,013	1,226	1,050	5,604	6,655	7,881	621	25	646	6,841	23,104
<b>2008 Total</b> .....	4,892	3,153	1,220	955	5,715	6,670	7,890	648	26	674	6,668	23,277
<b>2009 Total</b> .....	4,779	3,119	1,275	990	5,178	6,167	7,443	670	27	697	6,873	22,910
<b>2010</b>												
January .....	934	499	106	90	526	616	722	80	3	82	546	2,783
February .....	796	441	98	80	490	570	667	70	2	72	480	2,486
March .....	580	337	109	84	488	572	681	60	3	62	457	2,117
April .....	313	215	104	79	435	514	618	46	3	49	471	1,667
May .....	198	161	107	82	437	519	626	44	3	47	560	1,591
June .....	134	130	102	84	420	504	607	45	3	48	706	1,624
July .....	111	120	107	91	420	512	619	50	3	53	897	1,800
August .....	107	127	108	95	419	514	622	52	3	55	943	1,853
September .....	117	133	107	87	424	511	618	45	3	47	697	1,612
October .....	202	185	112	84	438	522	634	45	3	48	570	1,639
November .....	447	287	108	82	469	551	659	55	3	57	497	1,947
December .....	848	467	114	92	521	613	727	76	3	79	564	2,685
<b>Total</b> .....	<b>4,787</b>	<b>3,102</b>	<b>1,282</b>	<b>1,029</b>	<b>5,488</b>	<b>6,517</b>	<b>7,800</b>	<b>669</b>	<b>31</b>	<b>700</b>	<b>7,387</b>	<b>23,775</b>
<b>2011</b>												
January .....	973	529	E 113	89	546	635	748	E 81	E 3	E 84	542	2,876
February .....	772	433	E 100	79	497	576	676	E 68	E 3	E 71	482	2,434
March .....	607	364	E 116	81	509	591	706	E 63	E 3	E 65	483	2,226
April .....	349	236	E 113	82	465	548	661	E 51	E 3	E 54	526	1,826
May .....	208	168	E 117	87	456	543	660	E 47	E 3	E 49	578	1,663
June .....	133	133	E 113	83	433	515	629	E 46	E 3	E 49	705	1,649
July .....	112	126	E 117	88	433	521	638	E 53	E 3	E 55	942	1,874
August .....	109	133	E 117	89	443	533	650	E 53	E 3	E 55	923	1,872
September .....	122	141	E 115	84	443	527	642	E 46	E 3	E 49	686	1,640
October .....	229	216	E 121	81	469	550	671	E 49	E 3	E 52	578	1,746
November .....	431	283	E 119	86	486	572	691	E 56	E 3	E 59	543	2,006
December .....	688	398	E 122	94	526	620	742	E 71	E 3	E 74	612	2,515
<b>Total</b> .....	<b>4,732</b>	<b>3,161</b>	<b>E 1,383</b>	<b>1,024</b>	<b>5,707</b>	<b>6,731</b>	<b>8,114</b>	<b>E 684</b>	<b>E 33</b>	<b>E 717</b>	<b>7,602</b>	<b>24,326</b>
<b>2012</b>												
January .....	802	448	RE 123	94	534	628	751	E 77	E 3	E 80	651	R 2,731
February .....	668	391	E 114	87	507	594	708	E 70	E 3	E 73	649	R 2,488
March .....	R 408	R 263	E 122	89	484	573	R 694	E 59	E 3	E 62	680	R 2,107
April .....	R 283	R 212	RE 118	84	463	547	R 665	E 55	E 3	E 57	724	R 1,942
May .....	165	150	E 122	90	449	539	662	E 52	E 3	E 55	819	1,850
<b>5-Month Total</b> .....	<b>2,325</b>	<b>1,464</b>	<b>E 599</b>	<b>444</b>	<b>2,436</b>	<b>2,881</b>	<b>3,480</b>	<b>E 313</b>	<b>E 14</b>	<b>E 326</b>	<b>3,523</b>	<b>11,119</b>
<b>2011 5-Month Total</b> .....	<b>2,908</b>	<b>1,731</b>	<b>E 559</b>	<b>419</b>	<b>2,473</b>	<b>2,892</b>	<b>3,451</b>	<b>E 310</b>	<b>E 14</b>	<b>E 324</b>	<b>2,611</b>	<b>11,025</b>
<b>2010 5-Month Total</b> .....	<b>2,821</b>	<b>1,653</b>	<b>524</b>	<b>413</b>	<b>2,377</b>	<b>2,790</b>	<b>3,314</b>	<b>300</b>	<b>13</b>	<b>313</b>	<b>2,513</b>	<b>10,614</b>

<sup>a</sup> All commercial sector fuel use, including that at commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Table 7.4c for CHP fuel use.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and a small number of industrial electricity-only plants.

<sup>c</sup> All industrial sector fuel use other than that in "Lease and Plant Fuel" and "CHP."

<sup>d</sup> Natural gas consumed in the operation of pipelines, primarily in compressors.

<sup>e</sup> Natural gas used as fuel in the delivery of natural gas to consumers.

<sup>f</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>g</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

<sup>h</sup> Included in "Non-CHP."

<sup>i</sup> For 1989-1992, a small amount of consumption at independent power producers may be counted in both "Other Industrial" and "Electric Power Sector." See Note 7, "Natural Gas Consumption, 1989-1992," at end of section.

R=Revised. E=Estimate. NA=Not available. (s)=Less than 500 million cubic feet.

Notes: • Data are for natural gas, plus a small amount of supplemental

gaseous fuels. • See Note 8, "Natural Gas Adjustments, 1993-2000," at end of section. • See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> for all available data beginning in 1973.

Sources: • **Residential, Commercial, Lease and Plant Fuel, Other Industrial Total and Pipelines and Distribution: 1973-2006**—U.S. Energy Information Administration (EIA), *Natural Gas Annual (NGA)*, annual reports and unpublished revisions. **2007 forward**—EIA, *Natural Gas Monthly (NGM)*, July 2012, Table 2. • **Industrial CHP:** Table 7.4c. • **Vehicle Fuel: 1990 and 1991**—EIA, NGA 2000, (November 2001), Table 95. **1992-1998**—EIA, "Alternatives to Traditional Transportation Fuels 1999" (October 1999), Table 10, and "Alternatives to Traditional Transportation Fuels 2003" (February 2004), Table 10. Data for compressed natural gas and liquefied natural gas in gasoline-equivalent gallons were converted to cubic feet by multiplying by the motor gasoline conversion factor (see Table A3) and dividing by the natural gas end-use sectors conversion factor (see Table A4). **1999-2006**—EIA, NGA, annual reports. **2007 forward**—EIA, NGM, July 2012, Table 2. • **Electric Power Sector:** Table 7.4b.

**Table 4.4 Natural Gas in Underground Storage**  
(Volumes in Billion Cubic Feet)

	Natural Gas in Underground Storage, End of Period			Change in Working Gas From Same Period Previous Year		Storage Activity		
	Base Gas	Working Gas	Total <sup>a</sup>	Volume	Percent	Withdrawals	Injections	Net <sup>b,c</sup>
<b>1973 Total</b> .....	2,864	2,034	4,898	305	17.6	1,533	1,974	-442
<b>1975 Total</b> .....	3,162	2,212	5,374	162	7.9	1,760	2,104	-344
<b>1980 Total</b> .....	3,642	2,655	6,297	-99	-3.6	1,910	1,896	14
<b>1985 Total</b> .....	3,842	2,607	6,448	-270	-9.4	2,359	2,128	231
<b>1990 Total</b> .....	3,868	3,068	6,936	555	22.1	1,934	2,433	-499
<b>1995 Total</b> .....	4,349	2,153	6,503	-453	-17.4	2,974	2,566	408
<b>1996 Total</b> .....	4,341	2,173	6,513	19	.9	2,911	2,906	6
<b>1997 Total</b> .....	4,350	2,175	6,525	2	.1	2,824	2,800	24
<b>1998 Total</b> .....	4,326	2,730	7,056	554	25.5	2,379	2,905	-526
<b>1999 Total</b> .....	4,383	2,523	6,906	-207	-7.6	2,772	2,598	174
<b>2000 Total</b> .....	4,352	1,719	6,071	-806	-31.9	3,498	2,684	814
<b>2001 Total</b> .....	4,301	2,904	7,204	1,185	68.9	2,309	3,464	-1,156
<b>2002 Total</b> .....	4,340	2,375	6,715	-528	-18.2	3,138	2,670	468
<b>2003 Total</b> .....	4,303	2,563	6,866	187	7.9	3,099	3,292	-193
<b>2004 Total</b> .....	4,201	2,696	6,897	133	5.2	3,037	3,150	-113
<b>2005 Total</b> .....	4,200	2,635	6,835	-61	-2.3	3,057	3,002	55
<b>2006 Total</b> .....	4,211	3,070	7,281	435	16.5	2,493	2,924	-431
<b>2007 Total</b> .....	4,234	2,879	7,113	-191	-6.2	3,325	3,133	192
<b>2008 Total</b> .....	4,232	2,840	7,073	-39	-1.4	3,374	3,340	34
<b>2009 Total</b> .....	4,277	3,130	7,407	290	10.2	2,966	3,315	-349
<b>2010 January</b> .....	4,276	2,304	6,580	171	8.0	873	63	811
February .....	4,278	1,683	5,961	-75	-4.2	657	38	619
March .....	4,278	1,652	5,930	-7	-.4	238	207	31
April .....	4,278	2,011	6,289	101	5.3	68	427	-360
May .....	4,279	2,420	6,699	45	1.9	53	463	-410
June .....	4,287	2,740	7,027	-20	-.7	64	385	-321
July .....	4,287	2,966	7,253	-125	-4.0	112	339	-227
August .....	4,290	3,153	7,443	-206	-6.1	137	323	-186
September .....	4,294	3,508	7,801	-138	-3.8	52	411	-359
October .....	4,305	3,851	8,156	41	1.1	52	407	-355
November .....	4,309	3,769	8,078	-69	-1.8	237	163	74
December .....	4,301	3,111	7,412	-19	-.6	731	66	665
<b>Total</b> .....	<b>4,301</b>	<b>3,111</b>	<b>7,412</b>	<b>-19</b>	<b>-6</b>	<b>3,274</b>	<b>3,291</b>	<b>-17</b>
<b>2011 January</b> .....	4,306	2,308	6,614	4	.2	852	53	799
February .....	4,306	1,724	6,029	40	2.4	668	84	584
March .....	4,304	1,581	5,884	-72	-4.3	317	172	145
April .....	4,307	1,789	6,096	-222	-11.0	108	320	-212
May .....	4,308	2,188	6,495	-232	-9.6	66	464	-398
June .....	4,305	2,530	6,835	-210	-7.7	90	430	-340
July .....	4,304	2,774	7,079	-192	-6.5	124	368	-244
August .....	4,304	3,020	7,323	-133	-4.2	138	382	-244
September .....	4,305	3,416	7,721	-92	-2.6	64	462	-398
October .....	4,305	3,804	8,109	-46	-1.2	62	448	-385
November .....	4,302	3,843	8,145	74	2.0	198	235	-37
December .....	4,305	3,462	7,767	351	11.3	488	105	384
<b>Total</b> .....	<b>4,305</b>	<b>3,462</b>	<b>7,767</b>	<b>351</b>	<b>11.3</b>	<b>3,175</b>	<b>3,523</b>	<b>-348</b>
<b>2012 January</b> .....	4,307	2,916	7,223	608	26.4	633	88	545
February .....	4,307	2,455	6,762	731	42.4	526	67	459
March .....	4,325	2,477	6,802	896	56.7	217	256	-39
April .....	4,329	2,613	6,942	824	46.1	144	282	-137
May .....	4,334	2,890	7,225	703	32.1	92	375	-283
<b>5-Month Total</b> .....	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>1,612</b>	<b>1,067</b>	<b>545</b>
<b>2011 5-Month Total</b> .....	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>2,011</b>	<b>1,094</b>	<b>918</b>
<b>2010 5-Month Total</b> .....	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>1,889</b>	<b>1,197</b>	<b>691</b>

<sup>a</sup> For total underground storage capacity at the end of each calendar year, see Note 4, "Natural Gas Storage," at end of section.

<sup>b</sup> For 1980-2010, data differ from those shown on Table 4.1, which includes liquefied natural gas storage for that period.

<sup>c</sup> Positive numbers indicate that withdrawals are greater than injections. Negative numbers indicate that injections are greater than withdrawals. Net withdrawals or injections may not equal the difference between applicable ending stocks. See Note 4, "Natural Gas Storage," at end of section.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#naturalgas> for all available data beginning in 1973.

Sources: • **Storage Activity: 1973-1975**—U.S. Energy Information Administration (EIA), *Natural Gas Annual 1994, Volume 2*, Table 9.

**1976-1979**—EIA, *Natural Gas Production and Consumption 1979*, Table 1. **1980-1995**—EIA, *Historical Natural Gas Annual 1930 Through 2000*, Table 11. **1996-2006**—EIA, *Natural Gas Monthly (NGM)*, monthly issues. **2007 forward**—EIA, NGM, July 2012, Table 8. • **All Other Data: 1973 and 1974**—American Gas Association, *Gas Facts, 1972 Data*, Table 57, *Gas Facts, 1973 Data*, Table 57, and *Gas Facts, 1974 Data*, Table 40. **1975 and 1976**—Federal Energy Administration (FEA), Form FEA-G318-M-0, "Underground Gas Storage Report," and Federal Power Commission (FPC), Form FPC-8, "Underground Gas Storage Report." **1977 and 1978**—EIA, Form FEA-G318-M-0, "Underground Gas Storage Report," and Federal Energy Regulatory Commission (FERC), Form FERC-8, "Underground Gas Storage Report." **1979-1995**—EIA, Form EIA-191, "Underground Gas Storage Report," and FERC, Form FERC-8, "Underground Gas Storage Report." **1996-2006**—EIA, NGM, monthly issues. **2007 forward**—EIA, NGM, July 2012, Table 8.

## Natural Gas

**Note 1. Natural Gas Production.** Final annual data are from the U.S. Energy Information Administration (EIA) *Natural Gas Annual (NGA)*.

Data for the two most recent months presented are estimated. Some of the data for earlier months are also estimated or computed. For a discussion of computation and estimation procedures, see the EIA *Natural Gas Monthly (NGM)*.

Monthly data are considered preliminary until after publication of the EIA NGA. Preliminary monthly data are gathered from reports to the Interstate Oil Compact Commission and the U.S. Minerals Management Service. Volumetric data are converted, as necessary, to a standard 14.73 psi pressure base. Unless there are major changes, data are not revised until after publication of the EIA NGA.

Differences between annual data in the EIA NGA and the sum of preliminary monthly data (January–December) are allocated proportionally to the months to create final monthly data.

**Note 2. Natural Gas Extraction Loss.** Extraction loss is the reduction in volume of natural gas resulting from the removal of natural gas liquid constituents at natural gas processing plants.

Annual data are from the EIA NGA, where they are estimated on the basis of the type and quantity of liquid products extracted from the gas stream and the calculated volume of such products at standard conditions. For a detailed explanation of the calculations used to derive estimated extraction losses, see the EIA NGA.

Preliminary monthly data are estimated on the basis of extraction loss as an annual percentage of marketed production. This percentage is applied to each month's marketed production to estimate monthly extraction loss.

Monthly data are revised and considered final after the publication of the EIA NGA. Final monthly data are estimated by allocating annual extraction loss data to the months on the basis of total natural gas marketed production data from the EIA NGA.

**Note 3. Supplemental Gaseous Fuels.** Supplemental gaseous fuels are any substances that, introduced into or commingled with natural gas, increase the volume available for disposition. Such substances include, but are not limited to, propane-air, refinery gas, coke oven gas, still gas, manufactured gas, biomass gas, and air or inert gases added for Btu stabilization.

Annual data beginning with 1980 are from the EIA NGA. Unknown quantities of supplemental gaseous fuels are included in consumption data for 1979 and earlier years.

Monthly data are considered preliminary until after the publication of the EIA NGA. Monthly estimates are based on the annual ratio of supplemental gaseous fuels to the sum of dry gas production, net imports, and net withdrawals from storage. The ratio is applied to the monthly sum of the three elements to compute a monthly supplemental gaseous fuels figure.

Although the total amount of supplemental gaseous fuels consumed is known for 1980 forward, the amount consumed by each energy-use sector is estimated by EIA. These estimates are used to create natural gas (without supplemental gaseous fuels) data for Tables 1.3, 2.2, 2.3, 2.4, and 2.6 (note: to avoid double-counting in these tables, supplemental gaseous fuels are accounted for in their primary energy category: "Coal," "Petroleum," or "Biomass"). It is assumed that supplemental gaseous fuels are commingled with natural gas consumed by the residential, commercial, other industrial, and electric power sectors, but are not commingled with natural gas used for lease and plant fuel, pipelines and distribution, or vehicle fuel. The estimated consumption of supplemental gaseous fuels by each sector (residential, commercial, other industrial, and electric power) is calculated as that sector's natural gas consumption (see Table 4.3) divided by the sum of natural gas consumption by the residential, commercial, other industrial, and electric power sectors (see Table 4.3), and then multiplied by total supplemental gaseous fuels consumption (see Table 4.1). For estimated sectoral consumption of supplemental gaseous fuels in Btu, the residential, commercial, and other industrial values in cubic feet are multiplied by the "End-Use Sectors" conversion factors (see Table A4), and the electric power values in cubic feet are multiplied by the "Electric Power Sector" conversion factors (see Table A4). Total supplemental gaseous fuels consumption in Btu is calculated as the sum of the Btu values for the sectors.

**Note 4. Natural Gas Storage.** Natural gas in storage at the end of a reporting period may not equal the quantity derived by adding or subtracting net injections or withdrawals from the quantity in storage at the end of the previous period. The difference is due to changes in the quantity of native gas included in the base gas and/or losses in base gas due to migration from storage reservoirs.

Total underground storage capacity, which includes both active and inactive fields, at the end of each calendar year since 1975 (first year data were available), in billion cubic feet, was:

1975 ...	6,280	1988 ...	8,124	2001 ...	8,182
1976 ...	6,544	1989 ...	8,120	2002 ...	8,207
1977 ...	6,678	1990 ...	7,794	2003 ...	8,206
1978 ...	6,890	1991 ...	7,993	2004 ...	8,255
1979 ...	6,929	1992 ...	7,932	2005 ...	8,268
1980 ...	7,434	1993 ...	7,989	2006 ...	8,330
1981 ...	7,805	1994 ...	8,043	2007 ...	8,402
1982 ...	7,915	1995 ...	7,953	2008 ...	8,499
1983 ...	7,985	1996 ...	7,980	2009 ...	8,656
1984 ...	8,043	1997 ...	8,332	2010 ...	8,764
1985 ...	8,087	1998 ...	8,179	2011 ...	<sup>P</sup> 8,776
1986 ...	8,145	1999 ...	8,229		
1987 ...	8,124	2000 ...	8,241		

P=Preliminary

Monthly underground storage data are collected from the Federal Energy Regulatory Commission Form FERC-8 (interstate data) and EIA Form EIA-191 (intrastate data). Beginning in January 1991, all data are collected on the revised Form EIA-191. Injection and withdrawal data from the FERC-8/EIA-191 survey are adjusted to correspond to data from Form EIA-176 following publication of the EIA NGA.

The final monthly and annual storage and withdrawal data for 1980–2010 include both underground and liquefied natural gas (LNG) storage. Annual data on LNG additions and withdrawals are from Form EIA-176. Monthly data are estimated by computing the ratio of each month's underground storage additions and withdrawals to annual underground storage additions and withdrawals and applying the ratio to the annual LNG data.

**Note 5. Natural Gas Balancing Item.** The balancing item for natural gas represents the difference between the sum of the components of natural gas supply and the sum of components of natural gas disposition. The differences may be due to quantities lost or to the effects of data reporting problems. Reporting problems include differences due to the net result of conversions of flow data metered at varying temperature and pressure bases and converted to a standard temperature and pressure base; the effect of variations in company accounting and billing practices; differences between billing cycle and calendar period time frames; and imbalances resulting from the merger of data reporting systems that vary in scope, format, definitions, and type of respondents.

The increase of 0.2 trillion cubic feet (Tcf) in the “Balancing Item” category in 1983, followed by a decline of 0.5 Tcf in 1984, reflected unusually large differences resulting from the use of the annual billing cycle (essentially December 15 through the following December 14) consumption data in conjunction with calendar year supply data. Record cold temperatures during the last half of December 1983 resulted in a reported 0.3 Tcf increase in net withdrawals from underground storage for peak shaving as compared with the same period in 1982, but the effect of this cold weather was reflected primarily in 1984 consumption data. For underground storage data, see Table F2 in the May 1985 EIA NGM, which was published in July 1985.

**Note 6. Natural Gas Consumption.** Consumption includes use for lease and plant fuel, pipelines and distribution, vehicle fuel, and electric power plants, as well as deliveries to residential, commercial, and other industrial customers.

Final data for series other than “Other Industrial CHP” and “Electric Power Sector” are from the EIA NGA. Monthly data are considered preliminary until after publication of the EIA NGA. For more detailed information on the methods of estimating preliminary and final monthly data, see the EIA NGM.

**Note 7. Natural Gas Consumption, 1989–1992.** Prior to 1993, deliveries to nonutility generators were not separately collected from natural gas companies on Form

EIA-176, “Annual Report of Natural and Supplemental Gas Supply and Disposition.” As a result, for 1989 through 1992, those volumes are probably included in both the industrial and electric power sectors and double-counted in total consumption. In 1993, 0.28 trillion cubic feet was reported as delivered to nonutility generators.

**Note 8. Natural Gas Data Adjustments, 1993–2000.** For 1993–2000, the original data for natural gas delivered to industrial consumers (now “Other Industrial” in Table 4.3) included deliveries to both industrial users and independent power producers (IPPs). These data were adjusted to remove the estimated consumption at IPPs from “Other Industrial” and include it with electric utilities under “Electric Power Sector.” (To estimate the monthly IPP consumption, the monthly pattern for Other Industrial CHP in Table 4.3 was used.)

For 1996–2000, monthly data for several natural gas series shown in EIA's Natural Gas Navigator (see [http://www.eia.gov/dnav/ng/ng\\_cons\\_sum\\_dcu\\_nus\\_m.htm](http://www.eia.gov/dnav/ng/ng_cons_sum_dcu_nus_m.htm)) were not reconciled and updated to be consistent with the final annual data in EIA's NGA. In the *Monthly Energy Review*, monthly data for these series were adjusted so that the monthly data sum to the final annual values. The Table 4.1 data series (and years) that were adjusted are: Gross Withdrawals (1996, 1997), Marketed Production (1997), Extraction Loss (1997, 1998, 2000), Dry Gas Production (1996, 1997), Supplemental Gaseous Fuels (1997–2000), Balancing Item (1997–2000), and Total Consumption (1997–2000). The Table 4.3 data series (and years) that were adjusted are: Lease and Plant Fuel (1997–2000), Total Industrial (1997–2000), Pipelines and Distribution (2000), Total Transportation (2000), and Total Consumption (1997–2000).

**Note 9. Natural Gas Imports and Exports.** The United States imports natural gas via pipeline from Canada and Mexico; and imports liquefied natural gas (LNG) via tanker from Algeria, Australia, Brunei, Egypt, Equatorial Guinea, Indonesia, Malaysia, Nigeria, Norway, Oman, Peru, Qatar, Trinidad and Tobago, the United Arab Emirates, and Yemen. In addition, very small amounts of LNG arrived from Canada in 1973 (667 million cubic feet), 1977 (572 million cubic feet), and 1981 (6 million cubic feet). The United States exports natural gas via pipeline to Canada and Mexico; and exports LNG via tanker to Brazil, China, Chile, India, Japan, Russia, South Korea, Spain, and United Kingdom. Also, small amounts of LNG have gone to Mexico since 1998.

Annual and final monthly data are from the annual EIA Form FPC-14, “Annual Report for Importers and Exporters of Natural Gas,” which requires data to be reported by month for the calendar year.


Preliminary monthly data are EIA estimates. For a discussion of estimation procedures, see the EIA NGM. Preliminary data are revised after the publication of the EIA *U.S. Imports and Exports of Natural Gas*.

# **5. Crude Oil and Natural Gas Resource Development**


---

**Figure 5.1 Crude Oil and Natural Gas Resource Development Indicators**


Rotary Rigs in Operation by Type, 1973-2011




Rotary Rigs in Operation by Type, Monthly




Active Well Service Rig Count, Monthly




Footage Drilled, Monthly



Total Wells Drilled by Type, 1973-2011



Total Wells Drilled by Type, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#crude>.  
Sources: Tables 5.1 and 5.2.

**Table 5.1 Crude Oil and Natural Gas Drilling Activity Measurements**  
(Number of Rigs)

	Rotary Rigs in Operation <sup>a</sup>					Active Well Service Rig Count <sup>c</sup>
	By Site		By Type		Total <sup>b</sup>	
	Onshore	Offshore	Crude Oil	Natural Gas		
<b>1973 Average</b> .....	1,110	84	NA	NA	1,194	2,008
<b>1975 Average</b> .....	1,554	106	NA	NA	1,660	2,486
<b>1980 Average</b> .....	2,678	231	NA	NA	2,909	4,089
<b>1985 Average</b> .....	1,774	206	NA	NA	1,980	4,716
<b>1990 Average</b> .....	902	108	532	464	1,010	3,658
<b>1995 Average</b> .....	622	101	323	385	723	3,041
<b>1996 Average</b> .....	671	108	306	464	779	3,445
<b>1997 Average</b> .....	821	122	376	564	943	3,499
<b>1998 Average</b> .....	703	123	264	560	827	3,014
<b>1999 Average</b> .....	519	106	128	496	625	2,232
<b>2000 Average</b> .....	778	140	197	720	918	2,692
<b>2001 Average</b> .....	1,003	153	217	939	1,156	2,267
<b>2002 Average</b> .....	717	113	137	691	830	1,830
<b>2003 Average</b> .....	924	108	157	872	1,032	1,967
<b>2004 Average</b> .....	1,095	97	165	1,025	1,192	2,064
<b>2005 Average</b> .....	1,287	94	194	1,184	1,381	2,222
<b>2006 Average</b> .....	1,559	90	274	1,372	1,649	2,364
<b>2007 Average</b> .....	1,695	72	297	1,466	1,768	2,388
<b>2008 Average</b> .....	1,814	65	379	1,491	1,879	2,515
<b>2009 Average</b> .....	1,046	44	278	801	1,089	1,722
<b>2010</b>						
January .....	1,225	42	433	822	1,267	1,706
February .....	1,305	45	446	892	1,350	1,726
March .....	1,368	51	471	933	1,419	1,754
April .....	1,426	53	508	959	1,479	1,816
May .....	1,464	49	541	960	1,513	1,818
June .....	1,511	20	566	953	1,531	1,857
July .....	1,558	15	591	971	1,573	1,852
August .....	1,619	20	644	983	1,638	1,900
September .....	1,635	19	668	977	1,655	1,918
October .....	1,647	21	693	966	1,668	1,965
November .....	1,662	22	723	950	1,683	1,971
December .....	1,687	24	759	940	1,711	1,968
<b>Average</b> .....	<b>1,514</b>	<b>31</b>	<b>591</b>	<b>943</b>	<b>1,546</b>	<b>1,854</b>
<b>2011</b>						
January .....	1,686	26	793	909	1,711	2,004
February .....	1,692	26	801	907	1,718	1,990
March .....	1,694	26	830	884	1,720	2,044
April .....	1,762	28	896	885	1,790	2,052
May .....	1,804	32	948	878	1,836	2,047
June .....	1,829	34	979	877	1,863	2,069
July .....	1,865	35	1,014	880	1,900	2,116
August .....	1,923	35	1,055	894	1,957	2,136
September .....	1,946	32	1,063	907	1,978	2,115
October .....	1,982	35	1,077	933	2,017	2,100
November .....	1,974	37	1,125	880	2,011	2,100
December .....	1,961	42	1,177	824	2,002	2,131
<b>Average</b> .....	<b>1,846</b>	<b>32</b>	<b>984</b>	<b>887</b>	<b>1,879</b>	<b>2,075</b>
<b>2012</b>						
January .....	1,961	42	1,208	790	2,003	2,154
February .....	1,949	42	1,261	723	1,990	2,135
March .....	1,935	43	1,307	667	1,979	2,143
April .....	1,917	44	1,329	629	1,961	2,157
May .....	1,931	46	1,373	600	1,977	2,153
June .....	1,923	49	1,409	558	1,972	2,139
July .....	1,894	51	1,419	522	1,944	2,140
<b>7-Month Average</b> .....	<b>1,930</b>	<b>45</b>	<b>1,331</b>	<b>639</b>	<b>1,975</b>	<b>2,146</b>
<b>2011 7-Month Average</b> .....	<b>1,765</b>	<b>30</b>	<b>899</b>	<b>888</b>	<b>1,795</b>	<b>2,046</b>
<b>2010 7-Month Average</b> .....	<b>1,414</b>	<b>39</b>	<b>511</b>	<b>930</b>	<b>1,453</b>	<b>1,790</b>

<sup>a</sup> Rotary rigs in operation are reported weekly. Monthly data are averages of 4- or 5-week reporting periods, not calendar months. Multi-month data are averages of the reported data over the covered months, not averages of the weekly data. Annual data are averages over 52 or 53 weeks, not calendar years. Published data are rounded to the nearest whole number.

<sup>b</sup> Sum of rigs drilling for crude oil, rigs drilling for natural gas, and other rigs (not shown) drilling for miscellaneous purposes, such as service wells, injection wells, and stratigraphic tests.

<sup>c</sup> The number of rigs doing true workovers (where tubing is pulled from the well), or doing rod string and pump repair operations, and that are, on average, crewed and working every day of the month.

NA=Not available.

Note: Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#crude> for all available data beginning in 1973.

Sources: • **Rotary Rigs in Operation:** Baker Hughes, Inc., Houston, TX, *Rotary Rigs Running—by State*, used with permission. See [http://investor.shareholder.com/bhi/rig\\_counts/rc\\_index.cfm](http://investor.shareholder.com/bhi/rig_counts/rc_index.cfm). • **Active Well Service Rig Count:** Cameron International Corporation, Houston, TX. See <http://www.c-a-m.com/Forms/Product.aspx?prodID=cdc209c4-79a3-47e5-99c2-fdeda6d4aad6>.

**Table 5.2 Crude Oil and Natural Gas Exploratory and Development Wells**

	Wells Drilled												Total Footage Drilled Thousand Feet
	Exploratory				Development				Total				
	Crude Oil	Natural Gas	Dry	Total	Crude Oil	Natural Gas	Dry	Total	Crude Oil	Natural Gas	Dry	Total	
Number													
1973 Total	642	1,067	5,952	7,661	9,525	5,866	4,368	19,759	10,167	6,933	10,320	27,420	138,223
1975 Total	982	1,248	7,129	9,359	15,966	6,879	6,517	29,362	16,948	8,127	13,646	38,721	180,494
1980 Total	1,777	2,099	9,081	12,957	31,182	15,362	11,704	58,248	32,959	17,461	20,785	71,205	316,943
1985 Total	1,680	1,200	8,954	11,834	33,581	13,124	12,257	58,962	35,261	14,324	21,211	70,796	314,409
1990 Total	778	811	3,652	5,241	12,061	10,435	4,593	27,089	12,839	11,246	8,245	32,330	156,044
1995 Total	570	558	2,024	3,152	7,678	7,524	2,790	17,992	8,248	8,082	4,814	21,144	117,156
1996 Total	489	576	1,956	3,021	8,347	8,451	2,934	19,732	8,836	9,027	4,890	22,753	126,365
1997 Total	491	562	2,113	3,166	10,715	10,936	3,761	25,412	11,206	11,498	5,874	28,578	161,249
1998 Total	327	566	1,590	2,483	7,355	11,073	3,171	21,599	7,682	11,639	4,761	24,082	137,202
1999 Total	197	570	1,157	1,924	4,608	11,457	2,393	18,458	4,805	12,027	3,550	20,382	102,861
2000 Total	288	657	1,341	2,286	7,802	16,394	2,805	27,001	8,090	17,051	4,146	29,287	144,425
2001 Total	357	1,052	1,733	3,142	8,531	21,020	2,865	32,416	8,888	22,072	4,598	35,558	180,141
2002 Total	258	844	1,282	2,384	6,517	16,498	2,472	25,487	6,775	17,342	3,754	27,871	145,159
2003 Total	350	997	1,297	2,644	7,779	19,725	2,685	30,189	8,129	20,722	3,982	32,833	177,239
2004 Total	383	1,671	1,350	3,404	8,406	22,515	2,732	33,653	8,789	24,186	4,082	37,057	204,279
2005 Total	539	2,141	1,462	4,142	10,240	26,449	3,191	39,880	10,779	28,590	4,653	44,022	240,307
2006 Total	646	2,456	1,547	4,649	12,739	30,382	3,659	46,780	13,385	32,838	5,206	51,429	282,675
2007 Total	R 808	R 2,794	R 1,582	R 5,184	R 12,563	R 29,925	R 3,399	R 45,887	R 13,371	R 32,719	R 4,981	R 51,071	R 301,515
2008 Total	R 897	R 2,345	R 1,715	R 4,957	R 15,736	R 29,901	R 3,708	R 49,345	R 16,633	R 32,246	R 5,423	R 54,302	R 334,141
2009 Total	R 605	R 1,206	R 1,055	R 2,866	R 10,585	R 16,882	R 2,470	R 29,937	R 11,190	R 18,088	R 3,525	R 32,803	R 231,562
<b>2010</b>													
January	55	R 91	R 81	R 227	R 898	R 1,264	169	R 2,331	R 953	R 1,355	R 250	R 2,558	R 15,304
February	R 44	R 71	R 67	R 182	R 871	R 1,096	R 144	R 2,111	R 915	R 1,167	R 211	R 2,293	R 16,862
March	59	R 85	R 88	R 232	R 1,062	R 1,224	R 216	R 2,502	R 1,121	R 1,309	R 304	R 2,734	R 15,102
April	49	R 78	R 77	R 204	R 1,173	R 1,152	R 249	R 2,574	R 1,222	R 1,230	R 326	R 2,778	R 17,904
May	R 48	R 107	R 86	R 241	R 1,282	R 1,208	R 255	R 2,745	R 1,330	R 1,315	R 341	R 2,986	R 17,987
June	61	R 100	R 90	R 251	R 1,385	R 1,250	R 302	R 2,937	R 1,446	R 1,350	R 392	R 3,188	R 19,408
July	46	R 103	R 105	R 254	R 1,386	1,443	R 390	R 3,219	R 1,432	R 1,546	R 495	R 3,473	R 20,847
August	56	R 104	R 94	R 254	R 1,434	R 1,402	R 314	R 3,150	R 1,490	R 1,506	R 408	R 3,404	R 22,923
September	R 57	R 73	R 88	R 218	R 1,374	R 1,358	R 268	R 3,000	R 1,431	R 1,431	R 356	R 3,218	R 23,037
October	R 75	87	R 117	R 279	R 1,502	R 1,463	R 283	R 3,248	R 1,577	R 1,550	R 400	R 3,527	R 22,123
November	R 62	R 114	R 103	R 279	R 1,400	R 1,352	R 263	R 3,015	R 1,462	R 1,466	R 366	R 3,294	R 24,561
December	57	R 92	70	R 219	R 1,317	R 1,379	R 243	R 2,939	R 1,374	R 1,471	R 313	R 3,158	R 23,189
<b>Total</b>	<b>R 669</b>	<b>R 1,105</b>	<b>R 1,066</b>	<b>R 2,840</b>	<b>R 15,084</b>	<b>R 15,591</b>	<b>R 3,096</b>	<b>R 33,771</b>	<b>R 15,753</b>	<b>R 16,696</b>	<b>R 4,162</b>	<b>R 36,611</b>	<b>R 239,247</b>
<b>2011</b>													
January	66	R 73	R 79	R 218	R 1,408	R 1,126	235	R 2,769	R 1,474	R 1,199	R 314	R 2,987	R 21,306
February	R 59	57	R 56	R 172	R 1,261	R 1,025	R 183	R 2,469	R 1,320	R 1,082	R 239	R 2,641	R 19,243
March	R 63	R 75	R 63	R 201	R 1,481	R 1,145	R 251	R 2,877	R 1,544	R 1,220	R 314	R 3,078	R 22,524
April	68	68	62	198	R 1,470	R 1,108	248	R 2,826	R 1,538	R 1,176	310	R 3,024	R 22,474
May	R 80	83	R 79	R 242	R 1,596	R 1,046	R 287	R 2,929	R 1,676	R 1,129	R 366	R 3,171	R 23,619
June	80	90	73	243	R 1,698	R 1,120	R 281	R 3,099	R 1,778	R 1,210	R 354	R 3,342	R 25,148
July	R 85	70	R 101	R 256	R 1,662	R 1,001	277	R 2,940	R 1,747	R 1,071	R 378	R 3,196	R 24,175
August	72	R 69	R 73	R 214	R 1,742	R 1,084	R 300	R 3,126	R 1,814	R 1,153	R 373	R 3,340	R 25,810
September	82	R 53	R 73	R 208	R 1,561	R 1,094	270	R 2,925	R 1,643	R 1,147	R 343	R 3,133	R 24,689
October	R 72	R 52	R 97	R 221	R 1,548	R 957	R 282	R 2,787	R 1,620	R 1,009	R 379	R 3,008	R 23,857
November	R 85	R 54	R 99	R 238	R 1,627	R 941	R 296	R 2,864	R 1,712	R 995	R 395	R 3,102	R 24,867
December	R 71	R 41	R 86	R 198	R 1,531	R 788	R 230	R 2,549	R 1,602	R 829	R 316	R 2,747	R 22,253
<b>Total</b>	<b>R 883</b>	<b>R 785</b>	<b>R 941</b>	<b>R 2,609</b>	<b>R 18,585</b>	<b>R 12,435</b>	<b>R 3,140</b>	<b>R 34,160</b>	<b>R 19,468</b>	<b>R 13,220</b>	<b>R 4,081</b>	<b>R 36,769</b>	<b>R 279,965</b>
<b>2012</b>													
January	R 82	R 40	R 82	R 204	R 1,567	R 809	R 260	R 2,636	R 1,649	R 849	R 342	R 2,840	R 23,257
February	R 89	R 15	R 93	R 197	R 1,731	R 687	R 280	R 2,698	R 1,820	R 702	R 373	R 2,895	R 23,590
March	R 92	R 7	R 91	R 190	R 1,867	R 561	339	R 2,767	R 1,959	R 568	R 430	R 2,957	R 23,592
April	R 93	R 7	R 95	R 195	R 1,875	R 504	340	R 2,719	R 1,968	R 511	R 435	R 2,914	R 23,444
May	112	0	97	209	2,219	433	341	2,993	2,331	433	438	3,202	24,304
June	113	0	100	213	2,220	396	342	2,958	2,333	396	442	3,171	24,592
<b>6-Month Total</b>	<b>581</b>	<b>69</b>	<b>558</b>	<b>1,208</b>	<b>11,479</b>	<b>3,390</b>	<b>1,902</b>	<b>16,771</b>	<b>12,060</b>	<b>3,459</b>	<b>2,460</b>	<b>17,979</b>	<b>142,778</b>
<b>2011 6-Month Total</b>	<b>416</b>	<b>446</b>	<b>412</b>	<b>1,274</b>	<b>8,914</b>	<b>6,570</b>	<b>1,485</b>	<b>16,969</b>	<b>9,330</b>	<b>7,016</b>	<b>1,897</b>	<b>18,243</b>	<b>134,314</b>
<b>2010 6-Month Total</b>	<b>316</b>	<b>532</b>	<b>489</b>	<b>1,337</b>	<b>6,671</b>	<b>7,194</b>	<b>1,335</b>	<b>15,200</b>	<b>6,987</b>	<b>7,726</b>	<b>1,824</b>	<b>16,537</b>	<b>102,567</b>

R=Revised.

Notes: • Data are estimates. • Prior to 1990, these well counts include only the original drilling of a hole intended to discover or further develop already discovered crude oil or natural gas resources. Other drilling activities, such as drilling an old well deeper, drilling of laterals from the original well, drilling of service and injection wells, and drilling for resources other than crude oil or natural gas are excluded. After 1990, a new well is defined as the first hole in the ground whether it is lateral or not. Due to the methodology used to estimate ultimate well counts from the available partially reported data, the counts shown on this page are frequently

revised. See Note, "Crude Oil and Natural Gas Exploratory and Development Wells," at end of section. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#crude> for all available data beginning in 1973.

Sources: • **1973-1989:** U.S. Energy Information Administration (EIA) computations based on well reports submitted to the American Petroleum Institute. • **1990 forward:** EIA computations based on well reports submitted to IHS, Inc., Denver, CO.



## Crude Oil and Natural Gas Resource Development

**Note. Crude Oil and Natural Gas Exploratory and Development Wells.** Three well types are considered in the *Monthly Energy Review (MER)* drilling statistics: “completed for crude oil,” “completed for natural gas,” and “dry hole.” Wells that productively encounter both crude oil and natural gas are categorized as “completed for crude oil.” Both development wells and exploratory wells (new field wildcats, new pool tests, and extension tests) are included in the statistics. All other classes of wells drilled in connection with the search for producible hydrocarbons are excluded. If a lateral is drilled at the same time as the original hole it is not counted separately, but its footage is included.

Prior to the March 1985 MER, drilling statistics consisted of

completion data for the above types and classes of wells as reported to the American Petroleum Institute (API) during a given month. Due to time lags between the date of well completion and the date of completion reporting to the API, as-reported well completions proved to be an inaccurate indicator of drilling activity. During 1982, for example, as-reported well completions rose, while the number of actual completions fell. Consequently, the drilling statistics published since the March 1985 MER are U.S. Energy Information Administration (EIA) estimates produced by statistically imputing well counts and footage based on the partial data available from the API. These estimates are subject to continuous revision as new data, some of which pertain to earlier months and years, become available. Additional information about the EIA estimation methodology may be found in “Estimating Well Completions,” a feature article published in the March 1985 MER.


THIS PAGE INTENTIONALLY LEFT BLANK

## **6. Coal**


---

**Figure 6.1 Coal**  
(Million Short Tons)


Overview, 1973-2011




Overview, Monthly




Consumption by Sector, 1973-2011




Electric Power Sector Consumption, Monthly



Stocks, End of Year, 1973-2011



Electric Power Sector Stocks, End of Month



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#coal>.  
Sources: Tables 6.1-6.3.

**Table 6.1 Coal Overview**  
(Thousand Short Tons)

	Production <sup>a</sup>	Waste Coal Supplied <sup>b</sup>	Trade			Stock Change <sup>d,e</sup>	Losses and Unaccounted for <sup>f</sup>	Consumption
			Imports	Exports	Net Imports <sup>c</sup>			
<b>1973 Total</b> .....	<b>598,568</b>	<b>NA</b>	<b>127</b>	<b>53,587</b>	<b>-53,460</b>	<b>402</b>	<b>-17,878</b>	<b>562,584</b>
<b>1975 Total</b> .....	<b>654,641</b>	<b>NA</b>	<b>940</b>	<b>66,309</b>	<b>-65,369</b>	<b>32,154</b>	<b>-5,522</b>	<b>562,640</b>
<b>1980 Total</b> .....	<b>829,700</b>	<b>NA</b>	<b>1,194</b>	<b>91,742</b>	<b>-90,548</b>	<b>25,595</b>	<b>10,827</b>	<b>702,730</b>
<b>1985 Total</b> .....	<b>883,638</b>	<b>NA</b>	<b>1,952</b>	<b>92,680</b>	<b>-90,727</b>	<b>-27,934</b>	<b>2,796</b>	<b>818,049</b>
<b>1990 Total</b> .....	<b>1,029,076</b>	<b>3,339</b>	<b>2,699</b>	<b>105,804</b>	<b>-103,104</b>	<b>26,542</b>	<b>-1,730</b>	<b>904,498</b>
<b>1995 Total</b> .....	<b>1,032,974</b>	<b>8,561</b>	<b>9,473</b>	<b>88,547</b>	<b>-79,074</b>	<b>-275</b>	<b>632</b>	<b>962,104</b>
<b>1996 Total</b> .....	<b>1,063,856</b>	<b>8,778</b>	<b>8,115</b>	<b>90,473</b>	<b>-82,357</b>	<b>-17,456</b>	<b>1,411</b>	<b>1,006,321</b>
<b>1997 Total</b> .....	<b>1,089,932</b>	<b>8,096</b>	<b>7,487</b>	<b>83,545</b>	<b>-76,058</b>	<b>-11,253</b>	<b>3,678</b>	<b>1,029,544</b>
<b>1998 Total</b> .....	<b>1,117,535</b>	<b>8,690</b>	<b>8,724</b>	<b>78,048</b>	<b>-69,324</b>	<b>24,228</b>	<b>-4,430</b>	<b>1,037,103</b>
<b>1999 Total</b> .....	<b>1,100,431</b>	<b>8,683</b>	<b>9,089</b>	<b>58,476</b>	<b>-49,387</b>	<b>23,988</b>	<b>-2,906</b>	<b>1,038,647</b>
<b>2000 Total</b> .....	<b>1,073,612</b>	<b>9,089</b>	<b>12,513</b>	<b>58,489</b>	<b>-45,976</b>	<b>-48,309</b>	<b>938</b>	<b>1,084,095</b>
<b>2001 Total</b> .....	<b>1,127,689</b>	<b>10,085</b>	<b>19,787</b>	<b>48,666</b>	<b>-28,879</b>	<b>41,630</b>	<b>7,120</b>	<b>1,060,146</b>
<b>2002 Total</b> .....	<b>1,094,283</b>	<b>9,052</b>	<b>16,875</b>	<b>39,601</b>	<b>-22,726</b>	<b>10,215</b>	<b>4,040</b>	<b>1,066,355</b>
<b>2003 Total</b> .....	<b>1,071,753</b>	<b>10,016</b>	<b>25,044</b>	<b>43,014</b>	<b>-17,970</b>	<b>-26,659</b>	<b>-4,403</b>	<b>1,094,861</b>
<b>2004 Total</b> .....	<b>1,112,099</b>	<b>11,299</b>	<b>27,280</b>	<b>47,998</b>	<b>-20,718</b>	<b>-11,462</b>	<b>6,887</b>	<b>1,107,255</b>
<b>2005 Total</b> .....	<b>1,131,498</b>	<b>13,352</b>	<b>30,460</b>	<b>49,942</b>	<b>-19,482</b>	<b>-9,702</b>	<b>9,092</b>	<b>1,125,978</b>
<b>2006 Total</b> .....	<b>1,162,750</b>	<b>14,409</b>	<b>36,246</b>	<b>49,647</b>	<b>-13,401</b>	<b>42,642</b>	<b>8,824</b>	<b>1,112,292</b>
<b>2007 Total</b> .....	<b>1,146,635</b>	<b>14,076</b>	<b>36,347</b>	<b>59,163</b>	<b>-22,816</b>	<b>5,812</b>	<b>4,085</b>	<b>1,127,998</b>
<b>2008 Total</b> .....	<b>1,171,809</b>	<b>14,146</b>	<b>34,208</b>	<b>81,519</b>	<b>-47,311</b>	<b>12,354</b>	<b>5,740</b>	<b>1,120,548</b>
<b>2009 Total</b> .....	<b>1,074,923</b>	<b>13,666</b>	<b>22,639</b>	<b>59,097</b>	<b>-36,458</b>	<b>39,668</b>	<b>14,985</b>	<b>997,478</b>
<b>2010 January</b> .....	<b>85,711</b>	<b>1,187</b>	<b>1,665</b>	<b>5,866</b>	<b>-4,202</b>	<b>-10,695</b>	<b>-3,103</b>	<b>96,494</b>
February .....	83,087	908	1,239	5,386	-4,146	-7,306	1,154	86,001
March .....	96,904	1,192	1,899	6,554	-4,655	8,127	2,870	82,444
April .....	90,960	1,071	1,812	7,358	-5,545	11,519	2,176	72,790
May .....	85,401	1,138	1,475	7,220	-5,745	2,723	-3,500	81,570
June .....	88,621	1,219	1,771	7,387	-5,616	-9,407	647	92,983
July .....	90,795	1,273	1,390	6,928	-5,539	-15,499	1,446	100,582
August .....	93,350	1,261	1,702	7,001	-5,299	-8,766	-2,316	100,393
September .....	93,360	1,102	1,588	7,145	-5,556	5,111	-1,591	85,386
October .....	91,831	982	1,775	6,623	-4,849	11,463	-90	76,591
November .....	91,558	1,121	1,473	7,015	-5,542	8,878	-437	78,697
December .....	92,791	1,197	1,563	7,232	-5,669	-9,187	2,925	94,582
<b>Total</b> .....	<b>1,084,368</b>	<b>13,651</b>	<b>19,353</b>	<b>81,716</b>	<b>-62,363</b>	<b>-13,039</b>	<b>182</b>	<b>1,048,514</b>
<b>2011 January</b> .....	<b>91,398</b>	<b>1,187</b>	<b>1,014</b>	<b>8,509</b>	<b>-7,496</b>	<b>-11,828</b>	<b>949</b>	<b>95,968</b>
February .....	85,618	1,030	843	8,275	-7,432	-6,172	6,122	79,266
March .....	96,608	1,068	1,524	9,832	-8,308	3,658	7,382	78,327
April .....	88,335	910	1,136	8,843	-7,706	8,617	606	72,316
May .....	86,652	852	1,313	9,042	-7,730	1,917	-1,017	78,874
June .....	88,647	1,109	970	9,102	-8,132	-10,182	2,366	89,440
July .....	85,375	1,173	1,208	7,865	-6,657	-16,060	-3,366	99,317
August .....	95,362	1,142	1,545	9,387	-7,843	-11,060	2,297	97,425
September .....	93,889	1,087	835	8,723	-7,888	4,740	431	81,916
October .....	94,513	999	917	9,159	-8,242	13,286	-939	74,923
November .....	93,973	1,039	807	8,808	-8,001	10,170	4,486	72,355
December .....	93,965	934	976	9,713	-8,737	5,858	1,330	78,975
<b>Total</b> .....	<b>1,094,336</b>	<b>12,529</b>	<b>13,088</b>	<b>107,259</b>	<b>-94,171</b>	<b>-7,056</b>	<b>20,647</b>	<b>999,103</b>
<b>2012 January</b> .....	<b>94,944</b>	<b>1,068</b>	<b>789</b>	<b>9,126</b>	<b>-8,337</b>	<b>2,707</b>	<b>9,096</b>	<b>75,871</b>
February .....	85,763	891	534	8,460	-7,927	6,527	4,140	68,060
March .....	85,698	837	699	11,055	-10,356	10,595	2,613	62,971
April .....	76,449	<sup>F</sup> 1,069	623	12,529	-11,905	7,490	827	57,296
May .....	80,542	<sup>RF</sup> 1,069	986	12,257	-11,271	<sup>R</sup> 782	<sup>R</sup> 2,627	<sup>R</sup> 68,495
June .....	80,513	NA	<sup>R</sup> 719	<sup>R</sup> 12,749	<sup>R</sup> -12,030	NA	NA	NA
July .....	86,244	NA	NA	NA	NA	NA	NA	NA
<b>7-Month Total</b> .....	<b>590,152</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>	<b>NA</b>
<b>2011 7-Month Total</b> .....	<b>622,634</b>	<b>7,329</b>	<b>8,008</b>	<b>61,469</b>	<b>-53,461</b>	<b>-30,050</b>	<b>13,042</b>	<b>593,509</b>
<b>2010 7-Month Total</b> .....	<b>621,479</b>	<b>7,988</b>	<b>11,251</b>	<b>46,700</b>	<b>-35,449</b>	<b>-20,538</b>	<b>1,691</b>	<b>612,865</b>

<sup>a</sup> Beginning in 2001, includes a small amount of refuse recovery (coal recaptured from a refuse mine and cleaned to reduce the concentration of noncombustible materials).

<sup>b</sup> Waste coal (including fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste) consumed by the electric power and industrial sectors. Beginning in 1989, waste coal supplied is counted as a supply-side item to balance the same amount of waste coal included in "Consumption."

<sup>c</sup> Net imports equal imports minus exports. A minus sign indicates exports are greater than imports.

<sup>d</sup> For 1980-2007, excludes coal stocks in the residential and commercial sectors.

<sup>e</sup> A negative value indicates a decrease in stocks; a positive value indicates an increase.

<sup>f</sup> The difference between calculated coal supply and disposition, due to coal quantities lost or to data reporting problems.

R=Revised. NA=Not available. F=Forecast.

Notes: • For methodology used to calculate production, consumption, and stocks, see Note 1, "Coal Production," Note 2, "Coal Consumption," and Note 3, "Coal Stocks," at end of section. • Data include refined coal. • Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> for all available data beginning in 1973.

Sources: See end of section.

**Table 6.2 Coal Consumption by Sector**  
(Thousand Short Tons)

	End-Use Sectors										Electric Power Sector <sup>e,f</sup>	Total
	Residential	Commercial			Coke Plants	Industrial			Total	Transportation		
		CHP <sup>a</sup>	Other <sup>b</sup>	Total		Other Industrial						
						CHP <sup>c</sup>	Non-CHP <sup>d</sup>	Total				
<b>1973 Total</b> .....	4,113	(g)	7,004	7,004	94,101	(h)	68,038	68,038	162,139	116	389,212	562,584
<b>1975 Total</b> .....	2,823	(g)	6,587	6,587	83,598	(h)	63,646	63,646	147,244	24	405,962	562,640
<b>1980 Total</b> .....	1,355	(g)	5,097	5,097	66,657	(h)	60,347	60,347	127,004	(h)	569,274	702,730
<b>1985 Total</b> .....	1,711	(g)	6,068	6,068	41,056	(h)	75,372	75,372	116,429	(h)	693,841	818,049
<b>1990 Total</b> .....	1,345	1,191	4,189	5,379	38,877	27,781	48,549	76,330	115,207	(h)	782,567	904,498
<b>1995 Total</b> .....	755	1,419	3,633	5,052	33,011	29,363	43,693	73,055	106,067	(h)	850,230	962,104
<b>1996 Total</b> .....	721	1,660	3,625	5,285	31,706	29,434	42,254	71,689	103,395	(h)	896,921	1,006,321
<b>1997 Total</b> .....	711	1,738	4,015	5,752	30,203	29,853	41,661	71,515	101,718	(h)	921,364	1,029,544
<b>1998 Total</b> .....	534	1,443	2,879	4,322	28,189	28,553	38,887	67,439	95,628	(h)	936,619	1,037,103
<b>1999 Total</b> .....	585	1,490	2,803	4,293	28,108	27,763	36,975	64,738	92,846	(h)	940,922	1,038,647
<b>2000 Total</b> .....	454	1,547	2,126	3,673	28,939	28,031	37,177	65,208	94,147	(h)	985,821	1,084,095
<b>2001 Total</b> .....	481	1,448	2,441	3,888	26,075	25,755	39,514	65,268	91,344	(h)	964,433	1,060,146
<b>2002 Total</b> .....	533	1,405	2,506	3,912	23,656	26,232	34,515	60,747	84,403	(h)	977,507	1,066,355
<b>2003 Total</b> .....	551	1,816	1,869	3,685	24,248	24,846	36,415	61,261	85,509	(h)	1,005,116	1,094,861
<b>2004 Total</b> .....	512	1,917	2,693	4,610	23,670	26,613	35,582	62,195	85,865	(h)	1,016,268	1,107,255
<b>2005 Total</b> .....	378	1,922	2,420	4,342	23,434	25,875	34,465	60,340	83,774	(h)	1,037,485	1,125,978
<b>2006 Total</b> .....	290	1,886	1,050	2,936	22,957	25,262	34,210	59,472	82,429	(h)	1,026,636	1,112,292
<b>2007 Total</b> .....	353	1,927	1,247	3,173	22,715	22,537	34,078	56,615	79,331	(h)	1,045,141	1,127,998
<b>2008 Total</b> .....	351	2,021	1,134	3,155	22,070	21,902	32,491	54,393	76,463	(h)	1,040,580	1,120,548
<b>2009 Total</b> .....	353	1,798	1,059	2,857	15,326	19,766	25,549	45,314	60,641	(h)	933,627	997,478
<b>2010</b>												
January .....	43	193	156	349	1,472	2,094	2,084	4,178	5,650	(h)	90,452	96,494
February .....	37	167	136	303	1,584	1,978	2,215	4,193	5,777	(h)	79,884	86,001
March .....	33	149	121	271	1,801	2,124	2,106	4,230	6,030	(h)	76,110	82,444
April .....	21	117	54	171	1,786	2,220	1,749	3,969	5,755	(h)	66,842	72,790
May .....	21	118	55	173	1,794	2,010	1,975	3,985	5,779	(h)	75,597	81,570
June .....	24	135	62	197	1,772	1,898	2,061	3,959	5,732	(h)	87,030	92,983
July .....	24	142	48	190	1,783	2,122	1,944	4,066	5,849	(h)	94,519	100,582
August .....	25	152	52	203	1,814	2,194	1,909	4,103	5,917	(h)	94,247	100,393
September .....	22	133	45	178	1,894	1,941	2,174	4,115	6,010	(h)	79,176	85,386
October .....	26	121	86	207	1,731	1,958	2,178	4,136	5,866	(h)	70,492	76,591
November .....	27	128	90	218	1,787	1,854	2,297	4,151	5,938	(h)	72,514	78,697
December .....	35	165	116	281	1,874	2,246	1,957	4,203	6,077	(h)	88,189	94,582
<b>Total</b> .....	<b>339</b>	<b>1,720</b>	<b>1,022</b>	<b>2,742</b>	<b>21,092</b>	<b>24,638</b>	<b>24,650</b>	<b>49,289</b>	<b>70,381</b>	<b>(h)</b>	<b>975,052</b>	<b>1,048,514</b>
<b>2011</b>												
January .....	40	178	144	322	1,746	2,320	1,859	4,178	5,924	(h)	89,682	95,968
February .....	37	165	133	298	1,623	2,044	2,108	4,152	5,775	(h)	73,156	79,266
March .....	35	158	127	285	1,819	2,088	2,091	4,179	5,998	(h)	72,009	78,327
April .....	23	124	63	187	1,668	1,767	1,930	3,697	5,365	(h)	66,741	72,316
May .....	24	128	65	193	1,878	2,126	1,554	3,680	5,558	(h)	73,100	78,874
June .....	23	124	63	187	1,846	2,056	1,628	3,684	5,530	(h)	83,700	89,440
July .....	20	134	30	165	1,670	2,208	1,518	3,726	5,396	(h)	93,736	99,317
August .....	19	124	28	152	1,863	2,182	1,541	3,724	5,587	(h)	91,667	97,425
September .....	18	121	27	149	1,874	2,100	1,644	3,743	5,618	(h)	76,131	81,916
October .....	20	116	48	164	1,784	2,080	1,765	3,845	5,629	(h)	69,109	74,923
November .....	22	123	51	174	1,772	1,835	1,995	3,831	5,603	(h)	66,557	72,355
December .....	24	138	57	195	1,891	1,927	1,967	3,894	5,784	(h)	72,971	78,975
<b>Total</b> .....	<b>305</b>	<b>1,633</b>	<b>838</b>	<b>2,471</b>	<b>21,434</b>	<b>24,733</b>	<b>21,601</b>	<b>46,334</b>	<b>67,768</b>	<b>(h)</b>	<b>928,558</b>	<b>999,103</b>
<b>2012</b>												
January .....	27	154	68	222	1,701	2,102	1,587	3,690	5,390	(h)	70,231	75,871
February .....	24	137	60	197	1,687	1,890	1,811	3,701	5,388	(h)	62,450	68,060
March .....	23	131	57	188	1,895	1,921	1,732	3,653	5,548	(h)	57,211	62,971
April .....	F 26	F 111	F 98	F 209	F 2,051	F 1,589	F 2,064	F 3,653	F 5,704	(h)	51,357	57,296
May .....	F 20	F 117	F 44	F 160	F 2,011	F 1,680	F 1,796	F 3,477	F 5,488	(h)	62,827	68,495
<b>5-Month Total</b> .....	<b>E 121</b>	<b>650</b>	<b>E 327</b>	<b>E 977</b>	<b>E 9,345</b>	<b>9,183</b>	<b>E 8,990</b>	<b>E 18,173</b>	<b>E 27,519</b>	<b>(h)</b>	<b>304,076</b>	<b>332,692</b>
<b>2011 5-Month Total</b> .....	<b>159</b>	<b>752</b>	<b>533</b>	<b>1,285</b>	<b>8,734</b>	<b>10,344</b>	<b>9,543</b>	<b>19,887</b>	<b>28,621</b>	<b>(h)</b>	<b>374,687</b>	<b>404,752</b>
<b>2010 5-Month Total</b> .....	<b>157</b>	<b>745</b>	<b>522</b>	<b>1,267</b>	<b>8,437</b>	<b>10,426</b>	<b>10,129</b>	<b>20,555</b>	<b>28,992</b>	<b>(h)</b>	<b>388,884</b>	<b>419,300</b>

<sup>a</sup> Commercial combined-heat-and-power (CHP) and a small number of commercial electricity-only plants, such as those at hospitals and universities. See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> All commercial sector fuel use other than that in "Commercial CHP."

<sup>c</sup> Industrial combined-heat-and-power (CHP) and a small number of industrial electricity-only plants. See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>d</sup> All industrial sector fuel use other than that in "Coke Plants" and "Industrial CHP."

<sup>e</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>f</sup> Through 1988, data are for consumption at electric utilities only. Beginning in 1989, data also include consumption at independent power producers.

<sup>g</sup> Included in "Commercial Other."

<sup>h</sup> Included in "Industrial Non-CHP."

R=Revised. E=Estimate. F=Forecast.

Notes: • CHP monthly values are from Table 7.4c; electric power sector monthly values are from Table 7.4b; all other monthly values are estimates derived from collected quarterly and annual data. See Note 2, "Coal Consumption," at end of section. • Data include refined coal. • Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> for all available data beginning in 1973.

Sources: See end of section.

**Table 6.3 Coal Stocks by Sector**  
(Thousand Short Tons)

	Producers and Distributors	End-Use Sectors					Electric Power Sector <sup>b,c</sup>	Total
		Residential and Commercial	Industrial			Total		
			Coke Plants	Other <sup>a</sup>	Total			
1973 Year .....	12,530	290	6,998	10,370	17,368	17,658	86,967	117,155
1975 Year .....	12,108	233	8,797	8,529	17,326	17,559	110,724	140,391
1980 Year .....	24,379	NA	9,067	11,951	21,018	21,018	183,010	228,407
1985 Year .....	33,133	NA	3,420	10,438	13,857	13,857	156,376	203,367
1990 Year .....	33,418	NA	3,329	8,716	12,044	12,044	156,166	201,629
1995 Year .....	34,444	NA	2,632	5,702	8,334	8,334	126,304	169,083
1996 Year .....	28,648	NA	2,667	5,688	8,355	8,355	114,623	151,627
1997 Year .....	33,973	NA	1,978	5,597	7,576	7,576	98,826	140,374
1998 Year .....	36,530	NA	2,026	5,545	7,571	7,571	120,501	164,602
1999 Year .....	39,475	NA	1,943	5,569	7,511	7,511	<sup>c</sup> 141,604	188,590
2000 Year .....	31,905	NA	1,494	4,587	6,081	6,081	102,296	140,282
2001 Year .....	35,900	NA	1,510	6,006	7,516	7,516	138,496	181,912
2002 Year .....	43,257	NA	1,364	5,792	7,156	7,156	141,714	192,127
2003 Year .....	38,277	NA	905	4,718	5,623	5,623	121,567	165,468
2004 Year .....	41,151	NA	1,344	4,842	6,186	6,186	106,669	154,006
2005 Year .....	34,971	NA	2,615	5,582	8,196	8,196	101,137	144,304
2006 Year .....	36,548	NA	2,928	6,506	9,434	9,434	140,964	186,946
2007 Year .....	33,977	NA	1,936	5,624	7,560	7,560	151,221	192,758
2008 Year .....	34,688	498	2,331	6,007	8,338	8,338	161,589	205,112
2009 Year .....	47,718	529	1,957	5,109	7,066	7,595	189,467	244,780
<b>2010</b> January .....	48,854	510	1,832	4,798	6,630	7,140	178,091	234,085
February .....	49,069	490	1,708	4,486	6,194	6,684	171,026	226,779
March .....	50,936	471	1,583	4,175	5,758	6,229	177,742	234,906
April .....	50,761	482	1,715	4,207	5,922	6,404	189,260	246,425
May .....	50,900	494	1,846	4,239	6,086	6,579	191,669	249,148
June .....	51,497	505	1,978	4,272	6,250	6,755	181,490	239,741
July .....	47,935	509	1,948	4,345	6,294	6,803	169,504	224,242
August .....	48,638	513	1,918	4,419	6,337	6,851	159,987	215,476
September .....	49,913	517	1,889	4,492	6,381	6,899	163,776	220,587
October .....	49,430	529	1,901	4,503	6,404	6,933	175,686	232,050
November .....	50,571	541	1,913	4,514	6,428	6,968	183,389	240,928
December .....	<b>49,820</b>	<b>552</b>	<b>1,925</b>	<b>4,525</b>	<b>6,451</b>	<b>7,003</b>	<b>174,917</b>	<b>231,740</b>
<b>2011</b> January .....	48,295	536	1,937	4,305	6,241	6,777	164,840	219,913
February .....	45,750	520	1,948	4,084	6,032	6,552	161,439	213,741
March .....	44,336	503	1,959	3,864	5,823	6,326	166,737	217,399
April .....	45,585	500	1,958	3,975	5,933	6,433	173,999	226,016
May .....	46,775	497	1,957	4,086	6,042	6,539	174,619	227,933
June .....	45,398	494	1,956	4,196	6,152	6,646	165,707	217,751
July .....	46,926	498	2,082	4,217	6,300	6,798	147,967	201,691
August .....	44,445	502	2,221	4,238	6,459	6,961	139,225	190,631
September .....	43,763	506	2,405	4,259	6,664	7,170	144,438	195,371
October .....	44,415	533	2,473	4,330	6,803	7,336	156,906	208,657
November .....	42,971	560	2,541	4,400	6,941	7,502	168,354	218,827
December .....	<b>41,917</b>	<b>588</b>	<b>2,610</b>	<b>4,471</b>	<b>7,080</b>	<b>7,668</b>	<b>175,100</b>	<b>224,684</b>
<b>2012</b> January .....	<sup>F</sup> 38,444	571	2,507	4,249	6,756	7,327	181,621	227,392
February .....	<sup>F</sup> 39,975	554	2,403	4,028	6,432	6,986	186,958	233,919
March .....	<sup>F</sup> 41,478	537	2,300	3,807	6,108	6,645	196,391	244,514
April .....	<sup>F</sup> 41,726	<sup>F</sup> 537	<sup>F</sup> 2,429	<sup>F</sup> 3,917	<sup>F</sup> 6,346	<sup>F</sup> 6,884	203,394	252,004
May .....	<sup>F</sup> 41,274	<sup>F</sup> 537	<sup>F</sup> 2,557	<sup>F</sup> 4,038	<sup>F</sup> 6,595	<sup>F</sup> 7,132	202,816	251,222

<sup>a</sup> Through 1977, data are for stocks held by the manufacturing and transportation sectors. Beginning in 1978, data are for stocks held at manufacturing plants only.

<sup>b</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

<sup>c</sup> Through 1998, data are for stocks at electric utilities only. Beginning in 1999, data also include stocks at independent power producers.

NA=Not available. F=Forecast.

Notes: • Stocks are at end of period. • Electric power sector monthly values

are from Table 7.5; producers and distributors monthly values are estimates derived from collected annual data; all other monthly values are estimates derived from collected quarterly values. • Data include refined coal. • Data values preceded by "F" are derived from the U.S. Energy Information Administration's Short-Term Integrated Forecasting System. See Note 4, "Coal Forecast Values," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#coal> for all available data beginning in 1973.

Sources: See end of section.

## Coal

**Note 1. Coal Production.** Preliminary monthly estimates of national coal production are the sum of weekly estimates developed by the U.S. Energy Information Administration (EIA) and published in the *Weekly Coal Production* report. When a week extends into a new month, production is allocated on a daily basis and added to the appropriate month. Weekly estimates are based on Association of American Railroads (AAR) data showing the number of railcars loaded with coal during the week by Class I and certain other railroads.

Prior to 2002, the weekly coal production model converted AAR data into short tons of coal by using the average number of short tons of coal per railcar loaded reported in the “Quarterly Freight Commodity Statistics” from the Surface Transportation Board. If an average coal tonnage per railcar loaded was not available for a specific railroad, the national average was used. To derive the estimate of total weekly production, the total rail tonnage for the week was divided by the ratio of quarterly production shipped by rail and total quarterly production. Data for the corresponding quarter of previous years were used to derive this ratio. This method ensured that the seasonal variations were preserved in the production estimates.

Beginning in 2002, the weekly coal production model uses statistical autoregressive methods to estimate national coal production as a function of railcar loadings of coal, and heating degree-days and cooling degree-days. On Thursday of each week, EIA receives from the AAR data for the previous week. The latest weekly national data for heating degree-days and cooling degree-days are obtained from the National Oceanic and Atmospheric Administration’s Climate Prediction Center. The weekly coal model is run and a national level coal production estimate is obtained. The weekly coal model is refit every quarter after preliminary coal data are available.

When preliminary quarterly data become available, the monthly and weekly estimates are adjusted to conform to the quarterly figures. The adjustment procedure uses State-level production data and is explained in EIA’s *Quarterly Coal Report*. Initial estimates of annual production published in January of the following year are based on preliminary production data covering the first nine months (three quarters) and weekly/monthly estimates for the fourth quarter. The fourth quarter estimates may or may not be revised when preliminary data become available in March of the following year, depending on the magnitude of the difference between the estimates and the preliminary data. In any event, all quarterly, monthly, and weekly production figures are adjusted to conform to the final annual production data published in the *Monthly Energy Review* in the fall of the following year.

**Note 2. Coal Consumption.** Coal consumption data are reported by major end-use sector. Forecast data (designated

by an “F”) are derived from forecasted values shown in the EIA *Short-Term Energy Outlook* (DOE/EIA-0202) table titled “U.S. Coal Supply and Demand: Base Case.” The monthly estimates are based on the quarterly values, which are released in March, June, September, and December. The estimates are revised quarterly as collected data become available from the data sources. Sector-specific information follows.

**Residential and Commercial—**Coal consumption by the residential and commercial sectors is reported to EIA for the two sectors combined; EIA estimates the amount consumed by the sectors individually. To create the estimates, it is first assumed that an occupied coal-heated housing unit consumes fuel at the same Btu rate as an oil-heated housing unit. Then, for the years in which data are available on the number of occupied housing units by heating source (1973–1981 and subsequent odd-numbered years), residential consumption of coal is estimated by the following steps: a ratio is created of the number of occupied housing units heated by coal to the number of occupied housing units heated by oil; that ratio is then multiplied by the Btu quantity of oil consumed by the residential sector to derive an estimate of the Btu quantity of coal consumed by the residential sector; and, finally, the amount estimated as the residential sector consumption is subtracted from the residential and commercial sectors’ combined consumption to derive the commercial sector’s estimated consumption. The 2007 share is applied to 2008 forward, and the other missing years’ shares are interpolated.

**Industrial Coke Plants—**Prior to 1980, monthly coke plant consumption data were taken directly from reported data. For 1980–1987, coke plant consumption estimates were derived by proportioning reported quarterly data by using the ratios of monthly-to-quarterly consumption data in 1979, the last year in which monthly data were reported. Beginning in January 1988, monthly coke plant consumption estimates are derived from the reported quarterly data by using monthly ratios of raw steel production data from the American Iron and Steel Institute. The ratios are the monthly raw steel production from open hearth and basic oxygen process furnaces as a proportion of the quarterly production from those kinds of furnaces.

**Industrial Other—**Prior to 1978, monthly consumption data for the other industrial sector (all industrial users minus coke plants) were derived by using reported data to modify baseline consumption figures from the most recent Bureau of the Census Annual Survey of Manufactures or Census of Manufactures. For 1978 and 1979, monthly estimates were derived from data reported on Forms EIA-3 and EIA-6. For 1980–1987, monthly figures were estimated by proportioning quarterly data by using the ratios of monthly-to-quarterly consumption data in 1979, the last year in which monthly data were reported on Form EIA-3. Beginning in January 1988, monthly consumption for the other industrial sector is estimated from reported quarterly data by using ratios derived from industrial production indices published by the Board of Governors of the



Federal Reserve System. Indices for six major industry groups are used as the basis for calculating the ratios: food manufacturing, which is North American Industry Classification System (NAICS) code 311; paper manufacturing, NAICS 322; chemical manufacturing, NAICS 325; petroleum and coal products, NAICS 324; non-metallic mineral products manufacturing, NAICS 327; and primary metal manufacturing, NAICS 331. The monthly ratios are computed as the monthly sum of the weighted indices as a proportion of the quarterly sum of the weighted indices by using the 1977 proportion as the weights. Prior to 2008, quarterly consumption data for the other industrial sector were derived by adding beginning stocks at manufacturing plants to current receipts and subtracting ending stocks at manufacturing plants. In this calculation, current receipts are the greater of either reported receipts from manufacturing plants (Form EIA-3) or reported shipments to the other industrial sector (Form EIA-6), thereby ensuring that agriculture, forestry, fishing, and construction consumption data were included where appropriate. Beginning in 2008, quarterly consumption totals for other industrial coal include data for manufacturing and mining only. Over time, surveyed coal consumption data for agriculture, forestry, fishing, and construction dwindled to about 20,000 to 30,000 tons annually. Therefore, in 2008, EIA consolidated its programs by eliminating agriculture, forestry, fishing, and construction as surveyed sectors.

Electric Power Sector—Monthly consumption data for electric power plants are taken directly from reported data.

**Note 3. Coal Stocks.** Coal stocks data are reported by major end-use sector. Forecast data for the most recent months (designated by an “F”) are derived from forecasted values shown in the EIA *Short-Term Energy Outlook* (DOE/EIA-0202) table titled “U.S. Coal Supply and Demand: Base Case.” The monthly estimates are based on the quarterly values (released in March, June, September, and December) or annual values. The estimates are revised as collected data become available from the data sources. Sector-specific information follows.

Producers and Distributors—Prior to 1998, quarterly stocks at producers and distributors were taken directly from reported data. Monthly data were estimated by using one-third of the current quarterly change to indicate the monthly change in stocks. Beginning in 1998, end-of-year stocks are taken from reported data. Monthly stocks are estimated by a model.

Residential and Commercial—Prior to 1980, stock estimates for the residential and commercial sector were taken directly from reported data. For 1980–2007, stock estimates were not collected. Beginning in 2008, quarterly stocks data are collected on Form EIA-3 (data for “Commercial and Institutional Coal Users”).

Industrial Coke Plants—Prior to 1980, monthly stocks at coke plants were taken directly from reported data.

Beginning in 1980, coke plant stocks are estimated by using one-third of the current quarterly change to indicate the monthly change in stocks. Quarterly stocks are taken directly from data reported on Form EIA-5.

Industrial Other—Prior to 1978, stocks for the other industrial sector were derived by using reported data to modify baseline figures from a one-time Bureau of Mines survey of consumers. For 1978–1982, monthly estimates were derived by judgmentally proportioning reported quarterly data based on representative seasonal patterns of supply and demand. Beginning in 1983, other industrial coal stocks are estimated as indicated above for coke plants. Quarterly stocks are taken directly from data reported on Form EIA-3 and therefore include only manufacturing industries; data for agriculture, forestry, fishing, mining, and construction stocks are not available.

Electric Power Sector—Monthly stocks data at electric power plants are taken directly from reported data.

**Note 4. Coal Forecast Values.** Data values preceded by “F” in this section are forecast values. They are derived from EIA Short-Term Integrated Forecasting System (STIFS). The model is driven primarily by data and assumptions about key macroeconomic variables, the world oil price, and weather. The coal forecast relies on other variables as well, such as alternative fuel prices (natural gas and oil) and power generation by sources other than fossil fuels, including nuclear and hydroelectric power. Each month, EIA staff review the model output and make adjustments, if appropriate, based on their knowledge of developments in the coal industry.

The STIFS model results are published monthly in EIA’s *Short-Term Energy Outlook*, which is accessible on the Web at <http://www.eia.gov/emeu/steo/pub/contents.html>.

**Note 5. Additional Coal Information.** EIA’s *Quarterly Coal Report* provides additional information about coal data and estimation procedures.

## Table 6.1 Sources

### Production

1973–September 1977: U.S. Department of the Interior, Bureau of Mines, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977 forward: U.S. Energy Information Administration (EIA), *Weekly Coal Production*.

### Waste Coal Supplied

1989–1997: EIA, Form EIA-867, “Annual Nonutility Power Producer Report.”

1998–2000: EIA, Form EIA-860B, “Annual Electric Generator Report—Nonutility.”

2001–2003: EIA, Form EIA-906, “Power Plant Report,” and Form EIA-3, “Quarterly Coal Consumption and

Quality Report—Manufacturing Plants.”

2004–2007: EIA, Form EIA-906, “Power Plant Report,” Form EIA-920, “Combined Heat and Power Plant Report,” and Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants.”

2008 forward: EIA, Form EIA-923, “Power Plant Operations Report,” and Form EIA-3, “Quarterly Coal Consumption and Quality Report, Manufacturing and Transformation/Processing Coal Plants and Commercial and Institutional Coal Users”; and, for forecast values, EIA, Short-Term Integrated Forecasting System.

### Imports and Exports

U.S. Department of Commerce, Bureau of the Census, Monthly Reports IM 145 (Imports) and EM 545 (Exports).

### Stock Change

Calculated from data in Table 6.3. (The 1973 stock change value is calculated using the 1972 total stocks value of 116,753 thousand short tons from EIA, *Annual Energy Review*, Table 7.6. The 1972 stocks value excludes stocks at producers and distributors.)

### Losses and Unaccounted for

Calculated as the sum of production, imports, and waste coal supplied, minus exports, stock change, and consumption.

### Consumption

Table 6.2.

## Table 6.2 Sources

### Residential and Commercial Total

Coal consumption by the residential and commercial sectors combined is reported to the U.S. Energy Information Administration (EIA). EIA estimates the sectors individually using the method described in Note 2, “Consumption,” at the end of Section 6. Data for the residential and commercial sectors combined are from:

1973–1976: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

October 1977–1979: EIA, Form EIA-2, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

1980–1997: EIA, Form EIA-6, “Coal Distribution Report,” quarterly.

1998–2007: DOI, Mine Safety and Health Administration, Form 7000-2, “Quarterly Mine Employment and Coal Production.”

2008 forward: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report, Manufacturing and Transformation/Processing Coal Plants and Commercial and Institutional Coal Users” (data for “Commercial and Institutional Coal Users”); and, for forecast values, EIA, Short-Term Integrated Forecasting System (STIFS).

### Commercial CHP

Table 7.4c.

### Commercial Other

Calculated as “Commercial Total” minus “Commercial CHP.”

### Industrial Coke Plants

1973–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1980: EIA, Form EIA-5/5A, “Coke and Coal Chemicals—Monthly/Annual Supplement.”

1981–1984: EIA, Form EIA-5/5A, “Coke Plant Report—Quarterly/Annual Supplement.”

1985 forward: EIA, Form EIA-5, “Coke Plant Report—Quarterly”; and, for forecast values, EIA, STIFS.

### Other Industrial Total

1973–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1979: EIA, Form EIA-3, “Monthly Coal Consumption Report—Manufacturing Plants.”

1980–1997: EIA, Form EIA-3, “Quarterly Coal Consumption Report—Manufacturing Plants,” and Form EIA-6, “Coal Distribution Report,” quarterly.

1998–2007: EIA, Form EIA-3, “Quarterly Coal Consumption Report—Manufacturing Plants,” Form EIA-6A, “Coal Distribution Report,” annual, and Form EIA-7A, “Coal Production Report,” annual.

2008 forward: EIA, Form EIA-3, “Quarterly Coal Consumption and Quality Report, Manufacturing and Transformation/Processing Coal Plants and Commercial and Institutional Coal Users,” and Form EIA-7A, “Coal Production Report,” annual; and, for forecast values, EIA, STIFS.

### Other Industrial CHP

Table 7.4c.

### Other Industrial Non-CHP

Calculated as “Other Industrial Total” minus “Other Industrial CHP.”

### Transportation

1973–1976: DOI, BOM, *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, “Monthly Coal Report, Retail Dealers—Upper Lake Docks.”

October–December 1977: EIA, Form EIA-6, “Coal Distribution Report,” quarterly.

### Electric Power

Table 7.4b.

## Table 6.3 Sources

### Producers and Distributors

1973–1979: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), Form 6-1419Q, “Distribution of Bituminous Coal and Lignite Shipments.”

1980–1997: U.S. Energy Information Administration

(EIA), Form EIA-6, "Coal Distribution Report," quarterly. 1998–2007: EIA, Form EIA-6A, "Coal Distribution Report," annual. 2008 forward: EIA, Form EIA-7A, "Coal Production Report," annual, and Form EIA-8A, "Coal Stocks Report," annual; and, for forecast values, EIA, Short-Term Integrated Forecasting System (STIFS).

#### **Residential and Commercial**

1973–1976: DOI, BOM, *Minerals Yearbook*.

January–September 1977: DOI, BOM, Form 6-1400, "Monthly Coal Report, Retail Dealers—Upper Lake Docks."

October 1977–1979: EIA, Form EIA-2, "Monthly Coal Report, Retail Dealers—Upper Lake Docks."

2008 forward: EIA, Form EIA-3, "Quarterly Coal Consumption and Quality Report, Manufacturing and Transformation/Processing Coal Plants and Commercial and Institutional Coal Users" (data for "Commercial and Institutional Coal Users"); and, for forecast values, EIA, STIFS.

#### **Industrial Coke Plants**

1973–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1980: EIA, Form EIA-5/5A, "Coke and Coal Chemicals—Monthly/Annual."

1981–1984: EIA, Form EIA 5/5A, "Coke Plant Report—Quarterly/Annual Supplement."

1985 forward: EIA, Form EIA-5, "Coke Plant Report—Quarterly"; and, for forecast values, EIA, STIFS.

#### **Industrial Other**

1973–September 1977: DOI, BOM, *Minerals Yearbook* and *Minerals Industry Surveys*.

October 1977–1979: EIA, Form EIA-3, "Monthly Coal Consumption Report—Manufacturing Plants."

1980–2007: EIA, Form EIA-3, "Quarterly Coal Consumption Report—Manufacturing Plants."

2008 forward: EIA, Form EIA-3, "Quarterly Coal Consumption and Quality Report, Manufacturing and Transformation/Processing Coal Plants and Commercial and Institutional Coal Users"; and, for forecast values, EIA, STIFS.

#### **Electric Power**

Table 7.5.


THIS PAGE INTENTIONALLY LEFT BLANK

## 7. Electricity


---

**Figure 7.1 Electricity Overview**  
(Billion Kilowatthours)


Overview, 2011




Net Generation, 2011



Net Generation by Sector, 1989-2011




Net Generation by Sector, Monthly



End Use, 2011



Trade, 1973-2011



<sup>a</sup> Includes commercial sector.

<sup>b</sup> Electricity retail sales to ultimate customers reported by electric utilities and other energy service providers.

<sup>c</sup> See "Direct Use" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.  
Source: Table 7.1.

**Table 7.1 Electricity Overview**  
(Billion Kilowatthours)

	Net Generation				Trade			T&D Losses <sup>e</sup> and Unaccounted for <sup>f</sup>	End Use		
	Electric Power Sector <sup>a</sup>	Com- mercial Sector <sup>b</sup>	Indus- trial Sector <sup>c</sup>	Total	Imports <sup>d</sup>	Exports <sup>d</sup>	Net Imports <sup>d</sup>		Retail Sales <sup>g</sup>	Direct Use <sup>h</sup>	Total
1973 Total .....	1,861	NA	3	1,864	17	3	14	165	1,713	NA	1,713
1975 Total .....	1,918	NA	3	1,921	11	5	6	180	1,747	NA	1,747
1980 Total .....	2,286	NA	3	2,290	25	4	21	216	2,094	NA	2,094
1985 Total .....	2,470	NA	3	2,473	46	5	41	190	2,324	NA	2,324
1990 Total .....	2,901	6	131	3,038	18	16	2	203	2,713	125	2,837
1995 Total .....	3,194	8	151	3,353	43	4	39	229	3,013	151	3,164
1996 Total .....	3,284	9	151	3,444	43	3	40	231	3,101	153	3,254
1997 Total .....	3,329	9	154	3,492	43	9	34	224	3,146	156	3,302
1998 Total .....	3,457	9	154	3,620	40	14	26	221	3,264	161	3,425
1999 Total .....	3,530	9	156	3,695	43	14	29	240	3,312	172	3,484
2000 Total .....	3,638	8	157	3,802	49	15	34	244	3,421	171	3,592
2001 Total .....	3,580	7	149	3,737	39	16	22	202	3,394	163	3,557
2002 Total .....	3,698	7	153	3,858	37	16	21	248	3,465	166	3,632
2003 Total .....	3,721	7	155	3,883	30	24	6	228	3,494	168	3,662
2004 Total .....	3,808	8	154	3,971	34	23	11	266	3,547	168	3,716
2005 Total .....	3,902	8	145	4,055	44	19	25	269	3,661	150	3,811
2006 Total .....	3,908	8	148	4,065	43	24	18	266	3,670	147	3,817
2007 Total .....	4,005	8	143	4,157	51	20	31	298	3,765	126	3,890
2008 Total .....	3,974	8	137	4,119	57	24	33	287	3,733	132	3,865
2009 Total .....	3,810	8	132	3,950	52	18	34	261	3,597	127	3,724
2010 January .....	348	1	12	361	5	1	4	22	332	<sup>E</sup> 11	343
February .....	308	1	11	320	4	1	3	15	298	<sup>E</sup> 10	309
March .....	300	1	12	312	4	1	3	12	293	<sup>E</sup> 11	303
April .....	276	1	11	288	4	1	3	13	267	<sup>E</sup> 10	277
May .....	316	1	12	328	3	2	1	35	284	<sup>E</sup> 11	294
June .....	363	1	12	376	4	2	2	36	331	<sup>E</sup> 11	342
July .....	396	1	13	410	4	1	3	32	369	<sup>E</sup> 12	381
August .....	395	1	13	409	4	2	2	27	372	<sup>E</sup> 12	384
September .....	333	1	12	346	3	2	1	8	328	<sup>E</sup> 11	339
October .....	296	1	12	308	3	2	(s)	10	288	<sup>E</sup> 11	298
November .....	294	1	11	306	3	2	1	21	275	<sup>E</sup> 11	285
December .....	349	1	13	362	4	1	3	34	319	<sup>E</sup> 12	331
<b>Total .....</b>	<b>3,972</b>	<b>9</b>	<b>144</b>	<b>4,125</b>	<b>45</b>	<b>19</b>	<b>26</b>	<b>265</b>	<b>3,754</b>	<b>132</b>	<b>3,886</b>
2011 January .....	351	1	12	364	4	2	3	23	333	<sup>E</sup> 11	344
February .....	302	1	11	313	4	2	2	10	296	<sup>E</sup> 10	306
March .....	307	1	11	319	4	2	2	21	290	<sup>E</sup> 11	301
April .....	291	1	11	303	4	2	2	21	274	<sup>E</sup> 10	284
May .....	312	1	12	325	5	1	4	32	286	<sup>E</sup> 11	297
June .....	356	1	12	368	4	1	3	34	327	<sup>E</sup> 11	338
July .....	406	1	13	419	6	1	5	44	369	<sup>E</sup> 12	380
August .....	393	1	13	406	6	1	5	29	370	<sup>E</sup> 12	382
September .....	325	1	12	338	4	1	3	6	324	<sup>E</sup> 11	335
October .....	297	1	11	309	4	1	3	16	286	<sup>E</sup> 10	296
November .....	292	1	12	304	3	1	2	23	273	<sup>E</sup> 11	284
December .....	323	1	13	336	4	1	3	29	299	<sup>E</sup> 12	311
<b>Total .....</b>	<b>3,955</b>	<b>8</b>	<b>142</b>	<b>4,106</b>	<b>52</b>	<b>15</b>	<b>37</b>	<b>287</b>	<b>3,726</b>	<b><sup>E</sup>130</b>	<b>3,856</b>
2012 January .....	327	1	13	341	4	1	3	22	311	<sup>E</sup> 12	322
February .....	298	1	12	310	4	1	3	16	286	<sup>E</sup> 11	297
March .....	297	1	12	310	4	1	3	20	282	<sup>E</sup> 11	293
April .....	285	1	11	296	5	1	4	20	270	<sup>E</sup> 10	280
May .....	325	1	12	338	5	1	4	35	296	<sup>E</sup> 11	307
<b>5-Month Total .....</b>	<b>1,532</b>	<b>3</b>	<b>59</b>	<b>1,595</b>	<b>22</b>	<b>5</b>	<b>17</b>	<b>113</b>	<b>1,445</b>	<b><sup>E</sup>54</b>	<b>1,499</b>
2011 5-Month Total .....	1,563	3	58	1,624	21	8	13	106	1,478	<sup>E</sup> 53	1,531
2010 5-Month Total .....	1,547	3	58	1,609	21	7	15	97	1,474	<sup>E</sup> 53	1,526

<sup>a</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>b</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>c</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants. Through 1988, data are for industrial hydroelectric power only.

<sup>d</sup> Electricity transmitted across U.S. borders. Net imports equal imports minus exports.

<sup>e</sup> Transmission and distribution losses (electricity losses that occur between the point of generation and delivery to the customer). See Note 2, "Electrical System Energy Losses," at end of Section 2.

<sup>f</sup> Data collection frame differences and nonsampling error.

<sup>g</sup> Electricity retail sales to ultimate customers by electric utilities and, beginning in 1996, other energy service providers.

<sup>h</sup> Use of electricity that is 1) self-generated, 2) produced by either the same entity that consumes the power or an affiliate, and 3) used in direct support of a service or industrial process located within the same facility or group of facilities that house the generating equipment. Direct use is exclusive of station use.

<sup>E</sup>=Estimate. NA=Not available. (s)=Less than 0.5 billion kilowatthours.


Notes: • See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.


Sources: See end of section.

**Figure 7.2 Electricity Net Generation**  
(Billion Kilowatthours)


Total (All Sectors), Major Sources, 1989-2011




Total (All Sectors), Major Sources, Monthly




Total (All Sectors), Major Sources, 2011




Electric Power Sector, Major Sources, 2011



Commercial Sector, Major Sources, 2011



Industrial Sector, Major Sources, 2011



<sup>a</sup> Conventional hydroelectric power, wood, waste, geothermal, solar/PV, and wind.

<sup>b</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

<sup>c</sup> Conventional hydroelectric power.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.  
Sources: Tables 7.2a-7.2c.



**Table 7.2a Electricity Net Generation: Total (All Sectors)**  
(Sum of Tables 7.2b and 7.2c; Million Kilowatthours)

	Fossil Fuels				Nuclear Electric Power	Hydro-electric Pumped Storage <sup>e</sup>	Renewable Energy					Total	
	Coal <sup>a</sup>	Petroleum <sup>b</sup>	Natural Gas <sup>c</sup>	Other Gases <sup>d</sup>			Conventional Hydro-electric Power <sup>f</sup>	Biomass		Geo-thermal	Solar/PV <sup>i</sup>		Wind
								Wood <sup>g</sup>	Waste <sup>h</sup>				
<b>1973 Total</b> .....	847,651	314,343	340,858	NA	83,479	( )	275,431	130	198	1,966	NA	NA	1,864,057
<b>1975 Total</b> .....	852,786	289,095	299,778	NA	172,505	( )	303,153	18	174	3,246	NA	NA	1,920,755
<b>1980 Total</b> .....	1,161,562	245,994	346,240	NA	251,116	( )	279,182	275	158	5,073	NA	NA	2,289,600
<b>1985 Total</b> .....	1,402,128	100,202	291,946	NA	383,691	( )	284,311	743	640	9,325	11	6	2,473,002
<b>1990 Total</b> <sup>k</sup> .....	1,594,011	126,460	372,765	10,383	576,862	-3,508	292,866	32,522	13,260	15,434	367	2,789	3,037,827
<b>1995 Total</b> .....	1,709,426	74,554	496,058	13,870	673,402	-2,725	310,833	36,521	20,405	13,378	497	3,164	3,353,487
<b>1996 Total</b> .....	1,795,196	81,411	455,056	14,356	674,729	-3,088	347,162	36,800	20,911	14,329	521	3,234	3,444,188
<b>1997 Total</b> .....	1,845,016	92,555	479,399	13,351	628,644	-4,040	356,453	36,948	21,709	14,726	511	3,288	3,492,172
<b>1998 Total</b> .....	1,873,516	128,800	531,257	13,492	673,702	-4,467	323,336	36,338	22,448	14,774	502	3,026	3,620,295
<b>1999 Total</b> .....	1,881,087	118,061	556,396	14,126	728,254	-6,097	319,536	37,041	22,572	14,827	495	4,488	3,694,810
<b>2000 Total</b> .....	1,966,265	111,221	601,038	13,952	753,893	-5,539	275,573	37,595	23,131	14,093	493	5,593	3,902,105
<b>2001 Total</b> .....	1,903,956	124,880	639,129	9,939	768,826	-8,823	216,961	35,200	14,548	13,741	543	6,737	3,736,644
<b>2002 Total</b> .....	1,933,130	94,567	691,006	11,463	780,064	-8,743	264,329	38,665	15,044	14,491	555	10,354	3,858,452
<b>2003 Total</b> .....	1,973,737	119,406	649,908	15,600	763,733	-8,535	275,806	37,529	15,812	14,424	534	11,187	3,883,185
<b>2004 Total</b> .....	1,978,301	121,145	710,100	15,252	788,528	-8,488	268,417	38,117	15,421	14,811	575	14,144	3,970,555
<b>2005 Total</b> .....	2,012,873	122,225	760,960	13,464	781,986	-6,558	270,321	38,856	15,420	14,692	550	17,811	4,055,423
<b>2006 Total</b> .....	1,990,511	64,166	816,441	14,177	787,219	-6,558	289,246	38,762	16,099	14,568	508	26,589	4,064,702
<b>2007 Total</b> .....	2,016,456	65,739	896,590	13,453	806,425	-6,896	247,510	39,014	16,525	14,637	612	34,450	4,156,745
<b>2008 Total</b> .....	1,985,801	46,243	882,981	11,707	806,208	-6,288	254,831	37,300	17,734	14,840	864	55,363	4,119,388
<b>2009 Total</b> .....	1,755,904	38,937	920,979	10,632	798,855	-4,627	273,445	36,050	18,443	15,009	891	73,886	3,950,331
<b>2010 January</b> .....	173,320	4,348	74,173	909	72,569	-565	22,383	3,126	1,503	1,312	10	6,854	360,957
February .....	153,044	2,373	66,198	825	65,245	-351	20,590	2,895	1,382	1,159	33	5,432	319,735
March .....	144,406	2,470	63,431	1,010	64,635	-325	20,886	3,090	1,592	1,307	76	8,589	312,168
April .....	126,952	2,286	64,644	943	57,611	-335	19,097	2,932	1,558	1,240	112	9,764	287,800
May .....	143,272	2,994	73,665	1,017	66,658	-441	25,079	2,893	1,577	1,311	153	8,698	327,936
June .....	165,491	3,989	92,268	964	68,301	-472	29,854	3,094	1,627	1,264	176	8,049	375,759
July .....	179,600	4,411	114,624	963	71,913	-557	24,517	3,308	1,640	1,274	161	6,724	409,725
August .....	177,745	3,575	121,151	1,061	71,574	-600	20,119	3,319	1,642	1,297	156	6,686	408,884
September .....	148,746	2,783	93,004	954	69,371	-421	17,265	3,157	1,575	1,253	138	7,106	346,045
October .....	132,270	2,228	77,738	808	62,751	-438	17,683	3,003	1,547	1,222	75	7,944	307,921
November .....	135,185	2,079	69,227	907	62,655	-467	19,562	3,080	1,625	1,252	77	9,748	306,010
December .....	167,258	3,523	77,573	952	73,683	-530	23,169	3,275	1,650	1,330	44	9,059	362,119
<b>Total</b> .....	<b>1,847,290</b>	<b>37,061</b>	<b>987,697</b>	<b>11,313</b>	<b>806,968</b>	<b>-5,501</b>	<b>260,203</b>	<b>37,172</b>	<b>18,917</b>	<b>15,219</b>	<b>1,212</b>	<b>94,652</b>	<b>4,125,060</b>
<b>2011 January</b> .....	170,983	3,268	74,458	910	72,743	-426	26,148	3,258	1,503	1,478	31	8,659	363,855
February .....	138,295	2,201	65,852	770	64,789	-247	24,687	2,896	1,393	1,326	80	10,528	313,351
March .....	134,717	2,454	66,169	955	65,662	-350	31,737	3,041	1,655	1,465	113	10,537	319,092
April .....	124,293	2,279	70,529	913	54,547	-467	31,629	2,788	1,619	1,337	161	12,447	302,994
May .....	137,493	2,198	75,769	848	57,017	-419	33,105	2,802	1,702	1,438	201	11,635	324,757
June .....	158,308	2,439	91,096	980	65,270	-568	32,253	3,243	1,685	1,363	257	10,887	368,184
July .....	176,709	3,011	120,377	1,059	72,345	-709	31,570	3,348	1,767	1,372	226	7,382	419,480
August .....	171,472	2,407	119,646	999	71,339	-663	26,320	3,290	1,717	1,380	236	7,342	406,450
September .....	141,220	2,247	91,377	958	66,849	-554	21,500	3,113	1,621	1,334	183	6,883	337,606
October .....	126,872	1,934	79,078	949	63,354	-572	20,036	2,876	1,669	1,393	169	10,623	309,279
November .....	121,197	1,723	75,637	923	64,474	-441	21,374	2,980	1,689	1,377	78	12,354	304,268
December .....	132,706	2,000	86,606	1,005	71,837	-496	24,715	3,311	1,765	1,439	79	10,469	336,419
<b>Total</b> .....	<b>1,734,265</b>	<b>28,162</b>	<b>1,016,595</b>	<b>11,269</b>	<b>790,225</b>	<b>-5,912</b>	<b>325,074</b>	<b>36,946</b>	<b>19,786</b>	<b>16,700</b>	<b>1,814</b>	<b>119,747</b>	<b>4,105,734</b>
<b>2012 January</b> .....	129,064	2,232	91,213	1,096	72,382	-330	23,933	3,293	1,621	1,438	70	13,823	340,743
February .....	113,831	1,718	91,260	1,146	63,850	-226	20,813	3,029	1,523	1,361	119	11,047	310,298
March .....	106,032	1,576	92,739	1,023	61,730	-268	26,287	2,832	1,637	1,438	218	13,553	309,709
April .....	95,982	1,534	95,882	1,018	55,871	-242	26,748	2,515	1,643	1,354	307	12,611	296,101
May .....	116,476	1,677	107,928	1,034	62,081	-343	28,991	2,932	1,695	1,439	450	12,442	337,770
<b>5-Month Total</b> .....	<b>511,385</b>	<b>8,736</b>	<b>479,022</b>	<b>5,317</b>	<b>315,914</b>	<b>-1,410</b>	<b>126,772</b>	<b>14,601</b>	<b>8,119</b>	<b>7,030</b>	<b>1,164</b>	<b>63,476</b>	<b>1,594,620</b>
<b>2011 5-Month Total</b> .....	<b>705,782</b>	<b>12,400</b>	<b>352,776</b>	<b>4,395</b>	<b>314,758</b>	<b>-1,909</b>	<b>147,306</b>	<b>14,785</b>	<b>7,873</b>	<b>7,043</b>	<b>587</b>	<b>53,807</b>	<b>1,624,049</b>
<b>2010 5-Month Total</b> .....	<b>740,994</b>	<b>14,472</b>	<b>342,111</b>	<b>4,704</b>	<b>326,719</b>	<b>-2,016</b>	<b>108,034</b>	<b>14,936</b>	<b>7,611</b>	<b>6,328</b>	<b>384</b>	<b>39,337</b>	<b>1,608,596</b>

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, and waste oil.

<sup>c</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>d</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

<sup>e</sup> Pumped storage facility production minus energy used for pumping.

<sup>f</sup> Through 1989, hydroelectric pumped storage is included in "Conventional Hydroelectric Power."

<sup>g</sup> Wood and wood-derived fuels.

<sup>h</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>i</sup> Solar thermal and photovoltaic (PV) energy.

<sup>j</sup> Includes batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, all data except hydroelectric are for electric utilities only; hydroelectric data through 1988 include industrial plants as well as electric utilities. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.

Sources: See sources for Tables 7.2b and 7.2c.

**Table 7.2b Electricity Net Generation: Electric Power Sector**  
(Subset of Table 7.2a; Million Kilowatt-hours)

	Fossil Fuels				Nuclear Electric Power	Hydro-electric Pumped Storage <sup>e</sup>	Renewable Energy					Total <sup>j</sup>	
	Coal <sup>a</sup>	Petroleum <sup>b</sup>	Natural Gas <sup>c</sup>	Other Gases <sup>d</sup>			Conventional Hydro-electric Power <sup>f</sup>	Biomass		Geo-thermal	Solar/PV <sup>i</sup>		Wind
								Wood <sup>g</sup>	Waste <sup>h</sup>				
<b>1973 Total</b> .....	847,651	314,343	340,858	NA	83,479	{	272,083	130	198	1,966	NA	NA	1,860,710
<b>1975 Total</b> .....	852,786	289,095	299,778	NA	172,505	{	300,047	18	174	3,246	NA	NA	1,917,649
<b>1980 Total</b> .....	1,161,562	245,994	346,240	NA	251,116	{	276,021	275	158	5,073	NA	NA	2,286,439
<b>1985 Total</b> .....	1,402,128	100,202	291,946	NA	383,691	{	281,149	743	640	9,325	11	6	2,469,841
<b>1990 Total</b> <sup>k</sup> .....	1,572,109	118,864	309,486	621	576,862	-3,508	289,753	7,032	11,500	15,434	367	2,789	2,901,322
<b>1995 Total</b> .....	1,686,056	68,146	419,179	1,927	673,402	-2,725	305,410	7,597	17,986	13,378	497	3,164	3,194,230
<b>1996 Total</b> .....	1,771,973	74,783	378,757	1,341	674,729	-3,088	341,159	8,386	17,816	14,329	521	3,234	3,284,141
<b>1997 Total</b> .....	1,820,762	86,479	399,596	1,533	628,644	-4,040	350,648	8,680	18,485	14,726	511	3,288	3,329,375
<b>1998 Total</b> .....	1,850,193	122,211	449,293	2,315	673,702	-4,467	317,867	8,608	19,233	14,774	502	3,026	3,457,416
<b>1999 Total</b> .....	1,858,618	111,539	472,996	1,607	728,254	-6,097	314,663	8,961	19,493	14,827	495	4,488	3,529,982
<b>2000 Total</b> .....	1,943,111	105,192	517,978	2,028	753,893	-5,539	271,338	8,916	20,307	14,093	493	5,593	3,637,529
<b>2001 Total</b> .....	1,862,826	119,149	554,940	586	768,826	-8,823	213,749	8,294	12,944	13,741	543	6,737	3,580,053
<b>2002 Total</b> .....	1,910,613	89,733	607,683	1,970	780,064	-8,743	260,491	9,009	13,145	14,491	555	10,354	3,698,458
<b>2003 Total</b> .....	1,952,714	113,697	567,303	2,647	763,733	-8,535	271,512	9,528	13,808	14,424	534	11,187	3,721,159
<b>2004 Total</b> .....	1,967,188	114,678	627,172	3,568	788,528	-8,488	265,064	9,736	13,062	14,811	575	14,144	3,808,360
<b>2005 Total</b> .....	1,992,054	116,482	683,829	3,777	781,986	-6,558	267,040	10,570	13,031	14,692	550	17,811	3,902,192
<b>2006 Total</b> .....	1,969,737	59,708	734,417	4,254	787,219	-6,558	286,254	10,341	13,927	14,568	508	26,589	3,908,077
<b>2007 Total</b> .....	1,998,390	61,306	814,752	4,042	806,425	-6,896	245,843	10,711	14,294	14,637	612	34,450	4,005,343
<b>2008 Total</b> .....	1,968,838	42,881	802,372	3,200	806,208	-6,288	253,096	10,638	15,379	14,840	864	55,363	3,974,349
<b>2009 Total</b> .....	1,741,123	35,811	841,006	3,058	798,855	-4,627	271,506	10,738	15,954	15,009	891	73,886	3,809,837
<b>2010</b>													
January .....	171,660	4,111	66,847	275	72,569	-565	22,207	1,011	1,294	1,312	10	6,853	348,128
February .....	151,461	2,166	59,556	247	65,245	-351	20,421	926	1,207	1,159	33	5,431	307,994
March .....	142,665	2,299	56,492	275	64,635	-325	20,691	939	1,391	1,307	76	8,588	299,571
April .....	125,615	2,109	58,124	273	57,611	-335	18,898	837	1,334	1,240	112	9,763	276,121
May .....	141,669	2,801	66,862	279	66,658	-441	24,903	830	1,359	1,311	153	8,696	315,656
June .....	163,912	3,792	85,033	265	68,301	-472	29,711	955	1,409	1,264	175	8,048	362,985
July .....	177,778	4,199	106,961	267	71,913	-557	24,405	1,061	1,419	1,274	161	6,723	396,195
August .....	175,848	3,375	112,961	249	71,574	-600	20,019	1,074	1,413	1,297	156	6,685	394,651
September .....	147,157	2,608	85,498	240	69,371	-421	17,188	974	1,364	1,253	137	7,104	333,057
October .....	130,663	2,037	70,876	170	62,751	-438	17,561	887	1,330	1,222	75	7,942	295,646
November .....	133,815	1,879	62,305	219	62,655	-467	19,426	934	1,412	1,252	76	9,746	293,833
December .....	165,494	3,302	69,875	208	73,683	-530	23,024	1,018	1,443	1,330	43	9,058	348,549
<b>Total</b> .....	<b>1,827,738</b>	<b>34,679</b>	<b>901,389</b>	<b>2,967</b>	<b>806,968</b>	<b>-5,501</b>	<b>258,455</b>	<b>11,446</b>	<b>16,376</b>	<b>15,219</b>	<b>1,206</b>	<b>94,636</b>	<b>3,972,386</b>
<b>2011</b>													
January .....	169,157	3,056	67,038	247	72,743	-426	26,001	986	1,293	1,478	31	8,657	350,775
February .....	136,752	2,042	59,187	206	64,789	-247	24,517	873	1,204	1,326	79	10,525	301,735
March .....	133,163	2,282	59,350	250	65,662	-350	31,537	883	1,457	1,465	112	10,534	306,932
April .....	123,067	2,112	63,709	250	54,547	-467	31,422	674	1,439	1,337	160	12,444	291,282
May .....	135,794	2,053	68,567	250	57,017	-419	32,888	753	1,467	1,438	199	11,632	312,220
June .....	156,677	2,276	84,032	282	65,270	-568	32,097	921	1,470	1,363	254	10,884	355,569
July .....	174,850	2,840	112,765	296	72,345	-709	31,442	1,042	1,537	1,372	223	7,380	406,019
August .....	169,572	2,243	111,991	293	71,339	-663	26,217	1,020	1,481	1,380	233	7,339	393,059
September .....	139,458	2,075	84,392	287	66,849	-554	21,375	896	1,395	1,334	181	6,880	325,121
October .....	125,200	1,792	72,407	279	63,354	-572	19,905	752	1,444	1,393	167	10,618	297,294
November .....	119,867	1,597	68,418	242	64,474	-441	21,222	753	1,457	1,377	77	12,348	291,954
December .....	131,311	1,857	78,714	266	71,837	-496	24,520	951	1,538	1,439	79	10,464	323,103
<b>Total</b> .....	<b>1,714,870</b>	<b>26,223</b>	<b>930,568</b>	<b>3,148</b>	<b>790,225</b>	<b>-5,912</b>	<b>323,141</b>	<b>10,504</b>	<b>17,182</b>	<b>16,700</b>	<b>1,795</b>	<b>119,704</b>	<b>3,955,065</b>
<b>2012</b>													
January .....	127,430	1,940	83,532	422	72,382	-330	23,749	949	1,388	1,438	69	13,814	327,388
February .....	112,361	1,524	83,904	422	63,850	-226	20,649	875	1,295	1,361	117	11,040	297,729
March .....	104,552	1,375	85,611	275	61,730	-268	26,090	829	1,422	1,438	211	13,543	297,419
April .....	94,891	1,322	89,010	242	55,871	-242	26,580	628	1,418	1,354	297	12,602	284,567
May .....	115,362	1,496	100,315	271	62,081	-343	28,797	780	1,447	1,439	435	12,434	325,131
<b>5-Month Total</b> .....	<b>554,596</b>	<b>7,656</b>	<b>442,371</b>	<b>1,633</b>	<b>315,914</b>	<b>-1,410</b>	<b>125,866</b>	<b>4,061</b>	<b>6,969</b>	<b>7,030</b>	<b>1,129</b>	<b>63,432</b>	<b>1,532,233</b>
<b>2011 5-Month Total</b> .....	<b>697,934</b>	<b>11,545</b>	<b>317,851</b>	<b>1,203</b>	<b>314,758</b>	<b>-1,909</b>	<b>146,365</b>	<b>4,170</b>	<b>6,861</b>	<b>7,043</b>	<b>581</b>	<b>53,791</b>	<b>1,562,945</b>
<b>2010 5-Month Total</b> .....	<b>733,070</b>	<b>13,485</b>	<b>307,880</b>	<b>1,350</b>	<b>326,719</b>	<b>-2,016</b>	<b>107,121</b>	<b>4,543</b>	<b>6,585</b>	<b>6,328</b>	<b>383</b>	<b>39,330</b>	<b>1,547,469</b>

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal symfuel.  
<sup>b</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, and waste oil.  
<sup>c</sup> Natural gas, plus a small amount of supplemental gaseous fuels.  
<sup>d</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.  
<sup>e</sup> Pumped storage facility production minus energy used for pumping.  
<sup>f</sup> Through 1989, hydroelectric pumped storage is included in "Conventional Hydroelectric Power."  
<sup>g</sup> Wood and wood-derived fuels.  
<sup>h</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).  
<sup>i</sup> Solar thermal and photovoltaic (PV) energy.  
<sup>j</sup> Includes batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).  
<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.  
 NA=Not available.  
 Notes: • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.  
 Sources: See end of section.

**Table 7.2c Electricity Net Generation: Commercial and Industrial Sectors**  
(Subset of Table 7.2a; Million Kilowatthours)

	Commercial Sector <sup>a</sup>					Industrial Sector <sup>b</sup>							
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass	Total <sup>g</sup>	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>h</sup>	Hydro-electric Power <sup>i</sup>	Biomass		Total <sup>k</sup>
				Waste <sup>f</sup>							Wood <sup>j</sup>	Waste <sup>f</sup>	
1973 Total	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,347	NA	NA	3,347
1975 Total	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,106	NA	NA	3,106
1980 Total	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,161	NA	NA	3,161
1985 Total	NA	NA	NA	NA	NA	NA	NA	NA	NA	3,161	NA	NA	3,161
1990 Total	796	589	3,272	812	5,837	21,107	7,008	60,007	9,641	2,975	25,379	949	130,830
1995 Total	998	379	5,162	1,519	8,232	22,372	6,030	71,717	11,943	5,304	28,868	900	151,025
1996 Total	1,051	369	5,249	2,176	9,030	22,172	6,260	71,049	13,015	5,878	28,354	919	151,017
1997 Total	1,040	427	4,725	2,342	8,701	23,214	5,649	75,078	11,814	5,685	28,225	882	154,097
1998 Total	985	383	4,879	2,335	8,748	22,337	6,206	77,085	11,170	5,349	27,693	880	154,132
1999 Total	995	434	4,607	2,393	8,563	21,474	6,088	78,793	12,519	4,758	28,060	686	156,264
2000 Total	1,097	432	4,262	1,985	7,903	22,056	5,597	78,798	11,927	4,135	28,652	839	156,673
2001 Total	995	438	4,434	1,007	7,416	20,135	5,293	79,755	8,454	3,145	26,888	596	149,175
2002 Total	992	431	4,310	1,053	7,415	21,525	4,403	79,013	9,493	3,825	29,643	846	152,580
2003 Total	1,206	423	3,899	1,289	7,496	19,817	5,285	78,705	12,953	4,222	27,988	715	154,530
2004 Total	1,340	499	3,969	1,562	8,270	19,773	5,967	78,959	11,684	3,248	28,367	797	153,925
2005 Total	1,353	375	4,249	1,657	8,492	19,466	5,368	72,882	9,687	3,195	28,271	733	144,739
2006 Total	1,310	235	4,355	1,599	8,371	19,464	4,223	77,669	9,923	2,899	28,400	572	148,254
2007 Total	1,371	189	4,257	1,599	8,273	16,694	4,243	77,580	9,411	1,590	28,287	631	143,128
2008 Total	1,261	142	4,188	1,534	7,926	15,703	3,219	76,421	8,507	1,676	26,641	821	137,113
2009 Total	1,096	163	4,225	1,748	8,165	13,686	2,963	75,748	7,574	1,868	25,292	740	132,329
<b>2010</b>													
January	116	13	367	137	709	1,544	225	6,959	634	169	2,114	72	12,120
February	102	11	339	111	623	1,481	197	6,303	578	162	1,967	64	11,118
March	91	8	351	134	661	1,649	163	6,588	735	188	2,149	67	11,936
April	80	9	326	144	645	1,258	169	6,194	669	187	2,094	80	11,034
May	84	12	326	149	666	1,519	181	6,477	738	164	2,061	69	11,614
June	97	10	350	150	699	1,482	187	6,885	700	132	2,137	68	12,075
July	110	18	459	146	812	1,713	194	7,205	696	107	2,246	75	12,718
August	105	11	490	152	838	1,792	189	7,701	812	99	2,243	78	13,395
September	89	9	421	148	750	1,499	165	7,085	713	76	2,182	62	12,238
October	80	7	419	133	712	1,527	184	6,443	637	117	2,114	84	11,562
November	69	4	401	134	683	1,301	196	6,520	688	130	2,145	79	11,493
December	88	12	476	136	793	1,677	209	7,223	744	134	2,255	71	12,777
<b>Total</b>	<b>1,111</b>	<b>124</b>	<b>4,725</b>	<b>1,672</b>	<b>8,592</b>	<b>18,441</b>	<b>2,258</b>	<b>81,583</b>	<b>8,343</b>	<b>1,668</b>	<b>25,706</b>	<b>869</b>	<b>144,082</b>
<b>2011</b>													
January	103	13	402	139	739	1,723	198	7,017	663	137	2,271	71	12,341
February	95	8	350	125	656	1,447	151	6,314	564	160	2,021	64	10,961
March	97	7	341	134	666	1,457	165	6,478	705	188	2,156	65	11,494
April	71	5	347	118	622	1,155	162	6,473	662	196	2,112	62	11,089
May	77	6	373	160	714	1,622	140	6,829	597	208	2,047	74	11,822
June	82	8	368	144	693	1,549	155	6,696	698	147	2,321	71	11,921
July	96	13	431	155	791	1,763	158	7,181	762	118	2,304	76	12,669
August	86	7	408	160	752	1,814	157	7,248	706	100	2,268	76	12,639
September	76	6	356	150	674	1,686	166	6,629	670	123	2,215	76	11,811
October	63	8	359	153	668	1,609	135	6,312	669	126	2,123	72	11,317
November	64	6	378	155	691	1,266	121	6,841	680	147	2,226	77	11,623
December	78	6	413	154	739	1,317	138	7,480	738	188	2,359	73	12,577
<b>Total</b>	<b>989</b>	<b>93</b>	<b>4,526</b>	<b>1,746</b>	<b>8,403</b>	<b>18,406</b>	<b>1,846</b>	<b>81,500</b>	<b>8,115</b>	<b>1,838</b>	<b>26,422</b>	<b>858</b>	<b>142,266</b>
<b>2012</b>													
January	83	6	387	163	698	1,552	286	7,295	673	182	2,343	70	12,657
February	82	4	357	163	665	1,388	190	6,999	723	163	2,152	65	11,904
March	68	4	363	155	658	1,412	197	6,765	747	195	2,001	60	11,633
April	49	6	359	159	639	1,041	206	6,513	775	166	1,885	65	10,895
May	67	6	364	174	686	1,048	176	7,249	762	192	2,151	74	11,952
<b>5-Month Total</b>	<b>349</b>	<b>25</b>	<b>1,829</b>	<b>815</b>	<b>3,346</b>	<b>6,440</b>	<b>1,055</b>	<b>34,822</b>	<b>3,680</b>	<b>897</b>	<b>10,532</b>	<b>335</b>	<b>59,041</b>
<b>2011 5-Month Total</b>	<b>444</b>	<b>39</b>	<b>1,813</b>	<b>676</b>	<b>3,397</b>	<b>7,404</b>	<b>816</b>	<b>33,112</b>	<b>3,191</b>	<b>890</b>	<b>10,607</b>	<b>336</b>	<b>57,707</b>
<b>2010 5-Month Total</b>	<b>474</b>	<b>52</b>	<b>1,710</b>	<b>674</b>	<b>3,304</b>	<b>7,451</b>	<b>934</b>	<b>32,521</b>	<b>3,353</b>	<b>871</b>	<b>10,384</b>	<b>352</b>	<b>57,823</b>

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, and waste oil.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Includes a small amount of conventional hydroelectric power, other gases, photovoltaic (PV) energy, wind, wood, and other, which are not separately displayed.

<sup>h</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

<sup>i</sup> Conventional hydroelectric power.

<sup>j</sup> Wood and wood-derived fuels.

<sup>k</sup> Includes photovoltaic (PV) energy, wind, batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

NA=Not available.


Notes: • See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.


Sources: See end of section.

**Figure 7.3 Consumption of Selected Combustible Fuels for Electricity Generation**


**Coal by Sector, 1989-2011**




**Petroleum by Sector, 1989-2011**




**Natural Gas by Sector, 1989-2011**




**Other Gases<sup>b</sup> by Sector, 1989-2011**



**Wood by Sector, 1989-2011**



**Waste by Sector, 1989-2011**



<sup>a</sup> Includes commercial sector.

<sup>b</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.  
Sources: Tables 7.3a-7.3c.

**Table 7.3a Consumption of Combustible Fuels for Electricity Generation: Total (All Sectors)** (Sum of Tables 7.3b and 7.3c)

	Coal <sup>a</sup> Thousand Short Tons	Petroleum					Natural Gas <sup>f</sup> Billion Cubic Feet	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
		Distillate Fuel Oil <sup>b</sup> Thousand Barrels	Residual Fuel Oil <sup>c</sup> Thousand Barrels	Other Liquids <sup>d</sup> Thousand Barrels	Petroleum Coke <sup>e</sup> Thousand Short Tons	Total <sup>e</sup> Thousand Barrels			Wood <sup>h</sup> Trillion Btu	Waste <sup>i</sup> Trillion Btu	
<b>1973 Total</b> .....	389,212	47,058	513,190	NA	507	562,781	3,660	NA	1	2	NA
<b>1975 Total</b> .....	405,962	38,907	467,221	NA	70	506,479	3,158	NA	(s)	2	NA
<b>1980 Total</b> .....	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
<b>1985 Total</b> .....	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
<b>1990 Total</b> <sup>k</sup> .....	792,457	18,143	190,652	437	1,914	218,800	3,692	112	442	211	36
<b>1995 Total</b> .....	860,594	19,615	95,507	680	3,355	132,578	4,738	133	480	316	42
<b>1996 Total</b> .....	907,209	20,252	106,055	1,712	3,322	144,626	4,312	159	513	324	37
<b>1997 Total</b> .....	931,949	20,309	118,741	237	4,086	159,715	4,565	119	484	339	36
<b>1998 Total</b> .....	946,295	25,062	172,728	549	4,860	222,640	5,081	125	475	332	36
<b>1999 Total</b> .....	949,802	25,951	158,187	974	4,552	207,871	5,322	126	490	332	41
<b>2000 Total</b> .....	994,933	31,675	143,381	1,450	3,744	195,228	5,691	126	496	330	46
<b>2001 Total</b> .....	972,691	31,150	165,312	855	3,871	216,672	5,832	97	486	228	160
<b>2002 Total</b> .....	987,583	23,286	109,235	1,894	6,836	168,597	6,126	131	605	257	191
<b>2003 Total</b> .....	1,014,058	29,672	142,518	2,947	6,303	206,653	5,616	156	519	249	193
<b>2004 Total</b> .....	1,020,523	20,163	142,088	2,856	7,677	203,494	5,675	135	344	230	183
<b>2005 Total</b> .....	1,041,448	20,651	141,518	2,968	8,330	206,785	6,036	110	355	230	173
<b>2006 Total</b> .....	1,030,556	13,174	58,473	2,174	7,363	110,634	6,462	115	350	241	172
<b>2007 Total</b> .....	1,046,795	15,683	63,833	2,917	6,036	112,615	7,089	115	353	245	168
<b>2008 Total</b> .....	1,042,335	12,832	38,191	2,822	5,417	80,932	6,896	97	339	267	172
<b>2009 Total</b> .....	934,683	12,658	28,576	2,328	4,821	67,668	7,121	84	320	272	170
<b>2010</b>											
January .....	90,767	2,485	2,860	241	433	7,751	570	7	30	22	15
February .....	80,209	869	1,075	212	404	4,174	502	6	28	20	13
March .....	76,544	785	1,245	147	438	4,370	479	8	29	24	15
April .....	67,037	726	1,160	126	382	3,923	494	8	27	23	15
May .....	76,061	1,050	1,997	121	415	5,244	582	8	27	24	15
June .....	87,395	1,244	3,087	154	493	6,950	731	8	29	24	16
July .....	94,993	1,347	3,681	200	524	7,849	923	8	31	24	16
August .....	94,786	1,093	2,987	164	423	6,358	972	8	32	24	16
September .....	79,573	905	1,789	151	394	4,813	723	8	30	23	16
October .....	70,918	787	1,113	129	362	3,840	594	6	28	23	15
November .....	72,756	876	982	143	317	3,588	519	7	29	24	15
December .....	88,645	1,883	2,021	266	408	6,210	591	8	31	24	16
<b>Total</b> .....	<b>979,684</b>	<b>14,050</b>	<b>23,997</b>	<b>2,056</b>	<b>4,994</b>	<b>65,071</b>	<b>7,680</b>	<b>90</b>	<b>350</b>	<b>281</b>	<b>184</b>
<b>2011</b>											
January .....	90,106	1,238	1,700	231	526	5,802	564	7	30	22	12
February .....	73,505	854	1,007	124	387	3,919	503	6	27	21	11
March .....	72,340	839	1,122	133	465	4,421	504	7	28	24	14
April .....	66,870	957	1,328	121	304	3,924	548	7	24	23	13
May .....	73,511	909	1,222	110	316	3,820	603	7	25	24	14
June .....	84,072	969	1,261	145	388	4,316	729	8	29	25	14
July .....	94,214	1,161	1,542	167	479	5,265	966	8	30	26	15
August .....	92,177	809	1,333	122	415	4,341	948	8	30	25	14
September .....	76,612	778	958	162	392	3,861	710	8	28	24	13
October .....	69,524	711	940	124	307	3,311	600	8	26	24	13
November .....	66,789	715	904	135	250	3,002	568	8	26	24	13
December .....	73,190	835	927	134	331	3,551	639	8	30	25	14
<b>Total</b> .....	<b>932,911</b>	<b>10,775</b>	<b>14,246</b>	<b>1,707</b>	<b>4,561</b>	<b>49,533</b>	<b>7,880</b>	<b>91</b>	<b>333</b>	<b>287</b>	<b>162</b>
<b>2012</b>											
January .....	70,595	772	988	135	414	3,964	676	9	30	23	14
February .....	62,802	649	753	108	314	3,079	672	9	28	22	12
March .....	57,564	579	869	120	251	2,825	704	9	26	24	13
April .....	51,574	734	797	126	204	2,675	744	8	25	24	13
May .....	62,958	854	838	141	234	3,006	843	8	28	25	14
<b>5-Month Total</b> .....	<b>305,493</b>	<b>3,589</b>	<b>4,246</b>	<b>630</b>	<b>1,417</b>	<b>15,549</b>	<b>3,640</b>	<b>43</b>	<b>138</b>	<b>117</b>	<b>67</b>
<b>2011 5-Month Total</b> .....	<b>376,333</b>	<b>4,797</b>	<b>6,380</b>	<b>719</b>	<b>1,998</b>	<b>21,887</b>	<b>2,722</b>	<b>35</b>	<b>134</b>	<b>115</b>	<b>65</b>
<b>2010 5-Month Total</b> .....	<b>390,618</b>	<b>5,916</b>	<b>8,337</b>	<b>848</b>	<b>2,072</b>	<b>25,462</b>	<b>2,627</b>	<b>38</b>	<b>140</b>	<b>113</b>	<b>73</b>

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1973-1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980-2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. For 1973-1979, data are for steam plant use of petroleum. For 1980-2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, and waste oil.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Data are for fuels consumed to produce electricity. Data also include fuels consumed to produce useful thermal output at a small number of electric utility combined-heat-and-power (CHP) plants. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.

Sources: See sources for Tables 7.3b and 7.3c.

**Table 7.3b Consumption of Combustible Fuels for Electricity Generation: Electric Power Sector (Subset of Table 7.3a)**

	Coal <sup>a</sup> Thousand Short Tons	Petroleum					Natural Gas <sup>f</sup> Billion Cubic Feet	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
		Distillate Fuel Oil <sup>b</sup> Thousand Barrels	Residual Fuel Oil <sup>c</sup> Thousand Barrels	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup> Thousand Short Tons	Total <sup>e</sup> Thousand Barrels			Wood <sup>h</sup>	Waste <sup>i</sup>	
<b>1973 Total</b>	<b>389,212</b>	<b>47,058</b>	<b>513,190</b>	<b>NA</b>	<b>507</b>	<b>562,781</b>	<b>3,660</b>	<b>NA</b>	<b>1</b>	<b>2</b>	<b>NA</b>
<b>1975 Total</b>	<b>405,962</b>	<b>38,907</b>	<b>467,221</b>	<b>NA</b>	<b>70</b>	<b>506,479</b>	<b>3,158</b>	<b>NA</b>	<b>(s)</b>	<b>2</b>	<b>NA</b>
<b>1980 Total</b>	<b>569,274</b>	<b>29,051</b>	<b>391,163</b>	<b>NA</b>	<b>179</b>	<b>421,110</b>	<b>3,682</b>	<b>NA</b>	<b>3</b>	<b>2</b>	<b>NA</b>
<b>1985 Total</b>	<b>693,841</b>	<b>14,635</b>	<b>158,779</b>	<b>NA</b>	<b>231</b>	<b>174,571</b>	<b>3,044</b>	<b>NA</b>	<b>8</b>	<b>7</b>	<b>NA</b>
<b>1990 Total</b> <sup>k</sup>	<b>781,301</b>	<b>16,394</b>	<b>183,285</b>	<b>25</b>	<b>1,008</b>	<b>204,745</b>	<b>3,147</b>	<b>6</b>	<b>106</b>	<b>180</b>	<b>(s)</b>
<b>1995 Total</b>	<b>847,854</b>	<b>18,066</b>	<b>88,895</b>	<b>441</b>	<b>2,452</b>	<b>119,663</b>	<b>4,094</b>	<b>18</b>	<b>106</b>	<b>282</b>	<b>2</b>
<b>1996 Total</b>	<b>894,400</b>	<b>18,472</b>	<b>98,795</b>	<b>567</b>	<b>2,467</b>	<b>130,168</b>	<b>3,660</b>	<b>16</b>	<b>117</b>	<b>280</b>	<b>2</b>
<b>1997 Total</b>	<b>919,009</b>	<b>18,646</b>	<b>112,423</b>	<b>130</b>	<b>3,201</b>	<b>147,202</b>	<b>3,903</b>	<b>14</b>	<b>117</b>	<b>292</b>	<b>1</b>
<b>1998 Total</b>	<b>934,126</b>	<b>23,166</b>	<b>165,875</b>	<b>411</b>	<b>3,999</b>	<b>209,447</b>	<b>4,416</b>	<b>23</b>	<b>125</b>	<b>287</b>	<b>2</b>
<b>1999 Total</b>	<b>937,888</b>	<b>23,875</b>	<b>151,921</b>	<b>514</b>	<b>3,607</b>	<b>194,345</b>	<b>4,644</b>	<b>14</b>	<b>125</b>	<b>290</b>	<b>1</b>
<b>2000 Total</b>	<b>982,713</b>	<b>29,722</b>	<b>138,047</b>	<b>403</b>	<b>3,155</b>	<b>183,946</b>	<b>5,014</b>	<b>19</b>	<b>126</b>	<b>294</b>	<b>1</b>
<b>2001 Total</b>	<b>961,523</b>	<b>29,056</b>	<b>159,150</b>	<b>374</b>	<b>3,308</b>	<b>205,119</b>	<b>5,142</b>	<b>9</b>	<b>116</b>	<b>205</b>	<b>109</b>
<b>2002 Total</b>	<b>975,251</b>	<b>21,810</b>	<b>104,577</b>	<b>1,243</b>	<b>5,705</b>	<b>156,154</b>	<b>5,408</b>	<b>25</b>	<b>141</b>	<b>224</b>	<b>137</b>
<b>2003 Total</b>	<b>1,003,036</b>	<b>27,441</b>	<b>137,361</b>	<b>1,937</b>	<b>5,719</b>	<b>195,336</b>	<b>4,909</b>	<b>30</b>	<b>156</b>	<b>216</b>	<b>136</b>
<b>2004 Total</b>	<b>1,012,459</b>	<b>18,793</b>	<b>138,831</b>	<b>2,511</b>	<b>7,135</b>	<b>195,809</b>	<b>5,075</b>	<b>27</b>	<b>150</b>	<b>206</b>	<b>131</b>
<b>2005 Total</b>	<b>1,033,567</b>	<b>19,450</b>	<b>138,337</b>	<b>2,591</b>	<b>7,877</b>	<b>199,760</b>	<b>5,485</b>	<b>24</b>	<b>166</b>	<b>205</b>	<b>116</b>
<b>2006 Total</b>	<b>1,022,802</b>	<b>12,578</b>	<b>56,347</b>	<b>1,783</b>	<b>6,905</b>	<b>105,235</b>	<b>5,891</b>	<b>28</b>	<b>163</b>	<b>216</b>	<b>117</b>
<b>2007 Total</b>	<b>1,041,346</b>	<b>15,135</b>	<b>62,072</b>	<b>2,496</b>	<b>5,523</b>	<b>107,316</b>	<b>6,502</b>	<b>27</b>	<b>165</b>	<b>221</b>	<b>117</b>
<b>2008 Total</b>	<b>1,036,891</b>	<b>12,318</b>	<b>37,222</b>	<b>2,608</b>	<b>5,000</b>	<b>77,149</b>	<b>6,342</b>	<b>23</b>	<b>159</b>	<b>242</b>	<b>122</b>
<b>2009 Total</b>	<b>929,692</b>	<b>11,848</b>	<b>27,768</b>	<b>2,110</b>	<b>4,485</b>	<b>64,151</b>	<b>6,567</b>	<b>21</b>	<b>160</b>	<b>244</b>	<b>115</b>
<b>2010</b>											
January	90,080	2,441	2,804	219	404	7,482	519	2	16	20	9
February	79,537	833	1,023	196	379	3,946	456	2	15	18	8
March	75,772	756	1,214	130	415	4,176	432	2	15	21	9
April	66,559	695	1,132	112	360	3,741	449	2	14	20	9
May	75,311	1,021	1,964	104	390	5,040	536	2	13	21	10
June	86,725	1,220	3,059	137	463	6,733	681	2	15	21	10
July	94,194	1,306	3,643	185	495	7,610	869	2	16	22	10
August	93,922	1,066	2,962	149	392	6,136	915	2	16	22	10
September	78,881	880	1,760	136	371	4,628	671	1	15	21	10
October	70,205	762	1,076	112	337	3,634	547	1	13	20	10
November	72,206	849	949	125	290	3,373	473	1	15	21	10
December	87,854	1,847	1,973	244	383	5,978	538	1	16	22	10
<b>Total</b>	<b>971,245</b>	<b>13,677</b>	<b>23,560</b>	<b>1,848</b>	<b>4,679</b>	<b>62,477</b>	<b>7,085</b>	<b>20</b>	<b>177</b>	<b>249</b>	<b>116</b>
<b>2011</b>											
January	89,305	1,215	1,653	223	495	5,564	512	1	15	20	9
February	72,814	832	973	117	365	3,750	457	1	14	18	8
March	71,671	822	1,093	121	440	4,234	457	1	13	22	10
April	66,411	936	1,296	104	282	3,747	500	2	11	21	10
May	72,742	891	1,199	103	295	3,670	551	2	12	22	10
June	83,360	946	1,236	129	364	4,134	679	2	14	22	10
July	93,388	1,135	1,518	158	452	5,069	912	2	15	23	11
August	91,340	788	1,311	107	389	4,152	894	2	15	22	10
September	75,820	756	940	126	369	3,670	661	2	13	21	10
October	68,779	686	911	119	288	3,155	553	2	12	21	10
November	66,260	693	883	129	233	2,871	518	2	12	21	10
December	72,633	811	899	128	309	3,382	584	2	15	22	10
<b>Total</b>	<b>924,523</b>	<b>10,513</b>	<b>13,914</b>	<b>1,564</b>	<b>4,281</b>	<b>47,398</b>	<b>7,279</b>	<b>20</b>	<b>160</b>	<b>256</b>	<b>117</b>
<b>2012</b>											
January	69,864	754	961	124	331	3,497	623	3	15	21	10
February	62,146	635	728	97	263	2,775	623	3	14	19	9
March	56,908	563	849	111	201	2,528	655	2	13	21	10
April	51,168	713	776	102	154	2,360	697	2	10	21	10
May	62,595	837	811	134	187	2,717	790	2	12	22	11
<b>5-Month Total</b>	<b>302,681</b>	<b>3,502</b>	<b>4,124</b>	<b>568</b>	<b>1,137</b>	<b>13,879</b>	<b>3,388</b>	<b>11</b>	<b>62</b>	<b>104</b>	<b>50</b>
<b>2011 5-Month Total</b>	<b>372,943</b>	<b>4,697</b>	<b>6,214</b>	<b>668</b>	<b>1,877</b>	<b>20,966</b>	<b>2,477</b>	<b>7</b>	<b>65</b>	<b>102</b>	<b>46</b>
<b>2010 5-Month Total</b>	<b>387,259</b>	<b>5,746</b>	<b>8,138</b>	<b>761</b>	<b>1,948</b>	<b>24,385</b>	<b>2,391</b>	<b>9</b>	<b>72</b>	<b>100</b>	<b>46</b>

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.  
<sup>b</sup> Fuel oil nos. 1, 2, and 4. For 1973-1979, data are for gas turbine and internal combustion plant use of petroleum. For 1980-2000, electric utility data also include small amounts of kerosene and jet fuel.  
<sup>c</sup> Fuel oil nos. 5 and 6. For 1973-1979, data are for steam plant use of petroleum. For 1980-2000, electric utility data also include a small amount of fuel oil no. 4.  
<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, and waste oil.  
<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.  
<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.  
<sup>g</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.  
<sup>h</sup> Wood and wood-derived fuels.  
<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).  
<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).  
<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.  
 NA=Not available. (s)=Less than 0.5 trillion Btu.  
 Notes: • Data are for fuels consumed to produce electricity. Data also include fuels consumed to produce useful thermal output at a small number of electric utility combined-heat-and-power (CHP) plants. • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.  
 Sources: See end of section.

**Table 7.3c Consumption of Selected Combustible Fuels for Electricity Generation: Commercial and Industrial Sectors** (Subset of Table 7.3a)

	Commercial Sector <sup>a</sup>				Industrial Sector <sup>b</sup>						
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
				Waste <sup>f</sup>					Wood <sup>h</sup>	Waste <sup>f</sup>	
	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu			
<b>1989 Total</b> .....	<b>414</b>	<b>1,165</b>	<b>18</b>	<b>9</b>	<b>9,707</b>	<b>8,482</b>	<b>444</b>	<b>83</b>	<b>267</b>	<b>15</b>	<b>37</b>
<b>1990 Total</b> .....	<b>417</b>	<b>953</b>	<b>28</b>	<b>15</b>	<b>10,740</b>	<b>13,103</b>	<b>517</b>	<b>104</b>	<b>335</b>	<b>16</b>	<b>36</b>
<b>1995 Total</b> .....	<b>569</b>	<b>649</b>	<b>43</b>	<b>21</b>	<b>12,171</b>	<b>12,265</b>	<b>601</b>	<b>114</b>	<b>373</b>	<b>13</b>	<b>40</b>
<b>1996 Total</b> .....	<b>656</b>	<b>645</b>	<b>42</b>	<b>31</b>	<b>12,153</b>	<b>13,813</b>	<b>610</b>	<b>143</b>	<b>394</b>	<b>13</b>	<b>35</b>
<b>1997 Total</b> .....	<b>630</b>	<b>790</b>	<b>39</b>	<b>34</b>	<b>12,311</b>	<b>11,723</b>	<b>623</b>	<b>105</b>	<b>367</b>	<b>14</b>	<b>36</b>
<b>1998 Total</b> .....	<b>440</b>	<b>802</b>	<b>41</b>	<b>32</b>	<b>11,728</b>	<b>12,392</b>	<b>625</b>	<b>102</b>	<b>349</b>	<b>13</b>	<b>35</b>
<b>1999 Total</b> .....	<b>481</b>	<b>931</b>	<b>39</b>	<b>33</b>	<b>11,432</b>	<b>12,595</b>	<b>639</b>	<b>112</b>	<b>364</b>	<b>8</b>	<b>39</b>
<b>2000 Total</b> .....	<b>514</b>	<b>823</b>	<b>37</b>	<b>26</b>	<b>11,706</b>	<b>10,459</b>	<b>640</b>	<b>107</b>	<b>369</b>	<b>10</b>	<b>45</b>
<b>2001 Total</b> .....	<b>532</b>	<b>1,023</b>	<b>36</b>	<b>15</b>	<b>10,636</b>	<b>10,530</b>	<b>654</b>	<b>88</b>	<b>370</b>	<b>7</b>	<b>44</b>
<b>2002 Total</b> .....	<b>477</b>	<b>834</b>	<b>33</b>	<b>18</b>	<b>11,855</b>	<b>11,608</b>	<b>685</b>	<b>106</b>	<b>464</b>	<b>15</b>	<b>43</b>
<b>2003 Total</b> .....	<b>582</b>	<b>894</b>	<b>38</b>	<b>19</b>	<b>10,440</b>	<b>10,424</b>	<b>668</b>	<b>127</b>	<b>362</b>	<b>13</b>	<b>46</b>
<b>2004 Total</b> .....	<b>377</b>	<b>766</b>	<b>33</b>	<b>19</b>	<b>7,687</b>	<b>6,919</b>	<b>566</b>	<b>108</b>	<b>194</b>	<b>5</b>	<b>41</b>
<b>2005 Total</b> .....	<b>377</b>	<b>585</b>	<b>34</b>	<b>20</b>	<b>7,504</b>	<b>6,440</b>	<b>518</b>	<b>85</b>	<b>189</b>	<b>5</b>	<b>46</b>
<b>2006 Total</b> .....	<b>347</b>	<b>333</b>	<b>35</b>	<b>21</b>	<b>7,408</b>	<b>5,066</b>	<b>536</b>	<b>87</b>	<b>187</b>	<b>3</b>	<b>45</b>
<b>2007 Total</b> .....	<b>361</b>	<b>258</b>	<b>34</b>	<b>19</b>	<b>5,089</b>	<b>5,041</b>	<b>554</b>	<b>88</b>	<b>188</b>	<b>4</b>	<b>41</b>
<b>2008 Total</b> .....	<b>369</b>	<b>166</b>	<b>33</b>	<b>20</b>	<b>5,075</b>	<b>3,617</b>	<b>520</b>	<b>73</b>	<b>179</b>	<b>5</b>	<b>39</b>
<b>2009 Total</b> .....	<b>317</b>	<b>190</b>	<b>34</b>	<b>23</b>	<b>4,674</b>	<b>3,328</b>	<b>520</b>	<b>62</b>	<b>160</b>	<b>4</b>	<b>42</b>
<b>2010</b>											
January .....	32	18	3	2	654	252	48	5	14	1	4
February .....	28	16	3	2	643	212	43	5	13	1	4
March .....	26	12	3	2	746	182	44	6	14	1	4
April .....	23	11	3	2	456	171	42	6	14	1	4
May .....	23	14	3	2	727	190	44	6	14	1	4
June .....	27	13	3	2	643	204	47	6	14	1	5
July .....	30	26	4	2	769	213	50	6	15	1	5
August .....	29	15	4	2	835	207	53	7	15	1	5
September .....	26	13	3	2	666	171	48	6	15	1	5
October .....	23	11	3	2	690	195	44	5	14	1	5
November .....	21	7	3	2	529	208	43	6	14	1	4
December .....	26	15	4	2	765	217	48	6	15	1	5
<b>Total</b> .....	<b>314</b>	<b>172</b>	<b>39</b>	<b>24</b>	<b>8,125</b>	<b>2,422</b>	<b>555</b>	<b>70</b>	<b>172</b>	<b>8</b>	<b>55</b>
<b>2011</b>											
January .....	30	14	3	2	771	223	49	6	15	1	2
February .....	28	9	3	2	663	160	44	5	13	1	2
March .....	28	8	3	2	641	179	44	6	14	1	3
April .....	22	6	3	2	437	171	45	6	14	1	3
May .....	23	7	3	2	746	143	48	5	13	1	3
June .....	24	9	3	2	688	173	47	6	15	1	3
July .....	28	15	4	2	798	181	50	7	15	1	3
August .....	26	9	3	2	811	180	50	6	15	1	3
September .....	23	8	3	2	769	183	46	6	14	1	2
October .....	20	11	3	2	725	145	44	6	14	1	3
November .....	20	8	3	2	509	124	47	6	15	1	3
December .....	24	8	3	2	533	161	51	6	16	1	3
<b>Total</b> .....	<b>297</b>	<b>112</b>	<b>38</b>	<b>24</b>	<b>8,091</b>	<b>2,023</b>	<b>564</b>	<b>71</b>	<b>173</b>	<b>8</b>	<b>31</b>
<b>2012</b>											
January .....	25	7	3	2	706	460	50	6	15	1	2
February .....	25	5	3	2	631	299	47	6	15	1	2
March .....	22	6	3	2	634	291	46	7	14	1	2
April .....	19	8	3	2	387	306	44	7	15	1	2
May .....	20	8	3	2	342	281	51	7	16	1	3
<b>5-Month Total</b> .....	<b>112</b>	<b>34</b>	<b>14</b>	<b>10</b>	<b>2,700</b>	<b>1,637</b>	<b>238</b>	<b>32</b>	<b>75</b>	<b>3</b>	<b>12</b>
<b>2011 5-Month Total</b> .....	<b>132</b>	<b>45</b>	<b>15</b>	<b>9</b>	<b>3,259</b>	<b>877</b>	<b>230</b>	<b>28</b>	<b>69</b>	<b>3</b>	<b>13</b>
<b>2010 5-Month Total</b> .....	<b>132</b>	<b>71</b>	<b>14</b>	<b>10</b>	<b>3,227</b>	<b>1,006</b>	<b>221</b>	<b>28</b>	<b>69</b>	<b>3</b>	<b>21</b>

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, and waste oil.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).


Notes: • Data are for fuels consumed to produce electricity. Through 1988, data are not available. • See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1989.


Sources: • **1989-1997:** U.S. Energy Information Administration (EIA), Form EIA-867, "Annual Nonutility Power Producer Report." • **1998-2000:** EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001-2003:** EIA, Form EIA-906, "Power Plant Report." • **2004-2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."

**Figure 7.4 Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output**


Coal by Sector, 1989-2011




Petroleum by Sector, 1989-2011




Natural Gas by Sector, 1989-2011




Other Gases<sup>b</sup> by Sector, 1989-2011



Wood by Sector, 1989-2011



Waste by Sector, 1989-2011



<sup>a</sup> Includes commercial sector.

<sup>b</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.  
Sources: Tables 7.4a–7.4c.



**Table 7.4a Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output: Total (All Sectors)** (Sum of Tables 7.4b and 7.4c)

	Coal <sup>a</sup> Thousand Short Tons	Petroleum					Natural Gas <sup>f</sup> Billion Cubic Feet	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
		Distillate Fuel Oil <sup>b</sup> Thousand Barrels	Residual Fuel Oil <sup>c</sup> Thousand Barrels	Other Liquids <sup>d</sup> Thousand Barrels	Petroleum Coke <sup>e</sup> Thousand Short Tons	Total <sup>e</sup> Thousand Barrels			Wood <sup>h</sup> Trillion Btu	Waste <sup>i</sup> Trillion Btu	
<b>1973 Total</b>	389,212	47,058	513,190	NA	507	562,781	3,660	NA	1	2	NA
<b>1975 Total</b>	405,962	38,907	467,221	NA	70	506,479	3,158	NA	0	2	NA
<b>1980 Total</b>	569,274	29,051	391,163	NA	179	421,110	3,682	NA	3	2	NA
<b>1985 Total</b>	693,841	14,635	158,779	NA	231	174,571	3,044	NA	8	7	NA
<b>1990 Total</b> <sup>k</sup>	811,538	20,194	209,081	1,332	2,832	244,765	4,346	288	1,256	257	86
<b>1995 Total</b>	881,012	21,697	112,168	1,322	4,590	158,140	5,572	313	1,382	374	97
<b>1996 Total</b>	928,015	22,444	124,607	2,468	4,596	172,499	5,178	346	1,389	392	91
<b>1997 Total</b>	952,955	22,893	134,623	526	6,095	188,517	5,433	307	1,397	407	103
<b>1998 Total</b>	966,615	30,006	189,267	1,230	6,196	251,486	6,030	334	1,349	404	95
<b>1999 Total</b>	970,175	30,616	172,319	1,812	5,989	234,694	6,305	350	1,352	400	101
<b>2000 Total</b>	1,015,398	34,572	156,673	2,904	4,669	217,494	6,677	356	1,380	401	109
<b>2001 Total</b>	991,635	33,724	177,137	1,418	4,532	234,940	6,731	263	1,182	263	229
<b>2002 Total</b>	1,005,144	24,749	118,637	3,257	7,353	183,409	6,986	278	1,287	289	252
<b>2003 Total</b>	1,031,778	31,825	152,859	4,576	7,067	224,593	6,337	294	1,266	293	262
<b>2004 Total</b>	1,044,798	23,520	157,478	4,764	8,721	229,364	6,727	353	1,360	282	254
<b>2005 Total</b>	1,065,281	24,446	156,915	4,270	9,113	231,193	7,021	348	1,353	289	237
<b>2006 Total</b>	1,053,783	14,655	69,846	3,396	8,622	131,005	7,404	341	1,399	300	247
<b>2007 Total</b>	1,069,606	17,042	74,616	4,237	7,299	132,389	7,962	329	1,336	304	239
<b>2008 Total</b>	1,064,503	14,137	43,477	3,765	6,314	92,948	7,689	300	1,263	328	212
<b>2009 Total</b>	955,190	14,800	33,672	3,218	5,828	80,830	7,938	259	1,137	333	228
<b>2010</b>											
January	92,738	2,643	3,212	338	525	8,819	643	21	103	29	18
February	82,029	978	1,397	286	497	5,143	566	19	96	26	17
March	78,383	866	1,439	207	522	5,124	547	23	103	30	19
April	69,179	837	1,355	176	458	4,656	556	22	98	29	19
May	77,725	1,111	2,221	176	500	6,005	647	23	98	29	20
June	89,063	1,295	3,291	204	586	7,721	796	23	101	29	21
July	96,783	1,455	3,921	244	613	8,684	997	22	105	29	21
August	96,593	1,185	3,190	206	510	7,132	1,047	23	106	29	21
September	81,250	961	2,006	191	475	5,534	791	22	103	27	20
October	72,571	871	1,370	186	453	4,693	662	20	101	29	20
November	74,496	1,017	1,212	204	414	4,503	586	21	102	30	20
December	90,600	2,029	2,332	361	499	7,218	665	23	109	30	21
<b>Total</b>	<b>1,001,411</b>	<b>15,247</b>	<b>26,944</b>	<b>2,777</b>	<b>6,053</b>	<b>75,231</b>	<b>8,502</b>	<b>262</b>	<b>1,226</b>	<b>346</b>	<b>237</b>
<b>2011</b>											
January	92,180	1,302	2,014	286	602	6,611	639	22	108	29	15
February	75,364	934	1,197	161	490	4,742	568	20	96	26	14
March	74,254	890	1,327	175	573	5,256	570	24	100	29	16
April	68,631	1,020	1,541	170	409	4,774	615	23	95	27	15
May	75,353	962	1,405	147	434	4,683	671	23	94	29	16
June	85,880	1,013	1,452	188	475	5,030	794	24	104	29	17
July	96,079	1,208	1,739	206	566	5,982	1,037	24	105	30	17
August	93,974	851	1,523	165	498	5,029	1,020	24	103	30	16
September	78,352	816	1,129	225	465	4,497	777	23	101	29	15
October	71,305	762	1,162	152	388	4,018	666	25	97	29	15
November	68,515	748	1,082	164	358	3,784	636	23	100	30	15
December	75,036	868	1,109	162	408	4,181	713	25	109	31	17
<b>Total</b>	<b>954,925</b>	<b>11,374</b>	<b>16,678</b>	<b>2,203</b>	<b>5,666</b>	<b>58,586</b>	<b>8,707</b>	<b>281</b>	<b>1,214</b>	<b>349</b>	<b>189</b>
<b>2012</b>											
January	72,487	817	1,177	171	487	4,598	753	26	107	29	16
February	64,477	674	882	140	388	3,637	743	26	99	27	15
March	59,263	609	985	185	372	3,642	775	26	95	29	16
April	53,057	764	908	177	305	3,376	814	25	90	29	15
May	64,624	888	977	174	338	3,730	914	25	98	30	16
<b>5-Month Total</b>	<b>313,909</b>	<b>3,753</b>	<b>4,929</b>	<b>848</b>	<b>1,891</b>	<b>18,983</b>	<b>3,999</b>	<b>129</b>	<b>490</b>	<b>144</b>	<b>78</b>
<b>2011 5-Month Total</b>	<b>385,784</b>	<b>5,109</b>	<b>7,483</b>	<b>940</b>	<b>2,507</b>	<b>26,066</b>	<b>3,063</b>	<b>112</b>	<b>494</b>	<b>140</b>	<b>76</b>
<b>2010 5-Month Total</b>	<b>400,054</b>	<b>6,434</b>	<b>9,623</b>	<b>1,183</b>	<b>2,501</b>	<b>29,747</b>	<b>2,959</b>	<b>109</b>	<b>497</b>	<b>142</b>	<b>94</b>

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>b</sup> Fuel oil nos. 1, 2, and 4. Through 2000, electric utility data also include small amounts of kerosene and jet fuel.

<sup>c</sup> Fuel oil nos. 5 and 6. Through 2000, electric utility data also include a small amount of fuel oil no. 4.

<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, and waste oil.

<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.

<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>g</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes

non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities, independent power producers, commercial plants, and industrial plants.

NA=Not available.

Notes: • Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.

Sources: See sources for Tables 7.4b and 7.4c.

**Table 7.4b Consumption of Combustible Fuels for Electricity Generation and Useful Thermal Output: Electric Power Sector** (Subset of Table 7.4a)

	Coal <sup>a</sup> Thousand Short Tons	Petroleum					Natural Gas <sup>f</sup> Billion Cubic Feet	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
		Distillate Fuel Oil <sup>b</sup> Thousand Barrels	Residual Fuel Oil <sup>c</sup> Thousand Barrels	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup> Thousand Short Tons	Total <sup>e</sup> Thousand Barrels			Wood <sup>h</sup>	Waste <sup>i</sup>	
<b>1973 Total</b> .....	<b>389,212</b>	<b>47,058</b>	<b>513,190</b>	<b>NA</b>	<b>507</b>	<b>562,781</b>	<b>3,660</b>	<b>NA</b>	<b>1</b>	<b>2</b>	<b>NA</b>
<b>1975 Total</b> .....	<b>405,962</b>	<b>38,907</b>	<b>467,221</b>	<b>NA</b>	<b>70</b>	<b>506,479</b>	<b>3,158</b>	<b>NA</b>	<b>(s)</b>	<b>2</b>	<b>NA</b>
<b>1980 Total</b> .....	<b>569,274</b>	<b>29,051</b>	<b>391,163</b>	<b>NA</b>	<b>179</b>	<b>421,110</b>	<b>3,682</b>	<b>NA</b>	<b>3</b>	<b>2</b>	<b>NA</b>
<b>1985 Total</b> .....	<b>693,841</b>	<b>14,635</b>	<b>158,779</b>	<b>NA</b>	<b>231</b>	<b>174,571</b>	<b>3,044</b>	<b>NA</b>	<b>8</b>	<b>7</b>	<b>NA</b>
<b>1990 Total</b> <sup>k</sup> .....	<b>782,567</b>	<b>16,567</b>	<b>184,915</b>	<b>26</b>	<b>1,008</b>	<b>206,550</b>	<b>3,245</b>	<b>11</b>	<b>129</b>	<b>188</b>	<b>(s)</b>
<b>1995 Total</b> .....	<b>850,230</b>	<b>18,553</b>	<b>90,023</b>	<b>499</b>	<b>2,674</b>	<b>122,447</b>	<b>4,237</b>	<b>24</b>	<b>125</b>	<b>296</b>	<b>2</b>
<b>1996 Total</b> .....	<b>896,921</b>	<b>18,780</b>	<b>99,951</b>	<b>653</b>	<b>2,642</b>	<b>132,593</b>	<b>3,807</b>	<b>20</b>	<b>138</b>	<b>300</b>	<b>2</b>
<b>1997 Total</b> .....	<b>921,364</b>	<b>18,989</b>	<b>113,669</b>	<b>152</b>	<b>3,372</b>	<b>149,668</b>	<b>4,065</b>	<b>24</b>	<b>137</b>	<b>309</b>	<b>1</b>
<b>1998 Total</b> .....	<b>936,619</b>	<b>23,300</b>	<b>166,528</b>	<b>431</b>	<b>4,102</b>	<b>210,769</b>	<b>4,588</b>	<b>29</b>	<b>137</b>	<b>308</b>	<b>2</b>
<b>1999 Total</b> .....	<b>940,922</b>	<b>24,058</b>	<b>152,493</b>	<b>544</b>	<b>3,735</b>	<b>195,769</b>	<b>4,820</b>	<b>19</b>	<b>138</b>	<b>315</b>	<b>1</b>
<b>2000 Total</b> .....	<b>985,821</b>	<b>30,016</b>	<b>138,513</b>	<b>454</b>	<b>3,275</b>	<b>185,358</b>	<b>5,206</b>	<b>25</b>	<b>134</b>	<b>318</b>	<b>1</b>
<b>2001 Total</b> .....	<b>964,433</b>	<b>29,274</b>	<b>159,504</b>	<b>377</b>	<b>3,427</b>	<b>206,291</b>	<b>5,342</b>	<b>15</b>	<b>126</b>	<b>211</b>	<b>113</b>
<b>2002 Total</b> .....	<b>977,507</b>	<b>21,876</b>	<b>104,773</b>	<b>1,267</b>	<b>5,816</b>	<b>156,996</b>	<b>5,672</b>	<b>33</b>	<b>150</b>	<b>230</b>	<b>143</b>
<b>2003 Total</b> .....	<b>1,005,116</b>	<b>27,632</b>	<b>138,279</b>	<b>2,026</b>	<b>5,799</b>	<b>196,932</b>	<b>5,135</b>	<b>41</b>	<b>167</b>	<b>230</b>	<b>140</b>
<b>2004 Total</b> .....	<b>1,016,268</b>	<b>19,107</b>	<b>139,816</b>	<b>2,713</b>	<b>7,372</b>	<b>198,498</b>	<b>5,464</b>	<b>58</b>	<b>165</b>	<b>223</b>	<b>138</b>
<b>2005 Total</b> .....	<b>1,037,485</b>	<b>19,675</b>	<b>139,409</b>	<b>2,685</b>	<b>8,083</b>	<b>202,184</b>	<b>5,869</b>	<b>84</b>	<b>185</b>	<b>221</b>	<b>123</b>
<b>2006 Total</b> .....	<b>1,026,636</b>	<b>12,646</b>	<b>57,345</b>	<b>1,870</b>	<b>7,101</b>	<b>107,365</b>	<b>6,222</b>	<b>65</b>	<b>182</b>	<b>231</b>	<b>125</b>
<b>2007 Total</b> .....	<b>1,045,141</b>	<b>15,327</b>	<b>63,086</b>	<b>2,594</b>	<b>5,685</b>	<b>109,431</b>	<b>6,841</b>	<b>61</b>	<b>186</b>	<b>237</b>	<b>124</b>
<b>2008 Total</b> .....	<b>1,040,580</b>	<b>12,547</b>	<b>38,241</b>	<b>2,670</b>	<b>5,119</b>	<b>79,056</b>	<b>6,668</b>	<b>61</b>	<b>177</b>	<b>258</b>	<b>131</b>
<b>2009 Total</b> .....	<b>933,627</b>	<b>12,035</b>	<b>28,782</b>	<b>2,210</b>	<b>4,611</b>	<b>66,081</b>	<b>6,873</b>	<b>55</b>	<b>180</b>	<b>261</b>	<b>124</b>
<b>2010</b> .....	<b>90,452</b>	<b>2,459</b>	<b>2,887</b>	<b>222</b>	<b>413</b>	<b>7,636</b>	<b>546</b>	<b>5</b>	<b>17</b>	<b>21</b>	<b>10</b>
February .....	79,884	851	1,061	219	389	4,076	480	4	16	20	9
March .....	76,110	759	1,256	131	427	4,281	457	5	16	22	10
April .....	66,842	699	1,214	112	369	3,871	471	5	15	21	10
May .....	75,597	1,023	2,055	104	400	5,181	560	5	14	22	10
June .....	87,030	1,222	3,147	137	471	6,860	706	5	16	23	11
July .....	94,519	1,309	3,730	185	503	7,742	897	5	17	23	11
August .....	94,247	1,068	3,051	149	394	6,236	943	4	18	23	11
September .....	79,176	883	1,845	136	372	4,726	697	4	16	22	10
October .....	70,492	772	1,161	112	346	3,773	570	3	15	22	10
November .....	72,514	890	1,035	126	301	3,557	497	4	16	23	10
December .....	88,189	1,854	2,062	245	391	6,118	564	4	17	23	11
<b>Total</b> .....	<b>975,052</b>	<b>13,790</b>	<b>24,503</b>	<b>1,877</b>	<b>4,777</b>	<b>64,055</b>	<b>7,387</b>	<b>52</b>	<b>196</b>	<b>264</b>	<b>124</b>
<b>2011</b> .....	<b>89,682</b>	<b>1,225</b>	<b>1,759</b>	<b>224</b>	<b>500</b>	<b>5,707</b>	<b>542</b>	<b>4</b>	<b>16</b>	<b>21</b>	<b>10</b>
February .....	73,156	858	1,020	117	374	3,866	482	4	15	20	9
March .....	72,009	827	1,164	121	451	4,364	483	5	15	23	11
April .....	66,741	940	1,378	104	291	3,879	526	4	12	22	10
May .....	73,100	894	1,279	103	306	3,807	578	4	13	22	11
June .....	83,700	950	1,316	129	374	4,265	705	5	15	23	11
July .....	93,736	1,139	1,603	158	462	5,211	942	5	16	24	11
August .....	91,667	793	1,400	107	400	4,299	923	5	16	23	11
September .....	76,131	760	1,027	127	380	3,812	686	5	15	22	10
October .....	69,109	690	995	119	295	3,280	578	5	13	23	10
November .....	66,557	697	962	131	242	2,999	543	5	13	23	10
December .....	72,971	814	973	128	319	3,512	612	5	16	23	11
<b>Total</b> .....	<b>928,558</b>	<b>10,586</b>	<b>14,876</b>	<b>1,568</b>	<b>4,394</b>	<b>49,003</b>	<b>7,602</b>	<b>56</b>	<b>175</b>	<b>269</b>	<b>126</b>
<b>2012</b> .....	<b>70,231</b>	<b>758</b>	<b>1,054</b>	<b>125</b>	<b>342</b>	<b>3,649</b>	<b>651</b>	<b>6</b>	<b>16</b>	<b>22</b>	<b>11</b>
February .....	62,450	638	790	97	274	2,895	649	6	15	21	10
March .....	57,211	567	898	111	212	2,636	680	5	14	23	11
April .....	51,357	717	838	102	163	2,472	724	4	11	22	11
May .....	62,827	842	892	134	198	2,860	819	5	13	23	11
<b>5-Month Total</b> .....	<b>304,076</b>	<b>3,523</b>	<b>4,471</b>	<b>568</b>	<b>1,190</b>	<b>14,511</b>	<b>3,523</b>	<b>26</b>	<b>69</b>	<b>111</b>	<b>55</b>
<b>2011 5-Month Total</b> .....	<b>374,687</b>	<b>4,744</b>	<b>6,600</b>	<b>669</b>	<b>1,922</b>	<b>21,624</b>	<b>2,611</b>	<b>21</b>	<b>71</b>	<b>108</b>	<b>50</b>
<b>2010 5-Month Total</b> .....	<b>388,884</b>	<b>5,791</b>	<b>8,472</b>	<b>789</b>	<b>1,998</b>	<b>25,043</b>	<b>2,513</b>	<b>23</b>	<b>79</b>	<b>107</b>	<b>50</b>

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal symfuel.  
<sup>b</sup> Fuel oil nos. 1, 2, and 4. Through 2000, electric utility data also include small amounts of kerosene and jet fuel.  
<sup>c</sup> Fuel oil nos. 5 and 6. Through 2000, electric utility data also include a small amount of fuel oil no. 4.  
<sup>d</sup> Jet fuel, kerosene, other petroleum liquids, and waste oil.  
<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.  
<sup>f</sup> Natural gas, plus a small amount of supplemental gaseous fuels.  
<sup>g</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.  
<sup>h</sup> Wood and wood-derived fuels.  
<sup>i</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).  
<sup>j</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).  
<sup>k</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.  
 NA=Not available. (s)=Less than 0.5 trillion Btu.  
 Notes: • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.  
 Sources: See end of section.

**Table 7.4c Consumption of Selected Combustible Fuels for Electricity Generation and Useful Thermal Output: Commercial and Industrial Sectors** (Subset of Table 7.4a)

	Commercial Sector <sup>a</sup>				Industrial Sector <sup>b</sup>						
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Biomass	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Other Gases <sup>g</sup>	Biomass		Other <sup>i</sup>
				Waste <sup>f</sup>					Wood <sup>h</sup>	Waste <sup>f</sup>	
	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu	Thousand Short Tons	Thousand Barrels	Billion Cubic Feet	Trillion Btu			
<b>1989 Total</b> .....	1,125	1,967	30	22	24,867	25,444	914	195	926	35	85
<b>1990 Total</b> .....	1,191	2,056	46	28	27,781	36,159	1,055	275	1,125	41	86
<b>1995 Total</b> .....	1,419	1,245	78	40	29,363	34,448	1,258	290	1,255	38	95
<b>1996 Total</b> .....	1,660	1,246	82	53	29,434	38,661	1,289	325	1,249	39	89
<b>1997 Total</b> .....	1,738	1,584	87	58	29,853	37,265	1,282	283	1,259	41	102
<b>1998 Total</b> .....	1,443	1,807	87	54	28,553	38,910	1,355	305	1,211	42	93
<b>1999 Total</b> .....	1,490	1,613	84	54	27,763	37,312	1,401	331	1,213	31	99
<b>2000 Total</b> .....	1,547	1,615	85	47	28,031	30,520	1,386	331	1,244	35	108
<b>2001 Total</b> .....	1,448	1,832	79	25	25,755	26,817	1,310	248	1,054	27	101
<b>2002 Total</b> .....	1,405	1,250	74	26	26,232	25,163	1,240	245	1,136	34	92
<b>2003 Total</b> .....	1,816	1,449	58	29	24,846	26,212	1,144	253	1,097	34	103
<b>2004 Total</b> .....	1,917	2,009	72	34	26,613	28,857	1,191	295	1,193	24	94
<b>2005 Total</b> .....	1,922	1,630	68	34	25,875	27,380	1,084	264	1,166	34	94
<b>2006 Total</b> .....	1,886	935	68	36	25,262	22,706	1,115	277	1,216	33	102
<b>2007 Total</b> .....	1,927	752	70	31	22,537	22,207	1,050	268	1,148	36	98
<b>2008 Total</b> .....	2,021	671	66	34	21,902	13,222	955	239	1,084	35	60
<b>2009 Total</b> .....	1,798	521	76	36	19,766	14,228	990	204	955	35	82
<b>2010</b>											
January .....	193	55	7	3	2,094	1,128	90	17	86	4	6
February .....	167	47	7	3	1,978	1,021	80	15	79	4	7
March .....	149	26	7	3	2,124	817	84	18	86	4	7
April .....	117	24	6	3	2,220	761	79	18	83	5	7
May .....	118	28	6	4	2,010	796	82	18	83	3	7
June .....	135	26	6	3	1,898	835	84	18	85	3	8
July .....	142	59	8	3	2,122	883	91	17	88	3	8
August .....	152	46	9	3	2,194	849	95	19	88	3	8
September .....	133	27	7	3	1,941	780	87	18	87	3	8
October .....	121	21	7	3	1,958	899	84	17	86	5	8
November .....	128	22	7	3	1,854	924	82	17	86	5	8
December .....	165	55	8	3	2,246	1,045	92	19	91	4	8
<b>Total</b> .....	<b>1,720</b>	<b>437</b>	<b>86</b>	<b>36</b>	<b>24,638</b>	<b>10,740</b>	<b>1,029</b>	<b>210</b>	<b>1,029</b>	<b>47</b>	<b>91</b>
<b>2011</b>											
January .....	178	45	8	3	2,320	858	89	18	91	4	3
February .....	165	24	7	3	2,044	852	79	16	81	4	3
March .....	158	29	6	3	2,088	862	81	20	86	3	3
April .....	124	15	6	3	1,767	880	82	19	83	3	3
May .....	128	17	7	3	2,126	859	87	18	81	4	4
June .....	124	22	6	3	2,056	743	83	19	89	4	4
July .....	134	35	7	3	2,208	737	88	19	89	4	4
August .....	124	20	7	3	2,182	710	89	19	86	4	3
September .....	121	15	6	3	2,100	670	84	18	87	4	3
October .....	116	19	6	3	2,080	719	81	20	84	4	3
November .....	123	18	7	3	1,835	767	86	19	87	4	3
December .....	138	23	8	3	1,927	646	94	20	93	4	4
<b>Total</b> .....	<b>1,633</b>	<b>282</b>	<b>81</b>	<b>36</b>	<b>24,733</b>	<b>9,302</b>	<b>1,024</b>	<b>224</b>	<b>1,037</b>	<b>44</b>	<b>40</b>
<b>2012</b>											
January .....	154	30	7	3	2,102	919	94	21	91	4	3
February .....	137	16	7	3	1,890	726	87	20	84	4	3
March .....	131	17	6	3	1,921	989	89	21	81	3	3
April .....	111	14	6	3	1,589	891	84	20	79	4	3
May .....	117	15	6	3	1,680	855	90	21	85	4	4
<b>5-Month Total</b> .....	<b>650</b>	<b>92</b>	<b>32</b>	<b>14</b>	<b>9,183</b>	<b>4,380</b>	<b>444</b>	<b>103</b>	<b>421</b>	<b>18</b>	<b>16</b>
<b>2011 5-Month Total</b> .....	<b>752</b>	<b>130</b>	<b>33</b>	<b>14</b>	<b>10,344</b>	<b>4,311</b>	<b>419</b>	<b>91</b>	<b>422</b>	<b>18</b>	<b>17</b>
<b>2010 5-Month Total</b> .....	<b>745</b>	<b>180</b>	<b>32</b>	<b>15</b>	<b>10,426</b>	<b>4,524</b>	<b>413</b>	<b>85</b>	<b>417</b>	<b>20</b>	<b>35</b>

<sup>a</sup> Commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>b</sup> Industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>c</sup> Anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and coal synfuel.

<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, and waste oil.

<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>g</sup> Blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels.

<sup>h</sup> Wood and wood-derived fuels.

<sup>i</sup> Batteries, chemicals, hydrogen, pitch, purchased steam, sulfur, miscellaneous technologies, and, beginning in 2001, non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).


Notes: • See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1989.


Sources: • **1989-1997:** U.S. Energy Information Administration (EIA), Form EIA-867, "Annual Nonutility Power Producer Report." • **1998-2000:** EIA, Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001-2003:** EIA, Form EIA-906, "Power Plant Report." • **2004-2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."

**Figure 7.5 Stocks of Coal and Petroleum: Electric Power Sector**


Coal, 1973-2011




Coal, Monthly




Total Petroleum, 1973-2011




Total Petroleum, Monthly



Coal and Petroleum Stocks, 1973-2011



Petroleum by Major Type, End of Month



<sup>a</sup> Converted from short tons to barrels by multiplying by 5.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.  
 Sources: Tables 7.5, A1, and A5 (column 6).

**Table 7.5 Stocks of Coal and Petroleum: Electric Power Sector**


	Coal <sup>a</sup>	Petroleum				Total <sup>e</sup>
		Distillate Fuel Oil <sup>b</sup>	Residual Fuel Oil <sup>c</sup>	Other Liquids <sup>d</sup>	Petroleum Coke <sup>e</sup>	
		Thousand Barrels			Thousand Short Tons	
1973 Year .....	86,967	10,095	79,121	NA	312	90,776
1975 Year .....	110,724	16,432	108,825	NA	31	125,413
1980 Year .....	183,010	30,023	105,351	NA	52	135,635
1985 Year .....	156,376	16,386	57,304	NA	49	73,933
1990 Year .....	156,166	16,471	67,030	NA	94	83,970
1995 Year .....	126,304	15,392	35,102	NA	65	50,821
1996 Year .....	114,623	15,216	32,473	NA	91	48,146
1997 Year .....	98,826	15,456	33,336	NA	469	51,138
1998 Year .....	120,501	16,343	37,451	NA	559	56,591
1999 Year <sup>f</sup> .....	141,604	17,995	34,256	NA	372	54,109
2000 Year .....	102,296	15,127	24,748	NA	211	40,932
2001 Year .....	138,496	20,486	34,594	NA	390	57,031
2002 Year .....	141,714	17,413	25,723	800	1,711	52,490
2003 Year .....	121,567	19,153	25,820	779	1,484	53,170
2004 Year .....	106,669	19,275	26,596	879	937	51,434
2005 Year .....	101,137	18,778	27,624	1,012	530	50,062
2006 Year .....	140,964	18,013	28,823	1,380	674	51,583
2007 Year .....	151,221	18,395	24,136	1,902	554	47,203
2008 Year .....	161,589	17,761	21,088	1,955	739	44,498
2009 Year .....	189,467	17,886	19,068	2,257	1,394	46,181
<b>2010</b> January .....	178,091	17,193	18,035	2,198	1,406	44,454
February .....	171,026	17,409	18,532	2,222	1,280	44,562
March .....	177,742	17,353	18,679	2,105	1,240	44,337
April .....	189,260	17,295	18,353	2,228	1,243	44,090
May .....	191,669	17,185	17,935	2,235	1,188	43,294
June .....	181,490	17,040	17,411	2,172	1,117	42,209
July .....	169,504	16,917	16,441	2,268	1,046	40,856
August .....	159,987	16,737	16,288	2,292	1,112	40,878
September .....	163,776	16,608	17,269	2,330	1,158	41,996
October .....	175,686	16,698	17,781	2,377	1,197	42,840
November .....	183,389	17,024	17,492	2,410	1,098	42,414
<b>December .....</b>	<b>174,917</b>	<b>16,758</b>	<b>16,629</b>	<b>2,319</b>	<b>1,019</b>	<b>40,800</b>
<b>2011</b> January .....	164,840	16,673	16,061	2,383	801	39,123
February .....	161,439	16,654	15,575	2,435	707	38,200
March .....	166,737	16,498	15,393	2,437	489	36,776
April .....	173,999	16,301	15,180	2,460	522	36,551
May .....	174,619	16,195	15,235	2,447	548	36,617
June .....	165,707	16,779	16,356	2,564	491	38,152
July .....	147,967	16,550	16,090	2,561	462	37,510
August .....	139,225	16,583	15,804	2,581	435	37,144
September .....	144,438	16,691	15,654	2,593	389	36,884
October .....	156,906	16,955	15,942	2,640	413	37,601
November .....	168,354	17,148	15,832	2,677	453	37,923
<b>December .....</b>	<b>175,100</b>	<b>17,101</b>	<b>15,469</b>	<b>2,690</b>	<b>470</b>	<b>37,608</b>
<b>2012</b> January .....	181,621	17,179	15,248	2,718	394	37,116
February .....	186,958	17,024	15,174	2,766	357	36,749
March .....	196,391	16,929	15,326	2,792	405	37,073
April .....	203,394	16,876	15,144	2,834	368	36,697
May .....	202,816	16,801	14,809	2,862	301	35,975

<sup>a</sup> Anthracite, bituminous coal, subbituminous coal, and lignite.  
<sup>b</sup> Fuel oil nos. 1, 2 and 4. For 1973-1979, data are for gas turbine and internal combustion plant stocks of petroleum. For 1980-2000, electric utility data also include small amounts of kerosene and jet fuel.  
<sup>c</sup> Fuel oil nos. 5 and 6. For 1973-1979, data are for steam plant stocks of petroleum. For 1980-2000, electric utility data also include a small amount of fuel oil no. 4.  
<sup>d</sup> Jet fuel and kerosene. Through 2003, data also include a small amount of waste oil.  
<sup>e</sup> Petroleum coke is converted from short tons to barrels by multiplying by 5.  
<sup>f</sup> Through 1998, data are for electric utilities only. Beginning in 1999, data are for electric utilities and independent power producers.  
 NA=Not available.  
 Notes: • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Stocks


are at end of period. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.  
 Sources: • **1973-September 1977:** Federal Power Commission, Form FPC-4, "Monthly Power Plant Report." • **October 1977-1981:** Federal Energy Regulatory Commission, Form FPC-4, "Monthly Power Plant Report." • **1982-1988:** U.S. Energy Information Administration (EIA), Form EIA-759, "Monthly Power Plant Report." • **1989-1997:** EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-867, "Annual Nonutility Power Producer Report." • **1998-2000:** EIA, Form EIA-759, "Monthly Power Plant Report," and Form EIA-860B, "Annual Electric Generator Report—Nonutility." • **2001-2003:** EIA, Form EIA-906, "Power Plant Report." • **2004-2007:** EIA, Form EIA-906, "Power Plant Report," and Form EIA-920, "Combined Heat and Power Plant Report." • **2008 forward:** EIA, Form EIA-923, "Power Plant Operations Report."

**Figure 7.6 Electricity End Use**  
(Billion Kilowatthours)


Electricity End Use Overview, 1989-2011




Retail Sales<sup>a</sup> by Sector, May 2012




Retail Sales<sup>a</sup> by Sector, 1973-2011




Retail Sales<sup>a</sup> by Sector, Monthly



Retail Sales<sup>a</sup> Total, January-May



Retail Sales<sup>a</sup> Total, Monthly



<sup>a</sup> Electricity retail sales to ultimate customers reported by utilities and other energy service providers.  
<sup>b</sup> See "Direct Use" in Glossary.  
<sup>c</sup> Commercial sector, including public street and highway lighting, inter

departmental sales, and other sales to public authorities.  
<sup>d</sup> Transportation sector, including sales to railroads and railways.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#electricity>.  
 Source: Table 7.6.

**Table 7.6 Electricity End Use**  
(Million Kilowatthours)

	Retail Sales <sup>a</sup>					Direct Use <sup>f</sup>	Total End Use <sup>g</sup>	Discontinued Retail Sales Series	
	Residential	Commercial <sup>b</sup>	Industrial <sup>c</sup>	Transportation <sup>d</sup>	Total Retail Sales <sup>e</sup>			Commercial (Old) <sup>h</sup>	Other (Old) <sup>i</sup>
<b>1973 Total</b> .....	579,231	E 444,505	686,085	E 3,087	1,712,909	NA	1,712,909	388,266	59,326
<b>1975 Total</b> .....	588,140	E 468,296	687,680	E 2,974	1,747,091	NA	1,747,091	403,049	68,222
<b>1980 Total</b> .....	717,495	558,643	815,067	3,244	2,094,449	NA	2,094,449	488,155	73,732
<b>1985 Total</b> .....	793,934	689,121	836,772	4,147	2,323,974	NA	2,323,974	605,989	87,279
<b>1990 Total</b> .....	924,019	838,263	945,522	4,751	2,712,555	124,529	2,837,084	751,027	91,988
<b>1995 Total</b> .....	1,042,501	953,117	1,012,693	4,975	3,013,287	150,677	3,163,963	862,685	95,407
<b>1996 Total</b> .....	1,082,512	980,061	1,033,631	4,923	3,101,127	152,638	3,253,765	887,445	97,539
<b>1997 Total</b> .....	1,075,880	1,026,626	1,038,197	4,907	3,145,610	156,239	3,301,849	928,633	102,901
<b>1998 Total</b> .....	1,130,109	1,077,957	1,051,203	4,962	3,264,231	160,866	3,425,097	979,401	103,518
<b>1999 Total</b> .....	1,144,923	1,103,821	1,058,217	5,126	3,312,087	171,629	3,483,716	1,001,996	106,952
<b>2000 Total</b> .....	1,192,446	1,159,347	1,064,239	5,382	3,421,414	170,943	3,592,357	1,055,232	109,496
<b>2001 Total</b> .....	1,201,607	1,190,518	996,609	5,724	3,394,458	162,649	3,557,107	1,083,069	113,174
<b>2002 Total</b> .....	1,265,180	1,204,531	990,238	5,517	3,465,466	166,184	3,631,650	1,104,497	105,552
<b>2003 Total</b> .....	1,275,824	1,198,728	1,012,373	6,810	3,493,734	168,295	3,662,029	--	--
<b>2004 Total</b> .....	1,291,982	1,230,425	1,017,850	7,224	3,547,479	168,470	3,715,949	--	--
<b>2005 Total</b> .....	1,359,227	1,275,079	1,019,156	7,506	3,660,969	150,016	3,810,984	--	--
<b>2006 Total</b> .....	1,351,520	1,299,744	1,011,298	7,358	3,669,919	146,927	3,816,845	--	--
<b>2007 Total</b> .....	1,392,241	1,336,315	1,027,832	8,173	3,764,561	125,670	3,890,231	--	--
<b>2008 Total</b> .....	1,379,981	1,335,981	1,009,300	7,700	3,732,962	132,197	3,865,159	--	--
<b>2009 Total</b> .....	1,364,474	1,307,168	917,442	7,781	3,596,865	126,938	3,723,803	--	--
<b>2010</b>									
January .....	147,500	108,120	75,506	715	331,841	E 11,084	342,925	--	--
February .....	122,840	100,747	74,164	689	298,440	E 10,144	308,585	--	--
March .....	111,790	101,756	78,303	656	292,505	E 10,884	303,389	--	--
April .....	88,046	99,791	78,597	600	267,034	E 10,091	277,125	--	--
May .....	94,843	106,176	82,088	606	283,712	E 10,611	294,323	--	--
June .....	127,496	119,388	83,347	658	330,889	E 11,037	341,927	--	--
July .....	154,688	127,925	85,725	667	369,006	E 11,690	380,696	--	--
August .....	154,053	129,143	87,904	628	371,728	E 12,298	384,026	--	--
September .....	124,582	119,137	83,353	639	327,711	E 11,221	338,932	--	--
October .....	96,688	108,461	82,046	615	287,811	E 10,605	298,416	--	--
November .....	93,166	101,524	79,575	607	274,871	E 10,520	285,392	--	--
December .....	130,015	108,031	80,264	633	318,943	E 11,725	330,668	--	--
<b>Total</b> .....	<b>1,445,708</b>	<b>1,330,199</b>	<b>970,873</b>	<b>7,712</b>	<b>3,754,493</b>	<b>131,910</b>	<b>3,886,403</b>	--	--
<b>2011</b>									
January .....	144,911	107,884	79,055	710	332,561	E 11,301	343,862	--	--
February .....	120,685	99,368	75,223	633	295,909	E 10,037	305,945	--	--
March .....	105,065	103,507	80,817	655	290,044	E 10,506	300,550	--	--
April .....	94,069	100,019	79,099	618	273,805	E 10,119	283,924	--	--
May .....	97,755	106,841	80,741	615	285,951	E 10,831	296,783	--	--
June .....	126,008	117,460	82,775	637	326,881	E 10,899	337,780	--	--
July .....	154,888	127,139	85,907	645	368,580	E 11,630	380,209	--	--
August .....	153,688	128,200	87,565	620	370,073	E 11,570	381,643	--	--
September .....	122,842	117,403	83,311	630	324,186	E 10,787	334,973	--	--
October .....	94,576	107,655	82,860	608	285,699	E 10,356	296,055	--	--
November .....	93,126	99,782	79,561	584	273,053	E 10,639	283,692	--	--
December .....	116,087	104,030	78,655	649	299,421	E 11,505	310,926	--	--
<b>Total</b> .....	<b>1,423,700</b>	<b>1,319,288</b>	<b>975,569</b>	<b>7,606</b>	<b>3,726,163</b>	<b>E 130,179</b>	<b>3,856,342</b>	--	--
<b>2012</b>									
January .....	126,475	105,076	78,640	669	310,859	E 11,539	322,398	--	--
February .....	108,145	99,266	77,918	646	285,975	E 10,860	296,835	--	--
March .....	99,342	101,806	80,694	612	282,453	E 10,619	293,072	--	--
April .....	88,444	100,733	80,444	596	270,217	E 9,966	280,183	--	--
May .....	100,629	109,955	84,482	617	295,682	E 10,920	306,601	--	--
<b>5-Month Total</b> .....	<b>523,033</b>	<b>516,837</b>	<b>402,177</b>	<b>3,140</b>	<b>1,445,187</b>	<b>E 53,903</b>	<b>1,499,089</b>	--	--
<b>2011 5-Month Total</b> .....	<b>562,485</b>	<b>517,619</b>	<b>394,935</b>	<b>3,231</b>	<b>1,478,270</b>	<b>E 52,794</b>	<b>1,531,064</b>	--	--
<b>2010 5-Month Total</b> .....	<b>565,020</b>	<b>516,590</b>	<b>388,658</b>	<b>3,266</b>	<b>1,473,534</b>	<b>E 52,814</b>	<b>1,526,347</b>	--	--

<sup>a</sup> Electricity retail sales to ultimate customers reported by electric utilities and, beginning in 1996, other energy service providers.

<sup>b</sup> Commercial sector, including public street and highway lighting, interdepartmental sales, and other sales to public authorities.

<sup>c</sup> Industrial sector. Through 2002, excludes agriculture and irrigation; beginning in 2003, includes agriculture and irrigation.

<sup>d</sup> Transportation sector, including sales to railroads and railways.

<sup>e</sup> The sum of "Residential," "Commercial," "Industrial," and "Transportation."

<sup>f</sup> Use of electricity that is 1) self-generated, 2) produced by either the same entity that consumes the power or an affiliate, and 3) used in direct support of a service or industrial process located within the same facility or group of facilities that house the generating equipment. Direct use is exclusive of station use.

<sup>g</sup> The sum of "Total Retail Sales" and "Direct Use."

<sup>h</sup> "Commercial (Old)" is a discontinued series—data are for the commercial sector, excluding public street and highway lighting, interdepartmental sales, and other sales to public authorities.

<sup>i</sup> "Other (Old)" is a discontinued series—data are for public street and highway lighting, interdepartmental sales, other sales to public authorities, agriculture and irrigation, and transportation including railroads and railways.

E=Estimate. NA=Not available. --=Not applicable.

Notes: • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#electricity> for all available data beginning in 1973.

Sources: See end of section.

## Electricity

### Note. Classification of Power Plants Into Energy-Use Sectors.

The U.S. Energy Information Administration (EIA) classifies power plants (both electricity-only and combined-heat-and-power plants) into energy-use sectors based on the North American Industry Classification System (NAICS), which replaced the Standard Industrial Classification (SIC) system in 1997. Plants with a NAICS code of 22 are assigned to the Electric Power Sector. Those with NAICS codes beginning with 11 (agriculture, forestry, fishing, and hunting); 21 (mining, including oil and gas extraction); 23 (construction); 31–33 (manufacturing); 2212 (natural gas distribution); and 22131 (water supply and irrigation systems) are assigned to the Industrial Sector. Those with all other codes are assigned to the Commercial Sector. Form EIA-860, “Annual Electric Generator Report,” asks respondents to indicate the primary purpose of the facility by assigning a NAICS code from the list at [http://www.eia.gov/survey/form/eia\\_860/instructions\\_form.doc](http://www.eia.gov/survey/form/eia_860/instructions_form.doc).

### Table 7.1 Sources

#### Net Generation, Electric Power Sector

Table 7.2b.

#### Net Generation, Commercial and Industrial Sectors

Table 7.2c.

#### Imports and Exports, Electricity Trade With Canada and Mexico, 1973–1989

1973–September 1977: Unpublished Federal Power Commission data.

October 1977–1980: Unpublished Economic Regulatory Administration (ERA) data.

1981: U.S. Department of Energy (DOE), Office of Energy Emergency Operations, “Report on Electric Energy Exchanges with Canada and Mexico for Calendar Year 1981,” April 1982 (revised June 1982).

1982 and 1983: DOE, ERA, *Electricity Exchanges Across International Borders*.

1984–1986: DOE, ERA, *Electricity Transactions Across International Borders*.

1987 and 1988: DOE, ERA, Form ERA-781R, “Annual Report of International Electrical Export/Import Data.”

1989: DOE, Fossil Energy, Form FE-781R, “Annual Report of International Electrical Export/Import Data.”

#### Imports and Exports, Electricity Trade with Canada, 1990 Forward

National Energy Board of Canada, data for total sales (firm and interruptible; which exclude non-revenue, inadvertent, and service) from Canada to the United States, and data for total purchases (which exclude non-revenue, inadvertent,

and service) by Canada from the United States.

#### Imports and Exports, Electricity Trade with Mexico, 1990 Forward

DOE, Office of Electricity Delivery and Energy Reliability, Form OE-781R, “Monthly Electricity Imports and Exports Report,” and predecessor form. For 2001 forward, data from the California Independent System Operator are used in combination with the Form OE-781 values to estimate electricity trade with Mexico.

#### T&D Losses and Unaccounted for

Calculated as the sum of total net generation and imports minus end use and exports.

#### End Use

Table 7.6.

### Table 7.2b Sources

1973–September 1977: Federal Power Commission, Form FPC-4, “Monthly Power Plant Report.”

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, “Monthly Power Plant Report.”

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, “Monthly Power Plant Report.”

1989–1997: EIA, Form EIA-759, “Monthly Power Plant Report,” and Form EIA-867, “Annual Nonutility Power Producer Report.”

1998–2000: EIA, Form EIA-759, “Monthly Power Plant Report,” and Form EIA-860B, “Annual Electric Generator Report–Nonutility.”

2001–2003: EIA, Form EIA-906, “Power Plant Report.”

2004–2007: EIA, Form EIA-906, “Power Plant Report,” and Form EIA-920, “Combined Heat and Power Plant Report.”

2008 forward: EIA, Form EIA-923, “Power Plant Operations Report.”

### Table 7.2c Sources

#### Industrial Sector, Hydroelectric Power, 1973–1988

1973–September 1977: Federal Power Commission (FPC), Form FPC-4, “Monthly Power Plant Report,” for plants with generating capacity exceeding 10 megawatts, and FPC, Form FPC-12C, “Industrial Electric Generating Capacity,” for all other plants.

October 1977–1978: Federal Energy Regulatory Commission (FERC), Form FPC-4, “Monthly Power Plant Report,” for plants with generating capacity exceeding 10 megawatts, and FERC, Form FPC-12C, “Industrial Electric Generating Capacity,” for all other plants.

1979: FERC, Form FPC-4, “Monthly Power Plant Report,” for plants with generating capacity exceeding 10 megawatts, and U.S. Energy Information Administration (EIA) estimates for all other plants.



1980–1988: Estimated by EIA as the average generation over the 6-year period of 1974–1979.

### All Data, 1989 Forward

1989–1997: EIA, Form EIA-867, “Annual Nonutility Power Producer Report.”

1998–2000: EIA, Form EIA-860B, “Annual Electric Generator Report—Nonutility.”

2001–2003: EIA, Form EIA-906, “Power Plant Report.”

2004–2007: EIA, Form EIA-906, “Power Plant Report,” and Form EIA-920, “Combined Heat and Power Plant Report.”

2008 forward: EIA, Form EIA-923, “Power Plant Operations Report.”

### Table 7.3b Sources

1973–September 1977: Federal Power Commission, Form FPC-4, “Monthly Power Plant Report.”

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, “Monthly Power Plant Report.”

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, “Monthly Power Plant Report.”

1989–1997: EIA, Form EIA-759, “Monthly Power Plant Report,” and Form EIA-867, “Annual Nonutility Power Producer Report.”

1998–2000: EIA, Form EIA-759, “Monthly Power Plant Report,” and Form EIA-860B, “Annual Electric Generator Report—Nonutility.”

2001–2003: EIA, Form EIA-906, “Power Plant Report.”

2004–2007: EIA, Form EIA-906, “Power Plant Report,” and Form EIA-920, “Combined Heat and Power Plant Report.”

2008 forward: EIA, Form EIA-923, “Power Plant Operations Report.”

### Table 7.4b Sources

1973–September 1977: Federal Power Commission, Form FPC-4, “Monthly Power Plant Report.”

October 1977–1981: Federal Energy Regulatory Commission, Form FPC-4, “Monthly Power Plant Report.”

1982–1988: U.S. Energy Information Administration (EIA), Form EIA-759, “Monthly Power Plant Report.”

1989–1997: EIA, Form EIA-759, “Monthly Power Plant Report,” and Form EIA-867, “Annual Nonutility Power Producer Report.”

1998–2000: EIA, Form EIA-759, “Monthly Power Plant Report,” and Form EIA-860B, “Annual Electric Generator Report—Nonutility.”

2001–2003: EIA, Form EIA-906, “Power Plant Report.”

2004–2007: EIA, Form EIA-906, “Power Plant Report,” and Form EIA-920, “Combined Heat and Power Plant Report.”

2008 forward: EIA, Form EIA-923, “Power Plant Operations Report.”

### Table 7.6 Sources

#### Retail Sales, Residential and Industrial

1973–September 1977: Federal Power Commission, Form FPC-5, “Monthly Statement of Electric Operating Revenue and Income.”

October 1977–February 1980: Federal Energy Regulatory Commission (FERC), Form FPC-5, “Monthly Statement of Electric Operating Revenue and Income.”

March 1980–1982: FERC, Form FPC-5, “Electric Utility Company Monthly Statement.”

1983: U.S. Energy Information Administration (EIA), Form EIA-826, “Electric Utility Company Monthly Statement.”

1984–1997: EIA, Form EIA-861, “Annual Electric Utility Report.”

1998 forward: EIA, *Electric Power Monthly*, July 2012, Table 5.1.

#### Retail Sales, Commercial

1973–2002: Estimated by EIA as the sum of “Commercial (Old)” and the non-transportation portion of “Other (Old).” See estimation methodology at

[http://www.eia.gov/states/sep\\_use/notes/use\\_elec.pdf](http://www.eia.gov/states/sep_use/notes/use_elec.pdf).

2003 forward: EIA, *Electric Power Monthly*, July 2012, Table 5.1.

#### Retail Sales, Transportation

1973–2002: Estimated by EIA as the transportation portion of “Other (Old).” See estimation methodology at

[http://www.eia.gov/states/sep\\_use/notes/use\\_elec.pdf](http://www.eia.gov/states/sep_use/notes/use_elec.pdf).

2003 forward: EIA, *Electric Power Monthly*, July 2012, Table 5.1.

#### Direct Use, Annual

1989–1996: EIA, Form EIA-867, “Annual Nonutility Power Producer Report.”

1997–2010: EIA, *Electric Power Annual 2010*, November 2011, Table 7.2.

2011: Sum of monthly estimates.

#### Direct Use, Monthly

Annual shares are calculated as annual direct use divided by annual commercial and industrial net generation (on Table 7.1). Then monthly direct use estimates are calculated as the annual share multiplied by the monthly commercial and industrial net generation values. For 2011 and 2012, the 2010 annual share is used.

#### Discontinued Retail Sales Series Commercial (Old) and Other (Old)

1973–2002: See sources for “Residential” and “Industrial.”


THIS PAGE INTENTIONALLY LEFT BLANK

# 8. Nuclear Energy


---

## Figure 8.1 Nuclear Energy Overview


Operable Units, End of Year, 1973-2011




Electricity Net Generation, 1973-2011




Nuclear Share of Electricity Net Generation, 1973-2011



Nuclear Electricity Net Generation



Capacity Factor, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#nuclear>.  
Sources: Tables 7.2a and 8.1.

**Table 8.1 Nuclear Energy Overview**

	Total Operable Units <sup>a,b</sup>	Net Summer Capacity of Operable Units <sup>b,c</sup>	Nuclear Electricity Net Generation	Nuclear Share of Electricity Net Generation	Capacity Factor <sup>d</sup>
	Number	Million Kilowatts	Million Kilowatthours	Percent	
<b>1973 Total</b> .....	<b>42</b>	<b>22.683</b>	<b>83,479</b>	<b>4.5</b>	<b>53.5</b>
<b>1975 Total</b> .....	<b>57</b>	<b>37.267</b>	<b>172,505</b>	<b>9.0</b>	<b>55.9</b>
<b>1980 Total</b> .....	<b>71</b>	<b>51.810</b>	<b>251,116</b>	<b>11.0</b>	<b>56.3</b>
<b>1985 Total</b> .....	<b>96</b>	<b>79.397</b>	<b>383,691</b>	<b>15.5</b>	<b>58.0</b>
<b>1990 Total</b> .....	<b>112</b>	<b>99.624</b>	<b>576,862</b>	<b>19.0</b>	<b>66.0</b>
<b>1995 Total</b> .....	<b>109</b>	<b>99.515</b>	<b>673,402</b>	<b>20.1</b>	<b>77.4</b>
<b>1996 Total</b> .....	<b>109</b>	<b>100.784</b>	<b>674,729</b>	<b>19.6</b>	<b>76.2</b>
<b>1997 Total</b> .....	<b>107</b>	<b>99.716</b>	<b>628,644</b>	<b>18.0</b>	<b>71.1</b>
<b>1998 Total</b> .....	<b>104</b>	<b>97.070</b>	<b>673,702</b>	<b>18.6</b>	<b>78.2</b>
<b>1999 Total</b> .....	<b>104</b>	<b>97.411</b>	<b>728,254</b>	<b>19.7</b>	<b>85.3</b>
<b>2000 Total</b> .....	<b>104</b>	<b>97.860</b>	<b>753,893</b>	<b>19.8</b>	<b>88.1</b>
<b>2001 Total</b> .....	<b>104</b>	<b>98.159</b>	<b>768,826</b>	<b>20.6</b>	<b>89.4</b>
<b>2002 Total</b> .....	<b>104</b>	<b>98.657</b>	<b>780,064</b>	<b>20.2</b>	<b>90.3</b>
<b>2003 Total</b> .....	<b>104</b>	<b>99.209</b>	<b>763,733</b>	<b>19.7</b>	<b>87.9</b>
<b>2004 Total</b> .....	<b>104</b>	<b>99.628</b>	<b>788,528</b>	<b>19.9</b>	<b>90.1</b>
<b>2005 Total</b> .....	<b>104</b>	<b>99.988</b>	<b>781,986</b>	<b>19.3</b>	<b>89.3</b>
<b>2006 Total</b> .....	<b>104</b>	<b>100.334</b>	<b>787,219</b>	<b>19.4</b>	<b>89.6</b>
<b>2007 Total</b> .....	<b>104</b>	<b>100.266</b>	<b>806,425</b>	<b>19.4</b>	<b>91.8</b>
<b>2008 Total</b> .....	<b>104</b>	<b>100.755</b>	<b>806,208</b>	<b>19.6</b>	<b>91.1</b>
<b>2009 Total</b> .....	<b>104</b>	<b>101.004</b>	<b>798,855</b>	<b>20.2</b>	<b>90.3</b>
<b>2010 January</b> .....	104	<sup>e</sup> E 101.002	72,569	20.1	<sup>E</sup> 96.6
February .....	104	<sup>E</sup> 101.000	65,245	20.4	<sup>E</sup> 96.1
March .....	104	<sup>E</sup> 100.998	64,635	20.7	<sup>E</sup> 86.0
April .....	104	<sup>E</sup> 100.996	57,611	20.0	<sup>E</sup> 79.2
May .....	104	<sup>E</sup> 101.063	66,658	20.3	<sup>E</sup> 88.7
June .....	104	<sup>E</sup> 101.094	68,301	18.2	<sup>E</sup> 93.8
July .....	104	<sup>E</sup> 101.092	71,913	17.6	<sup>E</sup> 95.6
August .....	104	<sup>E</sup> 101.090	71,574	17.5	<sup>E</sup> 95.2
September .....	104	<sup>E</sup> 101.088	69,371	20.0	<sup>E</sup> 95.3
October .....	104	<sup>E</sup> 101.104	62,751	20.4	<sup>E</sup> 83.4
November .....	104	<sup>E</sup> 101.129	62,655	20.5	<sup>E</sup> 86.0
December .....	104	101.167	73,683	20.3	97.9
<b>Total</b> .....	<b>104</b>	<b>101.167</b>	<b>806,968</b>	<b>19.6</b>	<b>91.1</b>
<b>2011 January</b> .....	104	<sup>E</sup> 101.167	72,743	20.0	<sup>E</sup> 96.6
February .....	104	<sup>E</sup> 101.167	64,789	20.7	<sup>E</sup> 95.3
March .....	104	<sup>E</sup> 101.167	65,662	20.6	<sup>E</sup> 87.2
April .....	104	<sup>E</sup> 101.167	54,547	18.0	<sup>E</sup> 74.9
May .....	104	<sup>E</sup> 101.167	57,017	17.6	<sup>E</sup> 75.8
June .....	104	<sup>E</sup> 101.281	65,270	17.7	<sup>E</sup> 89.5
July .....	104	<sup>E</sup> 101.281	72,345	17.2	<sup>E</sup> 96.0
August .....	104	<sup>E</sup> 101.351	71,339	17.6	<sup>E</sup> 94.6
September .....	104	<sup>E</sup> 101.351	66,849	19.8	<sup>E</sup> 91.6
October .....	104	<sup>E</sup> 101.351	63,354	20.5	<sup>E</sup> 84.0
November .....	104	<sup>E</sup> 101.351	64,474	21.2	<sup>E</sup> 88.4
December .....	104	<sup>P</sup> 101.423	71,837	21.4	<sup>P</sup> 95.2
<b>Total</b> .....	<b>104</b>	<b>101.423</b>	<b>790,225</b>	<b>19.2</b>	<b>89.1</b>
<b>2012 January</b> .....	104	<sup>E</sup> 101.423	72,382	21.2	<sup>E</sup> 95.9
February .....	104	<sup>E</sup> 101.423	63,850	20.6	<sup>E</sup> 90.5
March .....	104	<sup>E</sup> 101.423	61,730	19.9	<sup>E</sup> 81.8
April .....	104	<sup>E</sup> 101.423	55,871	18.9	<sup>E</sup> 76.5
May .....	104	<sup>E</sup> 101.446	62,081	18.4	<sup>E</sup> 82.3
<b>5-Month Total</b> .....	<b>104</b>	<b>101.446</b>	<b>315,914</b>	<b>19.8</b>	<b>85.4</b>
<b>2011 5-Month Total</b> .....	<b>104</b>	<sup>E</sup> <b>101.167</b>	<b>314,758</b>	<b>19.4</b>	<sup>E</sup> <b>85.9</b>
<b>2010 5-Month Total</b> .....	<b>104</b>	<sup>E</sup> <b>101.063</b>	<b>326,719</b>	<b>20.3</b>	<sup>E</sup> <b>89.3</b>

<sup>a</sup> Total of nuclear generating units holding full-power licenses, or equivalent permission to operate, at end of period. See Note 1, "Operable Nuclear Reactors," at end of section. For additional information on nuclear generating units, see *Annual Energy Review 2010*, October 2011, Table 9.1, <http://www.eia.gov/totalenergy/data/annual/#nuclear>.

<sup>b</sup> At end of period.

<sup>c</sup> For the definition of "Net Summer Capacity," see Note 2, "Nuclear Capacity," at end of section.

<sup>d</sup> For an explanation of the method of calculating the capacity factor, see Note 2, "Nuclear Capacity," at end of section.

<sup>e</sup> Beginning in 2010, monthly capacity values are estimated in two steps: 1) updates reported on Form EIA-860M are added to specific months; and 2) the

difference between the resulting year-end capacity (from data reported on Form EIA-860M) and final capacity (reported on Form EIA-860) is distributed evenly across the 12 months.

P=Preliminary. E=Estimate.

Notes: • For a discussion of nuclear reactor unit coverage, see Note 1, "Operable Nuclear Reactors," at end of section. • Nuclear electricity net generation totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#nuclear> for all available data beginning in 1973.

Sources: See end of section.

## Nuclear Energy

**Note 1. Operable Nuclear Reactors.** A reactor is generally defined as operable while it possessed a full-power license from the Nuclear Regulatory Commission or its predecessor the Atomic Energy Commission, or equivalent permission to operate, at the end of the year or month shown. The definition is liberal in that it does not exclude units retaining full-power licenses during long, non-routine shutdowns that for a time rendered them unable to generate electricity. Examples are:

- (a) In 1985 the five then-active Tennessee Valley Authority (TVA) units (Browns Ferry 1, 2, and 3, and Sequoyah 1 and 2) were shut down under a regulatory forced outage. All five units were idle for several years, restarting in 2007, 1991, 1995, 1988, and 1988, respectively and were counted as operable during the shutdowns.
- (b) Shippingport was shut down from 1974 through 1976 for conversion to a light-water breeder reactor, but is counted as operable from 1957 until its retirement in 1982.
- (c) Calvert Cliffs 2 was shut down in 1989 and 1990 for replacement of pressurizer heater sleeves but is counted as operable during those years.

Exceptions to the definition are Shoreham and Three Mile Island 2. Shoreham was granted a full-power license in April 1989, but was shut down two months later and never restarted. In 1991, the license was changed to Possession Only. Although not operable at the end of the year, Shoreham is counted as operable during 1989. A major accident closed Three Mile Island 2 in 1979, and although the unit retained its full-power license for several years, it is considered permanently shut down since that year.

**Note 2. Nuclear Capacity.** Nuclear generating units may have more than one type of net capacity rating, including the following:

- (a) Net Summer Capacity—The steady hourly output that generating equipment is expected to supply to system load, exclusive of auxiliary power, as demonstrated by test at the

time of summer peak demand. Auxiliary power of a typical nuclear power plant is about 5 percent of gross generation.

- (b) Net Design Capacity or Net Design Electrical Rating (DER)—The nominal net electrical output of a unit, specified by the utility and used for plant design.

The monthly capacity factors are calculated as the monthly nuclear electricity net generation divided by the maximum possible nuclear electricity net generation for that month. The maximum possible nuclear electricity net generation is the number of hours in the month (assuming 24-hour days, with no adjustment for changes to or from Daylight Savings Time) multiplied by the net summer capacity of operable nuclear generating units at the end of the month. That fraction is then multiplied by 100 to obtain a percentage. Annual capacity factors are calculated as the annual nuclear electricity net generation divided by the annual maximum possible nuclear electricity net generation (the sum of the monthly values for maximum possible nuclear electricity net generation).

### Table 8.1 Sources

#### Total Operable Units and Net Summer Capacity of Operable Units

1973-1982: Compiled from various sources, primarily U.S. Department of Energy, Office of Nuclear Reactor Programs, "U.S. Central Station Nuclear Electric Generating Units: Significant Milestones."

1983 forward: U.S. Energy Information Administration (EIA), Form EIA-860, "Annual Electric Generator Report," Form EIA-860M, "Monthly Update to the Annual Electric Generator Report," and monthly updates as appropriate. For a list of currently operable units, see [http://www.eia.gov/nuclear/reactors/stats\\_table1.html](http://www.eia.gov/nuclear/reactors/stats_table1.html).

#### Nuclear Electricity Net Generation and Nuclear Share of Electricity Net Generation

See Table 7.2a.

#### Capacity Factor


Calculated by EIA using the method described above in Note 2.

## 9. Energy Prices


---

**Figure 9.1 Petroleum Prices**


Crude Oil Prices, 1973-2011




Composite Refiner Acquisition Cost, Monthly



Refiner Prices to End Users: Motor Gasoline, Diesel Fuel, and Jet Fuel, Monthly



Refiner Prices to End Users: No. 2 Fuel Oil, Propane, and Residual Fuel, Monthly



<sup>a</sup>Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
 Sources: Tables 9.1, 9.5, and 9.7.



**Table 9.1 Crude Oil Price Summary**  
(Dollars<sup>a</sup> per Barrel)

	Domestic First Purchase Price <sup>c</sup>	F.O.B. Cost of Imports <sup>d</sup>	Landed Cost of Imports <sup>e</sup>	Refiner Acquisition Cost <sup>b</sup>		
				Domestic	Imported	Composite
<b>1973 Average</b> .....	3.89	<sup>f</sup> 5.21	<sup>f</sup> 6.41	<sup>E</sup> 4.17	<sup>E</sup> 4.08	<sup>E</sup> 4.15
<b>1975 Average</b> .....	7.67	11.18	12.70	8.39	13.93	10.38
<b>1980 Average</b> .....	21.59	32.37	33.67	24.23	33.89	28.07
<b>1985 Average</b> .....	24.09	25.84	26.67	26.66	26.99	26.75
<b>1990 Average</b> .....	20.03	20.37	21.13	22.59	21.76	22.22
<b>1995 Average</b> .....	14.62	15.69	16.78	17.33	17.14	17.23
<b>1996 Average</b> .....	18.46	19.32	20.31	20.77	20.64	20.71
<b>1997 Average</b> .....	17.23	16.94	18.11	19.61	18.53	19.04
<b>1998 Average</b> .....	10.87	10.76	11.84	13.18	12.04	12.52
<b>1999 Average</b> .....	15.56	16.47	17.23	17.90	17.26	17.51
<b>2000 Average</b> .....	26.72	26.27	27.53	29.11	27.70	28.26
<b>2001 Average</b> .....	21.84	20.46	21.82	24.33	22.00	22.95
<b>2002 Average</b> .....	22.51	22.63	23.91	24.65	23.71	24.10
<b>2003 Average</b> .....	27.56	25.86	27.69	29.82	27.71	28.53
<b>2004 Average</b> .....	36.77	33.75	36.07	38.97	35.90	36.98
<b>2005 Average</b> .....	50.28	47.60	49.29	52.94	48.86	50.24
<b>2006 Average</b> .....	59.69	57.03	59.11	62.62	59.02	60.24
<b>2007 Average</b> .....	66.52	66.36	67.97	69.65	67.04	67.94
<b>2008 Average</b> .....	94.04	90.32	93.33	98.47	92.77	94.74
<b>2009 Average</b> .....	56.35	57.78	60.23	59.49	59.17	59.29
<b>2010</b>						
January .....	72.89	72.96	74.78	76.04	75.07	75.48
February .....	72.74	71.50	75.01	75.91	73.73	74.58
March .....	75.77	75.41	77.65	78.52	76.77	77.43
April .....	78.80	78.27	79.34	82.12	80.03	80.83
May .....	70.90	69.21	72.00	75.23	71.15	72.66
June .....	70.77	70.17	72.62	73.93	71.91	72.66
July .....	71.37	71.01	73.43	74.54	73.25	73.73
August .....	72.07	71.27	73.63	76.21	73.50	74.58
September .....	71.23	71.72	74.25	74.87	73.20	73.85
October .....	76.02	75.52	77.26	78.88	77.02	77.77
November .....	79.20	79.56	81.56	82.05	80.07	80.85
December .....	83.98	83.95	86.64	86.48	85.59	85.95
<b>Average</b> .....	<b>74.71</b>	<b>74.20</b>	<b>76.49</b>	<b>77.96</b>	<b>75.88</b>	<b>76.69</b>
<b>2011</b>						
January .....	85.66	86.80	89.61	88.73	87.99	88.28
February .....	86.69	92.07	94.25	89.50	91.72	90.85
March .....	99.19	104.19	104.80	102.34	102.48	102.43
April .....	108.80	111.52	112.54	111.96	113.08	112.65
May .....	102.46	105.92	108.28	107.55	107.99	107.82
June .....	97.30	104.35	105.19	102.53	105.36	104.23
July .....	97.82	105.60	106.19	102.67	105.94	104.68
August .....	89.00	97.72	99.27	95.89	99.01	97.70
September .....	90.22	100.84	101.03	96.89	101.05	99.39
October .....	92.28	101.92	102.55	98.34	102.00	100.57
November .....	100.18	105.79	105.98	106.69	107.67	107.28
December .....	98.71	103.09	105.62	104.51	106.52	105.69
<b>Average</b> .....	<b>95.73</b>	<b>101.68</b>	<b>102.99</b>	<b>100.74</b>	<b>102.70</b>	<b>101.93</b>
<b>2012</b>						
January .....	98.99	103.96	105.27	103.97	105.25	104.70
February .....	102.05	108.56	109.24	105.93	108.08	107.18
March .....	105.42	<sup>R</sup> 110.72	<sup>R</sup> 110.68	110.80	111.00	110.92
April .....	<sup>R</sup> 103.62	<sup>R</sup> 108.27	<sup>R</sup> 108.08	<sup>R</sup> 111.26	<sup>R</sup> 108.53	<sup>R</sup> 109.70
May .....	<sup>R</sup> 95.57	<sup>R</sup> 102.02	<sup>R</sup> 101.54	<sup>R</sup> 103.17	<sup>R</sup> 103.26	<sup>R</sup> 103.23
June .....	NA	NA	NA	<sup>E</sup> 92.06	<sup>E</sup> 92.15	<sup>E</sup> 92.12

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 1, "Crude Oil Refinery Acquisition Costs," at end of section.

<sup>c</sup> See Note 2, "Crude Oil Domestic First Purchase Prices," at end of section.

<sup>d</sup> See Note 3, "Crude Oil F.O.B. Costs," at end of section.

<sup>e</sup> See Note 4, "Crude Oil Landed Costs," at end of section.

<sup>f</sup> Based on October, November, and December data only.

<sup>R</sup>=Revised. <sup>NA</sup>=Not available. <sup>E</sup>=Estimate.

Notes: • Values for Domestic First Purchase Price and Refiner Acquisition Cost for the current two months and for F.O.B. and Landed Costs of Imports for the

current three months are preliminary. • F.O.B. and landed costs through 1980 reflect the period of reporting; prices since then reflect the period of loading. • Annual averages are the averages of the monthly prices, weighted by volume. • Geographic coverage is the 50 States, the District of Columbia, Puerto Rico, the Virgin Islands, and all U.S. Territories and Possessions.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1973.

Sources: See end of section.

**Table 9.2 F.O.B. Costs of Crude Oil Imports From Selected Countries**  
(Dollars<sup>a</sup> per Barrel)

	Selected Countries							Persian Gulf Nations <sup>b</sup>	Total OPEC <sup>c</sup>	Total Non-OPEC <sup>c</sup>
	Angola	Colombia	Mexico	Nigeria	Saudi Arabia	United Kingdom	Venezuela			
<b>1973 Average<sup>d</sup></b> .....	W	W	–	7.81	3.25	–	5.39	3.68	5.43	4.80
1975 Average .....	10.97	–	11.44	11.82	10.87	–	11.04	10.88	11.34	10.62
1980 Average .....	33.45	W	31.06	35.93	28.17	34.36	24.81	28.92	32.21	32.85
1985 Average .....	26.30	–	25.33	28.04	22.04	27.64	23.64	23.31	25.67	25.96
1990 Average .....	20.23	20.75	19.26	22.46	20.36	23.43	19.55	18.54	20.40	20.32
1995 Average .....	16.58	16.73	15.64	17.40	W	16.94	13.86	W	15.36	16.02
1996 Average .....	20.71	21.33	19.14	21.27	19.28	19.43	17.73	19.22	18.94	19.65
1997 Average .....	18.81	18.85	16.72	19.43	15.16	18.59	15.33	15.24	16.26	17.51
1998 Average .....	12.11	12.56	10.49	12.97	8.87	12.52	9.31	9.09	10.20	11.21
1999 Average .....	17.46	17.20	15.89	17.32	17.65	19.14	14.33	17.15	15.90	16.84
2000 Average .....	27.90	29.04	25.39	28.70	24.62	27.21	24.45	24.72	25.56	26.77
2001 Average .....	23.25	24.25	18.89	24.85	18.98	23.30	18.01	18.89	19.73	21.04
2002 Average .....	24.09	24.64	21.60	25.38	23.92	24.50	20.13	23.38	22.18	22.93
2003 Average .....	28.22	28.89	24.83	29.40	25.03	28.76	23.81	25.17	25.36	26.21
2004 Average .....	37.26	37.73	31.55	38.71	34.08	37.30	31.78	33.08	33.95	33.58
2005 Average .....	52.48	51.89	43.00	55.95	47.96	54.48	46.39	47.21	49.60	45.79
2006 Average .....	62.23	59.77	52.91	65.69	56.09	66.03	55.80	56.02	59.18	55.35
2007 Average .....	67.80	67.93	61.35	76.64	W	69.96	64.10	69.93	69.58	62.69
2008 Average .....	95.66	91.17	84.61	102.06	93.03	96.33	88.06	91.44	93.15	87.15
2009 Average .....	57.07	57.90	56.47	64.61	57.87	65.63	55.58	59.53	58.53	57.16
<b>2010</b> January .....	74.62	70.08	72.96	75.91	W	–	70.86	W	73.42	72.49
February .....	W	68.70	69.16	76.07	W	–	68.83	71.89	71.77	71.14
March .....	78.11	73.90	72.76	81.27	W	–	70.88	76.10	75.83	74.91
April .....	84.40	74.85	75.57	85.94	W	W	72.59	80.01	78.88	77.73
May .....	71.86	64.32	68.30	74.28	W	–	66.37	73.60	70.45	68.24
June .....	72.90	67.19	67.64	75.61	W	–	66.19	72.49	71.39	69.20
July .....	74.77	70.00	68.53	79.63	W	–	67.25	71.76	72.16	69.87
August .....	77.11	69.88	69.53	75.70	W	W	68.27	72.79	72.38	70.35
September .....	W	69.71	69.90	80.93	74.06	–	67.59	73.34	73.24	70.24
October .....	W	76.06	73.93	84.59	W	–	72.10	78.28	77.55	73.80
November .....	85.99	78.92	77.14	86.61	W	–	75.03	80.99	80.95	78.49
December .....	W	81.62	81.75	93.68	W	–	77.78	W	85.72	82.40
<b>Average</b> .....	<b>78.18</b>	<b>72.56</b>	<b>72.46</b>	<b>80.83</b>	<b>76.44</b>	<b>W</b>	<b>70.30</b>	<b>75.65</b>	<b>75.23</b>	<b>73.24</b>
<b>2011</b> January .....	95.97	83.36	84.36	99.86	W	–	81.25	W	89.74	83.92
February .....	W	87.23	88.77	109.07	W	–	85.11	97.25	96.01	88.67
March .....	113.63	101.29	102.55	117.98	W	–	97.56	107.36	106.19	102.44
April .....	122.52	114.17	109.90	126.05	W	–	106.56	114.82	115.15	107.71
May .....	113.33	106.15	105.13	117.66	W	–	101.60	110.29	108.50	103.81
June .....	115.13	102.78	103.43	119.13	W	–	100.59	106.39	108.22	100.42
July .....	114.80	100.30	104.84	119.68	W	–	100.62	109.06	110.09	100.90
August .....	W	95.01	98.21	115.61	W	–	97.17	106.98	104.19	93.57
September .....	112.49	97.45	100.28	115.43	109.99	–	95.72	108.41	105.82	97.08
October .....	109.74	102.37	101.48	114.46	W	–	96.93	105.62	105.20	98.65
November .....	112.49	106.97	107.94	115.35	W	–	105.44	106.51	108.16	104.17
December .....	111.26	103.10	105.96	W	W	–	105.75	104.48	106.42	100.80
<b>Average</b> .....	<b>111.82</b>	<b>100.19</b>	<b>100.92</b>	<b>115.35</b>	<b>107.08</b>	<b>–</b>	<b>97.23</b>	<b>106.49</b>	<b>105.34</b>	<b>98.51</b>
<b>2012</b> January .....	111.10	106.69	107.79	114.12	W	–	105.08	107.51	107.51	101.40
February .....	121.45	114.47	110.14	124.31	W	–	110.37	111.12	113.85	103.42
March .....	W	118.46	114.81	128.10	W	–	112.76	118.06	117.06	<sup>R</sup> 104.75
April .....	<sup>R</sup> 118.84	<sup>R</sup> 114.06	<sup>R</sup> 110.54	W	W	–	<sup>R</sup> 109.60	115.01	<sup>R</sup> 113.97	<sup>R</sup> 102.91
May .....	110.74	103.26	103.64	111.23	W	–	102.37	105.06	105.15	99.16

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).

<sup>c</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary.

On this table, "Total OPEC" for all years includes Algeria, Iran, Iraq, Kuwait, Libya, Nigeria, Qatar, Saudi Arabia, United Arab Emirates, and Venezuela; for 1973–2008, also includes Indonesia; for 1973–1992 and again beginning in 2008, also includes Ecuador (although Ecuador rejoined OPEC in November 2007, on this table Ecuador is included in "Total Non-OPEC" for 2007); for 1974–1995, also includes Gabon (although Gabon was a member of OPEC for only 1975–1994); and beginning in 2007, also includes Angola. Data for all countries not included in "Total OPEC" are included in "Total Non-OPEC."

<sup>d</sup> Based on October, November, and December data only.

<sup>R</sup>=Revised. –=No data reported. W=Value withheld to avoid disclosure of individual company data.

Notes: • The Free on Board (F.O.B.) cost at the country of origin excludes all costs related to insurance and transportation. See "F.O.B." in Glossary, and Note 3, "Crude Oil F.O.B. Costs," at end of section. • Values for the current two months are preliminary. • Prices through 1980 reflect the period of reporting; prices since then reflect the period of loading. • Annual averages are averages of the monthly prices, including prices not published, weighted by volume. • Cargoes that are purchased on a "netback" basis, or under similar contractual arrangements whereby the actual purchase price is not established at the time the crude oil is acquired for importation into the United States, are not included in the published data until the actual prices have been determined and reported. • U.S. geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1973.

Sources: See end of section.

**Table 9.3 Landed Costs of Crude Oil Imports From Selected Countries**  
(Dollars<sup>a</sup> per Barrel)

	Selected Countries								Persian Gulf Nations <sup>b</sup>	Total OPEC <sup>c</sup>	Total Non-OPEC <sup>c</sup>
	Angola	Canada	Colombia	Mexico	Nigeria	Saudi Arabia	United Kingdom	Venezuela			
1973 Average <sup>d</sup>	W	5.33	W	–	9.08	5.37	–	5.99	5.91	6.85	5.64
1975 Average	11.81	12.84	–	12.61	12.70	12.50	–	12.36	12.64	12.70	12.70
1980 Average	34.76	30.11	W	31.77	37.15	29.80	35.68	25.92	30.59	33.56	33.99
1985 Average	27.39	25.71	–	25.63	28.96	24.72	28.36	24.43	25.50	26.86	26.53
1990 Average	21.51	20.48	22.34	19.64	23.33	21.82	22.65	20.31	20.55	21.23	20.98
1995 Average	17.66	16.65	17.45	16.19	18.25	16.84	17.91	14.81	16.78	16.61	16.95
1996 Average	21.86	19.94	22.02	19.64	21.95	20.49	20.88	18.59	20.45	20.14	20.47
1997 Average	20.24	17.63	19.71	17.30	20.64	17.52	20.64	16.35	17.44	17.73	18.45
1998 Average	13.37	11.62	13.26	11.04	14.14	11.16	13.55	10.16	11.18	11.46	12.22
1999 Average	18.37	17.54	18.09	16.12	17.63	17.48	18.26	15.58	17.37	16.94	17.51
2000 Average	29.57	26.69	29.68	26.03	30.04	26.58	29.26	26.05	26.77	27.29	27.80
2001 Average	25.13	20.72	25.88	19.37	26.55	20.98	25.32	19.81	20.73	21.52	22.17
2002 Average	25.43	22.98	25.28	22.09	26.45	24.77	26.35	21.93	24.13	23.83	23.97
2003 Average	30.14	26.76	30.55	25.48	31.07	27.50	30.62	25.70	27.54	27.70	27.68
2004 Average	39.62	34.51	39.03	32.25	40.95	37.11	39.28	33.79	36.53	36.84	35.29
2005 Average	54.31	44.73	53.42	43.47	57.55	50.31	55.28	47.87	49.68	51.36	47.31
2006 Average	64.85	53.90	62.13	53.76	68.26	59.19	67.44	57.37	58.92	61.21	57.14
2007 Average	71.27	60.38	70.91	62.31	78.01	70.78	72.47	66.13	69.83	71.14	63.96
2008 Average	98.18	90.00	93.43	85.97	104.83	94.75	96.95	90.76	93.59	95.49	90.59
2009 Average	61.32	57.60	58.50	57.35	68.01	62.14	63.87	57.78	62.15	61.90	58.58
<b>2010</b> January	77.32	72.59	74.26	73.23	78.58	76.63	77.97	72.63	76.34	75.91	73.59
February	79.06	73.37	73.11	69.48	79.25	77.29	77.84	70.91	77.27	76.24	73.33
March	80.93	76.82	76.08	73.07	83.68	77.57	79.07	72.92	77.55	78.40	76.84
April	82.26	78.36	76.33	75.03	86.80	79.53	80.25	75.21	79.15	80.07	78.61
May	74.80	69.16	66.52	68.71	76.90	77.52	W	68.53	76.20	73.95	70.20
June	76.54	69.14	69.64	68.02	78.14	76.01	77.67	68.30	75.14	74.55	70.92
July	77.20	70.25	71.61	69.31	81.07	75.46	76.60	69.59	74.75	74.81	72.03
August	78.40	70.10	71.49	69.95	79.15	76.06	79.52	70.14	75.81	75.42	71.81
September	80.49	68.66	70.85	70.47	81.58	77.15	W	68.88	76.64	76.39	71.89
October	85.33	69.23	76.72	74.73	86.01	81.81	W	74.29	81.24	80.52	74.15
November	86.98	75.40	80.24	77.55	89.15	84.62	87.10	77.53	84.09	84.38	78.96
December	91.77	80.76	82.76	82.37	95.44	90.45	92.50	80.79	89.99	89.25	83.97
<b>Average</b>	<b>80.63</b>	<b>72.80</b>	<b>74.25</b>	<b>72.86</b>	<b>83.15</b>	<b>79.25</b>	<b>80.12</b>	<b>72.43</b>	<b>78.58</b>	<b>78.27</b>	<b>74.67</b>
<b>2011</b> January	99.58	81.43	85.88	85.00	101.24	96.59	W	84.70	96.57	94.03	85.02
February	110.07	80.65	90.14	89.08	108.94	103.20	W	89.88	101.81	99.96	89.03
March	114.40	89.32	105.74	103.03	117.17	110.12	118.42	101.22	109.56	109.23	101.20
April	124.01	99.26	112.47	110.55	126.47	116.13	124.67	107.95	115.18	116.64	108.91
May	116.76	98.29	109.70	105.62	119.95	112.19	W	104.04	111.48	111.90	105.06
June	116.73	92.36	104.31	103.71	120.81	110.00	W	102.32	108.97	109.87	100.83
July	117.98	91.76	101.35	105.38	121.80	111.06	W	103.04	110.19	111.58	100.38
August	113.36	84.05	95.08	98.78	115.83	109.38	W	99.54	108.26	106.24	93.81
September	112.63	85.19	99.17	99.90	117.19	109.91	W	99.10	108.82	107.67	95.59
October	114.82	88.21	104.14	101.97	116.09	108.90	W	99.89	108.07	107.98	97.91
November	115.14	93.80	108.52	108.46	117.05	108.61	W	106.90	108.35	110.09	102.90
December	115.65	95.74	106.64	106.31	117.10	108.27	W	108.02	107.53	109.63	102.52
<b>Average</b>	<b>114.05</b>	<b>90.03</b>	<b>102.53</b>	<b>101.22</b>	<b>116.40</b>	<b>108.81</b>	<b>118.35</b>	<b>100.14</b>	<b>108.06</b>	<b>107.85</b>	<b>98.75</b>
<b>2012</b> January	115.13	93.43	110.54	108.38	115.41	110.49	W	106.23	110.61	110.32	101.31
February	121.40	92.14	115.19	111.24	126.42	114.73	W	111.72	114.22	115.76	103.02
March	128.35	<sup>R</sup> 88.73	119.93	115.20	<sup>R</sup> 130.46	<sup>R</sup> 117.55	–	<sup>R</sup> 114.29	<sup>R</sup> 117.14	<sup>R</sup> 118.26	<sup>R</sup> 103.98
April	<sup>R</sup> 121.68	<sup>R</sup> 85.63	<sup>R</sup> 114.33	<sup>R</sup> 111.55	<sup>R</sup> 124.01	<sup>R</sup> 118.29	<sup>R</sup> W	<sup>R</sup> 110.78	<sup>R</sup> 118.29	<sup>R</sup> 117.40	<sup>R</sup> 100.13
May	114.50	83.31	106.22	104.29	115.38	112.05	–	103.59	111.42	109.74	95.57

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
<sup>b</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).  
<sup>c</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. On this table, "Total OPEC" for all years includes Algeria, Iran, Iraq, Kuwait, Libya, Nigeria, Qatar, Saudi Arabia, United Arab Emirates, and Venezuela; for 1973–2008, also includes Indonesia; for 1973–1992 and again beginning in 2008, also includes Ecuador (although Ecuador rejoined OPEC in November 2007, on this table Ecuador is included in "Total Non-OPEC" for 2007); for 1974–1995, also includes Gabon (although Gabon was a member of OPEC for only 1975–1994); and beginning in 2007, also includes Angola. Data for all countries not included in "Total OPEC" are included in "Total Non-OPEC."  
<sup>d</sup> Based on October, November, and December data only.  
<sup>R</sup> Revised. – =No data reported. W=Value withheld to avoid disclosure of individual company data.  
Notes: • See "Landed Costs" in Glossary, and Note 4, "Crude Oil Landed

Costs," at end of section. • Values for the current two months are preliminary.  
• Prices through 1980 reflect the period of reporting; prices since then reflect the period of loading. • Annual averages are averages of the monthly prices, including prices not published, weighted by volume. • Cargoes that are purchased on a "netback" basis, or under similar contractual arrangements whereby the actual purchase price is not established at the time the crude oil is acquired for importation into the United States, are not included in the published data until the actual prices have been determined and reported. • U.S. geographic coverage is the 50 States and the District of Columbia.  
Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1973.  
Sources: • **October 1973-September 1977:** Federal Energy Administration, Form FEA-F701-M-0, "Transfer Pricing Report." • **October 1977-December 1977:** U.S. Energy Information Administration (EIA), Form FEA-F701-M-0, "Transfer Pricing Report." • **1978-2009:** EIA, *Petroleum Marketing Annual 2009*, Table 22.  
• **2010 forward:** EIA, *Petroleum Marketing Monthly*, August 2012, Table 22.

**Table 9.4 Motor Gasoline Retail Prices, U.S. City Average**  
(Dollars<sup>a</sup> per Gallon, Including Taxes)

	Leaded Regular	Unleaded Regular	Unleaded Premium <sup>b</sup>	All Types <sup>c</sup>
1973 Average .....	0.388	NA	NA	NA
1975 Average .....	0.567	NA	NA	NA
1980 Average .....	1.191	1.245	NA	1.221
1985 Average .....	1.115	1.202	1.340	1.196
1990 Average .....	1.149	1.164	1.349	1.217
1995 Average .....	NA	1.147	1.336	1.205
1996 Average .....	NA	1.231	1.413	1.288
1997 Average .....	NA	1.234	1.416	1.291
1998 Average .....	NA	1.059	1.250	1.115
1999 Average .....	NA	1.165	1.357	1.221
2000 Average .....	NA	1.510	1.693	1.563
2001 Average .....	NA	1.461	1.657	1.531
2002 Average .....	NA	1.358	1.556	1.441
2003 Average .....	NA	1.591	1.777	1.638
2004 Average .....	NA	1.880	2.068	1.923
2005 Average .....	NA	2.295	2.491	2.338
2006 Average .....	NA	2.589	2.805	2.635
2007 Average .....	NA	2.801	3.033	2.849
2008 Average .....	NA	3.266	3.519	3.317
2009 Average .....	NA	2.350	2.607	2.401
<b>2010</b> January .....	NA	2.731	2.987	2.779
February .....	NA	2.659	2.922	2.709
March .....	NA	2.780	3.035	2.829
April .....	NA	2.858	3.113	2.906
May .....	NA	2.869	3.124	2.915
June .....	NA	2.736	3.000	2.783
July .....	NA	2.736	2.997	2.783
August .....	NA	2.745	3.015	2.795
September .....	NA	2.704	2.968	2.754
October .....	NA	2.795	3.055	2.843
November .....	NA	2.852	3.109	2.899
December .....	NA	2.985	3.234	3.031
<b>Average</b> .....	<b>NA</b>	<b>2.788</b>	<b>3.047</b>	<b>2.836</b>
<b>2011</b> January .....	NA	3.091	3.345	3.139
February .....	NA	3.167	3.424	3.215
March .....	NA	3.546	3.807	3.594
April .....	NA	3.816	4.074	3.863
May .....	NA	3.933	4.192	3.982
June .....	NA	3.702	3.972	3.753
July .....	NA	3.654	3.915	3.703
August .....	NA	3.630	3.893	3.680
September .....	NA	3.612	3.887	3.664
October .....	NA	3.468	3.745	3.521
November .....	NA	3.423	3.700	3.475
December .....	NA	3.278	3.553	3.329
<b>Average</b> .....	<b>NA</b>	<b>3.527</b>	<b>3.792</b>	<b>3.577</b>
<b>2012</b> January .....	NA	3.399	3.663	3.447
February .....	NA	3.572	3.840	3.622
March .....	NA	3.868	4.138	3.918
April .....	NA	3.927	4.194	3.976
May .....	NA	3.792	4.062	3.839
June .....	NA	3.552	3.825	3.602
July .....	NA	3.451	3.726	3.502

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> The 1981 average (available in Web file) is based on September through December data only.

<sup>c</sup> Also includes types of motor gasoline not shown separately.

NA=Not available.

Notes: • See Note 5, "Motor Gasoline Prices," at end of section. • In September 1981, the Bureau of Labor Statistics changed the weights used in the calculation of average motor gasoline prices. From September 1981 forward, gasohol is included in the average for all types, and unleaded premium is weighted

more heavily. • Geographic coverage for 1973-1977 is 56 urban areas. Geographic coverage for 1978 forward is 85 urban areas.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1973.

Sources: • **Monthly Data:** U.S. Department of Labor, Bureau of Labor Statistics, *Consumer Prices: Energy*. • **Annual Data: 1973—***Platt's Oil Price Handbook and Oilmanac*, 1974, 51st Edition. **1974 forward—**calculated by the U.S. Energy Information Administration as the simple averages of monthly data.

**Table 9.5 Refiner Prices of Residual Fuel Oil**  
(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Residual Fuel Oil Sulfur Content Less Than or Equal to 1 Percent		Residual Fuel Oil Sulfur Content Greater Than 1 Percent		Average	
	Sales for Resale	Sales to End Users	Sales for Resale	Sales to End Users	Sales for Resale	Sales to End Users
<b>1978 Average</b> .....	0.293	0.314	0.245	0.275	0.263	0.298
<b>1980 Average</b> .....	0.608	0.675	0.479	0.523	0.528	0.607
<b>1985 Average</b> .....	0.610	0.644	0.560	0.582	0.577	0.610
<b>1990 Average</b> .....	0.472	0.505	0.372	0.400	0.413	0.444
<b>1995 Average</b> .....	0.383	0.436	0.338	0.377	0.363	0.392
<b>1996 Average</b> .....	0.456	0.526	0.389	0.433	0.420	0.455
<b>1997 Average</b> .....	0.415	0.488	0.366	0.403	0.387	0.423
<b>1998 Average</b> .....	0.299	0.354	0.287	0.287	0.280	0.305
<b>1999 Average</b> .....	0.382	0.405	0.329	0.362	0.354	0.374
<b>2000 Average</b> .....	0.627	0.708	0.512	0.566	0.566	0.602
<b>2001 Average</b> .....	0.523	0.642	0.428	0.492	0.476	0.531
<b>2002 Average</b> .....	0.546	0.640	0.508	0.544	0.530	0.569
<b>2003 Average</b> .....	0.728	0.804	0.588	0.651	0.661	0.698
<b>2004 Average</b> .....	0.764	0.835	0.601	0.692	0.681	0.739
<b>2005 Average</b> .....	1.115	1.168	0.842	0.974	0.971	1.048
<b>2006 Average</b> .....	1.202	1.342	1.085	1.173	1.136	1.218
<b>2007 Average</b> .....	1.406	1.436	1.314	1.350	1.350	1.374
<b>2008 Average</b> .....	1.918	2.144	1.843	1.889	1.866	1.964
<b>2009 Average</b> .....	1.337	1.413	1.344	1.306	1.342	1.341
<b>2010</b> January .....	1.767	1.852	1.705	1.660	1.721	1.725
February .....	1.725	1.862	1.650	1.574	1.666	1.681
March .....	1.739	1.862	1.700	1.609	1.711	1.692
April .....	1.827	1.887	1.725	1.655	1.748	1.718
May .....	1.675	1.898	1.675	1.601	1.675	1.686
June .....	1.629	1.874	1.604	1.555	1.612	1.636
July .....	1.686	1.858	1.604	1.536	1.629	1.639
August .....	1.705	1.895	1.625	1.571	1.642	1.676
September .....	1.716	1.883	1.612	1.558	1.632	1.645
October .....	1.793	1.913	1.688	1.637	1.712	1.721
November .....	1.865	2.025	1.741	1.701	1.768	1.804
December .....	2.036	2.215	1.814	1.784	1.865	1.931
<b>Average</b> .....	<b>1.756</b>	<b>1.920</b>	<b>1.679</b>	<b>1.619</b>	<b>1.697</b>	<b>1.713</b>
<b>2011</b> January .....	NA	2.302	1.896	1.870	1.918	2.013
February .....	2.100	2.451	2.079	2.019	2.086	2.150
March .....	2.344	2.654	2.307	2.245	2.321	2.403
April .....	2.555	2.741	2.427	2.370	2.448	2.475
May .....	2.463	2.786	2.374	2.325	2.392	2.440
June .....	2.467	2.905	2.377	2.312	2.402	2.473
July .....	2.547	2.877	2.430	2.362	2.474	2.508
August .....	2.394	2.896	2.392	2.342	2.392	2.512
September .....	2.368	2.882	2.370	2.318	2.369	2.473
October .....	2.512	2.891	2.375	2.276	2.406	2.454
November .....	2.566	2.853	2.424	2.368	2.459	2.521
December .....	2.473	2.891	2.335	2.348	2.371	2.509
<b>Average</b> .....	<b>2.389</b>	<b>2.736</b>	<b>2.316</b>	<b>2.257</b>	<b>2.336</b>	<b>2.401</b>
<b>2012</b> January .....	2.591	2.965	2.480	2.452	2.512	2.620
February .....	2.739	3.070	2.632	2.556	2.654	2.705
March .....	2.921	3.159	2.717	2.601	2.772	2.784
April .....	2.805	3.201	2.624	2.596	2.670	2.731
May .....	2.589	3.170	2.513	2.652	2.536	2.784

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
NA=Not available.

Notes: • Sales for resale are those made to purchasers other than ultimate consumers. Sales to end users are those made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and commercial consumers. • Values for the current month are preliminary. • Prices prior to 1983 are U.S. Energy Information Administration (EIA) estimates. See Note

6, "Historical Petroleum Prices," at end of section. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1978.

Sources: • **1978-2009:** EIA, *Petroleum Marketing Annual 2009*, Table 16.  
• **2010 forward:** EIA, *Petroleum Marketing Monthly*, August 2012, Table 16.

**Table 9.6 Refiner Prices of Petroleum Products for Resale**  
(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Finished Motor Gasoline <sup>b</sup>	Finished Aviation Gasoline	Kerosene-Type Jet Fuel	Kerosene	No. 2 Fuel Oil	No. 2 Diesel Fuel	Propane (Consumer Grade)
1978 Average .....	0.434	0.537	0.386	0.404	0.369	0.365	0.237
1980 Average .....	0.941	1.128	0.868	0.864	0.803	0.801	0.415
1985 Average .....	0.835	1.130	0.794	0.874	0.776	0.772	0.398
1990 Average .....	0.786	1.063	0.773	0.839	0.697	0.694	0.386
1995 Average .....	0.626	0.975	0.539	0.580	0.511	0.538	0.344
1996 Average .....	0.713	1.055	0.646	0.714	0.639	0.659	0.461
1997 Average .....	0.700	1.065	0.613	0.653	0.590	0.606	0.416
1998 Average .....	0.526	0.912	0.450	0.465	0.422	0.444	0.288
1999 Average .....	0.645	1.007	0.533	0.550	0.493	0.546	0.342
2000 Average .....	0.963	1.330	0.880	0.969	0.886	0.898	0.595
2001 Average .....	0.886	1.256	0.763	0.821	0.756	0.784	0.540
2002 Average .....	0.828	1.146	0.716	0.752	0.694	0.724	0.431
2003 Average .....	1.002	1.288	0.871	0.955	0.881	0.883	0.607
2004 Average .....	1.288	1.627	1.208	1.271	1.125	1.187	0.751
2005 Average .....	1.670	2.076	1.723	1.757	1.623	1.737	0.933
2006 Average .....	1.969	2.490	1.961	2.007	1.834	2.012	1.031
2007 Average .....	2.182	2.758	2.171	2.249	2.072	2.203	1.194
2008 Average .....	2.586	3.342	3.020	2.851	2.745	2.994	1.437
2009 Average .....	1.767	2.480	1.719	1.844	1.657	1.713	0.921
<b>2010</b> January .....	2.097	2.759	2.121	2.282	2.075	2.078	1.332
February .....	2.033	2.662	1.999	2.216	1.986	2.025	1.324
March .....	2.197	2.906	2.129	2.219	2.100	2.163	1.179
April .....	2.265	2.999	2.247	2.281	2.214	2.312	1.144
May .....	2.152	2.945	2.186	2.110	2.129	2.177	1.098
June .....	2.113	2.835	2.094	2.103	2.037	2.120	1.049
July .....	2.113	2.891	2.100	2.046	2.001	2.098	1.012
August .....	2.095	2.842	2.138	2.125	2.041	2.161	1.084
September .....	2.088	2.805	2.131	2.163	2.093	2.190	1.151
October .....	2.198	2.890	2.263	2.384	2.221	2.325	1.253
November .....	2.243	2.868	2.342	NA	2.308	2.392	1.277
December .....	2.383	3.024	2.459	2.744	2.435	2.486	1.322
<b>Average .....</b>	<b>2.165</b>	<b>2.874</b>	<b>2.185</b>	<b>2.299</b>	<b>2.147</b>	<b>2.214</b>	<b>1.212</b>
<b>2011</b> January .....	2.472	3.161	2.585	2.804	2.585	2.621	1.380
February .....	2.584	3.248	2.783	2.974	2.737	2.820	1.401
March .....	2.934	3.607	3.095	3.196	2.996	3.134	1.403
April .....	3.218	4.035	3.259	3.296	3.167	3.296	1.433
May .....	3.174	4.096	3.188	W	3.039	3.116	1.515
June .....	2.970	3.847	3.101	3.054	2.956	3.079	1.503
July .....	3.058	4.011	3.090	3.158	3.024	3.135	1.513
August .....	2.949	3.899	3.040	3.089	2.927	3.032	1.522
September .....	2.896	3.878	3.025	3.073	2.927	3.035	1.557
October .....	2.805	3.616	2.962	3.096	2.915	3.035	1.511
November .....	2.701	3.494	3.089	3.258	3.050	3.157	1.498
December .....	2.614	3.424	2.951	3.006	2.928	2.927	1.444
<b>Average .....</b>	<b>2.867</b>	<b>3.739</b>	<b>3.014</b>	<b>3.065</b>	<b>2.907</b>	<b>3.034</b>	<b>1.467</b>
<b>2012</b> January .....	2.747	3.576	3.059	3.197	3.027	3.018	1.341
February .....	2.936	3.788	3.186	3.293	3.166	3.163	1.282
March .....	3.203	4.052	3.296	3.306	3.211	3.308	1.293
April .....	<sup>R</sup> 3.189	4.157	3.255	3.243	3.153	3.252	1.163
May .....	3.016	4.004	3.079	2.996	2.976	3.039	0.950

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 5, "Motor Gasoline Prices," at end of section.

R=Revised. NA=Not available. W=Value withheld to avoid disclosure of individual company data.

Notes: • Sales for resale are those made to purchasers other than ultimate consumers. Sales to end users are shown in Table 9.7; they are sales made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and residential and commercial consumers. • Values

for the current month are preliminary. • Prices prior to 1983 are U.S. Energy Information Administration (EIA) estimates. See Note 6, "Historical Petroleum Prices," at end of section. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1978.

Sources: • **1978-2009:** EIA, *Petroleum Marketing Annual 2009*, Table 4. • **2010 forward:** EIA, *Petroleum Marketing Monthly*, August 2012, Table 4.

**Table 9.7 Refiner Prices of Petroleum Products to End Users**  
(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Finished Motor Gasoline <sup>b</sup>	Finished Aviation Gasoline	Kerosene-Type Jet Fuel	Kerosene	No. 2 Fuel Oil	No. 2 Diesel Fuel	Propane (Consumer Grade)
1978 Average .....	0.484	0.516	0.387	0.421	0.400	0.377	0.335
1980 Average .....	1.035	1.084	0.868	0.902	0.788	0.818	0.482
1985 Average .....	0.912	1.201	0.796	1.030	0.849	0.789	0.717
1990 Average .....	0.883	1.120	0.766	0.923	0.734	0.725	0.745
1995 Average .....	0.765	1.005	0.540	0.589	0.562	0.560	0.492
1996 Average .....	0.847	1.116	0.651	0.740	0.673	0.681	0.605
1997 Average .....	0.839	1.128	0.613	0.745	0.636	0.642	0.552
1998 Average .....	0.673	0.975	0.452	0.501	0.482	0.494	0.405
1999 Average .....	0.781	1.059	0.543	0.605	0.558	0.584	0.458
2000 Average .....	1.106	1.306	0.899	1.123	0.927	0.935	0.603
2001 Average .....	1.032	1.323	0.775	1.045	0.829	0.842	0.506
2002 Average .....	0.947	1.288	0.721	0.990	0.737	0.762	0.419
2003 Average .....	1.156	1.493	0.872	1.224	0.933	0.944	0.577
2004 Average .....	1.435	1.819	1.207	1.160	1.173	1.243	0.839
2005 Average .....	1.829	2.231	1.735	1.957	1.705	1.786	1.089
2006 Average .....	2.128	2.682	1.998	2.244	1.982	2.096	1.358
2007 Average .....	2.345	2.849	2.165	2.263	2.241	2.267	1.489
2008 Average .....	2.775	3.273	3.052	3.283	2.986	3.150	1.892
2009 Average .....	1.888	2.442	1.704	2.675	1.962	1.834	1.220
<b>2010</b> January .....	2.240	2.914	2.129	2.986	2.369	2.192	1.913
February .....	2.173	2.855	2.018	2.974	2.310	2.144	2.009
March .....	2.301	3.103	2.144	2.978	2.425	2.265	NA
April .....	2.370	3.201	2.272	3.040	2.527	2.410	1.326
May .....	2.353	3.129	2.199	2.938	2.487	2.343	1.264
June .....	2.251	2.981	2.105	2.965	2.393	2.284	1.204
July .....	2.247	3.028	2.103	NA	2.246	2.212	1.162
August .....	2.250	2.967	2.158	2.772	2.379	2.260	1.211
September .....	2.219	2.893	2.148	2.898	2.346	2.269	1.283
October .....	2.319	3.000	2.298	3.058	2.580	2.389	1.425
November .....	2.378	3.095	2.374	3.130	2.641	2.457	NA
December .....	2.514	3.218	2.484	3.276	2.749	2.554	1.863
<b>Average .....</b>	<b>2.301</b>	<b>3.028</b>	<b>2.201</b>	<b>3.063</b>	<b>2.462</b>	<b>2.314</b>	<b>1.481</b>
<b>2011</b> January .....	2.615	3.323	2.623	3.358	2.889	2.681	NA
February .....	2.712	3.374	2.818	3.506	3.020	2.867	1.823
March .....	3.072	3.767	3.161	3.697	3.255	3.189	1.763
April .....	3.340	4.132	3.306	3.796	3.430	3.370	NA
May .....	3.419	4.091	3.220	3.894	3.337	3.231	1.648
June .....	3.184	3.913	3.138	3.802	3.193	3.183	1.681
July .....	3.172	4.027	3.118	3.812	3.294	3.214	1.620
August .....	3.134	3.920	3.057	3.851	3.251	3.143	1.650
September .....	3.090	3.915	3.059	3.873	3.288	3.127	1.702
October .....	2.980	3.697	2.987	3.823	3.346	3.108	1.706
November .....	2.922	3.620	3.124	3.892	3.403	3.225	1.773
December .....	2.808	W	2.963	3.824	3.255	3.024	1.691
<b>Average .....</b>	<b>3.050</b>	<b>3.803</b>	<b>3.054</b>	<b>3.616</b>	<b>3.193</b>	<b>3.117</b>	<b>1.709</b>
<b>2012</b> January .....	2.914	3.732	3.087	3.848	3.345	3.093	1.655
February .....	3.087	W	3.206	3.874	3.495	3.224	1.518
March .....	3.389	4.133	3.337	3.919	3.522	3.378	1.470
April .....	<sup>R</sup> 3.405	4.313	3.283	3.916	3.509	<sup>R</sup> 3.342	1.352
May .....	3.289	W	3.099	3.741	3.259	3.164	1.080

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 5, "Motor Gasoline Prices," at end of section.

R=Revised. NA=Not available. W=Value withheld to avoid disclosure of individual company data.

Notes: • Sales to end users are those made directly to ultimate consumers, including bulk consumers (such as agriculture, industry, and electric utilities) and residential and commercial consumers. Sales for resale are shown in Table 9.6; they are sales made to purchasers other than ultimate consumers. • Values for

the current month are preliminary. • Prices prior to 1983 are U.S. Energy Information Administration (EIA) estimates. See Note 6, "Historical Petroleum Prices," at end of section. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1978.

Sources: • **1978-2009:** EIA, *Petroleum Marketing Annual 2009*, Table 2. • **2010 forward:** EIA, *Petroleum Marketing Monthly*, August 2012, Table 2.

**Table 9.8a No. 2 Distillate Prices to Residences: Northeastern States**  
(Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Maine	New Hampshire	Vermont	Massachusetts	Rhode Island	Connecticut	New York	New Jersey	Pennsylvania
<b>1978 Average</b> .....	0.486	0.503	0.508	0.488	0.507	0.501	0.501	0.496	0.488
<b>1980 Average</b> .....	0.963	1.004	1.015	0.978	1.011	0.983	0.982	0.979	0.964
<b>1985 Average</b> .....	0.997	1.024	1.077	1.070	1.067	1.080	1.113	1.059	1.023
<b>1990 Average</b> .....	0.989	1.028	1.070	1.084	1.086	1.098	1.125	1.087	1.026
<b>1995 Average</b> .....	0.787	0.779	0.853	0.844	0.874	0.864	0.955	0.888	0.826
<b>1996 Average</b> .....	0.972	0.940	0.969	0.976	0.986	0.986	1.063	1.024	0.953
<b>1997 Average</b> .....	0.942	0.942	0.987	0.960	0.989	0.963	1.065	1.033	0.950
<b>1998 Average</b> .....	0.788	0.788	0.873	0.818	0.868	0.831	0.948	0.892	0.814
<b>1999 Average</b> .....	0.813	0.770	0.854	0.836	0.858	0.852	0.969	0.913	0.815
<b>2000 Average</b> .....	1.297	1.281	1.255	1.273	1.259	1.291	1.442	1.404	1.224
<b>2001 Average</b> .....	1.217	1.256	1.261	1.221	1.236	1.239	1.363	1.314	1.159
<b>2002 Average</b> .....	1.129	1.119	1.172	1.141	1.124	1.118	1.218	1.220	1.064
<b>2003 Average</b> .....	1.314	1.312	1.309	1.386	1.344	1.355	1.436	1.489	1.304
<b>2004 Average</b> .....	1.511	1.497	1.505	1.559	1.511	1.518	1.627	1.662	1.489
<b>2005 Average</b> .....	1.986	1.972	1.987	2.064	2.000	2.012	2.105	2.166	1.974
<b>2006 Average</b> .....	2.294	2.283	2.408	2.355	2.360	2.357	2.458	2.467	2.286
<b>2007 Average</b> .....	2.540	2.535	2.679	2.576	2.602	2.615	2.674	2.664	2.508
<b>2008 Average</b> .....	3.199	3.207	3.323	3.197	3.210	3.195	3.293	3.267	3.157
<b>2009</b> January .....	2.506	2.537	2.774	2.356	2.346	2.576	2.543	2.389	2.427
February .....	2.404	2.426	2.693	2.226	2.209	2.429	2.447	2.288	2.268
March .....	2.237	2.283	2.545	2.166	2.127	2.362	2.334	2.166	2.202
April .....	2.250	2.246	2.437	2.192	2.143	2.314	2.338	2.187	2.177
May .....	2.175	2.151	2.370	2.142	2.169	2.225	2.300	2.187	2.190
June .....	2.295	2.201	2.376	2.371	2.385	2.413	2.428	2.381	2.211
July .....	2.268	2.077	2.324	2.312	2.285	2.354	2.291	2.322	2.137
August .....	2.350	2.243	2.378	2.432	2.454	2.490	2.523	2.454	2.257
September .....	2.333	2.272	2.403	2.386	2.357	2.349	2.455	2.437	2.196
October .....	2.391	2.373	2.484	2.470	2.537	2.516	2.574	2.541	2.315
November .....	2.461	2.484	2.604	2.619	2.685	2.645	2.747	2.710	2.520
December .....	2.486	2.523	2.640	2.634	2.718	2.665	2.733	2.731	2.536
<b>Average</b> .....	<b>2.382</b>	<b>2.377</b>	<b>2.593</b>	<b>2.358</b>	<b>2.376</b>	<b>2.487</b>	<b>2.504</b>	<b>2.404</b>	<b>2.330</b>
<b>2010</b> January .....	2.583	2.611	2.753	2.762	2.856	2.764	2.893	2.928	2.692
February .....	2.536	2.600	2.705	2.729	2.777	2.730	2.845	2.871	2.697
March .....	2.560	2.632	2.747	2.795	2.800	2.758	2.801	2.929	2.755
April .....	2.565	2.651	2.771	2.868	2.959	2.815	2.845	2.946	2.752
May .....	2.511	2.636	2.710	2.811	2.921	2.736	2.781	2.873	2.680
June .....	2.479	2.574	2.649	2.716	2.829	2.705	2.691	2.747	2.561
July .....	2.478	2.532	2.614	2.656	2.728	2.653	2.651	2.715	2.519
August .....	2.469	2.513	2.619	2.651	2.735	2.634	2.668	2.701	2.543
September .....	2.539	2.543	2.657	2.686	2.745	2.647	2.721	2.754	2.583
October .....	2.677	2.642	2.784	2.860	2.942	2.822	2.848	2.912	2.759
November .....	2.774	2.772	2.924	2.969	3.044	2.946	2.969	3.077	2.892
December .....	2.910	2.904	3.032	3.126	3.197	3.106	3.147	3.278	3.061
<b>Average</b> .....	<b>2.639</b>	<b>2.680</b>	<b>2.795</b>	<b>2.850</b>	<b>2.927</b>	<b>2.835</b>	<b>2.894</b>	<b>2.973</b>	<b>2.780</b>
<b>2011</b> January .....	3.071	3.102	3.186	3.313	3.368	3.268	3.281	3.458	3.237
February .....	3.188	3.269	3.330	3.493	3.536	3.477	3.428	3.624	3.369

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

Notes: • States are grouped in Tables 9.8a–9.8c by geographic region of the country. • Values for the current month are preliminary. • Prices prior to 1983 are U.S. Energy Information Administration (EIA) estimates. See Note 6, "Historical Petroleum Prices," at end of section.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1978.

Sources: • 1978–2009: EIA, *Petroleum Marketing Annual 2009*, Table 15.

• 2010 and 2011: EIA, *Petroleum Marketing Monthly*, July 2011, Table 15.

Due to budget cuts in 2011, EIA adjusted its data programs. No. 2 distillate fuel oil prices to residences (Tables 9.8a–9.8c) will not be available for March 2011 forward.



**Table 9.8b No. 2 Distillate Prices to Residences: Selected South Atlantic and Midwestern States** (Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Delaware	District of Columbia	Maryland	Virginia	West Virginia	Ohio	Michigan	Indiana	Illinois	Wisconsin	Minnesota
1978 Average	0.478	0.507	0.492	0.491	0.462	0.474	0.479	0.485	0.465	0.447	0.478
1980 Average	0.954	1.026	0.979	0.985	0.922	0.919	0.978	0.996	0.958	0.915	0.999
1985 Average	1.046	1.143	1.088	1.063	0.980	0.997	1.021	0.991	0.975	0.983	1.019
1990 Average	1.058	1.078	1.119	1.106	0.991	0.981	1.009	0.993	0.961	0.942	1.014
1995 Average	0.870	1.010	0.936	0.844	0.815	0.808	0.860	0.816	0.785	0.812	0.801
1996 Average	0.984	1.178	1.063	0.952	0.960	0.921	0.977	0.912	0.893	0.899	0.909
1997 Average	0.984	1.174	1.057	0.948	0.962	0.913	0.942	0.865	0.870	0.933	0.899
1998 Average	0.858	1.022	0.902	0.856	0.818	0.767	0.804	0.748	0.735	0.801	0.738
1999 Average	0.884	1.011	0.907	0.870	0.789	0.820	0.883	0.793	0.716	0.847	0.774
2000 Average	1.270	W	1.351	1.269	1.251	1.220	NA	1.207	1.095	1.171	1.156
2001 Average	1.234	1.431	1.342	1.202	1.139	1.160	NA	1.133	1.121	1.180	1.122
2002 Average	1.164	W	1.201	1.057	1.054	1.058	1.109	1.025	0.975	1.073	1.051
2003 Average	1.433	W	1.455	1.311	1.304	1.284	1.321	1.202	1.198	1.269	1.218
2004 Average	1.570	W	1.632	1.462	1.493	1.475	1.539	1.537	1.405	1.465	1.433
2005 Average	2.075	W	2.127	2.044	2.043	2.009	2.053	2.017	2.021	1.993	1.987
2006 Average	2.381	W	2.398	2.268	2.261	2.244	2.329	2.317	2.312	2.297	2.268
2007 Average	2.584	W	2.668	2.407	2.478	2.494	2.588	2.557	2.528	2.571	2.587
2008 Average	3.187	W	3.273	3.124	3.221	3.147	3.067	3.105	3.152	3.088	3.065
<b>2009</b> January	2.428	W	2.470	2.225	2.329	2.041	1.991	2.062	2.069	2.004	1.974
February	2.310	W	2.407	2.145	2.188	1.888	1.866	1.912	1.869	1.854	1.813
March	2.253	W	2.275	1.999	2.042	1.826	1.806	1.822	1.836	1.781	1.735
April	2.267	W	2.263	NA	2.035	1.917	1.810	1.922	1.983	1.870	1.890
May	2.253	W	2.224	1.824	2.008	1.941	1.807	1.972	NA	1.975	1.872
June	2.289	W	2.320	2.037	2.119	2.180	2.095	2.176	2.060	2.200	2.156
July	2.253	W	2.307	2.055	2.122	2.103	1.964	2.181	NA	2.166	2.092
August	2.340	W	2.397	2.140	2.217	2.279	2.153	2.321	2.147	2.284	2.297
September	2.309	W	2.396	2.118	2.253	2.205	2.179	2.318	NA	2.262	2.232
October	2.505	W	2.561	2.322	2.397	2.364	2.336	2.391	2.386	2.331	2.301
November	2.683	W	2.707	2.408	2.504	2.479	2.485	2.520	2.483	2.421	2.388
December	2.724	W	2.763	2.495	2.496	2.493	2.447	2.507	2.427	2.395	2.394
<b>Average</b>	<b>2.421</b>	<b>W</b>	<b>2.473</b>	<b>2.193</b>	<b>2.265</b>	<b>2.130</b>	<b>2.096</b>	<b>2.189</b>	<b>2.155</b>	<b>2.105</b>	<b>2.124</b>
<b>2010</b> January	2.878	W	2.861	2.594	2.681	2.572	2.526	2.565	2.526	2.466	2.505
February	2.857	W	2.833	2.561	2.714	2.533	2.501	2.510	2.516	2.421	W
March	2.988	W	2.894	2.587	2.712	2.585	2.640	2.614	2.660	2.537	2.580
April	NA	W	2.858	NA	2.676	2.566	2.731	2.679	2.777	2.640	2.668
May	2.853	W	2.808	2.435	2.583	2.574	2.669	NA	2.783	2.567	2.581
June	2.695	W	2.705	2.356	2.501	2.436	2.505	2.482	NA	2.478	2.557
July	2.655	W	2.636	2.345	2.499	2.436	2.481	2.510	2.582	2.508	2.466
August	2.617	W	2.669	2.351	2.547	2.511	2.508	2.550	W	2.514	2.559
September	2.678	W	2.692	2.397	2.577	2.554	2.596	2.607	2.732	2.562	2.596
October	2.847	W	2.822	2.567	2.720	2.695	2.734	2.701	NA	2.702	2.719
November	NA	W	2.985	2.754	2.834	2.802	2.830	2.864	2.915	2.788	2.866
December	3.223	W	3.195	2.920	3.024	2.923	2.933	2.979	3.030	2.894	2.965
<b>Average</b>	<b>2.951</b>	<b>W</b>	<b>2.925</b>	<b>2.621</b>	<b>2.724</b>	<b>2.653</b>	<b>2.657</b>	<b>2.670</b>	<b>2.749</b>	<b>2.610</b>	<b>2.470</b>
<b>2011</b> January	3.431	W	3.377	3.093	3.204	3.039	3.041	3.109	3.098	3.008	3.031
February	3.560	W	3.508	3.222	3.365	3.189	3.196	3.246	3.286	3.169	3.184

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
NA=Not available. W=Value withheld to avoid disclosure of individual company data.

Notes: • States are grouped in Tables 9.8a–9.8c by geographic region of the country. • Values for the current month are preliminary. • Prices prior to 1983 are U.S. Energy Information Administration (EIA) estimates. See Note 6, "Historical

Petroleum Prices," at end of section.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1978.

Sources: • 1978-2009: EIA, *Petroleum Marketing Annual 2009*, Table 15.  
• 2010 and 2011: EIA, *Petroleum Marketing Monthly*, July 2011, Table 15.

Due to budget cuts in 2011, EIA adjusted its data programs. No. 2 distillate fuel oil prices to residences (Tables 9.8a–9.8c) will not be available for March 2011 forward.

**Table 9.8c No. 2 Distillate Prices to Residences: Selected Western States and U.S. Average** (Dollars<sup>a</sup> per Gallon, Excluding Taxes)

	Idaho	Washington	Oregon	Alaska	U.S. Average
1978 Average .....	0.436	0.486	0.458	0.532	0.490
1980 Average .....	0.916	1.008	0.973	0.978	0.974
1985 Average .....	0.972	1.011	0.971	1.083	1.053
1990 Average .....	0.974	1.029	0.970	1.101	1.063
1995 Average .....	0.839	0.962	0.894	0.834	0.867
1996 Average .....	0.933	1.080	0.989	0.909	0.989
1997 Average .....	0.953	1.139	1.031	0.973	0.984
1998 Average .....	0.784	0.978	0.861	0.852	0.852
1999 Average .....	0.762	1.065	0.938	0.966	0.876
2000 Average .....	1.170	1.445	1.368	1.337	1.311
2001 Average .....	1.038	1.336	1.211	1.377	1.250
2002 Average .....	0.919	1.204	1.060	1.087	1.129
2003 Average .....	1.188	1.487	1.303	1.243	1.355
2004 Average .....	1.495	1.749	1.594	1.524	1.548
2005 Average .....	2.123	2.385	2.146	2.061	2.052
2006 Average .....	2.391	2.681	2.411	2.395	2.365
2007 Average .....	2.598	2.909	2.500	2.518	2.592
2008 Average .....	3.078	3.401	3.060	3.485	3.219
<b>2009</b> January .....	1.879	2.388	1.939	2.160	2.426
February .....	1.762	2.253	1.819	NA	2.309
March .....	1.674	2.124	1.727	1.946	2.210
April .....	1.863	2.414	1.986	2.140	2.211
May .....	1.878	2.473	2.050	2.256	2.167
June .....	2.148	2.544	2.278	2.506	2.307
July .....	2.123	2.335	2.149	2.362	2.219
August .....	2.158	2.489	2.326	2.554	2.369
September .....	2.273	2.658	2.357	NA	2.334
October .....	2.333	2.737	2.469	NA	2.458
November .....	2.459	2.871	2.551	NA	2.608
December .....	2.354	2.830	2.475	NA	2.628
<b>Average .....</b>	<b>2.048</b>	<b>2.491</b>	<b>2.132</b>	<b>2.503</b>	<b>2.386</b>
<b>2010</b> January .....	2.392	2.918	2.583	NA	2.763
February .....	2.412	2.817	2.536	2.790	2.658
March .....	2.569	2.924	2.664	2.884	2.757
April .....	2.747	3.105	2.817	2.965	2.787
May .....	2.675	3.053	2.685	2.958	2.723
June .....	NA	2.892	2.653	2.891	2.623
July .....	2.540	NA	NA	2.878	2.584
August .....	2.598	2.757	2.625	2.901	2.597
September .....	2.676	NA	2.760	2.944	2.641
October .....	2.853	3.174	2.871	3.041	2.795
November .....	2.937	3.195	2.935	3.070	2.926
December .....	2.980	3.242	2.991	3.134	3.089
<b>Average .....</b>	<b>2.716</b>	<b>3.039</b>	<b>2.776</b>	<b>2.951</b>	<b>2.798</b>
<b>2011</b> January .....	3.005	3.350	3.079	3.210	3.251
February .....	3.173	3.537	3.295	3.366	3.409

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

NA=Not available.

Notes: • States are grouped in Tables 9.8a–9.8c by geographic region of the country. • Values for the current month are preliminary. • Prices prior to 1983 are U.S. Energy Information Administration (EIA) estimates. See Note 6, "Historical

Petroleum Prices," at end of section.


Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1978.

Sources: • 1978-2009: EIA, *Petroleum Marketing Annual 2009*, Table 15.  
• 2010 and 2011: EIA, *Petroleum Marketing Monthly*, July 2011, Table 15.

Due to budget cuts in 2011, EIA adjusted its data programs. No. 2 distillate fuel oil prices to residences (Tables 9.8a–9.8c) will not be available for March 2011 forward.


**Figure 9.2 Average Retail Prices of Electricity**  
(Cents<sup>a</sup> per Kilowatthour)

By Sector, 1973-2011



<sup>a</sup>Prices are not adjusted for inflation. See "Nominal Price" in Glossary.  
<sup>b</sup>Public street and highway lighting, interdepartmental sales, other sales to public authorities, agricultural and irrigation, and transportation including railroads and railways.


By Sector, Monthly



Note: Includes taxes.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
Source: Table 9.9.


**Figure 9.3 Cost of Fossil-Fuel Receipts at Electric Generating Plants**  
(Dollars<sup>a</sup> per Million Btu, Including Taxes)

Costs, 1973-2011



<sup>a</sup>Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

Costs, Monthly



Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
Source: Table 9.10.

**Table 9.9 Average Retail Prices of Electricity**  
(Cents<sup>a</sup> per Kilowatthour, Including Taxes)

	Residential	Commercial <sup>b</sup>	Industrial <sup>c</sup>	Transportation <sup>d</sup>	Other <sup>e</sup>	Total
<b>1973 Average</b> .....	2.50	2.40	1.30	NA	2.10	2.00
<b>1975 Average</b> .....	3.50	3.50	2.10	NA	3.10	2.90
<b>1980 Average</b> .....	5.40	5.50	3.70	NA	4.80	4.70
<b>1985 Average</b> .....	7.39	7.27	4.97	NA	6.09	6.44
<b>1990 Average</b> .....	7.83	7.34	4.74	NA	6.40	6.57
<b>1995 Average</b> .....	8.40	7.69	4.66	NA	6.88	6.89
<b>1996 Average</b> .....	8.36	7.64	4.60	NA	6.91	6.86
<b>1997 Average</b> .....	8.43	7.59	4.53	NA	6.91	6.85
<b>1998 Average</b> .....	8.26	7.41	4.48	NA	6.63	6.74
<b>1999 Average</b> .....	8.16	7.26	4.43	NA	6.35	6.64
<b>2000 Average</b> .....	8.24	7.43	4.64	NA	6.56	6.81
<b>2001 Average</b> .....	8.58	7.92	5.05	NA	7.20	7.29
<b>2002 Average</b> .....	8.44	7.89	4.88	NA	6.75	7.20
<b>2003 Average</b> .....	8.72	8.03	5.11	7.54	--	7.44
<b>2004 Average</b> .....	8.95	8.17	5.25	7.18	--	7.61
<b>2005 Average</b> .....	9.45	8.67	5.73	8.57	--	8.14
<b>2006 Average</b> .....	10.40	9.46	6.16	9.54	--	8.90
<b>2007 Average</b> .....	10.65	9.65	6.39	9.70	--	9.13
<b>2008 Average</b> .....	11.26	10.36	6.83	10.74	--	9.74
<b>2009 Average</b> .....	11.51	10.17	6.81	10.65	--	9.82
<b>2010</b> .....						
January .....	10.49	9.55	6.50	10.17	--	9.28
February .....	10.89	9.89	6.55	10.48	--	9.47
March .....	11.11	9.95	6.53	10.28	--	9.48
April .....	11.71	9.95	6.55	10.52	--	9.53
May .....	11.91	10.15	6.64	10.52	--	9.72
June .....	11.91	10.56	6.96	11.14	--	10.18
July .....	12.04	10.72	7.23	10.95	--	10.46
August .....	12.03	10.62	7.22	10.86	--	10.40
September .....	11.95	10.52	7.00	10.53	--	10.17
October .....	11.86	10.25	6.80	10.49	--	9.81
November .....	11.62	9.99	6.56	10.47	--	9.55
December .....	11.06	9.82	6.60	10.39	--	9.52
<b>Average</b> .....	<b>11.54</b>	<b>10.19</b>	<b>6.77</b>	<b>10.57</b>	--	<b>9.83</b>
<b>2011</b> .....						
January .....	10.95	9.85	6.59	10.39	--	9.55
February .....	11.12	10.07	6.70	10.69	--	9.64
March .....	11.59	10.01	6.60	10.35	--	9.64
April .....	11.75	10.05	6.60	10.14	--	9.64
May .....	12.01	10.27	6.75	10.80	--	9.87
June .....	12.05	10.75	7.21	11.12	--	10.35
July .....	12.16	10.77	7.39	11.32	--	10.57
August .....	12.15	10.82	7.46	10.93	--	10.58
September .....	12.25	10.67	7.23	10.88	--	10.39
October .....	12.13	10.30	6.82	10.37	--	9.90
November .....	11.88	10.06	6.60	10.04	--	9.67
December .....	11.52	9.85	6.60	9.90	--	9.64
<b>Average</b> .....	<b>11.80</b>	<b>10.32</b>	<b>6.89</b>	<b>10.58</b>	--	<b>9.99</b>
<b>2012</b> .....						
January .....	11.43	9.88	6.50	9.73	--	9.65
February .....	11.55	10.01	6.52	9.62	--	9.64
March .....	11.76	9.91	6.52	9.86	--	9.59
April .....	11.95	9.86	6.44	10.05	--	9.52
May .....	11.97	10.02	6.57	9.83	--	9.70
<b>5-Month Average</b> .....	<b>11.71</b>	<b>9.94</b>	<b>6.51</b>	<b>9.81</b>	--	<b>9.62</b>
<b>2011 5-Month Average</b> .....	<b>11.43</b>	<b>10.05</b>	<b>6.65</b>	<b>10.47</b>	--	<b>9.67</b>
<b>2010 5-Month Average</b> .....	<b>11.13</b>	<b>9.90</b>	<b>6.56</b>	<b>10.39</b>	--	<b>9.49</b>

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Price" in Glossary.

<sup>b</sup> Commercial sector. For 1973–2002, prices exclude public street and highway lighting, interdepartmental sales, and other sales to public authorities.

<sup>c</sup> Industrial sector. For 1973–2002, prices exclude agriculture and irrigation.

<sup>d</sup> Transportation sector, including railroads and railways.

<sup>e</sup> Public street and highway lighting, interdepartmental sales, other sales to public authorities, agriculture and irrigation, and transportation including railroads and railways.

NA=Not available. -- =Not applicable.

Notes: • Beginning in 2003, the category "Other" has been replaced by "Transportation," and the categories "Commercial" and "Industrial" have been redefined. • Prices are calculated by dividing revenue by sales. Revenue may not correspond to sales for a particular month because of energy service provider billing and accounting procedures. That lack of correspondence could result in uncharacteristic increases or decreases in the monthly prices. • Prices include State and local taxes, energy or demand charges, customer service charges, environmental surcharges, franchise fees, fuel adjustments, and other

miscellaneous charges applied to end-use customers during normal billing operations. Prices do not include deferred charges, credits, or other adjustments, such as fuel or revenue from purchased power, from previous reporting periods.

• See Note 7, "Electricity Retail Prices," at end of section for plant coverage, and for information on preliminary and final values. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1973.

Sources: • **1973-September 1977:** Federal Power Commission, Form FPC-5, "Monthly Statement of Electric Operating Revenues and Income." • **October 1977-February 1980:** Federal Energy Regulatory Commission (FERC), Form FPC-5, "Monthly Statement of Electric Operating Revenues and Income." • **March 1980-1982:** FERC, Form FERC-5, "Electric Utility Company Monthly Statement." • **1983:** U.S. Energy Information Administration (EIA), Form EIA-826, "Electric Utility Company Monthly Statement." • **1984-1997:** EIA, Form EIA-861, "Annual Electric Utility Report." • **1998 forward:** EIA, *Electric Power Monthly*, July 2012, Table 5.3.

**Table 9.10 Cost of Fossil-Fuel Receipts at Electric Generating Plants**  
(Dollars<sup>a</sup> per Million Btu, Including Taxes)


	Coal	Petroleum				Natural Gas <sup>e</sup>	All Fossil Fuels <sup>f</sup>
		Residual Fuel Oil <sup>b</sup>	Distillate Fuel Oil <sup>c</sup>	Petroleum Coke	Total <sup>d</sup>		
<b>1973 Average</b> .....	0.41	0.79	NA	NA	0.80	0.34	0.48
<b>1975 Average</b> .....	.81	2.01	NA	NA	2.02	.75	1.04
<b>1980 Average</b> .....	1.35	4.27	NA	NA	4.35	2.20	1.93
<b>1985 Average</b> .....	1.65	4.24	NA	NA	4.32	3.44	2.09
<b>1990 Average</b> .....	1.45	3.32	5.38	.80	3.35	2.32	1.69
<b>1995 Average</b> .....	1.32	2.59	3.99	.65	2.57	1.98	1.45
<b>1996 Average</b> .....	1.29	3.03	4.87	.78	3.03	2.64	1.52
<b>1997 Average</b> .....	1.27	2.79	4.49	.91	2.73	2.76	1.52
<b>1998 Average</b> .....	1.25	2.08	3.30	.71	2.02	2.38	1.44
<b>1999 Average</b> .....	1.22	2.44	4.03	.65	2.36	2.57	1.44
<b>2000 Average</b> .....	1.20	4.29	6.65	.58	4.18	4.30	1.74
<b>2001 Average</b> .....	1.23	3.73	6.30	.78	3.69	4.49	1.73
<b>2002 Average<sup>g</sup></b> .....	1.25	3.73	5.34	.78	3.34	3.56	1.86
<b>2003 Average</b> .....	1.28	4.66	6.82	.72	4.33	5.39	2.28
<b>2004 Average</b> .....	1.36	4.73	8.02	.83	4.29	5.96	2.48
<b>2005 Average</b> .....	1.54	7.06	11.72	1.11	6.44	8.21	3.25
<b>2006 Average</b> .....	1.69	7.85	13.28	1.33	6.23	6.94	3.02
<b>2007 Average</b> .....	1.77	8.64	14.85	1.51	7.17	7.11	3.23
<b>2008 Average</b> .....	2.07	13.62	21.46	2.11	10.87	9.01	4.12
<b>2009 Average</b> .....	2.21	8.98	13.22	1.61	7.02	4.74	3.04
<b>2010</b> January .....	2.23	11.85	15.73	1.72	9.72	6.71	3.74
February .....	2.27	12.11	15.69	1.80	9.51	6.07	3.45
March .....	2.31	12.44	16.42	2.09	8.95	5.29	3.16
April .....	2.29	13.17	17.10	2.18	7.95	4.71	3.01
May .....	2.26	12.36	16.54	2.22	9.47	4.79	3.12
June .....	2.25	11.96	16.12	2.15	9.26	5.12	3.34
July .....	2.27	12.28	15.89	2.42	9.63	5.18	3.51
August .....	2.30	12.28	16.24	2.65	9.18	4.92	3.39
September .....	2.28	12.34	16.53	2.67	9.35	4.45	3.10
October .....	2.27	13.53	17.14	2.43	9.13	4.30	2.94
November .....	2.26	14.06	17.43	2.22	10.86	4.35	2.94
December .....	2.23	14.61	18.56	2.57	11.29	5.43	3.32
<b>Average</b> .....	<b>2.27</b>	<b>12.57</b>	<b>16.61</b>	<b>2.28</b>	<b>9.54</b>	<b>5.09</b>	<b>3.26</b>
<b>2011</b> January .....	2.33	14.65	19.48	2.92	11.71	5.35	3.36
February .....	2.36	15.98	20.93	2.67	12.08	5.06	3.26
March .....	2.34	17.65	22.60	2.94	13.71	4.61	3.12
April .....	2.39	18.30	24.06	2.99	13.73	4.85	3.29
May .....	2.44	17.73	23.17	3.22	13.70	4.85	3.38
June .....	2.42	18.81	22.89	2.57	13.82	5.03	3.49
July .....	2.45	20.17	22.96	3.14	12.22	4.96	3.61
August .....	2.48	19.51	22.48	2.95	11.68	4.72	3.44
September .....	2.44	20.81	22.67	2.79	12.17	4.54	3.26
October .....	2.39	19.69	23.04	2.80	13.68	4.32	3.12
November .....	2.37	19.46	23.33	2.18	13.27	4.08	3.03
December .....	2.35	21.01	22.31	2.29	12.76	4.00	3.00
<b>Average</b> .....	<b>2.40</b>	<b>18.43</b>	<b>22.41</b>	<b>2.80</b>	<b>12.88</b>	<b>4.71</b>	<b>3.29</b>
<b>2012</b> January .....	2.43	20.93	22.96	2.26	13.28	3.67	2.97
February .....	2.39	21.12	23.82	2.01	13.32	3.32	2.83
March .....	2.40	21.79	24.91	1.86	12.83	2.96	2.72
April .....	2.44	22.96	24.72	2.09	13.43	2.74	2.66
May .....	2.44	22.73	23.20	2.15	14.40	2.90	2.74
<b>5-Month Average</b> .....	<b>2.42</b>	<b>21.79</b>	<b>23.78</b>	<b>2.08</b>	<b>13.43</b>	<b>3.10</b>	<b>2.79</b>
<b>2011 5-Month Average</b> .....	<b>2.37</b>	<b>16.92</b>	<b>21.82</b>	<b>2.96</b>	<b>12.98</b>	<b>4.95</b>	<b>3.28</b>
<b>2010 5-Month Average</b> .....	<b>2.27</b>	<b>12.26</b>	<b>16.15</b>	<b>2.01</b>	<b>9.21</b>	<b>5.53</b>	<b>3.29</b>

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
<sup>b</sup> For 1973–2001, electric utility data are for heavy oil (fuel oil nos. 5 and 6, and small amounts of fuel oil no. 4).  
<sup>c</sup> For 1973–2001, electric utility data are for light oil (fuel oil nos. 1 and 2).  
<sup>d</sup> Distillate fuel oil, residual fuel oil, petroleum coke, jet fuel, kerosene, other petroleum, and waste oil. For 1973–1982, data do not include refined motor oil, bunker oil, and liquefied petroleum gases. For 1973–1989, data do not include petroleum coke.  
<sup>e</sup> Natural gas, plus a small amount of supplemental gaseous fuels. For 1973–2000, data also include a small amount of blast furnace gas and other gases derived from fossil fuels.  
<sup>f</sup> Weighted average of costs shown under "Coal," "Petroleum," and "Natural Gas."


<sup>g</sup> Through 2001, data are for electric utilities only. Beginning in 2002, data also include independent power producers, and electric generating plants in the commercial and industrial sectors. See Note 8, "Costs of Fossil-Fuel Receipts at Electric Generating Plants," at end of section for plant coverage.  
 NA=Not available.  
 Notes: • Receipts are purchases of fuel. • Yearly costs are averages of monthly values, weighted by quantities in Btu. • Geographic coverage is the 50 States and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1973.  
 Sources: See end of section.

**Figure 9.4 Natural Gas Prices**  
(Dollars<sup>a</sup> per Thousand Cubic Feet)


Selected Prices, 1973-2011



Consuming Sectors, 1973-2011



Consuming Sectors, Monthly



<sup>a</sup>Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.  
<sup>b</sup>Includes taxes.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#prices>.  
Source: Table 9.11.

**Table 9.11 Natural Gas Prices**  
(Dollars<sup>a</sup> per Thousand Cubic Feet)

	Wellhead Price	City-gate Price	Consuming Sectors <sup>b</sup>								
			Residential		Commercial <sup>c</sup>		Industrial <sup>d</sup>		Transportation	Electric Power <sup>e</sup>	
			Price <sup>f</sup>	Percentage of Sector <sup>g</sup>	Price <sup>f</sup>	Percentage of Sector <sup>g</sup>	Price <sup>f</sup>	Percentage of Sector <sup>g</sup>	Vehicle Fuel <sup>h</sup> Price <sup>f</sup>	Price <sup>f</sup>	Percentage of Sector <sup>g,i</sup>
<b>1973 Average</b> .....	0.22	NA	1.29	NA	0.94	NA	0.50	NA	NA	0.38	92.1
<b>1975 Average</b> .....	.44	NA	1.71	NA	1.35	NA	.96	NA	NA	.77	96.1
<b>1980 Average</b> .....	1.59	NA	3.68	NA	3.39	NA	2.56	NA	NA	2.27	96.9
<b>1985 Average</b> .....	2.51	3.75	6.12	NA	5.50	NA	3.95	68.8	NA	3.55	94.0
<b>1990 Average</b> .....	1.71	3.03	5.80	99.2	4.83	86.6	2.93	35.2	3.39	2.38	76.8
<b>1995 Average</b> .....	1.55	2.78	6.06	99.0	5.05	76.7	2.71	24.5	3.98	2.02	71.4
<b>1996 Average</b> .....	2.17	3.27	6.34	99.0	5.40	77.6	3.42	19.4	4.34	2.69	68.4
<b>1997 Average</b> .....	2.32	3.66	6.94	98.8	5.80	70.8	3.59	18.1	4.44	2.78	68.0
<b>1998 Average</b> .....	1.96	3.07	6.82	97.7	5.48	67.0	3.14	16.1	4.59	2.40	63.7
<b>1999 Average</b> .....	2.19	3.10	6.69	95.2	5.33	66.1	3.12	18.8	4.34	2.62	58.3
<b>2000 Average</b> .....	3.68	4.62	7.76	92.6	6.59	63.9	4.45	19.8	5.54	4.38	50.5
<b>2001 Average</b> .....	4.00	5.72	9.63	92.4	8.43	66.0	5.24	20.8	6.60	4.61	40.2
<b>2002 Average</b> .....	2.95	4.12	7.89	97.9	6.63	77.4	4.02	22.7	5.10	<sup>e</sup> 3.68	83.9
<b>2003 Average</b> .....	4.88	5.85	9.63	97.5	8.40	78.2	5.89	22.1	6.19	5.77	91.2
<b>2004 Average</b> .....	5.46	6.65	10.75	97.7	9.43	78.0	6.53	23.6	7.16	6.11	89.8
<b>2005 Average</b> .....	7.33	8.67	12.70	98.1	11.34	82.1	8.56	24.0	9.14	8.47	91.3
<b>2006 Average</b> .....	6.39	8.61	13.73	98.1	12.00	80.8	7.87	23.4	8.72	7.11	93.4
<b>2007 Average</b> .....	6.25	8.16	13.08	98.0	11.34	80.4	7.68	22.2	8.50	7.31	92.2
<b>2008 Average</b> .....	7.97	9.18	13.89	97.5	12.23	79.9	9.65	20.5	11.75	9.26	101.1
<b>2009 Average</b> .....	3.67	6.48	12.14	97.4	10.06	77.8	5.33	18.8	8.13	4.93	101.1
<b>2010</b>											
January .....	5.69	6.84	10.56	97.4	9.65	81.2	6.93	19.0	NA	6.98	101.0
February .....	5.30	6.64	10.69	97.8	9.71	81.8	6.76	18.6	NA	6.27	100.5
March .....	4.70	6.50	10.98	97.6	9.70	79.7	6.01	18.4	NA	5.47	101.0
April .....	4.10	5.88	11.97	96.2	9.55	75.7	5.12	17.7	NA	4.91	100.9
May .....	4.24	5.81	13.12	97.1	9.49	73.0	5.07	17.9	NA	4.96	100.9
June .....	4.27	6.02	14.86	96.9	9.73	71.9	5.03	18.0	NA	5.31	100.6
July .....	4.44	6.31	16.21	96.8	10.07	70.6	5.49	18.3	NA	5.34	100.6
August .....	4.38	6.22	16.65	96.4	9.96	69.8	5.37	17.8	NA	5.06	100.5
September .....	3.83	5.72	15.64	96.7	9.57	68.5	4.61	17.5	NA	4.61	100.7
October .....	4.05	5.70	13.37	96.8	9.28	71.8	4.74	16.8	NA	4.45	101.3
November .....	4.12	5.48	10.88	97.4	8.86	77.7	4.60	17.6	NA	4.55	101.0
December .....	4.68	5.74	9.88	97.4	8.56	80.2	5.42	17.8	NA	5.68	101.3
<b>Average</b> .....	<b>4.48</b>	<b>6.18</b>	<b>11.39</b>	<b>97.4</b>	<b>9.47</b>	<b>77.5</b>	<b>5.49</b>	<b>18.0</b>	<b>6.25</b>	<b>5.27</b>	<b>100.8</b>
<b>2011</b>											
January .....	<sup>E</sup> 4.37	5.68	9.79	96.1	8.66	68.4	5.56	16.4	NA	5.63	101.5
February .....	<sup>E</sup> 4.34	5.75	10.00	96.1	8.81	67.7	5.67	16.2	NA	5.28	102.1
March .....	<sup>E</sup> 3.95	5.68	10.20	95.8	8.81	64.9	5.11	16.3	NA	4.82	101.2
April .....	<sup>E</sup> 4.05	5.62	11.04	95.5	8.98	61.6	5.26	15.7	NA	5.03	101.8
May .....	<sup>E</sup> 4.12	5.78	12.14	95.8	9.18	58.4	5.10	16.3	NA	5.01	101.1
June .....	<sup>E</sup> 4.20	6.08	14.15	95.9	9.49	56.5	5.09	15.7	NA	5.19	101.2
July .....	<sup>E</sup> 4.27	6.14	15.54	95.9	9.70	54.9	4.95	16.7	NA	5.11	100.2
August .....	<sup>E</sup> 4.20	6.19	16.01	95.2	9.90	52.8	5.13	15.9	NA	4.84	100.9
September .....	<sup>E</sup> 3.82	5.93	15.09	95.1	9.55	51.9	4.72	15.7	NA	4.69	101.5
October .....	<sup>E</sup> 3.62	5.43	12.46	95.1	8.89	52.7	4.59	15.6	NA	4.47	101.6
November .....	<sup>E</sup> 3.35	5.25	10.58	94.6	8.60	61.2	4.53	15.9	NA	4.24	101.2
December .....	<sup>E</sup> 3.14	5.03	9.69	95.9	8.28	64.7	4.47	16.5	NA	4.15	101.4
<b>Average</b> .....	<sup>E</sup> <b>3.95</b>	<b>5.62</b>	<b>10.81</b>	<b>95.7</b>	<b>8.86</b>	<b>62.3</b>	<b>5.02</b>	<b>16.1</b>	<b>NA</b>	<b>4.87</b>	<b>101.2</b>
<b>2012</b>											
January .....	<sup>E</sup> 2.89	4.86	9.55	95.7	8.23	65.1	4.47	15.5	NA	3.81	100.6
February .....	<sup>E</sup> 2.46	4.75	9.40	95.6	7.97	63.4	4.25	15.6	NA	3.45	100.5
March .....	<sup>E</sup> 2.25	4.84	10.36	95.6	8.46	60.8	3.64	15.7	NA	3.07	100.2
April .....	<sup>E</sup> 1.89	4.21	10.75	94.8	8.10	56.3	3.14	15.1	NA	2.85	100.9
May .....	<sup>E</sup> 1.94	4.32	12.19	94.8	8.09	53.2	2.94	15.5	NA	3.02	100.9
<b>5-Month Average</b> ...	<sup>E</sup> <b>2.29</b>	<b>4.69</b>	<b>10.00</b>	<b>95.5</b>	<b>8.18</b>	<b>61.3</b>	<b>3.72</b>	<b>15.5</b>	<b>NA</b>	<b>3.22</b>	<b>100.6</b>
<b>2011 5-Month Average</b> ...	<sup>E</sup> <b>4.17</b>	<b>5.70</b>	<b>10.27</b>	<b>95.9</b>	<b>8.82</b>	<b>65.5</b>	<b>5.35</b>	<b>16.2</b>	<b>NA</b>	<b>5.16</b>	<b>101.5</b>
<b>2010 5-Month Average</b> ...	<b>4.81</b>	<b>6.51</b>	<b>11.02</b>	<b>97.4</b>	<b>9.65</b>	<b>79.5</b>	<b>6.05</b>	<b>18.4</b>	<b>NA</b>	<b>5.73</b>	<b>100.8</b>

<sup>a</sup> Prices are not adjusted for inflation. See "Nominal Dollars" in Glossary.

<sup>b</sup> See Note 9, "Natural Gas Prices," at end of section.

<sup>c</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>d</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>e</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 2001, data are for electric utilities only; beginning in 2002, data also include independent power producers. See Note 8, "Costs of Fossil-Fuel Receipts at Electric Generating Plants," at end of section for plant coverage.

<sup>f</sup> Includes taxes.

<sup>g</sup> The percentage of the sector's consumption in Table 4.3 for which price data are available. For details on how the percentages are derived, see Table 9.11 Sources at end of section.

<sup>h</sup> Much of the natural gas delivered for vehicle fuel represents deliveries to fueling stations that are used primarily or exclusively by fleet vehicles. Thus, the prices are often those associated with the cost of gas in the operation of fleet vehicles.

<sup>i</sup> Percentages exceed 100 percent when reported natural gas receipts are greater than reported natural gas consumption—this can occur when combined-heat-and-power plants report fuel receipts related to non-electric generating activities.

NA=Not available. E=Estimate.

Notes: • Prices are for natural gas, plus a small amount of supplemental gaseous fuels. • Prices are intended to include all taxes. See Note 9, "Natural Gas Prices," at end of section. • Wellhead annual and year-to-date prices are simple averages of the monthly prices; all other annual and year-to-date prices are volume-weighted averages of the monthly prices. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#prices> for all available data beginning in 1973.

Sources: See end of section.

## Energy Prices

**Note 1. Crude Oil Domestic First Purchase Prices.** The average domestic first purchase price represents the average price at which all domestic crude oil is purchased. Prior to February 1976, the price represented an estimate of the average of posted prices; beginning with February 1976, the price represents an average of actual first purchase prices. The data series was previously called “Actual Domestic Wellhead Price.”

**Note 2. Crude Oil F.O.B. Costs.** F.O.B. literally means “Free on Board.” It denotes a transaction whereby the seller makes the product available with an agreement on a given port at a given price; it is the responsibility of the buyer to arrange for the transportation and insurance.

**Note 3. Crude Oil Landed Costs.** The landed cost of imported crude oil from selected countries does not represent the total cost of all imported crude. Prior to April 1975, imported crude costs to U.S. company-owned refineries in the Caribbean were not included in the landed cost, and costs of crude oil from countries that export only small amounts to the United States were also excluded. Beginning in April 1975, however, coverage was expanded to include U.S. company-owned refineries in the Caribbean. Landed costs do not include supplemental fees.

**Note 4. Crude Oil Refinery Acquisition Costs.** Beginning with January 1981, refiner acquisition costs of crude oil are from data collected on U.S. Energy Information Administration (EIA) Form EIA-14, “Refiners’ Monthly Cost Report.” Those costs were previously published from data collected on Economic Regulatory Administration (ERA) Form ERA-49, “Domestic Crude Oil Entitlements Program Refiners Monthly Report.” Form ERA-49 was discontinued with the decontrol of crude oil on January 28, 1981. Crude oil purchases and costs are defined for Form EIA-14 in accordance with conventions used for Form ERA-49. The respondents for the two forms are also essentially the same. However, due to possible different interpretations of the filing requirements and a different method for handling prior period adjustments, care must be taken when comparing the data collected on the two forms.

The refiner acquisition cost of crude oil is the average price paid by refiners for crude oil booked into their refineries in accordance with accounting procedures generally accepted and consistently and historically applied by the refiners concerned. Domestic crude oil is that oil produced in the United States or from the outer continental shelf as defined in 43 USC Section 1331. Imported crude oil is either that oil reported on Form ERA-51, “Transfer Pricing Report,” or any crude oil that is not domestic oil. The composite cost is the weighted average of domestic and imported crude oil costs.

Crude oil costs and volumes reported on Form ERA-49 excluded unfinished oils but included the Strategic Petroleum Reserve (SPR). Crude oil costs and volumes reported

on Federal Energy Administration (FEA) Form FEA-P110-M-1, “Refiners’ Monthly Cost Allocation Report,” included unfinished oils but excluded SPR. Imported averages derived from Form ERA-49 exclude oil purchased for SPR, whereas the composite averages derived from Form ERA-49 include SPR. None of the prices derived from Form EIA-14 include either unfinished oils or SPR.

**Note 5. Motor Gasoline Prices.** Several different series of motor gasoline prices are published in this section. U.S. city average retail prices of motor gasoline are calculated monthly by the Bureau of Labor Statistics during the development of the Consumer Price Index (CPI). These prices include all Federal, State, and local taxes paid at the time of sale. From 1974–1977, prices were collected in 56 urban areas. From 1978 forward, prices are collected from a new sample of service stations in 85 urban areas selected to represent all urban consumers—about 80 percent of the total U.S. population. The service stations are selected initially, and on a replacement basis, in such a way that they represent the purchasing habits of the CPI population. Service stations in the current sample include those providing all types of service (i.e., full-, mini-, and self-serve).

Refiner prices of finished motor gasoline for resale and to end users are determined by the EIA in a monthly survey of refiners and gas plant operators (Form EIA-782A). The prices do not include any Federal, State, or local taxes paid at the time of sale. Estimates of prices prior to January 1983 are based on Form FEA-P302-M-1/EIA-460, “Petroleum Industry Monthly Report for Product Prices,” and also exclude all Federal, State, or local taxes paid at the time of sale. Sales for resale are those made to purchasers who are other-than-ultimate consumers. Sales to end users are sales made directly to the consumer of the product, including bulk consumers (such as agriculture, industry, and utilities) and residential and commercial consumers.

**Note 6. Historical Petroleum Prices.** Starting in January 1983, Form EIA-782, “Monthly Petroleum Product Sales Report,” replaced 10 previous surveys. Every attempt was made to continue the most important price series. However, prices published through December 1982 and those published since January 1983 do not necessarily form continuous data series due to changes in survey forms, definitions, instructions, populations, samples, processing systems, and statistical procedures. To provide historical data, continuous series were generated for annual data 1978–1982 and for monthly data 1981 and 1982 by estimating the prices that would have been published had Form EIA-782 survey and system been in operation at that time. This form of estimation was performed after detailed adjustment was made for product and sales type matching and for discontinuity due to other factors. An important difference between the previous and present prices is the distinction between wholesale and resale and between retail and end user. The resale category continues to include sales among resellers. However, sales to bulk consumers, such as utility, industrial, and commercial accounts previously included in



the wholesale category, are now counted as made to end users. The end-user category continues to include retail sales through company-owned and operated outlets but also includes sales to the bulk consumers such as agriculture, industry, and electric utilities. Additional information may be found in “Estimated Historic Time Series for the EIA-782,” a feature article by Paula Weir, printed in the December 1983 [3] *Petroleum Marketing Monthly*, published by EIA.

**Note 7. Electricity Retail Prices.** Average annual retail prices of electricity have the following plant coverage: Through 1979, annual data are for Classes A and B privately owned electric utilities only. For 1980–1982, annual data are for selected Class A utilities whose electric operating revenues were \$100 million or more during the previous year. For 1983, annual data are for a selected sample of electric utilities. Beginning in 1984, data are for a census of electric utilities. Beginning in 1996, annual data also include energy service providers selling to retail customers.

Average monthly retail prices of electricity have the following plant coverage: Through 1985, monthly data are derived from selected privately owned electric utilities and, therefore, are not national averages. Beginning in 1986, monthly data are based on a sample of publicly and privately owned electric utilities. Beginning in 1996, monthly data also include energy service providers selling to retail customers.

Preliminary monthly data are from Form EIA-826, “Monthly Electric Sales and Revenue Report With State Distributions Report,” which is a monthly collection of data from approximately 450 of the largest publicly and privately owned electric utilities as well as a census of energy service providers with retail sales in deregulated States; a model is then applied to the collected data to estimate for the entire universe of U.S. electric utilities. Preliminary annual data are the sum of the monthly revenues divided by the sum of the monthly sales. When final annual data become available each year from Form EIA-861, “Annual Electric Power Industry Report,” their ratios to the preliminary Form EIA-826 values are used to derive adjusted final monthly values.

**Note 8. Costs of Fossil-Fuel Receipts at Electric Generating Plants.** Data for 1973–1982 cover all regulated electric generating plants at which the generator nameplate capacity of all steam-electric units combined totaled 25 megawatts or greater. From 1974–1982, peaking units were included in the data and counted towards the 25-megawatt-or-greater total. Data for 1983–1990 cover all regulated electric generating plants at which the generator nameplate capacity of all steam-electric units combined totaled 50 megawatts or greater. Data for 1991–2001 cover all regulated electric generating plants at which the generator nameplate capacity of all steam-electric units and combined-cycle units together totaled 50

megawatts or greater. Data for 2002 forward cover the aforementioned regulated generating plants plus unregulated generating plants (independent power producers, as well as combined-heat-and-power generating plants and electricity-only plants in the commercial and industrial sector) whose total facility fossil-fueled nameplate generating capacity is 50 or more megawatts, regardless of unit type.

**Note 9. Natural Gas Prices.** Natural gas prices are intended to include all taxes. Instructions on the data collection forms specifically direct that all Federal, State, and local taxes, surcharges, and/or adjustments billed to consumers are to be included. However, sales and other taxes itemized on more than 3,000 consumers’ bills are sometimes excluded by the reporting utilities. Delivered-to-consumers prices for 1987 forward represent natural gas delivered and sold to residential, commercial, industrial, vehicle fuel, and electric power consumers. They do not include the price of natural gas delivered on behalf of third parties to residential, commercial, industrial, and vehicle fuel customers except for certain States in the residential and commercial sectors for 2002 forward. Volumes of natural gas delivered on behalf of third parties are included in the consumption data shown in Table 4.3. Additional information is available in the EIA *Natural Gas Monthly*, Appendix C.

## Table 9.1 Sources

### Domestic First Purchase Price

1973–1976: U.S. Department of the Interior (DOI), Bureau of Mines (BOM), *Minerals Yearbook*, “Crude Petroleum and Petroleum Products” chapter.

1977: Federal Energy Administration, based on Form FEA-P124, “Domestic Crude Oil Purchaser’s Monthly Report.”

1978–2009: U.S. Energy Information Administration (EIA), *Petroleum Marketing Annual 2009*, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, August 2012, Table 1.

### F.O.B. and Landed Cost of Imports

October 1973–September 1977: Federal Energy Administration, Form FEA-F701-M-0, “Transfer Pricing Report.”

October–December 1977: EIA, Form FEA-F701-M-0, “Transfer Pricing Report.”

1978–2009: EIA, *Petroleum Marketing Annual 2009*, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, August 2012, Table 1.

### Refiner Acquisition Cost

1973: EIA estimates. The domestic price was derived by adding estimated transportation costs to the reported domestic first purchase price. The imported price was derived by adding an estimated ocean transport cost to the average “Free Alongside Ship” value published by the U.S. Bureau of the Census.

1974–1976: DOI, BOM, *Minerals Yearbook*, “Crude Petroleum and Petroleum Products” chapter.

1977: January–September, FEA, based on Form FEA-P110-M-1, “Refiners’ Monthly Cost Allocation Report.” October–December, EIA, based on Form FEA-P110-M-1, “Refiners’ Monthly Cost Allocation Report.”

1978–2009: EIA, *Petroleum Marketing Annual 2009*, Table 1.

2010 forward: EIA, *Petroleum Marketing Monthly*, August 2012, Table 1.

## Table 9.2 Sources

October 1973–September 1977: Federal Energy Administration, Form FEA-F701-M-0, “Transfer Pricing Report.” October 1977–December 1977: U.S. Energy Information Administration (EIA), Form FEA-F701-M-0, “Transfer Pricing Report.”

1978–2009: EIA, *Petroleum Marketing Annual 2009*, Table 21.

2010 forward: EIA, *Petroleum Marketing Monthly*, August 2012, Table 21.

## Table 9.10 Sources

1973–September 1977: Federal Power Commission, Form FPC-423, “Monthly Report of Cost and Quality of Fuels for Electric Utility Plants.”

October 1977–December 1977: Federal Energy Regulatory Commission, Form FERC-423, “Monthly Report of Cost and Quality of Fuels for Electric Utility Plants.”

1978 and 1979: U.S. Energy Information Administration (EIA), Form FERC-423, “Monthly Report of Cost and Quality of Fuels for Electric Utility Plants.”

1980–1989: EIA, *Electric Power Monthly*, May issues.

1990–2000: EIA, *Electric Power Monthly*, March 2003, Table 26.

2001–2007: EIA, *Electric Power Monthly*, October 2008, Table 4.1; Federal Energy Regulatory Commission, Form FERC-423, “Monthly Report of Cost and Quality of Fuels for Electric Utility Plants”; and EIA, Form EIA-423, “Monthly Cost and Quality of Fuels for Electric Plants Report.”

2008 forward: EIA, *Electric Power Monthly*, July 2012, Table 4.1; and Form EIA-923, “Power Plant Operations Report.”

## Table 9.11 Sources

### All Prices Except Vehicle Fuel and Electric Power

1973–2006: U.S. Energy Information Administration (EIA), *Natural Gas Annual (NGA)*, annual reports and unpublished revisions.

2007 forward: EIA, *Natural Gas Monthly (NGM)*, July 2012, Table 3.

### Vehicle Fuel Price

EIA, NGA, annual reports.

### Electric Power Sector Price

1973–1998: EIA, NGA 2000, Table 96.

1999–2002: EIA, NGM, October 2004, Table 4.

2003–2007: Federal Energy Regulatory Commission, Form FERC-423, “Monthly Report of Cost and Quality of Fuels for Electric Utility Plants,” and EIA, Form EIA-423 “Monthly Cost and Quality of Fuels for Electric Plants Report.”

2008 forward: Form EIA-923, “Power Plant Operations Report.”

### Percentage of Residential Sector

1989–2009: EIA, Form EIA-176, “Annual Report of Natural and Supplemental Gas Supply and Disposition.”

2010 forward: Estimated by EIA as the average of the three previous annual values.

### Percentage of Commercial Sector

1987–2006: EIA, NGA, annual reports. Calculated as the total amount of natural gas delivered to commercial consumers minus the amount delivered for the account of others, and then divided by the total amount delivered to commercial consumers.

2007 forward: EIA, NGM, July 2012, Table 3.

### Percentage of Industrial Sector

1982–2006: EIA, NGA, annual reports. Calculated as the total amount of natural gas delivered to industrial consumers minus the amount delivered for the account of others, and then divided by the total amount delivered to industrial consumers.

2007 forward: EIA, NGM, July 2012, Table 3.

### Percentage of Electric Power Sector

1973–2001: Calculated by EIA as the quantity of natural gas receipts by electric utilities reported on Form FERC-423, “Monthly Report of Cost and Quantity of Fuels for Electric Utility Plants” (and predecessor forms) divided by the quantity of natural gas consumed by the electric power sector (for 1973–1988, see *Monthly Energy Review*, Table 7.3b; for 1989–2001, see *Monthly Energy Review*, Table 7.4b).

2002–2007: Calculated by EIA as the quantity of natural gas receipts by electric utilities and independent power producers reported on Form FERC-423, “Monthly Report of Cost and Quantity of Fuels for Electric Utility Plants,” and EIA-423, “Monthly Cost and Quality of Fuels for Electric Plants Report,” divided by the quantity of natural gas consumed by the electric power sector (see *Monthly Energy Review*, Table 7.4b).


2008 forward: Calculated by EIA as the quantity of natural gas receipts by electric utilities and independent power producers reported on Form EIA-923, “Power Plant Operations Report,” divided by the quantity of natural gas consumed by the electric power sector (see *Monthly Energy Review*, Table 7.4b).

# 10. Renewable Energy


---

**Figure 10.1 Renewable Energy Consumption**  
(Quadrillion Btu)


Total and Major Sources, 1973-2011




By Source, 2011




By Sector, 2011



Compared With Other Resources, 1973-2011



Compared With Other Resources, 2011



<sup>a</sup> See Table 10.1 for definition.  
<sup>b</sup> Conventional hydroelectric power.  
<sup>c</sup> Geothermal, solar/PV, and wind.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#renewable>.  
Sources: Tables 1.3 and 10.1-10.2c.

**Table 10.1 Renewable Energy Production and Consumption by Source**  
(Trillion Btu)

	Production <sup>a</sup>			Consumption								
	Biomass		Total Renewable Energy <sup>d</sup>	Hydroelectric Power <sup>e</sup>	Geothermal <sup>f</sup>	Solar/PV <sup>g</sup>	Wind <sup>h</sup>	Biomass				Total Renewable Energy
	Bio-fuels <sup>b</sup>	Total <sup>c</sup>						Wood <sup>i</sup>	Waste <sup>j</sup>	Bio-fuels <sup>k</sup>	Total	
1973 Total .....	NA	1,529	4,411	2,861	20	NA	NA	1,527	2	NA	1,529	4,411
1975 Total .....	NA	1,499	4,687	3,155	34	NA	NA	1,497	2	NA	1,499	4,687
1980 Total .....	NA	2,475	5,428	2,900	53	NA	NA	2,474	2	NA	2,475	5,428
1985 Total .....	93	3,016	6,084	2,970	97	(s)	(s)	2,687	236	93	3,016	6,084
1990 Total .....	111	2,735	6,041	3,046	171	59	29	2,216	408	111	2,735	6,041
1995 Total .....	198	3,099	6,558	3,205	152	69	33	2,370	531	200	3,101	6,560
1996 Total .....	141	3,155	7,012	3,590	163	70	33	2,437	577	143	3,157	7,014
1997 Total .....	186	3,108	7,018	3,640	167	70	34	2,371	551	184	3,105	7,016
1998 Total .....	202	2,929	6,494	3,297	168	69	31	2,184	542	201	2,927	6,493
1999 Total .....	211	2,965	6,517	3,268	171	68	46	2,214	540	209	2,963	6,516
2000 Total .....	233	3,006	6,104	2,811	164	66	57	2,262	511	236	3,008	6,106
2001 Total .....	254	2,624	5,164	2,242	164	64	70	2,006	364	253	2,622	5,163
2002 Total .....	308	2,705	5,734	2,689	171	63	105	1,995	402	303	2,701	5,729
2003 Total .....	402	2,805	5,982	2,825	175	62	115	2,002	401	404	2,807	5,983
2004 Total .....	487	2,998	6,070	2,690	178	63	142	2,121	389	499	3,010	6,082
2005 Total .....	564	3,104	6,229	2,703	181	63	178	2,137	403	577	3,117	6,242
2006 Total .....	720	3,216	6,599	2,869	181	68	264	2,099	397	771	3,267	6,649
2007 Total .....	978	3,461	6,509	2,446	186	76	341	2,070	413	991	3,474	6,523
2008 Total .....	1,387	3,864	7,202	2,511	192	89	546	2,040	436	1,372	3,849	7,186
2009 Total .....	1,584	3,928	7,616	2,669	200	98	721	1,891	453	1,568	3,912	7,600
2010 January .....	152	359	672	218	18	10	67	168	39	142	349	662
February .....	142	332	610	201	16	9	53	154	35	136	326	605
March .....	158	366	682	204	18	10	84	168	40	149	357	673
April .....	152	351	661	186	17	10	95	160	39	149	348	657
May .....	157	358	717	245	18	11	85	162	39	155	356	715
June .....	152	355	753	291	17	11	79	164	39	155	357	755
July .....	158	367	701	239	17	11	66	170	40	158	368	701
August .....	160	371	662	196	18	11	65	171	40	159	370	660
September .....	156	360	626	168	17	11	69	166	38	153	357	622
October .....	163	369	646	173	17	10	77	166	39	160	366	643
November .....	164	369	682	191	17	10	95	165	40	157	363	676
December .....	168	383	726	226	18	10	88	174	41	163	377	720
Total .....	1,884	4,341	8,136	2,539	208	126	923	1,988	469	1,837	4,294	8,090
2011 January .....	170	383	754	255	20	12	84	174	40	154	367	739
February .....	152	344	717	241	18	12	103	156	36	146	337	710
March .....	171	377	822	310	20	13	103	166	40	160	366	811
April .....	163	359	821	309	18	13	121	158	38	154	351	812
May .....	171	371	840	323	19	14	114	160	40	165	365	835
June .....	167	375	828	315	19	14	106	168	40	166	374	827
July .....	172	384	797	308	19	14	72	171	41	162	374	787
August .....	175	384	746	257	19	14	72	169	41	173	382	744
September .....	167	371	680	210	18	13	67	165	40	160	365	673
October .....	176	379	711	195	19	14	104	163	40	167	370	702
November .....	177	382	742	209	19	12	121	164	41	165	370	730
December .....	186	403	779	241	19	13	102	175	42	173	390	766
Total .....	2,047	4,511	9,236	3,171	226	158	1,168	1,987	477	1,947	4,411	9,135
2012 January .....	177	389	792	233	19	15	135	173	40	R 154	R 367	R 769
February .....	164	362	705	203	18	15	108	161	37	R 152	R 350	R 694
March .....	172	372	797	256	19	16	132	161	40	R 163	R 364	R 788
April .....	164	357	776	261	18	17	123	153	40	R 160	R 353	773
May .....	173	377	819	283	19	19	121	164	40	172	376	819
5-Month Total .....	849	1,857	3,890	1,237	95	82	619	811	197	802	1,810	3,843
2011 5-Month Total .....	826	1,833	3,954	1,437	95	64	525	814	193	779	1,786	3,907
2010 5-Month Total .....	761	1,766	3,341	1,054	86	51	384	812	193	731	1,737	3,312

<sup>a</sup> Production equals consumption for all renewable energy sources except biofuels.

<sup>b</sup> Total biomass inputs to the production of fuel ethanol and biodiesel.

<sup>c</sup> Wood and wood-derived fuels, biomass waste, and total biomass inputs to the production of fuel ethanol and biodiesel.

<sup>d</sup> Hydroelectric power, geothermal, solar thermal/photovoltaic, wind, and biomass.

<sup>e</sup> Conventional hydroelectricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>f</sup> Geothermal electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6), and geothermal heat pump and direct use energy.

<sup>g</sup> Solar thermal and photovoltaic (PV) electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6), and solar thermal direct use energy.

<sup>h</sup> Wind electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>i</sup> Wood and wood-derived fuels.

<sup>j</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>k</sup> Fuel ethanol (minus denaturant) and biodiesel consumption, plus losses and co-products from the production of fuel ethanol and biodiesel.

R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • Most data for the residential, commercial, industrial, and transportation sectors are estimates. See notes and sources for Tables 10.2a and 10.2b. • See Note, "Renewable Energy Production and Consumption," at end of section.

• Totals may not equal sum of components due to independent rounding.

• Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> for all available data beginning in 1973.

Sources: Tables 10.2a–10.4.

**Table 10.2a Renewable Energy Consumption: Residential and Commercial Sectors**  
(Trillion Btu)

	Residential Sector				Commercial Sector <sup>a</sup>								
	Geo-thermal <sup>b</sup>	Solar/ PV <sup>c</sup>	Biomass	Total	Hydro- electric Power <sup>e</sup>	Geo- thermal <sup>b</sup>	Solar/ PV <sup>f</sup>	Wind <sup>g</sup>	Biomass				Total
			Wood <sup>d</sup>						Wood <sup>d</sup>	Waste <sup>h</sup>	Fuel Ethanol <sup>i</sup>	Total	
<b>1973 Total</b> .....	NA	NA	354	354	NA	NA	NA	NA	7	NA	NA	7	7
<b>1975 Total</b> .....	NA	NA	425	425	NA	NA	NA	NA	8	NA	NA	8	8
<b>1980 Total</b> .....	NA	NA	850	850	NA	NA	NA	NA	21	NA	NA	21	21
<b>1985 Total</b> .....	NA	NA	1,010	1,010	NA	NA	NA	NA	24	NA	(s)	24	24
<b>1990 Total</b> .....	6	56	580	641	1	3	-	-	66	28	(s)	94	98
<b>1995 Total</b> .....	7	64	520	591	1	5	-	-	72	40	(s)	113	118
<b>1996 Total</b> .....	7	65	540	612	1	5	-	-	76	53	(s)	129	135
<b>1997 Total</b> .....	8	64	430	502	1	6	-	-	73	58	(s)	131	138
<b>1998 Total</b> .....	8	64	380	452	1	7	-	-	64	54	(s)	118	127
<b>1999 Total</b> .....	9	63	390	461	1	7	-	-	67	54	(s)	121	129
<b>2000 Total</b> .....	9	61	420	489	1	8	-	-	71	47	(s)	119	128
<b>2001 Total</b> .....	9	59	370	438	1	8	-	-	67	25	(s)	92	101
<b>2002 Total</b> .....	10	57	380	448	(s)	9	-	-	69	26	(s)	95	104
<b>2003 Total</b> .....	13	57	400	470	1	11	-	-	71	29	1	101	113
<b>2004 Total</b> .....	14	57	410	481	1	12	-	-	70	34	1	105	118
<b>2005 Total</b> .....	16	58	430	504	1	14	-	-	70	34	1	105	120
<b>2006 Total</b> .....	18	63	380	462	1	14	-	-	65	36	1	103	118
<b>2007 Total</b> .....	22	70	410	502	1	14	-	-	70	31	2	103	118
<b>2008 Total</b> .....	26	80	450	557	1	15	(s)	-	73	34	2	109	125
<b>2009 Total</b> .....	33	89	430	552	1	17	(s)	(s)	72	36	3	112	129
<b>2010</b>													
January .....	3	10	36	48	(s)	2	(s)	(s)	6	3	(s)	9	11
February .....	3	9	32	44	(s)	1	(s)	(s)	5	3	(s)	8	10
March .....	3	10	36	48	(s)	2	(s)	(s)	6	3	(s)	9	11
April .....	3	9	35	47	(s)	2	(s)	(s)	6	3	(s)	9	11
May .....	3	10	36	48	(s)	2	(s)	(s)	6	4	(s)	10	12
June .....	3	9	35	47	(s)	2	(s)	(s)	6	3	(s)	9	11
July .....	3	10	36	48	(s)	2	(s)	(s)	6	3	(s)	9	11
August .....	3	10	36	48	(s)	2	(s)	(s)	6	3	(s)	10	11
September .....	3	9	35	47	(s)	2	(s)	(s)	6	3	(s)	9	11
October .....	3	10	36	48	(s)	2	(s)	(s)	6	3	(s)	9	11
November .....	3	9	35	47	(s)	2	(s)	(s)	6	3	(s)	9	10
December .....	3	10	36	48	(s)	2	(s)	(s)	6	3	(s)	9	11
<b>Total</b> .....	<b>37</b>	<b>114</b>	<b>420</b>	<b>571</b>	<b>1</b>	<b>19</b>	<b>(s)</b>	<b>(s)</b>	<b>72</b>	<b>36</b>	<b>3</b>	<b>111</b>	<b>130</b>
<b>2011</b>													
January .....	3	12	37	52	(s)	2	(s)	(s)	6	3	(s)	9	11
February .....	3	11	33	47	(s)	2	(s)	(s)	5	3	(s)	9	10
March .....	3	12	37	52	(s)	2	(s)	(s)	6	3	(s)	9	11
April .....	3	12	35	50	(s)	2	(s)	(s)	6	3	(s)	9	10
May .....	3	12	37	52	(s)	2	(s)	(s)	6	3	(s)	9	11
June .....	3	12	35	50	(s)	2	(s)	(s)	6	3	(s)	9	11
July .....	3	12	37	52	(s)	2	(s)	(s)	6	3	(s)	9	11
August .....	3	12	37	52	(s)	2	(s)	(s)	6	3	(s)	9	11
September .....	3	12	35	50	(s)	2	(s)	(s)	6	3	(s)	9	11
October .....	3	12	37	52	(s)	2	(s)	(s)	6	3	(s)	9	11
November .....	3	12	35	50	(s)	2	(s)	(s)	6	3	(s)	9	11
December .....	3	12	37	52	(s)	2	(s)	(s)	6	3	(s)	10	11
<b>Total</b> .....	<b>40</b>	<b>140</b>	<b>430</b>	<b>610</b>	<b>1</b>	<b>20</b>	<b>(s)</b>	<b>(s)</b>	<b>71</b>	<b>36</b>	<b>3</b>	<b>110</b>	<b>131</b>
<b>2012</b>													
January .....	3	14	36	54	(s)	2	(s)	(s)	6	3	(s)	9	11
February .....	3	13	34	51	(s)	2	(s)	(s)	6	3	(s)	9	10
March .....	3	14	36	54	(s)	2	(s)	(s)	6	3	(s)	9	11
April .....	3	14	35	52	(s)	2	(s)	(s)	6	3	(s)	9	11
May .....	3	14	36	54	(s)	2	(s)	(s)	6	3	(s)	9	11
<b>5-Month Total</b> .....	<b>16</b>	<b>70</b>	<b>179</b>	<b>265</b>	<b>(s)</b>	<b>8</b>	<b>(s)</b>	<b>(s)</b>	<b>29</b>	<b>14</b>	<b>1</b>	<b>45</b>	<b>54</b>
<b>2011 5-Month Total</b> .....	<b>16</b>	<b>58</b>	<b>178</b>	<b>252</b>	<b>1</b>	<b>8</b>	<b>(s)</b>	<b>(s)</b>	<b>29</b>	<b>14</b>	<b>1</b>	<b>45</b>	<b>54</b>
<b>2010 5-Month Total</b> .....	<b>15</b>	<b>47</b>	<b>174</b>	<b>236</b>	<b>(s)</b>	<b>8</b>	<b>(s)</b>	<b>(s)</b>	<b>30</b>	<b>15</b>	<b>1</b>	<b>46</b>	<b>54</b>

<sup>a</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants. See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> Geothermal heat pump and direct use energy.

<sup>c</sup> Solar thermal direct use energy, and photovoltaic (PV) electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6). Includes distributed solar thermal and PV energy used in the commercial, industrial, and electric power sectors.

<sup>d</sup> Wood and wood-derived fuels.

<sup>e</sup> Conventional hydroelectricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>f</sup> Photovoltaic (PV) electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6) at commercial plants with capacity of 1 megawatt or greater.

<sup>g</sup> Wind electricity net generation (converted to Btu using the fossil-fuels heat

rate—see Table A6).

<sup>h</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>i</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10, consumed by the commercial sector.

NA=Not available. - =No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Data are estimates, except for commercial sector solar/PV, hydroelectric power, wind, and waste. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> for all available data beginning in 1973.

Sources: See end of section.

**Table 10.2b Renewable Energy Consumption: Industrial and Transportation Sectors**  
(Trillion Btu)

	Industrial Sector <sup>a</sup>										Transportation Sector			
	Hydro-electric Power <sup>b</sup>	Geo-thermal <sup>c</sup>	Solar/PV <sup>d</sup>	Wind <sup>e</sup>	Biomass					Total	Biomass			
					Wood <sup>f</sup>	Waste <sup>g</sup>	Fuel Ethanol <sup>h</sup>	Losses and Co-products <sup>i</sup>	Total		Fuel Ethanol <sup>j</sup>	Bio-diesel	Total	
1973 Total	35	NA	NA	NA	1,165	NA	NA	NA	NA	1,165	1,200	NA	NA	NA
1975 Total	32	NA	NA	NA	1,063	NA	NA	NA	NA	1,063	1,096	NA	NA	NA
1980 Total	33	NA	NA	NA	1,600	NA	NA	NA	NA	1,600	1,633	NA	NA	NA
1985 Total	33	NA	NA	NA	1,645	230	1	42	1,918	1,951	1,951	50	NA	50
1990 Total	31	2	-	-	1,442	192	1	49	1,684	1,717	1,717	60	NA	60
1995 Total	55	3	-	-	1,652	195	2	86	1,934	1,992	1,992	112	NA	112
1996 Total	61	3	-	-	1,683	224	1	61	1,969	2,033	2,033	81	NA	81
1997 Total	58	3	-	-	1,731	184	1	80	1,996	2,057	2,057	102	NA	102
1998 Total	55	3	-	-	1,603	180	1	86	1,872	1,929	1,929	113	NA	113
1999 Total	49	4	-	-	1,620	171	1	90	1,882	1,934	1,934	118	NA	118
2000 Total	42	4	-	-	1,636	145	1	99	1,881	1,928	1,928	135	NA	135
2001 Total	33	5	-	-	1,443	129	3	108	1,681	1,719	1,719	141	1	142
2002 Total	39	5	-	-	1,396	146	3	130	1,676	1,720	1,720	168	2	170
2003 Total	43	3	-	-	1,363	142	4	169	1,679	1,726	1,726	228	2	230
2004 Total	33	4	-	-	1,476	132	6	203	1,817	1,853	1,853	286	3	290
2005 Total	32	4	-	-	1,452	148	7	230	1,837	1,873	1,873	327	12	339
2006 Total	29	4	-	-	1,472	130	10	285	1,897	1,930	1,930	442	33	475
2007 Total	16	5	-	-	1,405	144	10	377	1,936	1,956	1,956	557	46	602
2008 Total	17	5	-	-	1,340	144	12	532	2,028	2,049	2,049	786	40	826
2009 Total	18	4	-	-	1,208	155	13	617	1,994	2,016	2,016	894	42	935
2010 January	2	(s)	(s)	-	109	15	1	60	185	187	187	81	(s)	81
February	2	(s)	(s)	-	100	13	1	56	170	172	172	76	3	79
March	2	(s)	(s)	-	110	15	1	62	188	190	190	83	2	85
April	2	(s)	(s)	-	105	15	1	60	181	183	183	84	4	87
May	2	(s)	(s)	-	106	14	1	62	183	185	185	89	3	92
June	1	(s)	(s)	-	107	13	2	60	182	183	183	90	2	93
July	1	(s)	(s)	-	111	14	2	62	188	190	190	91	3	94
August	1	(s)	(s)	-	111	14	2	63	190	191	191	91	3	94
September	1	(s)	(s)	-	110	13	1	61	185	187	187	86	4	90
October	1	(s)	(s)	-	110	15	2	64	190	192	192	91	3	94
November	1	(s)	(s)	-	108	15	1	65	190	191	191	88	3	91
December	1	(s)	(s)	-	114	15	2	67	198	199	199	92	3	94
Total	16	4	(s)	-	1,301	169	17	742	2,230	2,250	2,250	1,040	34	1,074
2011 January	1	(s)	(s)	(s)	115	15	1	66	197	199	199	83	3	86
February	2	(s)	(s)	(s)	102	14	1	59	176	178	178	81	4	85
March	2	(s)	(s)	(s)	109	14	1	66	190	192	192	87	6	93
April	2	(s)	(s)	(s)	105	14	1	62	182	185	185	83	8	91
May	2	(s)	(s)	(s)	105	14	2	65	185	187	187	90	9	99
June	1	(s)	(s)	(s)	112	14	2	63	190	192	192	92	9	102
July	1	(s)	(s)	(s)	112	14	1	64	192	194	194	85	11	96
August	1	(s)	(s)	(s)	110	14	2	65	191	192	192	96	10	106
September	1	(s)	(s)	(s)	109	14	1	62	187	188	188	83	14	97
October	1	(s)	(s)	(s)	107	15	1	65	189	190	190	89	12	100
November	1	(s)	(s)	(s)	110	15	1	66	192	194	194	84	13	98
December	2	(s)	(s)	(s)	116	15	2	69	202	204	204	90	13	102
Total	18	4	(s)	(s)	1,311	172	17	772	2,273	2,295	2,295	1,042	112	1,154
2012 January	2	(s)	(s)	(s)	114	15	1	67	197	199	199	81	R 5	R 86
February	2	(s)	(s)	(s)	106	14	1	61	183	185	185	82	R 8	R 89
March	2	(s)	(s)	(s)	104	14	1	64	184	186	186	87	R 10	98
April	2	(s)	(s)	(s)	101	14	1	61	178	180	180	86	R 11	R 98
May	2	(s)	(s)	(s)	108	14	2	64	188	190	190	93	14	107
5-Month Total	9	2	(s)	(s)	535	71	7	316	930	940	940	429	48	477
2011 5-Month Total	9	2	(s)	(s)	535	71	7	317	930	941	941	424	30	454
2010 5-Month Total	8	2	(s)	-	530	71	7	299	907	917	917	412	12	424

<sup>a</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants. See Note, "Classification of Power Plants Into Energy-Use Sectors," at end of Section 7.

<sup>b</sup> Conventional hydroelectricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>c</sup> Geothermal heat pump and direct use energy.

<sup>d</sup> Photovoltaic (PV) electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6) at industrial plants with capacity of 1 megawatt or greater.

<sup>e</sup> Wind electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>f</sup> Wood and wood-derived fuels.

<sup>g</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and tire-derived fuels).

<sup>h</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10,

consumed by the industrial sector.

<sup>i</sup> Losses and co-products from the production of fuel ethanol and biodiesel. Does not include natural gas, electricity, and other non-biomass energy used in the production of fuel ethanol and biodiesel—these are included in the industrial sector consumption statistics for the appropriate energy source.

<sup>j</sup> The fuel ethanol (minus denaturant) portion of motor fuels, such as E10 and E85, consumed by the transportation sector.

R=Revised. NA=Not available. - =No data reported. (s)=Less than 0.5 trillion Btu.

Notes: • Data are estimates, except for industrial sector hydroelectric power in 1973-1978 and 1989 forward, solar/PV, and wind. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> for all available data beginning in 1973.

Sources: See end of section.

**Table 10.2c Renewable Energy Consumption: Electric Power Sector**  
(Trillion Btu)

	Hydro-electric Power <sup>a</sup>	Geo-thermal <sup>b</sup>	Solar/PV <sup>c</sup>	Wind <sup>d</sup>	Biomass			Total
					Wood <sup>e</sup>	Waste <sup>f</sup>	Total	
<b>1973 Total</b> .....	2,827	20	NA	NA	1	2	3	2,851
<b>1975 Total</b> .....	3,122	34	NA	NA	(s)	2	2	3,158
<b>1980 Total</b> .....	2,867	53	NA	NA	3	2	4	2,925
<b>1985 Total</b> .....	2,937	97	(s)	(s)	8	7	14	3,049
<b>1990 Total</b> <sup>g</sup> .....	3,014	161	4	29	129	188	317	3,524
<b>1995 Total</b> .....	3,149	138	5	33	125	296	422	3,747
<b>1996 Total</b> .....	3,528	148	5	33	138	300	438	4,153
<b>1997 Total</b> .....	3,581	150	5	34	137	309	446	4,216
<b>1998 Total</b> .....	3,241	151	5	31	137	308	444	3,872
<b>1999 Total</b> .....	3,218	152	5	46	138	315	453	3,874
<b>2000 Total</b> .....	2,768	144	5	57	134	318	453	3,427
<b>2001 Total</b> .....	2,209	142	6	70	126	211	337	2,763
<b>2002 Total</b> .....	2,650	147	6	105	150	230	380	3,288
<b>2003 Total</b> .....	2,781	148	5	115	167	230	397	3,445
<b>2004 Total</b> .....	2,656	148	6	142	165	223	388	3,340
<b>2005 Total</b> .....	2,670	147	6	178	185	221	406	3,406
<b>2006 Total</b> .....	2,839	145	5	264	182	231	412	3,665
<b>2007 Total</b> .....	2,430	145	6	341	186	237	423	3,345
<b>2008 Total</b> .....	2,494	146	9	546	177	258	435	3,630
<b>2009 Total</b> .....	2,650	146	9	721	180	261	441	3,967
<b>2010</b> January .....	217	13	(s)	67	17	21	39	335
February .....	199	11	(s)	53	16	20	36	300
March .....	202	13	1	84	16	22	39	338
April .....	184	12	1	95	15	21	36	329
May .....	243	13	1	85	14	22	36	378
June .....	290	12	2	79	16	23	39	421
July .....	238	12	2	66	17	23	40	358
August .....	195	13	2	65	18	23	41	315
September .....	168	12	1	69	16	22	38	288
October .....	171	12	1	77	15	22	37	298
November .....	190	12	1	95	16	23	39	337
December .....	225	13	(s)	88	17	23	41	367
<b>Total</b> .....	<b>2,521</b>	<b>148</b>	<b>12</b>	<b>923</b>	<b>196</b>	<b>264</b>	<b>459</b>	<b>4,064</b>
<b>2011</b> January .....	254	14	(s)	84	16	21	38	391
February .....	239	13	1	103	15	20	35	390
March .....	308	14	1	103	15	23	38	463
April .....	307	13	2	121	12	22	33	476
May .....	321	14	2	113	13	22	35	486
June .....	313	13	2	106	15	23	38	473
July .....	307	13	2	72	16	24	40	434
August .....	256	13	2	72	16	23	39	383
September .....	209	13	2	67	15	22	37	327
October .....	194	14	2	104	13	23	36	349
November .....	207	13	1	120	13	23	36	377
December .....	239	14	1	102	16	23	39	396
<b>Total</b> .....	<b>3,153</b>	<b>163</b>	<b>18</b>	<b>1,168</b>	<b>175</b>	<b>269</b>	<b>444</b>	<b>4,945</b>
<b>2012</b> January .....	232	14	1	135	16	22	38	420
February .....	201	13	1	108	15	21	35	359
March .....	255	14	2	132	14	23	37	440
April .....	259	13	3	123	11	22	33	432
May .....	281	14	4	121	13	23	36	457
<b>5-Month Total</b> .....	<b>1,228</b>	<b>69</b>	<b>11</b>	<b>619</b>	<b>69</b>	<b>111</b>	<b>180</b>	<b>2,106</b>
<b>2011 5-Month Total</b> .....	<b>1,428</b>	<b>69</b>	<b>6</b>	<b>525</b>	<b>71</b>	<b>108</b>	<b>179</b>	<b>2,206</b>
<b>2010 5-Month Total</b> .....	<b>1,045</b>	<b>62</b>	<b>4</b>	<b>384</b>	<b>79</b>	<b>107</b>	<b>186</b>	<b>1,680</b>

<sup>a</sup> Conventional hydroelectricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>b</sup> Geothermal electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>c</sup> Solar thermal and photovoltaic (PV) electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>d</sup> Wind electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6).

<sup>e</sup> Wood and wood-derived fuels.

<sup>f</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass. Through 2000, also includes non-renewable waste (municipal solid waste from non-biogenic sources, and

tire-derived fuels).

<sup>g</sup> Through 1988, data are for electric utilities only. Beginning in 1989, data are for electric utilities and independent power producers.

NA=Not available. (s)=Less than 0.5 trillion Btu.

Notes: • The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> for all available data beginning in 1973.

Sources: • **Biomass:** Table 7.4b. • **All Other Data:** Tables 7.2b and A6.



**Table 10.3 Fuel Ethanol Overview**

	Feed-stock <sup>a</sup>	Losses and Co-products <sup>b</sup>	Denaturant <sup>c</sup>	Production <sup>d</sup>			Trade <sup>d</sup>	Stocks <sup>d,f</sup>	Stock Change <sup>d,g</sup>	Consumption <sup>d</sup>			Consumption Minus Denaturant <sup>h</sup>
							Net Imports <sup>e</sup>						
				TBtu	TBtu	Mbbl	Mbbl			MMgal	TBtu	Mbbl	
<b>1981 Total</b> .....	13	6	40	1,978	83	7	NA	NA	NA	1,978	83	7	7
<b>1985 Total</b> .....	93	42	294	14,693	617	52	NA	NA	NA	14,693	617	52	51
<b>1990 Total</b> .....	111	49	356	17,802	748	63	NA	NA	NA	17,802	748	63	62
<b>1995 Total</b> .....	198	86	647	32,325	1,358	115	387	2,186	-207	32,919	1,383	117	114
<b>1996 Total</b> .....	141	61	464	23,178	973	83	313	2,065	-121	23,612	992	84	82
<b>1997 Total</b> .....	186	80	613	30,674	1,288	109	85	2,925	860	29,899	1,256	107	104
<b>1998 Total</b> .....	202	86	669	33,453	1,405	119	66	3,406	481	33,038	1,388	118	115
<b>1999 Total</b> .....	211	90	698	34,881	1,465	124	87	4,024	618	34,350	1,443	122	119
<b>2000 Total</b> .....	233	99	773	38,627	1,622	138	116	3,400	-624	39,367	1,653	140	137
<b>2001 Total</b> .....	253	108	841	42,028	1,765	150	315	4,298	898	41,445	1,741	148	144
<b>2002 Total</b> .....	307	130	1,019	50,956	2,140	182	306	6,200	1,902	49,360	2,073	176	171
<b>2003 Total</b> .....	400	169	1,335	66,772	2,804	238	292	5,978	-222	67,286	2,826	240	233
<b>2004 Total</b> .....	484	203	1,621	81,058	3,404	289	3,542	6,002	24	84,576	3,552	301	293
<b>2005 Total</b> .....	552	230	1,859	92,961	3,904	331	3,234	5,563	-439	96,634	4,059	344	335
<b>2006 Total</b> .....	688	285	2,326	116,294	4,884	414	17,408	8,760	3,197	130,505	5,481	465	453
<b>2007 Total</b> .....	914	376	3,105	155,263	6,521	553	10,457	10,535	1,775	163,945	6,886	584	569
<b>2008 Total</b> .....	1,300	531	4,433	221,637	9,309	790	12,610	14,226	3,691	230,556	9,683	821	800
<b>2009 Total</b> .....	1,517	616	5,688	260,424	10,938	928	4,720	16,594	2,368	262,776	11,037	936	910
<b>2010 January</b> .....	149	60	541	25,625	1,076	91	-234	18,251	1,657	23,734	997	85	82
February .....	138	56	496	23,802	1,000	85	-482	19,297	1,046	22,274	936	79	77
March .....	154	62	537	26,486	1,112	94	-1,104	20,222	925	24,457	1,027	87	85
April .....	147	59	522	25,384	1,066	90	-927	20,042	-180	24,637	1,035	88	85
May .....	152	61	534	26,244	1,102	93	-368	19,851	-191	26,067	1,095	93	90
June .....	149	60	522	25,632	1,077	91	-341	18,565	-1,286	26,577	1,116	95	92
July .....	154	62	543	26,584	1,117	95	-578	17,809	-756	26,762	1,124	95	93
August .....	157	63	538	26,964	1,132	96	-695	17,380	-429	26,698	1,121	95	93
September .....	152	61	533	26,221	1,101	93	-924	17,437	57	25,240	1,060	90	88
October .....	160	64	563	27,471	1,154	98	-830	17,278	-159	26,800	1,126	95	93
November .....	161	65	585	27,747	1,165	99	-923	18,150	872	25,952	1,090	92	90
December .....	165	67	592	28,457	1,195	101	-1,711	17,941	-209	26,955	1,132	96	93
<b>Total</b> .....	<b>1,839</b>	<b>742</b>	<b>6,506</b>	<b>316,617</b>	<b>13,298</b>	<b>1,127</b>	<b>-9,115</b>	<b>17,941</b>	<b>1,347</b>	<b>306,155</b>	<b>12,858</b>	<b>1,090</b>	<b>1,061</b>
<b>2011 January</b> .....	165	66	581	28,524	1,198	102	-1,359	20,672	2,732	24,433	1,026	87	85
February .....	147	59	535	25,400	1,067	90	-1,425	20,809	137	23,838	1,001	85	83
March .....	163	65	548	28,194	1,184	100	-2,003	21,440	631	25,560	1,074	91	89
April .....	154	62	507	26,591	1,117	95	-2,865	20,807	-633	24,359	1,023	87	85
May .....	161	64	545	27,756	1,166	99	-1,743	20,387	-420	26,433	1,110	94	92
June .....	157	63	535	27,064	1,137	96	-1,533	18,833	-1,554	27,085	1,138	96	94
July .....	160	64	555	27,624	1,160	98	-2,731	18,700	-133	25,026	1,051	89	87
August .....	163	65	575	28,110	1,181	100	-790	17,900	-800	28,120	1,181	100	97
September .....	154	62	525	26,645	1,119	95	-1,820	18,437	537	24,288	1,020	86	84
October .....	163	65	557	28,092	1,180	100	-2,388	18,072	-365	26,069	1,095	93	90
November .....	164	66	573	28,335	1,190	101	-3,258	18,343	271	24,806	1,042	88	86
December .....	172	69	600	29,772	1,250	106	-3,407	18,261	-82	26,447	1,111	94	92
<b>Total</b> .....	<b>1,922</b>	<b>770</b>	<b>6,636</b>	<b>332,107</b>	<b>13,948</b>	<b>1,182</b>	<b>-25,322</b>	<b>18,261</b>	<b>321</b>	<b>306,464</b>	<b>12,871</b>	<b>1,091</b>	<b>1,063</b>
<b>2012 January</b> .....	167	67	583	29,063	1,221	103	-1,789	21,753	3,492	23,782	999	85	82
February .....	154	61	528	26,653	1,119	95	-1,785	22,572	819	24,049	1,010	86	83
March .....	160	64	522	27,706	1,164	99	-1,626	22,952	380	25,700	1,079	91	89
April .....	152	61	494	26,368	1,107	94	-1,549	22,370	-582	25,401	1,067	90	88
May .....	160	64	520	27,718	1,164	99	-1,013	21,851	-519	27,224	1,143	97	95
<b>5-Month Total</b> ...	<b>793</b>	<b>316</b>	<b>2,647</b>	<b>137,508</b>	<b>5,775</b>	<b>490</b>	<b>-7,762</b>	<b>21,851</b>	<b>3,590</b>	<b>126,156</b>	<b>5,299</b>	<b>449</b>	<b>438</b>
<b>2011 5-Month Total</b> ...	<b>790</b>	<b>316</b>	<b>2,716</b>	<b>136,465</b>	<b>5,732</b>	<b>486</b>	<b>-9,394</b>	<b>20,387</b>	<b>2,447</b>	<b>124,624</b>	<b>5,234</b>	<b>444</b>	<b>432</b>
<b>2010 5-Month Total</b> ...	<b>741</b>	<b>299</b>	<b>2,630</b>	<b>127,541</b>	<b>5,357</b>	<b>454</b>	<b>-3,114</b>	<b>19,851</b>	<b>3,257</b>	<b>121,170</b>	<b>5,089</b>	<b>431</b>	<b>420</b>

<sup>a</sup> Total corn and other biomass inputs to the production of undenatured ethanol used for fuel ethanol.

<sup>b</sup> Losses and co-products from the production of fuel ethanol. Does not include natural gas, electricity, and other non-biomass energy used in the production of fuel ethanol—these are included in the industrial sector consumption statistics for the appropriate energy source.

<sup>c</sup> The amount of denaturant in fuel ethanol produced.

<sup>d</sup> Includes denaturant.

<sup>e</sup> Through 2009, data are for fuel ethanol imports only; data for fuel ethanol exports are not available. Beginning in 2010, data are for fuel ethanol imports minus fuel ethanol exports.

<sup>f</sup> Stocks are at end of period.

<sup>g</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase.

<sup>h</sup> Consumption of fuel ethanol minus denaturant. Data for fuel ethanol minus denaturant are used to develop data for "Renewable Energy/Biomass" in Tables 10.1–10.2b, as well as in Sections 1 and 2.

<sup>i</sup> Derived from the preliminary December 2010 stocks value (17,940 thousand

barrels), not the final December 2010 value (17,941 thousand barrels) that is shown under "Stocks."

NA=Not available.

Notes: • Mbbl = thousand barrels. MMgal = million U.S. gallons. TBtu = trillion Btu. • Fuel ethanol data in thousand barrels are converted to million gallons by multiplying by 0.042, and are converted to Btu by multiplying by the approximate heat content of fuel ethanol—see Table A3. • Through 1980, data are not available. For 1981-1992, data are estimates. For 1993-2008, only data for feedstock, losses and co-products, and denaturant are estimates. Beginning in 2009, only data for feedstock, and losses and co-products, are estimates. • See "Denaturant," "Ethanol," "Fuel Ethanol," and "Fuel Ethanol Minus Denaturant" in Glossary. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> for all available data beginning in 1981.

Sources: See end of section.

**Table 10.4 Biodiesel Overview**

	Feed-stock <sup>a</sup>	Losses and Co-products <sup>b</sup>	Production			Trade			Stocks <sup>d</sup>	Stock Change <sup>e</sup>	Balancing Item <sup>f</sup>	Consumption		
						Imports	Exports	Net Imports <sup>c</sup>						
			TBtu	TBtu	Mbbl	MMgal	TBtu	Mbbl				Mbbl	Mbbl	Mbbl
<b>2001 Total</b> .....	1	(s)	204	9	1	78	39	39	NA	NA	NA	243	10	1
<b>2002 Total</b> .....	1	(s)	250	10	1	191	56	135	NA	NA	NA	385	16	2
<b>2003 Total</b> .....	2	(s)	338	14	2	94	110	-16	NA	NA	NA	322	14	2
<b>2004 Total</b> .....	4	(s)	666	28	4	97	124	-26	NA	NA	NA	640	27	3
<b>2005 Total</b> .....	12	(s)	2,162	91	12	207	206	1	NA	NA	NA	2,163	91	12
<b>2006 Total</b> .....	32	(s)	5,963	250	32	1,069	828	242	NA	NA	NA	6,204	261	33
<b>2007 Total</b> .....	63	1	11,662	490	62	3,342	6,477	-3,135	NA	NA	NA	8,528	358	46
<b>2008 Total</b> .....	88	1	16,145	678	87	7,502	16,128	-8,626	NA	NA	NA	7,519	316	40
<b>2009 Total</b> .....	67	1	12,281	516	66	1,844	6,332	-4,489	711	711	669	7,750	326	42
<b>2010 January</b> .....	3	(s)	633	27	3	41	296	-256	1,049	338	0	40	2	(s)
February .....	4	(s)	696	29	4	31	139	-108	1,039	-10	0	599	25	3
March .....	4	(s)	804	34	4	60	433	-374	1,057	18	0	412	17	2
April .....	4	(s)	814	34	4	45	227	-182	1,009	-48	0	680	29	4
May .....	4	(s)	760	32	4	80	251	-171	1,016	7	0	582	24	3
June .....	4	(s)	644	27	3	54	304	-249	968	-48	0	443	19	2
July .....	4	(s)	657	28	4	32	199	-167	830	-138	0	628	26	3
August .....	4	(s)	653	27	3	52	225	-173	771	-59	0	539	23	3
September .....	4	(s)	723	30	4	69	131	-62	682	-89	0	749	31	4
October .....	4	(s)	676	28	4	18	132	-114	650	-32	0	594	25	3
November .....	3	(s)	528	22	3	30	57	-27	676	26	0	475	20	3
December .....	3	(s)	588	25	3	34	109	-75	672	-4	0	517	22	3
<b>Total</b> .....	44	1	8,177	343	44	546	2,503	-1,958	672	-39	0	6,258	263	34
<b>2011 January</b> .....	5	(s)	842	35	5	49	217	-169	738	976	0	597	25	3
February .....	5	(s)	961	40	5	37	88	-51	869	131	0	779	33	4
March .....	8	(s)	1,419	60	8	53	197	-144	984	115	0	1,160	49	6
April .....	9	(s)	1,692	71	9	52	222	-169	1,012	28	0	1,494	63	8
May .....	10	(s)	1,838	77	10	48	192	-144	1,102	90	0	1,604	67	9
June .....	11	(s)	1,938	81	10	48	117	-69	1,216	114	0	1,755	74	9
July .....	12	(s)	2,183	92	12	62	142	-80	1,267	51	0	2,052	86	11
August .....	12	(s)	2,273	95	12	65	71	-7	1,663	396	0	1,871	79	10
September .....	12	(s)	2,283	96	12	65	193	-127	1,201	-462	0	2,617	110	14
October .....	14	(s)	2,508	105	13	82	132	-49	1,481	280	0	2,179	92	12
November .....	14	(s)	2,494	105	13	66	131	-65	1,436	-45	0	2,474	104	13
December .....	14	(s)	2,604	109	14	234	39	195	1,902	466	0	2,333	98	13
<b>Total</b> .....	125	2	23,034	967	123	861	1,740	-879	1,902	91,240	0	20,915	878	112
<b>2012 January</b> .....	9	(s)	1,700	71	9	44	248	-204	R 2,527	R 625	0	R 872	R 37	R 5
February .....	10	(s)	1,837	77	10	58	119	-62	R 2,869	R 342	0	R 1,433	R 60	R 8
March .....	12	(s)	2,193	92	12	55	149	-93	R 3,053	R 184	0	R 1,915	R 80	R 10
April .....	12	(s)	2,180	92	12	49	221	-171	R 2,932	R -121	0	R 2,130	R 89	R 11
May .....	13	(s)	2,373	100	13	94	306	-212	2,514	-418	0	2,579	108	14
<b>5-Month Total</b> .....	56	1	10,283	432	55	301	1,042	-742	2,514	612	0	8,930	375	48
<b>2011 5-Month Total</b> .....	37	(s)	6,751	284	36	239	916	-677	1,102	440	0	5,634	237	30
<b>2010 5-Month Total</b> .....	20	(s)	3,708	156	20	256	1,347	-1,090	1,016	305	0	2,313	97	12

<sup>a</sup> Total vegetable oil and other biomass inputs to the production of biodiesel.  
<sup>b</sup> Losses and co-products from the production of biodiesel. Does not include natural gas, electricity, and other non-biomass energy used in the production of biodiesel—these are included in the industrial sector consumption statistics for the appropriate energy source.  
<sup>c</sup> Net imports equal imports minus exports.  
<sup>d</sup> Stocks are at end of period.  
<sup>e</sup> A negative value indicates a decrease in stocks and a positive value indicates an increase.  
<sup>f</sup> Beginning in 2009, because of incomplete data coverage and different data sources, "Balancing Item" is used to balance biodiesel supply and disposition.  
<sup>g</sup> Derived from the preliminary December 2010 stocks value (662 thousand barrels), not the final December 2010 value (672 thousand barrels) that is shown

under "Stocks."  
 R=Revised. NA=Not available. (s)=Less than 0.5 trillion Btu.  
 Notes: • Mbbl = thousand barrels. MMgal = million U.S. gallons. TBtu = trillion Btu. • Biodiesel data in thousand barrels are converted to million gallons by multiplying by 0.042, and are converted to Btu by multiplying by 5.359 million Btu per barrel (the approximate heat content of biodiesel—see Table A3). • Through 2000, data are not available. Beginning in 2001, data not from U.S. Energy Information Administration (EIA) surveys are estimates. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#renewable> for all available data beginning in 2001.  
 Sources: See end of section.

## Renewable Energy

**Note. Renewable Energy Production and Consumption.** In Tables 1.1, 1.3, and 10.1, renewable energy consumption consists of: conventional hydroelectricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6); geothermal electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6), and geothermal heat pump and geothermal direct use energy; solar thermal and photovoltaic electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6), and solar thermal direct use energy; wind electricity net generation (converted to Btu using the fossil-fuels heat rate—see Table A6); wood and wood-derived fuels consumption; biomass waste (municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass) consumption; fuel ethanol (minus denaturant) and biodiesel consumption; and losses and co-products from the production of fuel ethanol and biodiesel. In Tables 1.1, 1.2, and 10.1, renewable production is assumed to equal consumption for all renewable energy sources except biofuels (biofuels production comprises biomass inputs to the production of fuel ethanol and biodiesel).

### Table 10.2a Sources

#### Residential Sector, Geothermal

Oregon Institute of Technology, Geo-Heat Center. Monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. (The annual estimate for the current year is set equal to that of the previous year.)

#### Residential Sector, Solar/PV

1989–2009: U.S. Energy Information Administration (EIA) estimates based on Form EIA-63A, “Annual Solar Thermal Collector Manufacturers Survey,” and Form EIA-63B, “Annual Photovoltaic Module/Cell Manufacturers Survey.” Monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.

2010 forward: EIA estimates based on Form EIA-63B, “Annual Photovoltaic Cell/Module Shipments Report”; Form EIA-63A, “Annual Solar Thermal Collector Manufacturers Survey” (pre-2010 data); and SEIA/GTM Research, *U.S. Solar Market Insight: 2010 Year in Review*. Monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. (The annual estimate for 2012 is derived using the average annual growth rate for 2009–2011.)

#### Residential Sector, Wood

1973–1979: EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.

1980 forward: EIA, Form EIA-457, “Residential Energy Consumption Survey”; and EIA estimates based on Form EIA-457 and regional heating degree-day data. Monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. (The annual estimate for the current year is set equal to that of the previous year.)

#### Commercial Sector, Hydroelectric Power

1989 forward: Commercial sector conventional hydroelectricity net generation data from EIA, Form EIA-923, “Power Plant Operations Report,” and predecessor forms, are converted to Btu by multiplying by the fossil-fuels heat rate—see Table A6.

#### Commercial Sector, Geothermal

Oregon Institute of Technology, Geo-Heat Center. Monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. (The annual estimate for the current year is set equal to that of the previous year.)

#### Commercial Sector, Solar/PV

2008 forward: Commercial sector solar thermal and photovoltaic (PV) electricity net generation data from EIA, Form EIA-923, “Power Plant Operations Report,” are converted to Btu by multiplying by the fossil-fuels heat rate—see Table A6.

#### Commercial Sector, Wind

2009 forward: Commercial sector wind electricity net generation data from EIA, Form EIA-923, “Power Plant Operations Report,” are converted to Btu by multiplying by the fossil-fuels heat rate—see Table A6.

#### Commercial Sector, Wood

1973–1979: EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.

1980–1983: EIA, *Estimates of U.S. Wood Energy Consumption 1980-1983*, Table ES1.

1984: EIA estimate based on the 1983 value.

1985–1988: Values interpolated.

1989 forward: EIA, *Monthly Energy Review (MER)*, Tables 7.4a–7.4c; and EIA estimates based on Form EIA-871, “Commercial Buildings Energy Consumption Survey.” Data for wood consumption at commercial combined-heat-and-power (CHP) plants are calculated as total wood consumption at electricity-only and CHP plants (MER, Table 7.4a) minus wood consumption in the electric power sector (MER, Table 7.4b) and at industrial CHP plants (MER, Table 7.4c). Annual estimates for wood consumption at other commercial plants are based on Form EIA-871 (the annual estimate for the current year is set equal to that of the previous year); monthly estimates are created by dividing

the annual estimates by the number of days in the year and then multiplying by the number of days in the month.

### **Commercial Sector, Biomass Waste**

EIA, MER, Table 7.4c.

### **Commercial Sector, Fuel Ethanol (Minus Denaturant)**

EIA, MER, Tables 3.5, 3.7a, and 10.3. Calculated as commercial sector motor gasoline consumption (Table 3.7a) divided by total motor gasoline product supplied (Table 3.5), and then multiplied by fuel ethanol (minus denaturant) consumption (Table 10.3).

## **Table 10.2b Sources**

### **Industrial Sector, Hydroelectric Power**

Industrial sector conventional hydroelectricity net generation data from Table 7.2c are converted to Btu by multiplying by the fossil-fuels heat rate—see Table A6.

### **Industrial Sector, Geothermal**

Oregon Institute of Technology, Geo-Heat Center. Monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month. (The annual estimate for the current year is set equal to that of the previous year.)

### **Industrial Sector, Solar/PV**

2010 forward: Industrial sector solar thermal and photovoltaic (PV) electricity net generation data from the U.S. Energy Information Administration (EIA), Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the fossil-fuels heat rate—see Table A6.

### **Industrial Sector, Wind**

2011 forward: Industrial sector wind electricity net generation data from EIA, Form EIA-923, "Power Plant Operations Report," are converted to Btu by multiplying by the fossil-fuels heat rate—see Table A6.

### **Industrial Sector, Wood**

1973–1979: EIA, *Estimates of U.S. Wood Energy Consumption from 1949 to 1981*, Table A2.

1980–1983: EIA, *Estimates of U.S. Wood Energy Consumption 1980-1983*, Table ES1.

1984: EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 1.

1985 and 1986: Values interpolated.

1987: EIA, *Estimates of Biofuels Consumption in the United States During 1987*, Table 2.

1988: Value interpolated.

1989 forward: EIA, *Monthly Energy Review (MER)*, Table 7.4c; and EIA estimates based on Form EIA-846, "Manufacturing Energy Consumption Survey." Data for wood consumption at industrial combined-heat-and-power (CHP) plants are from MER, Table 7.4c. Annual estimates for wood consumption at other industrial plants are based on Form EIA-846 (the annual estimate for the current year is set equal to that of the previous year); monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.

### **Industrial Sector, Biomass Waste**

1981: EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8; and EIA, MER, Table 10.2c. Estimates are calculated as total waste consumption minus electric power sector waste consumption.

1982 and 1983: EIA estimates for total waste consumption based on *Estimates of U.S. Biofuels Consumption 1990*, Table 8; and EIA, MER, Table 10.2c. Estimates are calculated as total waste consumption minus electric power sector waste consumption.

1984: EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8; and EIA, MER, Table 10.2c. Estimates are calculated as total waste consumption minus electric power sector waste consumption.

1985 and 1986: Values interpolated.

1987: EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 8; and EIA, MER, Table 10.2c. Estimates are calculated as total waste consumption minus electric power sector waste consumption.

1988: Value interpolated.

1989 forward: EIA, MER, Table 7.4c; and EIA estimates based on information presented in Government Advisory Associates, *Resource Recovery Yearbook* and *Methane Recovery Yearbook*, and information provided by the U.S. Environmental Protection Agency, Landfill Methane Outreach Program. Data for waste consumption at industrial CHP plants are from MER, Table 7.4c. Annual estimates for waste consumption at other industrial plants are based on the non-EIA sources listed above (the annual estimate for the current year is set equal to that of the previous year); monthly estimates are created by dividing the annual estimates by the number of days in the year and then multiplying by the number of days in the month.

### **Industrial Sector, Fuel Ethanol (Minus Denaturant)**

EIA, MER, Tables 3.5, 3.7b, and 10.3. Calculated as industrial sector motor gasoline consumption (Table 3.7b) divided by total motor gasoline product supplied (Table

3.5), and then multiplied by fuel ethanol (minus denaturant) consumption (Table 10.3).

### **Industrial Sector, Losses and Co-products**

Calculated as fuel ethanol losses and co-products (Table 10.3) plus biodiesel losses and co-products (Table 10.4).

### **Transportation Sector, Fuel Ethanol (Minus Denaturant)**

EIA, MER, Tables 3.5, 3.7c, and 10.3. Calculated as transportation sector motor gasoline consumption (Table 3.7c) divided by total motor gasoline product supplied (Table 3.5), and then multiplied by fuel ethanol (minus denaturant) consumption (Table 10.3).

### **Transportation Sector, Biodiesel**

EIA, MER, Table 10.4. Transportation sector biodiesel consumption is assumed to equal total biodiesel consumption.

## **Table 10.3 Sources**

### **Feedstock**

Calculated as fuel ethanol production (in thousand barrels) minus denaturant, and then multiplied by the fuel ethanol feedstock factor—see Table A3.

### **Losses and Co-products**

Calculated as fuel ethanol feedstock plus denaturant minus fuel ethanol production.

### **Denaturant**

1981–2008: Data in thousand barrels for petroleum denaturant in fuel ethanol produced are estimated as 2 percent of fuel ethanol production; these data are converted to Btu by multiplying by 4.645 million Btu per barrel (the estimated quantity-weighted factor of pentanes plus and conventional motor gasoline used as denaturant).

2009 and 2010: U.S. Energy Information Administration (EIA), *Petroleum Supply Annual (PSA)*, annual reports, Table 1. Data in thousand barrels for net production of pentanes plus at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 4.620 million Btu per barrel (the approximate heat content of pentanes plus). Data in thousand barrels for net production of conventional motor gasoline and motor gasoline blending components at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 5.253 million Btu per barrel (the approximate heat content of conventional motor gasoline). Total denaturant is the sum of the values for pentanes plus, conventional motor gasoline, and motor gasoline blending components.

2011 and 2012: EIA, *Petroleum Supply Monthly (PSM)*, monthly reports, Table 1. Data in thousand barrels for net production of pentanes plus at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to

Btu by multiplying by 4.620 million Btu per barrel (the approximate heat content of pentanes plus). Data in thousand barrels for net production of conventional motor gasoline and motor gasoline blending components at renewable fuels and oxygenate plants are multiplied by -1; these data are converted to Btu by multiplying by 5.253 million Btu per barrel (the approximate heat content of conventional motor gasoline). Total denaturant is the sum of the values for pentanes plus, conventional motor gasoline, and motor gasoline blending components.

### **Production**

1981–1992: Fuel ethanol production is assumed to equal fuel ethanol consumption—see sources for "Consumption."

1993–2004: Calculated as fuel ethanol consumption plus fuel ethanol stock change minus fuel ethanol net imports. These data differ slightly from the original production data from EIA, Form EIA-819, "Monthly Oxygenate Report," and predecessor form, which were not reconciled and updated to be consistent with the final balance.

2005–2008: EIA, Form EIA-819, "Monthly Oxygenate Report."

2009 and 2010: EIA, PSA, annual reports, Table 1, data for net production of fuel ethanol at renewable fuels and oxygenate plants.

2011 and 2012: EIA, PSM, monthly reports, Table 1, data for net production of fuel ethanol at renewable fuels and oxygenate plants.

### **Trade, Stocks, and Stock Change**

1992–2010: EIA, PSA, annual reports, Table 1.

2011 and 2012: EIA, PSM, monthly reports, Table 1.

### **Consumption**

1981–1989: EIA, *Estimates of U.S. Biofuels Consumption 1990*, Table 10; and interpolated values for 1982, 1983, 1985, 1986, and 1988.

1990–1992: EIA, *Estimates of U.S. Biomass Energy Consumption 1992*, Table D2; and interpolated value for 1991.

1993–2004: EIA, PSA, annual reports, Tables 2 and 16. Calculated as 10 percent of oxygenated finished motor gasoline field production (Table 2), plus fuel ethanol refinery input (Table 16).

2005–2008: EIA, PSA, annual reports, Tables 1 and 15. Calculated as motor gasoline blending components adjustments (Table 1), plus finished motor gasoline adjustments (Table 1), plus fuel ethanol refinery and blender net inputs (Table 15).

2009 and 2010: EIA, PSA, annual reports, Table 1. Calculated as fuel ethanol refinery and blender net inputs minus fuel ethanol adjustments.

2011 and 2012: EIA, PSM, monthly reports, Table 1. Calculated as fuel ethanol refinery and blender net inputs minus fuel ethanol adjustments.

### **Consumption Minus Denaturant**

Calculated as fuel ethanol consumption minus the amount of denaturant in fuel ethanol consumed. Denaturant in fuel ethanol consumed is estimated by multiplying denaturant in fuel ethanol produced by the fuel ethanol consumption-to-production ratio.

## **Table 10.4 Sources**

### **Feedstock**

Calculated as biodiesel production in thousand barrels multiplied by 5.433 million Btu per barrel (the biodiesel feedstock factor—see Table A3).

### **Losses and Co-products**

Calculated as biodiesel feedstock minus biodiesel production.

### **Production**

2001–2005: U.S. Department of Agriculture, Commodity Credit Corporation, Bioenergy Program records. Annual data are derived from quarterly data. Monthly data are estimated by dividing the annual data by the number of days in the year and then multiplying by the number of days in the month.

2006: U.S. Department of Commerce, Bureau of the Census, “M311K—Fats and Oils: Production, Consumption, and Stocks,” data for soybean oil consumed in methyl esters (biodiesel). In addition, the U.S. Energy Information Administration (EIA) estimates that 14.4 million gallons of yellow grease were consumed in methyl esters (biodiesel).

2007: U.S. Department of Commerce, Bureau of the Census, “M311K—Fats and Oils: Production, Consumption, and Stocks,” data for all fats and oils consumed in methyl esters (biodiesel).

2008: EIA, *Monthly Biodiesel Production Report*, December 2009 (release date October 2010), Table 11. Monthly data for 2008 are estimated based on U.S. Department of

Commerce, Bureau of the Census, M311K data, multiplied by the EIA 2008 annual value’s share of the M311K 2008 annual value.

2009 forward: EIA, *Monthly Biodiesel Production Report*, monthly reports, Table 1.

### **Trade**

For imports, U.S. Department of Agriculture, data for the following Harmonized Tariff Schedule codes: 3824.90.40.20, “Fatty Esters Animal/Vegetable Mixture” (data through June 2010); 3824.90.40.30, “Biodiesel/Mixes” (data for July 2010–2011); 3826.00.00.00, “Biodiesel B30-99” (data for 2012); and 3826.00.10.00, “Biodiesel B100” (data for 2012). For exports, U.S. Department of Agriculture, data for the following Schedule B codes: 3824.90.40.00, “Fatty Substances Animal/Vegetable/Mixture” (data through 2010); 3824.90.40.30, “Biodiesel <70%” (data for 2011); and 3826.00.00.00, “Biodiesel B=>30” (data for 2012). Although these categories include products other than biodiesel (such as biodiesel coprocessed with petroleum feedstocks; and products destined for soaps, cosmetics, and other items), biodiesel is the largest component. In the absence of other reliable data for biodiesel trade, EIA sees these data as good substitutes.

### **Stocks and Stock Change**

2009 and 2010: EIA, *Petroleum Supply Annual (PSA)*, annual reports, Table 1, data for renewable fuels except fuel ethanol.

2011 and 2012: EIA, *Petroleum Supply Monthly*, monthly reports, Table 1, data for renewable fuels except fuel ethanol.

### **Balancing Item**

Calculated as biodiesel consumption and biodiesel stock change minus biodiesel production and biodiesel net imports.

### **Consumption**

2001–2008: Calculated as biodiesel production plus biodiesel net imports.

January and February 2009: EIA, PSA, Table 1, data for refinery and blender net inputs of renewable fuels except fuel ethanol.


March 2009 forward: Calculated as biodiesel production plus biodiesel net imports minus biodiesel stock change.

# **11. International Petroleum**


---

**Figure 11.1a World Crude Oil Production Overview**  
(Million Barrels per Day)


World Production, 1973-2011




World Production, Monthly



Selected Producers, 1973-2011



Selected Producers, Monthly




Notes: • OPEC is the Organization of the Petroleum Exporting Countries. • The Persian Gulf Nations are Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, and the United Arab Emirates. Production from the Neutral Zone between Kuwait and Saudi Arabia is included in "Per-

sian Gulf Nations." Web Page: <http://www.eia.gov/totalenergy/data/monthly/#international>. Sources: Tables 11.1a and 11.1b.



**Figure 11.1b World Crude Oil Production by Selected Country**  
(Million Barrels per Day)



Note: OPEC is the Organization of the Petroleum Exporting Countries.  
 Web Page: <http://www.eia.gov/totalenergy/data/monthly/#international>.  
 Sources: Tables 11.1a and 11.1b.

**Table 11.1a World Crude Oil Production: OPEC Members**  
(Thousand Barrels per Day)

	Algeria	Angola	Ecuador	Iran	Iraq	Kuwait <sup>a</sup>	Libya	Nigeria	Qatar	Saudi Arabia <sup>a</sup>	United Arab Emirates	Venezuela	Total OPEC <sup>b</sup>
1973 Average	1,097	162	209	5,861	2,018	3,020	2,175	2,054	570	7,596	1,533	3,366	29,661
1975 Average	983	165	161	5,350	2,262	2,084	1,480	1,783	438	7,075	1,664	2,346	25,790
1980 Average	1,106	150	204	1,662	2,514	1,656	1,787	2,055	472	9,900	1,709	2,168	25,383
1985 Average	1,036	231	281	2,250	1,433	1,023	1,059	1,495	301	3,388	1,193	1,677	15,367
1990 Average	1,180	475	285	3,088	2,040	1,175	1,375	1,810	406	6,410	2,117	2,137	22,498
1995 Average	1,162	646	392	3,643	560	2,057	1,390	1,993	442	8,231	2,233	2,750	25,500
1996 Average	1,227	709	396	3,686	579	2,062	1,401	2,001	510	8,218	2,278	2,938	26,003
1997 Average	1,259	714	388	3,664	1,155	2,007	1,446	2,132	550	8,362	2,316	3,280	27,274
1998 Average	1,226	735	375	3,634	2,150	2,085	1,390	2,153	696	8,389	2,345	3,167	28,346
1999 Average	1,177	745	373	3,557	2,508	1,898	1,319	2,130	665	7,833	2,169	2,826	27,199
2000 Average	1,214	746	395	3,696	2,571	2,079	1,410	2,165	737	8,404	2,368	3,155	28,940
2001 Average	1,265	742	412	3,724	2,390	1,998	1,367	2,256	714	8,031	2,205	3,010	28,114
2002 Average	1,349	896	393	3,444	2,023	1,894	1,319	2,118	679	7,634	2,082	2,604	26,435
2003 Average	1,516	903	411	3,743	1,308	2,136	1,421	2,275	715	8,775	2,348	2,335	27,885
2004 Average	1,582	1,052	528	4,001	2,011	2,376	1,515	2,329	783	9,101	2,478	2,557	30,313
2005 Average	1,692	1,250	532	4,139	1,878	2,529	1,633	2,627	835	9,550	2,535	2,565	31,766
2006 Average	1,699	1,413	536	4,028	1,996	2,535	1,681	2,440	850	9,152	2,636	2,511	31,476
2007 Average	1,708	1,744	511	3,912	2,086	2,464	1,702	2,350	851	8,722	2,603	2,433	31,085
2008 Average	1,705	1,981	505	4,050	2,375	2,586	1,736	2,165	924	9,261	2,681	2,394	32,363
2009 Average	1,585	1,907	486	4,037	2,391	2,350	1,650	2,208	927	8,250	2,413	2,239	30,442
<b>2010</b> January	1,540	2,040	464	4,088	2,475	2,250	1,650	2,480	969	8,240	2,414	2,090	30,699
February	1,540	2,060	470	4,100	2,475	2,250	1,650	2,420	1,036	8,440	2,414	2,140	30,995
March	1,540	2,070	478	4,112	2,375	2,250	1,650	2,430	1,055	8,540	2,414	2,090	31,004
April	1,540	2,070	480	4,120	2,375	2,250	1,650	2,360	1,072	8,740	2,414	2,110	31,181
May	1,540	2,030	478	4,120	2,375	2,250	1,650	2,310	1,091	8,740	2,415	2,140	31,138
June	1,540	1,980	491	4,127	2,425	2,250	1,650	2,410	1,113	9,240	2,415	2,140	31,780
July	1,540	1,970	492	4,033	2,325	2,350	1,650	2,410	1,136	9,340	2,415	2,140	31,801
August	1,540	1,890	485	4,040	2,325	2,350	1,650	2,510	1,164	9,340	2,415	2,140	31,849
September	1,540	1,790	490	4,047	2,375	2,350	1,650	2,550	1,193	9,340	2,415	2,140	31,880
October	1,540	1,790	497	4,053	2,375	2,350	1,650	2,580	1,216	8,840	2,415	2,140	31,446
November	1,540	1,790	508	4,060	2,375	2,350	1,650	2,510	1,235	9,040	2,415	2,240	31,713
December	1,540	1,790	499	4,068	2,525	2,350	1,650	2,490	1,235	8,940	2,415	2,240	31,742
<b>Average</b>	<b>1,540</b>	<b>1,939</b>	<b>486</b>	<b>4,080</b>	<b>2,399</b>	<b>2,300</b>	<b>1,650</b>	<b>2,455</b>	<b>1,127</b>	<b>8,900</b>	<b>2,415</b>	<b>2,146</b>	<b>31,437</b>
<b>2011</b> January	1,540	1,790	500	4,076	2,625	2,350	1,650	2,580	1,280	9,140	2,520	2,240	32,291
February	1,540	1,790	509	4,084	2,525	2,350	1,340	2,570	1,280	9,140	2,520	2,240	31,888
March	1,540	1,790	501	4,092	2,525	2,450	300	2,450	1,290	8,940	2,620	2,240	30,738
April	1,540	1,740	504	4,100	2,525	2,550	200	2,500	1,300	8,940	2,720	2,240	30,859
May	1,540	1,640	497	4,100	2,575	2,550	200	2,570	1,300	8,940	2,720	2,240	30,872
June	1,540	1,690	495	4,100	2,575	2,550	100	2,570	1,300	9,640	2,720	2,240	31,520
July	1,540	1,740	492	4,050	2,625	2,550	100	2,570	1,300	9,840	2,720	2,240	31,767
August	1,540	1,790	495	4,050	2,625	2,600	0	2,600	1,300	9,940	2,720	2,240	31,900
September	1,540	1,840	496	4,050	2,725	2,600	100	2,600	1,300	9,740	2,720	2,240	31,951
October	1,540	1,790	502	4,000	2,725	2,600	300	2,400	1,300	9,540	2,720	2,240	31,657
November	1,540	1,940	504	4,000	2,725	2,600	550	2,500	1,300	9,840	2,720	2,240	32,459
December	1,540	1,890	501	3,950	2,725	2,600	800	2,400	1,300	9,840	2,820	2,240	32,606
<b>Average</b>	<b>1,540</b>	<b>1,786</b>	<b>500</b>	<b>4,054</b>	<b>2,626</b>	<b>2,530</b>	<b>465</b>	<b>2,525</b>	<b>1,296</b>	<b>9,458</b>	<b>2,688</b>	<b>2,240</b>	<b>31,708</b>
<b>2012</b> January	1,550	1,890	504	3,850	2,675	2,650	1,000	2,500	1,300	9,840	2,620	2,240	32,619
February	1,550	1,940	503	3,800	2,575	2,650	1,200	2,550	1,300	9,840	2,620	2,240	32,768
March	1,550	1,790	499	3,750	2,725	2,650	1,350	2,500	1,200	10,040	2,620	2,240	32,914
April	1,550	1,890	500	3,600	2,965	2,650	1,400	2,600	1,190	10,040	2,620	2,240	33,245
May	1,550	1,840	498	3,525	2,925	2,650	1,400	2,550	1,200	9,840	2,620	2,240	32,838
<b>5-Month Average</b>	<b>1,550</b>	<b>1,869</b>	<b>501</b>	<b>3,704</b>	<b>2,774</b>	<b>2,650</b>	<b>1,270</b>	<b>2,539</b>	<b>1,238</b>	<b>9,920</b>	<b>2,620</b>	<b>2,240</b>	<b>32,876</b>
<b>2011 5-Month Average</b>	<b>1,540</b>	<b>1,749</b>	<b>502</b>	<b>4,090</b>	<b>2,556</b>	<b>2,451</b>	<b>730</b>	<b>2,534</b>	<b>1,290</b>	<b>9,018</b>	<b>2,621</b>	<b>2,240</b>	<b>31,322</b>
<b>2010 5-Month Average</b>	<b>1,540</b>	<b>2,054</b>	<b>474</b>	<b>4,108</b>	<b>2,414</b>	<b>2,250</b>	<b>1,650</b>	<b>2,400</b>	<b>1,045</b>	<b>8,541</b>	<b>2,414</b>	<b>2,114</b>	<b>31,003</b>

<sup>a</sup> Except for the period from August 1990 through May 1991, includes about one-half of the production in the Kuwait-Saudi Arabia Neutral Zone. Kuwaiti Neutral Zone output was discontinued following Iraq's invasion of Kuwait on August 2, 1990, but was resumed in June 1991. In May 2012, Neutral Zone production by both Kuwait and Saudi Arabia totaled about 600 thousand barrels per day. Data for Saudi Arabia include approximately 150 thousand barrels per day from the Abu Safah field produced on behalf of Bahrain.

<sup>b</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. On Tables 11.1a and 11.1b, countries are classified as "OPEC" or "Non-OPEC" in all years based on their status in the most current year. For

example, Ecuador rejoined OPEC in 2007, and is thus included in "Total OPEC" for all years; and Indonesia left OPEC at the end of 2008, and is thus included in "Total Non-OPEC" for all years.

Notes: • Data are for crude oil and lease condensate; they exclude natural gas plant liquids. • Monthly data are often preliminary figures and may not average to the annual totals because of rounding or because updates to the preliminary monthly data are not available.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#international> for all available data beginning in 1973.

Sources: See end of section.

**Table 11.1b World Crude Oil Production: Persian Gulf Nations, Non-OPEC, and World** (Thousand Barrels per Day)

	Persian Gulf Nations <sup>b</sup>	Selected Non-OPEC <sup>a</sup> Producers									Total Non-OPEC <sup>a</sup>	World
		Canada	China	Egypt	Mexico	Norway	Former U.S.S.R.	Russia	United Kingdom	United States		
1973 Average	20,668	1,798	1,090	165	465	32	8,324	NA	2	9,208	26,018	55,679
1975 Average	18,934	1,430	1,490	235	705	189	9,523	NA	12	8,375	27,039	52,828
1980 Average	17,961	1,435	2,114	595	1,936	486	11,706	NA	1,622	8,597	34,175	59,558
1985 Average	9,630	1,471	2,505	887	2,745	773	11,585	NA	2,530	8,971	38,598	53,965
1990 Average	15,278	1,553	2,774	873	2,553	1,630	10,975	NA	1,820	7,355	37,999	60,497
1995 Average	17,208	1,805	2,990	920	2,711	2,766	---	5,995	2,489	6,560	36,934	62,434
1996 Average	17,367	1,837	3,131	922	2,944	3,091	---	5,850	2,568	6,465	37,815	63,818
1997 Average	18,095	1,922	3,200	856	3,104	3,142	---	5,920	2,518	6,452	38,532	65,806
1998 Average	19,337	1,981	3,198	834	3,160	3,011	---	5,854	2,616	6,252	38,685	67,032
1999 Average	18,667	1,907	3,195	852	2,998	3,019	---	6,079	2,684	5,881	38,768	65,967
2000 Average	19,892	1,977	3,249	768	3,104	3,222	---	6,479	2,275	5,822	39,583	68,522
2001 Average	19,098	2,029	3,300	720	3,218	3,226	---	6,917	2,282	5,801	40,003	68,116
2002 Average	17,794	2,171	3,390	715	3,263	3,131	---	7,408	2,292	5,746	40,826	67,262
2003 Average	19,063	2,306	3,409	713	3,459	3,042	---	8,132	2,093	5,681	41,515	69,400
2004 Average	20,787	2,398	3,485	673	3,476	2,954	---	8,805	1,845	5,419	42,133	72,446
2005 Average	21,501	2,369	3,609	623	3,423	2,698	---	9,043	1,649	5,178	41,871	73,637
2006 Average	21,232	2,525	3,673	535	3,345	2,491	---	9,247	1,490	5,102	41,804	73,280
2007 Average	20,672	2,628	3,729	530	3,143	2,270	---	9,437	1,498	5,064	41,715	72,800
2008 Average	21,913	2,579	3,790	566	2,839	2,182	---	9,357	1,391	4,950	41,212	73,575
2009 Average	20,402	2,579	3,799	587	2,646	2,067	---	9,495	1,328	5,361	41,788	72,230
2010 January	20,471	2,497	3,968	579	2,660	2,060	---	9,615	1,379	R 5,396	R 42,147	R 72,846
February	20,750	2,712	3,938	578	2,655	2,038	---	9,648	1,274	5,543	R 42,561	R 73,556
March	20,781	2,621	3,981	577	2,641	1,983	---	9,683	1,429	R 5,513	R 42,762	R 73,766
April	21,007	2,695	3,961	576	2,639	1,967	---	9,646	1,378	R 5,376	R 42,556	R 73,737
May	21,025	2,745	4,040	576	2,639	1,921	---	9,691	1,297	R 5,397	R 42,613	R 73,752
June	21,604	2,772	4,108	575	2,592	1,611	---	9,727	1,076	R 5,387	R 42,091	R 73,871
July	21,634	2,765	4,056	575	2,618	1,864	---	9,710	1,055	R 5,318	R 42,331	R 74,132
August	21,669	2,783	4,104	574	2,604	1,648	---	9,623	1,070	R 5,449	R 42,209	R 74,058
September	21,755	2,648	4,183	574	2,615	1,637	---	9,725	1,194	R 5,614	R 42,480	R 74,360
October	21,284	2,690	4,181	573	2,615	1,952	---	9,816	1,195	R 5,604	R 42,784	R 74,231
November	21,510	2,942	4,263	573	2,556	1,868	---	9,723	1,248	R 5,568	R 43,113	R 74,826
December	21,568	2,933	4,126	572	2,620	1,886	---	9,719	1,207	R 5,630	R 43,084	R 74,826
Average	21,257	2,734	4,076	575	2,621	1,869	---	9,694	1,233	5,482	R 42,561	R 73,998
2011 January	22,026	2,870	4,195	570	2,632	1,905	---	9,769	1,316	RE 5,529	R 43,003	R 75,295
February	21,934	2,906	4,147	569	2,602	1,861	---	9,773	1,085	RE 5,442	R 42,619	R 74,507
March	21,952	2,854	4,139	568	2,620	1,808	---	9,753	1,073	RE 5,641	R 42,716	R 73,454
April	22,170	2,848	4,127	567	2,621	1,874	---	9,795	1,164	RE 5,571	R 42,521	R 73,380
May	22,220	2,564	4,104	566	2,603	1,607	---	9,818	1,017	RE 5,657	R 41,759	R 72,632
June	22,920	2,664	4,172	565	2,592	1,660	---	9,770	1,018	RE 5,612	R 41,977	R 73,497
July	23,120	2,916	4,073	564	2,580	1,737	---	9,837	946	RE 5,480	R 42,030	R 73,797
August	23,270	3,068	4,030	563	2,598	1,714	---	9,832	767	RE 5,705	R 42,338	R 74,239
September	23,170	2,983	3,964	562	2,534	1,636	---	9,557	890	RE 5,622	R 41,701	R 73,652
October	22,920	3,032	3,926	561	2,598	1,756	---	9,902	998	RE 5,930	R 42,601	R 74,258
November	23,220	3,022	4,006	560	2,573	1,764	---	9,595	1,039	RE 6,054	R 42,736	R 75,195
December	23,270	3,120	3,998	559	2,601	1,713	---	9,869	1,010	RE 6,069	R 43,017	R 75,623
Average	22,687	2,904	4,073	564	2,596	1,752	---	9,774	1,026	RE 5,694	R 42,419	R 74,126
2012 January	22,970	R 3,105	4,089	558	2,562	1,761	---	9,894	999	RE 6,162	R 43,050	R 75,669
February	22,820	R 3,237	4,109	558	2,588	1,745	---	9,889	1,016	RE 6,210	R 42,888	R 75,656
March	23,020	R 3,042	4,066	558	2,596	1,715	---	9,891	968	RE 6,288	R 42,611	R 75,525
April	23,100	R 3,154	4,111	558	2,586	1,720	---	9,861	981	RE 6,230	R 42,563	R 75,809
May	22,795	3,074	4,105	558	2,587	1,699	---	9,882	893	E 6,265	42,439	75,276
5-Month Average	22,942	3,121	4,096	558	2,584	1,728	---	9,883	971	E 6,231	42,709	75,585
2011 5-Month Average	22,062	2,806	4,142	568	2,616	1,810	---	9,782	1,132	5,571	42,522	73,843
2010 5-Month Average	20,806	2,653	3,978	577	2,647	1,993	---	9,657	1,353	5,444	42,527	73,529

<sup>a</sup> See "Organization of the Petroleum Exporting Countries (OPEC)" in Glossary. On Tables 11.1a and 11.1b, countries are classified as "OPEC" or "Non-OPEC" in all years based on their status in the most current year. For example, Ecuador rejoined OPEC in 2007, and is thus included in "Total OPEC" for all years; and Indonesia left OPEC at the end of 2008, and is thus included in "Total Non-OPEC" for all years.

<sup>b</sup> Bahrain, Iran, Iraq, Kuwait, Qatar, Saudi Arabia, United Arab Emirates, and the Neutral Zone (between Kuwait and Saudi Arabia).

R=Revised. NA=Not available. -- =Not applicable. E=Estimate.


Notes: • Data are for crude oil and lease condensate; they exclude natural gas plant liquids. • Monthly data are often preliminary figures and may not average to the annual totals because of rounding or because updates to the preliminary monthly data are not available. • Data for countries may not sum to World totals due to independent rounding. • U.S. geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#international> for all available data beginning in 1973.


Sources: See end of section.

**Figure 11.2 Petroleum Consumption in OECD Countries**  
(Million Barrels per Day)


Overview, 1973-2011



OECD Total, April



By Selected OECD Country



Note: OECD is the Organization for Economic Cooperation and Development.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#international>.  
Source: Table 11.2.

**Table 11.2 Petroleum Consumption in OECD Countries**  
(Thousand Barrels per Day)

	France	Germany <sup>a</sup>	Italy	United Kingdom	OECD Europe <sup>b</sup>	Canada	Japan	South Korea	United States	Other OECD <sup>c</sup>	OECD <sup>d</sup>	World
<b>1973 Average</b> .....	2,601	3,324	2,068	2,341	15,879	1,729	4,949	281	17,308	1,768	41,913	57,237
<b>1975 Average</b> .....	2,252	2,957	1,855	1,911	14,314	1,779	4,621	311	16,322	1,885	39,232	56,198
<b>1980 Average</b> .....	2,256	3,082	1,934	1,725	14,995	1,873	4,960	537	17,056	2,449	41,870	63,113
<b>1985 Average</b> .....	1,753	2,651	1,705	1,617	12,770	1,526	4,436	552	15,726	2,564	37,575	60,083
<b>1990 Average</b> .....	1,826	2,682	1,868	1,776	13,729	1,737	5,315	1,048	16,988	2,784	41,601	66,533
<b>1995 Average</b> .....	1,920	2,882	1,942	1,816	14,714	1,817	5,693	2,008	17,725	3,135	45,092	70,679
<b>1996 Average</b> .....	1,949	2,922	1,920	1,852	14,998	1,871	5,739	2,101	18,309	3,206	46,224	71,665
<b>1997 Average</b> .....	1,969	2,917	1,934	1,810	15,140	1,940	5,702	2,255	18,620	3,355	47,013	73,450
<b>1998 Average</b> .....	2,043	2,923	1,943	1,792	15,448	1,931	5,507	1,917	18,917	3,486	47,206	74,105
<b>1999 Average</b> .....	2,031	2,836	1,891	1,811	15,357	2,016	5,642	2,084	19,519	3,567	48,185	75,819
<b>2000 Average</b> .....	2,000	2,767	1,854	1,765	15,226	2,014	5,515	2,135	19,701	3,624	48,216	76,791
<b>2001 Average</b> .....	2,054	2,807	1,832	1,747	15,395	2,043	5,412	2,132	19,649	3,633	48,264	77,519
<b>2002 Average</b> .....	1,985	2,710	1,870	1,739	15,335	2,065	5,319	2,149	19,761	3,595	48,224	78,167
<b>2003 Average</b> .....	2,001	2,662	1,860	1,759	15,443	2,191	5,428	2,175	20,034	3,627	48,898	79,706
<b>2004 Average</b> .....	2,009	2,649	1,829	1,785	15,546	2,282	5,319	2,155	20,731	3,723	49,756	82,533
<b>2005 Average</b> .....	1,991	2,621	1,781	1,820	15,662	2,315	5,328	2,191	20,802	3,822	50,120	84,083
<b>2006 Average</b> .....	1,991	2,639	1,777	1,806	15,667	2,229	5,197	2,180	20,687	3,854	49,815	85,162
<b>2007 Average</b> .....	1,979	2,416	1,729	1,753	15,491	2,283	5,037	2,241	20,680	3,901	49,633	85,865
<b>2008 Average</b> .....	1,945	2,542	1,667	1,727	15,394	2,225	4,795	2,142	19,498	3,892	47,946	85,458
<b>2009 Average</b> .....	1,868	2,453	1,544	1,641	14,660	2,153	4,406	2,188	18,771	3,767	45,945	84,720
<b>2010</b>												
January .....	1,756	2,161	1,369	1,586	13,537	2,128	4,779	2,361	18,652	3,519	44,976	NA
February .....	1,955	2,454	1,535	1,688	14,760	2,256	5,002	2,383	18,850	3,845	47,096	NA
March .....	1,913	2,505	1,563	1,683	14,831	2,162	4,738	2,253	19,099	3,742	46,826	NA
April .....	1,845	2,260	1,520	1,646	14,281	2,133	4,327	2,249	19,044	3,792	45,825	NA
May .....	1,693	2,354	1,451	1,615	13,915	2,181	3,841	2,170	18,866	3,764	44,737	NA
June .....	1,836	2,510	1,578	1,599	14,718	2,266	3,967	2,177	19,537	3,864	46,529	NA
July .....	1,829	2,571	1,658	1,631	14,929	2,210	4,170	2,111	19,319	3,781	46,520	NA
August .....	1,741	2,547	1,506	1,643	14,564	2,360	4,388	2,221	19,662	3,628	46,822	NA
September .....	1,945	2,747	1,624	1,640	15,378	2,381	4,441	2,192	19,438	3,721	47,551	NA
October .....	1,753	2,622	1,532	1,667	14,943	2,244	4,035	2,225	18,974	3,673	46,094	NA
November .....	1,788	2,585	1,567	1,647	15,023	2,285	4,595	2,392	18,977	3,836	47,108	NA
December .....	1,939	2,324	1,630	1,526	14,614	2,238	5,005	2,495	19,722	3,872	47,945	NA
<b>Average</b> .....	<b>1,831</b>	<b>2,470</b>	<b>1,544</b>	<b>1,630</b>	<b>14,621</b>	<b>2,237</b>	<b>4,437</b>	<b>2,268</b>	<b>19,180</b>	<b>3,752</b>	<b>46,495</b>	<b>87,231</b>
<b>2011</b>												
January .....	1,773	2,230	1,352	1,600	13,637	2,277	4,899	2,429	19,121	3,579	45,942	NA
February .....	1,916	2,433	1,554	1,652	14,763	2,281	5,067	2,349	18,869	3,912	47,241	NA
March .....	1,789	2,393	1,445	1,635	14,305	2,274	4,551	2,295	19,248	3,946	46,620	NA
April .....	1,747	2,258	1,461	1,621	13,946	2,135	3,994	2,011	18,613	3,849	44,546	NA
May .....	1,734	2,403	1,425	1,555	14,018	2,157	3,787	2,022	18,363	3,804	44,152	NA
June .....	1,786	2,270	1,510	1,687	14,414	2,221	3,943	2,112	19,277	3,944	45,911	NA
July .....	1,799	2,409	1,477	1,562	14,393	2,299	4,226	2,188	18,555	3,840	45,501	NA
August .....	1,804	2,638	1,400	1,617	14,709	2,362	4,425	2,212	19,153	3,891	46,752	NA
September .....	1,919	2,551	1,541	1,671	15,005	2,263	4,278	2,241	18,795	3,938	46,520	NA
October .....	1,777	2,508	1,465	1,578	14,357	2,250	4,394	2,216	18,563	3,743	45,523	NA
November .....	1,730	2,447	1,405	1,595	14,168	2,274	4,602	2,252	18,734	3,977	46,007	NA
December .....	1,737	2,262	1,423	1,531	13,756	2,315	5,429	2,436	18,738	3,953	46,627	NA
<b>Average</b> .....	<b>1,792</b>	<b>2,400</b>	<b>1,454</b>	<b>1,608</b>	<b>14,284</b>	<b>2,259</b>	<b>4,464</b>	<b>2,230</b>	<b>18,835</b>	<b>3,863</b>	<b>45,937</b>	<b>87,999</b>
<b>2012</b>												
January .....	1,745	2,133	1,263	1,440	13,081	2,107	5,161	2,366	18,280	3,639	44,634	NA
February .....	1,950	2,483	1,306	1,565	14,364	2,124	5,550	2,410	18,760	3,869	47,076	NA
March .....	1,725	2,219	1,316	1,614	13,605	2,402	5,156	2,153	18,213	3,943	45,472	NA
April .....	1,686	2,231	1,293	1,600	13,472	2,258	4,390	2,099	18,330	3,810	44,358	NA
<b>4-Month Average</b> .....	<b>1,774</b>	<b>2,263</b>	<b>1,295</b>	<b>1,554</b>	<b>13,620</b>	<b>2,224</b>	<b>5,062</b>	<b>2,256</b>	<b>18,390</b>	<b>3,814</b>	<b>45,366</b>	<b>NA</b>
<b>2011 4-Month Average</b> .....	<b>1,804</b>	<b>2,326</b>	<b>1,450</b>	<b>1,626</b>	<b>14,149</b>	<b>2,242</b>	<b>4,622</b>	<b>2,271</b>	<b>18,968</b>	<b>3,819</b>	<b>46,071</b>	<b>NA</b>
<b>2010 4-Month Average</b> .....	<b>1,865</b>	<b>2,343</b>	<b>1,496</b>	<b>1,650</b>	<b>14,343</b>	<b>2,168</b>	<b>4,707</b>	<b>2,310</b>	<b>18,912</b>	<b>3,721</b>	<b>46,161</b>	<b>NA</b>

<sup>a</sup> Data are for unified Germany, i.e., the former East Germany and West Germany.

<sup>b</sup> "OECD Europe" consists of Austria, Belgium, Czech Republic, Denmark, Finland, France, Germany, Greece, Hungary, Iceland, Ireland, Italy, Luxembourg, the Netherlands, Norway, Poland, Portugal, Slovakia, Spain, Sweden, Switzerland, Turkey, and the United Kingdom.

<sup>c</sup> "Other OECD" consists of Australia, Chile, Mexico, New Zealand, and the U.S. Territories.

<sup>d</sup> The Organization for Economic Cooperation and Development (OECD) consists of "OECD Europe," Canada, Japan, South Korea, the United States, and "Other OECD."

R=Revised. NA=Not available.

Notes: • Totals may not equal sum of components due to independent


rounding. • U.S. geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#international> for all available data beginning in 1973.


Sources: • **United States:** Table 3.1. • **Chile, East Germany, Former Czechoslovakia, Hungary, Mexico, Poland, South Korea, Non-OECD Countries, U.S. Territories, and World: 1973-1979—**U.S. Energy Information Administration (EIA), International Energy Database. • **Countries Other Than United States: 1980-2008—**EIA, International Energy Statistics (IES). • **OECD Countries, and U.S. Territories: 2009 forward—**EIA, IES. • **World: 2009 forward—**EIA, *Short Term Energy Outlook*, August 2012, Table 3a. • **All Other Data—**International Energy Agency (IEA), *Quarterly Oil Statistics and Energy Balances in OECD Countries*, various issues.

**Figure 11.3 Petroleum Stocks in OECD Countries**  
(Billion Barrels)


Overview, End of Year, 1973-2011



OECD Stocks, End of Month, April



By Selected OECD Country, End of Month



Note: OECD is the Organization for Economic Cooperation and Development.  
Web Page: <http://www.eia.gov/totalenergy/data/monthly/#international>.  
Source: Table 11.3.

**Table 11.3 Petroleum Stocks in OECD Countries**  
(Million Barrels)

	France	Germany <sup>a</sup>	Italy	United Kingdom	OECD Europe <sup>b</sup>	Canada	Japan	South Korea	United States	Other OECD <sup>c</sup>	OECD <sup>d</sup>
1973 Year .....	201	181	152	156	1,070	140	303	NA	1,008	67	2,588
1975 Year .....	225	187	143	165	1,154	174	375	NA	1,133	67	2,903
1980 Year .....	243	319	170	168	1,464	164	495	NA	1,392	72	3,587
1985 Year .....	139	277	156	131	1,154	112	500	13	1,519	110	3,408
1990 Year .....	143	280	143	103	1,188	143	572	64	1,621	117	3,706
1995 Year .....	155	302	141	101	1,228	132	631	92	1,563	113	3,758
1996 Year .....	154	303	135	103	1,235	127	651	123	1,507	118	3,762
1997 Year .....	161	299	129	100	1,246	144	685	124	1,560	115	3,875
1998 Year .....	169	323	135	104	1,331	139	649	129	1,647	111	4,006
1999 Year .....	160	290	130	101	1,233	142	629	132	1,493	105	3,733
2000 Year .....	170	272	140	100	1,294	144	634	140	1,468	117	3,796
2001 Year .....	165	273	134	113	1,281	154	634	143	1,586	112	3,910
2002 Year .....	170	253	138	104	1,247	155	615	140	1,548	103	3,808
2003 Year .....	179	273	135	100	1,290	165	636	155	1,568	96	3,910
2004 Year .....	177	267	136	101	1,292	154	635	149	1,645	99	3,974
2005 Year .....	185	283	132	95	1,342	168	612	135	1,698	103	4,058
2006 Year .....	182	283	133	103	1,374	169	631	152	1,720	103	4,148
2007 Year .....	180	275	133	90	1,358	175	621	143	1,665	108	4,072
2008 Year .....	179	279	128	99	1,407	174	630	135	1,737	114	4,196
2009 Year .....	175	284	126	94	1,398	169	589	155	1,776	105	4,193
<b>2010</b> January .....	182	295	127	95	1,439	172	593	162	1,786	111	4,263
February .....	175	290	134	99	1,424	174	587	163	1,785	117	4,249
March .....	172	289	129	93	1,404	180	581	164	1,787	114	4,230
April .....	172	284	135	95	1,414	181	590	166	1,810	111	4,272
May .....	173	286	131	99	1,422	177	599	166	1,830	108	4,302
June .....	170	280	133	96	1,405	178	597	167	1,842	120	4,308
July .....	168	282	127	96	1,389	186	598	170	1,855	116	4,314
August .....	171	289	133	93	1,406	195	597	169	1,862	115	4,343
September .....	163	286	127	95	1,365	193	582	174	1,861	111	4,286
October .....	161	285	129	94	1,375	195	599	170	1,847	112	4,298
November .....	170	287	126	92	1,367	197	604	171	1,827	108	4,274
<b>December</b> .....	<b>168</b>	<b>287</b>	<b>133</b>	<b>89</b>	<b>1,371</b>	<b>196</b>	<b>588</b>	<b>165</b>	<b>1,794</b>	<b>106</b>	<b>4,221</b>
<b>2011</b> January .....	173	291	140	97	1,412	187	596	168	1,803	105	4,271
February .....	170	288	131	95	1,383	182	591	162	1,773	108	4,200
March .....	167	286	132	93	1,371	<sup>R</sup> 184	575	170	1,770	105	<sup>R</sup> 4,175
April .....	163	291	132	93	1,357	191	601	173	1,776	109	4,207
May .....	168	288	130	91	1,360	189	599	170	1,805	110	4,232
June .....	167	286	130	85	1,352	190	593	175	1,808	108	4,225
July .....	164	290	130	87	1,343	189	599	173	1,820	109	4,232
August .....	162	283	132	89	1,347	188	598	171	1,801	111	4,215
September .....	160	277	130	85	1,326	189	601	174	1,781	105	4,175
October .....	165	278	130	86	1,315	192	599	174	1,770	105	4,155
November .....	164	277	131	93	1,330	193	603	170	1,772	105	4,172
<b>December</b> .....	<b>165</b>	<b>279</b>	<b>128</b>	<b>88</b>	<b>1,320</b>	<b>190</b>	<b>589</b>	<b>167</b>	<b>1,751</b>	<b>105</b>	<b>4,122</b>
<b>2012</b> January .....	166	284	132	90	1,341	<sup>R</sup> 192	594	164	<sup>R</sup> 1,772	107	<sup>R</sup> 4,170
February .....	165	283	132	90	1,340	<sup>R</sup> 193	583	171	<sup>R</sup> 1,765	99	<sup>R</sup> 4,151
March .....	165	281	130	<sup>R</sup> 88	<sup>R</sup> 1,348	<sup>R</sup> 184	580	164	<sup>R</sup> 1,778	<sup>R</sup> 99	<sup>R</sup> 4,154
April .....	163	280	131	90	1,344	185	592	174	1,777	100	4,173

<sup>a</sup> Through December 1983, the data for Germany are for the former West Germany only. Beginning with January 1984, the data for Germany are for the unified Germany, i.e., the former East Germany and West Germany.

<sup>b</sup> "OECD Europe" consists of Austria, Belgium, Denmark, Finland, France, Germany, Greece, Iceland, Ireland, Italy, Luxembourg, the Netherlands, Norway, Portugal, Spain, Sweden, Switzerland, Turkey, and the United Kingdom, and, for 1984 forward, Czech Republic, Hungary, Poland, and Slovakia.

<sup>c</sup> "Other OECD" consists of Australia, New Zealand, and the U.S. Territories, and, for 1984 forward, Mexico.

<sup>d</sup> The Organization for Economic Cooperation and Development (OECD) consists of "OECD Europe," Canada, Japan, South Korea, the United States, and "Other OECD."

R=Revised. NA=Not available.

Notes: • Stocks are at end of period. • Petroleum stocks include crude oil (including strategic reserves), unfinished oils, natural gas plant liquids, and refined

products. • In the United States in January 1975, 1981, and 1983, numerous respondents were added to bulk terminal and pipeline surveys, thereby affecting subsequent stocks reported. New-basis end-of-year U.S. stocks, in million barrels, would have been 1,121 in 1974, 1,425 in 1980, and 1,461 in 1982. • Totals may not equal sum of components due to independent rounding. • U.S. geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#international> for all available data beginning in 1973.

Sources: • **United States:** Table 3.4. • **U.S. Territories:** 1983 forward—U.S. Energy Information Administration, International Energy Database.

• **All Other Data:** 1973-1982—International Energy Agency (IEA), *Quarterly Oil Statistics and Energy Balances*, various issues. 1983—IEA, Monthly Oil and Gas Statistics Database. 1984 forward—IEA, Monthly Oil Data Service, July 12, 2012.

# International Petroleum

## Tables 11.1a and 11.1b Sources

### United States

Table 3.1.

### All Other Countries and World, Annual Data

1973–1979: U.S. Energy Information Administration (EIA), *International Energy Annual 1981*, Table 8.

1980 forward: EIA, International Energy Database, August 2012.

### All Other Countries and World, Monthly Data

1973–1980: *Petroleum Intelligence Weekly (PIW)*, *Oil & Gas Journal (OGJ)*, and EIA adjustments.

1981–1993: *PIW*, *OGJ*, and other industry sources.

1994 forward: EIA, International Energy Database, August 2012.




## **12. Environment**


---

**Figure 12.1 Carbon Dioxide Emissions From Energy Consumption by Source**  
(Million Metric Tons of Carbon Dioxide)


Total,<sup>a</sup> 1973-2011




Total,<sup>a</sup> Monthly




By Major Source, 1973-2011




By Major Source, Monthly



Total,<sup>a</sup> January-May



By Major Source, May 2012



<sup>a</sup>Excludes emissions from biomass energy consumption.  
<sup>b</sup>Includes coal coke net imports.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#environment>.  
Source: Table 12.1.

**Table 12.1 Carbon Dioxide Emissions From Energy Consumption by Source**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal <sup>b</sup>	Natural Gas <sup>c</sup>	Petroleum										Total <sup>h,i</sup>	
			Aviation Gasoline	Distillate Fuel Oil <sup>d</sup>	Jet Fuel	Kero-sene	LPG <sup>e</sup>	Lubri-cants	Motor Gasoline <sup>f</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>g</sup>		
<b>1973 Total</b> .....	<b>1,207</b>	<b>1,181</b>	<b>6</b>	<b>480</b>	<b>155</b>	<b>32</b>	<b>91</b>	<b>13</b>	<b>911</b>	<b>51</b>	<b>508</b>	<b>100</b>	<b>2,346</b>	<b>4,733</b>
<b>1975 Total</b> .....	<b>1,181</b>	<b>1,047</b>	<b>5</b>	<b>443</b>	<b>146</b>	<b>24</b>	<b>82</b>	<b>11</b>	<b>911</b>	<b>48</b>	<b>443</b>	<b>97</b>	<b>2,209</b>	<b>4,437</b>
<b>1980 Total</b> .....	<b>1,436</b>	<b>1,063</b>	<b>4</b>	<b>446</b>	<b>156</b>	<b>24</b>	<b>87</b>	<b>13</b>	<b>900</b>	<b>46</b>	<b>453</b>	<b>142</b>	<b>2,272</b>	<b>4,770</b>
<b>1985 Total</b> .....	<b>1,638</b>	<b>926</b>	<b>3</b>	<b>445</b>	<b>178</b>	<b>17</b>	<b>86</b>	<b>12</b>	<b>930</b>	<b>55</b>	<b>216</b>	<b>93</b>	<b>2,035</b>	<b>4,600</b>
<b>1990 Total</b> .....	<b>1,821</b>	<b>1,025</b>	<b>3</b>	<b>470</b>	<b>223</b>	<b>6</b>	<b>69</b>	<b>13</b>	<b>988</b>	<b>67</b>	<b>220</b>	<b>127</b>	<b>2,187</b>	<b>5,039</b>
<b>1995 Total</b> .....	<b>1,913</b>	<b>1,184</b>	<b>3</b>	<b>498</b>	<b>222</b>	<b>8</b>	<b>78</b>	<b>13</b>	<b>1,044</b>	<b>75</b>	<b>152</b>	<b>114</b>	<b>2,207</b>	<b>5,314</b>
<b>1996 Total</b> .....	<b>1,995</b>	<b>1,205</b>	<b>3</b>	<b>524</b>	<b>232</b>	<b>9</b>	<b>84</b>	<b>12</b>	<b>1,063</b>	<b>78</b>	<b>152</b>	<b>132</b>	<b>2,290</b>	<b>5,501</b>
<b>1997 Total</b> .....	<b>2,040</b>	<b>1,211</b>	<b>3</b>	<b>534</b>	<b>234</b>	<b>10</b>	<b>85</b>	<b>13</b>	<b>1,075</b>	<b>79</b>	<b>142</b>	<b>138</b>	<b>2,313</b>	<b>5,575</b>
<b>1998 Total</b> .....	<b>2,064</b>	<b>1,189</b>	<b>2</b>	<b>538</b>	<b>238</b>	<b>12</b>	<b>75</b>	<b>14</b>	<b>1,107</b>	<b>89</b>	<b>158</b>	<b>125</b>	<b>2,358</b>	<b>5,622</b>
<b>1999 Total</b> .....	<b>2,062</b>	<b>1,192</b>	<b>3</b>	<b>555</b>	<b>245</b>	<b>11</b>	<b>91</b>	<b>14</b>	<b>1,127</b>	<b>93</b>	<b>148</b>	<b>130</b>	<b>2,417</b>	<b>5,682</b>
<b>2000 Total</b> .....	<b>2,155</b>	<b>1,241</b>	<b>3</b>	<b>580</b>	<b>254</b>	<b>10</b>	<b>102</b>	<b>14</b>	<b>1,135</b>	<b>84</b>	<b>163</b>	<b>117</b>	<b>2,461</b>	<b>5,867</b>
<b>2001 Total</b> .....	<b>2,088</b>	<b>1,187</b>	<b>2</b>	<b>598</b>	<b>243</b>	<b>11</b>	<b>92</b>	<b>13</b>	<b>1,151</b>	<b>88</b>	<b>145</b>	<b>132</b>	<b>2,473</b>	<b>5,759</b>
<b>2002 Total</b> .....	<b>2,095</b>	<b>1,227</b>	<b>2</b>	<b>587</b>	<b>237</b>	<b>6</b>	<b>98</b>	<b>12</b>	<b>1,183</b>	<b>94</b>	<b>125</b>	<b>127</b>	<b>2,472</b>	<b>5,806</b>
<b>2003 Total</b> .....	<b>2,136</b>	<b>1,191</b>	<b>2</b>	<b>610</b>	<b>231</b>	<b>8</b>	<b>95</b>	<b>11</b>	<b>1,188</b>	<b>94</b>	<b>138</b>	<b>140</b>	<b>2,518</b>	<b>5,857</b>
<b>2004 Total</b> .....	<b>2,160</b>	<b>1,195</b>	<b>2</b>	<b>632</b>	<b>240</b>	<b>10</b>	<b>98</b>	<b>12</b>	<b>1,214</b>	<b>105</b>	<b>155</b>	<b>142</b>	<b>2,609</b>	<b>5,975</b>
<b>2005 Total</b> .....	<b>2,182</b>	<b>1,175</b>	<b>2</b>	<b>640</b>	<b>246</b>	<b>10</b>	<b>94</b>	<b>12</b>	<b>1,214</b>	<b>105</b>	<b>164</b>	<b>141</b>	<b>2,628</b>	<b>5,997</b>
<b>2006 Total</b> .....	<b>2,147</b>	<b>1,158</b>	<b>2</b>	<b>648</b>	<b>240</b>	<b>8</b>	<b>93</b>	<b>11</b>	<b>1,224</b>	<b>104</b>	<b>122</b>	<b>150</b>	<b>2,603</b>	<b>5,919</b>
<b>2007 Total</b> .....	<b>2,172</b>	<b>1,233</b>	<b>2</b>	<b>652</b>	<b>238</b>	<b>5</b>	<b>94</b>	<b>12</b>	<b>1,227</b>	<b>98</b>	<b>129</b>	<b>148</b>	<b>2,603</b>	<b>6,020</b>
<b>2008 Total</b> .....	<b>2,139</b>	<b>1,243</b>	<b>2</b>	<b>615</b>	<b>226</b>	<b>2</b>	<b>89</b>	<b>11</b>	<b>1,166</b>	<b>92</b>	<b>111</b>	<b>130</b>	<b>2,444</b>	<b>5,838</b>
<b>2009 Total</b> .....	<b>1,876</b>	<b>1,222</b>	<b>2</b>	<b>564</b>	<b>204</b>	<b>3</b>	<b>91</b>	<b>10</b>	<b>1,157</b>	<b>87</b>	<b>91</b>	<b>111</b>	<b>2,320</b>	<b>5,429</b>
<b>2010</b>														
January .....	182	149	(s)	49	17	(s)	10	1	92	5	9	9	193	524
February .....	163	131	(s)	46	15	(s)	9	1	84	5	7	9	176	471
March .....	156	113	(s)	51	18	(s)	8	1	95	7	8	11	200	470
April .....	138	88	(s)	48	17	(s)	7	1	96	6	9	11	194	422
May .....	155	84	(s)	48	18	(s)	7	1	99	6	8	10	197	437
June .....	176	86	(s)	48	19	(s)	7	1	97	7	7	10	196	459
July .....	190	96	(s)	47	19	(s)	7	1	101	7	9	10	200	487
August .....	190	99	(s)	50	19	(s)	7	1	100	8	7	11	203	493
September .....	161	86	(s)	50	18	(s)	7	1	96	7	8	10	196	444
October .....	145	87	(s)	50	18	(s)	8	1	97	6	7	9	196	429
November .....	148	103	(s)	49	17	1	8	1	92	7	8	9	191	444
December .....	178	143	(s)	55	17	1	11	1	96	6	8	10	205	528
<b>Total</b> .....	<b>1,982</b>	<b>1,265</b>	<b>2</b>	<b>590</b>	<b>210</b>	<b>3</b>	<b>94</b>	<b>11</b>	<b>1,146</b>	<b>77</b>	<b>96</b>	<b>120</b>	<b>2,349</b>	<b>5,607</b>
<b>2011</b>														
January .....	179	154	(s)	52	17	(s)	10	1	91	6	9	10	198	531
February .....	148	130	(s)	46	15	1	8	1	84	4	9	9	177	456
March .....	147	118	(s)	53	17	(s)	8	1	95	6	8	12	200	466
April .....	135	97	(s)	47	17	(s)	6	1	92	6	9	10	188	421
May .....	148	88	(s)	48	18	(s)	7	1	95	7	7	9	192	428
June .....	167	87	(s)	50	19	(s)	6	1	94	7	7	10	193	449
July .....	185	100	(s)	45	18	(s)	7	1	97	6	5	11	191	477
August .....	182	99	(s)	52	19	(s)	7	1	96	8	5	10	198	480
September .....	153	87	(s)	50	17	(s)	7	1	92	6	7	9	189	430
October .....	140	93	(s)	52	17	(s)	8	1	93	7	6	8	192	425
November .....	135	107	(s)	52	17	(s)	8	1	89	6	6	10	188	431
December .....	148	134	(s)	50	17	(s)	9	1	93	5	8	10	193	476
<b>Total</b> .....	<b>1,867</b>	<b>1,294</b>	<b>2</b>	<b>596</b>	<b>209</b>	<b>2</b>	<b>92</b>	<b>10</b>	<b>1,111</b>	<b>75</b>	<b>86</b>	<b>116</b>	<b>2,299</b>	<b>5,471</b>
<b>2012</b>														
January .....	142	146	(s)	50	16	(s)	9	1	89	6	6	10	<sup>R</sup> 189	477
February .....	127	133	(s)	49	16	(s)	8	1	87	5	6	10	182	443
March .....	118	112	(s)	<sup>R</sup> 49	17	(s)	8	1	93	6	6	9	<sup>R</sup> 190	<sup>R</sup> 421
April .....	108	103	(s)	<sup>R</sup> 47	16	(s)	7	1	92	6	6	9	<sup>R</sup> 184	396
May .....	128	98	(s)	49	18	(s)	8	1	97	6	4	9	193	420
<b>5-Month Total</b> .....	<b>624</b>	<b>592</b>	<b>1</b>	<b>244</b>	<b>83</b>	<b>(s)</b>	<b>41</b>	<b>4</b>	<b>458</b>	<b>29</b>	<b>29</b>	<b>48</b>	<b>937</b>	<b>2,158</b>
<b>2011 5-Month Total</b> .....	<b>756</b>	<b>587</b>	<b>1</b>	<b>246</b>	<b>85</b>	<b>1</b>	<b>40</b>	<b>4</b>	<b>457</b>	<b>30</b>	<b>42</b>	<b>49</b>	<b>955</b>	<b>2,303</b>
<b>2010 5-Month Total</b> .....	<b>794</b>	<b>565</b>	<b>1</b>	<b>241</b>	<b>85</b>	<b>1</b>	<b>41</b>	<b>4</b>	<b>467</b>	<b>30</b>	<b>41</b>	<b>50</b>	<b>961</b>	<b>2,324</b>

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Includes coal coke net imports.

<sup>c</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>d</sup> Distillate fuel oil, excluding biodiesel.

<sup>e</sup> Liquefied petroleum gases.

<sup>f</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>g</sup> Aviation gasoline blending components, crude oil, motor gasoline blending components, pentanes plus, petrochemical feedstocks, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products.

<sup>h</sup> Includes electric power sector use of geothermal energy and non-biomass waste. See Table 12.6.

<sup>i</sup> Excludes emissions from biomass energy consumption. See Table 12.7.

R=Revised. (s)=Less than 0.5 million metric tons.


Notes: • Data are estimates for carbon dioxide emissions from energy consumption, including the nonfuel use of fossil fuels. See "Section 12 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 12.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> for all available data beginning in 1973.


Sources: See end of section.

**Figure 12.2 Carbon Dioxide Emissions From Energy Consumption by Sector**  
(Million Metric Tons of Carbon Dioxide)


Total<sup>a</sup> by End-Use Sector,<sup>b</sup> 1973-2011




Residential Sector by Major Source, 1973-2011




Commercial Sector by Major Source, 1973-2011




Industrial Sector by Major Source, 1973-2011



Transportation Sector by Major Source, 1973-2011



Electric Power Sector by Major Source, 1973-2011



<sup>a</sup> Excludes emissions from biomass energy consumption.

<sup>b</sup> Emissions from energy consumption in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of

total electricity retail sales.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#environment>.  
Sources: Tables 12.2-12.6.

**Table 12.2 Carbon Dioxide Emissions From Energy Consumption: Residential Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum				Retail Elec- tricity <sup>e</sup>	Total <sup>f</sup>
			Distillate Fuel Oil <sup>c</sup>	Kerosene	LPG <sup>d</sup>	Total		
<b>1973 Total</b> .....	<b>9</b>	<b>264</b>	<b>147</b>	<b>16</b>	<b>36</b>	<b>199</b>	<b>435</b>	<b>907</b>
<b>1975 Total</b> .....	<b>6</b>	<b>266</b>	<b>132</b>	<b>12</b>	<b>32</b>	<b>176</b>	<b>419</b>	<b>867</b>
<b>1980 Total</b> .....	<b>3</b>	<b>256</b>	<b>96</b>	<b>8</b>	<b>20</b>	<b>124</b>	<b>529</b>	<b>911</b>
<b>1985 Total</b> .....	<b>4</b>	<b>241</b>	<b>80</b>	<b>11</b>	<b>20</b>	<b>111</b>	<b>553</b>	<b>909</b>
<b>1990 Total</b> .....	<b>3</b>	<b>238</b>	<b>72</b>	<b>5</b>	<b>22</b>	<b>98</b>	<b>624</b>	<b>963</b>
<b>1995 Total</b> .....	<b>2</b>	<b>263</b>	<b>66</b>	<b>5</b>	<b>25</b>	<b>96</b>	<b>678</b>	<b>1,039</b>
<b>1996 Total</b> .....	<b>2</b>	<b>284</b>	<b>68</b>	<b>6</b>	<b>30</b>	<b>104</b>	<b>710</b>	<b>1,099</b>
<b>1997 Total</b> .....	<b>2</b>	<b>270</b>	<b>64</b>	<b>7</b>	<b>29</b>	<b>99</b>	<b>719</b>	<b>1,090</b>
<b>1998 Total</b> .....	<b>1</b>	<b>247</b>	<b>56</b>	<b>8</b>	<b>27</b>	<b>91</b>	<b>759</b>	<b>1,097</b>
<b>1999 Total</b> .....	<b>1</b>	<b>257</b>	<b>61</b>	<b>8</b>	<b>33</b>	<b>102</b>	<b>762</b>	<b>1,122</b>
<b>2000 Total</b> .....	<b>1</b>	<b>271</b>	<b>66</b>	<b>7</b>	<b>35</b>	<b>108</b>	<b>805</b>	<b>1,185</b>
<b>2001 Total</b> .....	<b>1</b>	<b>259</b>	<b>66</b>	<b>7</b>	<b>33</b>	<b>106</b>	<b>805</b>	<b>1,172</b>
<b>2002 Total</b> .....	<b>1</b>	<b>265</b>	<b>63</b>	<b>4</b>	<b>34</b>	<b>101</b>	<b>835</b>	<b>1,203</b>
<b>2003 Total</b> .....	<b>1</b>	<b>276</b>	<b>66</b>	<b>5</b>	<b>34</b>	<b>106</b>	<b>847</b>	<b>1,230</b>
<b>2004 Total</b> .....	<b>1</b>	<b>264</b>	<b>68</b>	<b>6</b>	<b>32</b>	<b>106</b>	<b>856</b>	<b>1,228</b>
<b>2005 Total</b> .....	<b>1</b>	<b>262</b>	<b>62</b>	<b>6</b>	<b>32</b>	<b>101</b>	<b>897</b>	<b>1,261</b>
<b>2006 Total</b> .....	<b>1</b>	<b>237</b>	<b>52</b>	<b>5</b>	<b>28</b>	<b>85</b>	<b>869</b>	<b>1,192</b>
<b>2007 Total</b> .....	<b>1</b>	<b>257</b>	<b>53</b>	<b>3</b>	<b>31</b>	<b>87</b>	<b>897</b>	<b>1,241</b>
<b>2008 Total</b> .....	<b>1</b>	<b>266</b>	<b>49</b>	<b>2</b>	<b>35</b>	<b>85</b>	<b>878</b>	<b>1,229</b>
<b>2009 Total</b> .....	<b>1</b>	<b>259</b>	<b>44</b>	<b>2</b>	<b>35</b>	<b>81</b>	<b>819</b>	<b>1,159</b>
<b>2010 January</b> .....	(s)	51	6	(s)	3	10	91	151
February .....	(s)	43	6	(s)	3	9	74	126
March .....	(s)	31	4	(s)	3	7	65	103
April .....	(s)	17	2	(s)	2	5	51	73
May .....	(s)	11	3	(s)	2	5	59	75
June .....	(s)	7	3	(s)	2	6	79	92
July .....	(s)	6	2	(s)	3	5	97	108
August .....	(s)	6	2	(s)	3	5	96	107
September .....	(s)	6	2	(s)	3	5	72	83
October .....	(s)	11	3	(s)	3	6	56	73
November .....	(s)	24	3	(s)	3	7	56	87
December .....	(s)	46	6	(s)	3	10	81	137
<b>Total</b> .....	<b>1</b>	<b>259</b>	<b>43</b>	<b>2</b>	<b>33</b>	<b>78</b>	<b>875</b>	<b>1,212</b>
<b>2011 January</b> .....	(s)	53	5	(s)	3	9	87	148
February .....	(s)	42	5	(s)	3	8	67	117
March .....	(s)	33	4	(s)	3	7	59	99
April .....	(s)	19	2	(s)	2	5	53	77
May .....	(s)	11	2	(s)	3	4	58	74
June .....	(s)	7	3	(s)	2	5	76	88
July .....	(s)	6	2	(s)	3	5	96	107
August .....	(s)	6	3	(s)	3	6	92	104
September .....	(s)	7	3	(s)	3	6	69	81
October .....	(s)	12	4	(s)	3	7	54	73
November .....	(s)	23	4	(s)	3	7	53	83
December .....	(s)	37	6	(s)	3	9	66	113
<b>Total</b> .....	<b>1</b>	<b>256</b>	<b>43</b>	<b>1</b>	<b>33</b>	<b>78</b>	<b>827</b>	<b>1,162</b>
<b>2012 January</b> .....	(s)	43	6	(s)	3	9	68	121
February .....	(s)	36	5	(s)	3	8	58	102
March .....	(s)	22	4	(s)	3	7	51	80
April .....	(s)	15	3	(s)	3	6	45	66
May .....	(s)	9	3	(s)	3	6	55	70
<b>5-Month Total</b> .....	<b>(s)</b>	<b>126</b>	<b>21</b>	<b>(s)</b>	<b>15</b>	<b>36</b>	<b>277</b>	<b>439</b>
<b>2011 5-Month Total</b> .....	<b>(s)</b>	<b>157</b>	<b>18</b>	<b>1</b>	<b>14</b>	<b>33</b>	<b>324</b>	<b>515</b>
<b>2010 5-Month Total</b> .....	<b>(s)</b>	<b>153</b>	<b>21</b>	<b>1</b>	<b>14</b>	<b>35</b>	<b>339</b>	<b>527</b>

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Liquefied petroleum gases.

<sup>e</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 12.6.

<sup>f</sup> Excludes emissions from biomass energy consumption. See Table 12.7.

(s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption. See "Section 12 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 12.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> for all available data beginning in 1973.

Sources: See end of section.

**Table 12.3 Carbon Dioxide Emissions From Energy Consumption: Commercial Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum						Retail Electricity <sup>f</sup>	Total <sup>g</sup>	
			Distillate Fuel Oil <sup>c</sup>	Kerosene	LPG <sup>d</sup>	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil			Total
1973 Total	15	141	47	5	9	6	NA	52	120	334	609
1975 Total	14	136	43	4	8	6	NA	39	100	333	583
1980 Total	11	141	38	3	6	8	NA	44	98	412	662
1985 Total	13	132	46	2	6	7	NA	18	79	480	704
1990 Total	12	142	39	1	6	8	0	18	73	566	793
1995 Total	11	164	35	2	7	1	(s)	11	56	620	851
1996 Total	12	171	35	2	8	2	(s)	11	57	643	883
1997 Total	12	174	32	2	8	3	(s)	9	54	686	926
1998 Total	9	164	31	2	7	3	(s)	7	51	724	947
1999 Total	10	165	32	2	9	2	(s)	6	51	735	960
2000 Total	9	173	36	2	9	3	(s)	7	58	783	1,022
2001 Total	9	164	37	2	9	3	(s)	6	57	797	1,027
2002 Total	9	170	32	1	9	3	(s)	6	52	795	1,026
2003 Total	8	173	35	1	10	4	(s)	9	59	796	1,036
2004 Total	10	170	34	1	10	3	(s)	10	58	816	1,054
2005 Total	9	163	33	2	8	3	(s)	9	55	842	1,069
2006 Total	6	154	29	1	8	3	(s)	6	48	836	1,043
2007 Total	7	164	28	1	8	4	(s)	6	47	861	1,078
2008 Total	7	171	27	(s)	10	3	(s)	6	46	850	1,074
2009 Total	6	169	30	(s)	9	4	(s)	6	49	785	1,008
2010 January	1	27	4	(s)	1	(s)	(s)	1	6	66	101
February	1	24	4	(s)	1	(s)	(s)	1	6	60	91
March	1	18	3	(s)	1	(s)	(s)	1	4	59	82
April	(s)	12	2	(s)	1	(s)	(s)	(s)	3	57	73
May	(s)	9	2	(s)	1	(s)	0	(s)	3	66	78
June	(s)	7	2	(s)	1	(s)	0	(s)	4	74	85
July	(s)	6	2	(s)	1	(s)	0	(s)	3	80	90
August	(s)	7	2	(s)	1	(s)	(s)	(s)	3	81	91
September	(s)	7	1	(s)	1	(s)	(s)	(s)	3	69	79
October	(s)	10	2	(s)	1	(s)	(s)	(s)	4	63	77
November	(s)	16	2	(s)	1	(s)	(s)	(s)	4	61	81
December	1	25	4	(s)	1	(s)	(s)	1	6	68	100
Total	6	168	30	(s)	9	4	(s)	6	49	805	1,027
2011 January	1	29	4	(s)	1	(s)	(s)	1	6	65	100
February	1	23	3	(s)	1	(s)	(s)	1	5	55	84
March	1	20	3	(s)	1	(s)	(s)	(s)	4	58	83
April	(s)	13	2	(s)	1	(s)	0	(s)	3	57	73
May	(s)	9	1	(s)	1	(s)	0	(s)	2	63	75
June	(s)	7	2	(s)	1	(s)	0	(s)	3	70	81
July	(s)	7	2	(s)	1	(s)	0	(s)	3	79	89
August	(s)	7	2	(s)	1	(s)	0	(s)	4	77	88
September	(s)	8	2	(s)	1	(s)	0	(s)	4	66	77
October	(s)	12	3	(s)	1	(s)	0	1	4	61	77
November	(s)	15	3	(s)	1	(s)	(s)	1	5	57	77
December	(s)	22	4	(s)	1	(s)	(s)	1	6	59	87
Total	5	171	30	(s)	9	4	(s)	6	49	767	991
2012 January	(s)	24	4	(s)	1	(s)	(s)	1	6	57	88
February	(s)	21	3	(s)	1	(s)	(s)	1	5	53	80
March	(s)	14	3	(s)	1	(s)	(s)	1	5	52	71
April	(s)	11 <sup>R</sup>	2	(s)	1	(s)	(s)	(s)	3	51	66
May	(s)	8	2	(s)	1	(s)	0	(s)	4	61	73
5-Month Total	2	79	15	(s)	4	1	(s)	3	23	274	378
2011 5-Month Total	3	94	13	(s)	4	1	(s)	2	21	298	414
2010 5-Month Total	3	90	14	(s)	4	2	(s)	3	23	309	424

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Liquefied petroleum gases.

<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>f</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 12.6.

<sup>g</sup> Excludes emissions from biomass energy consumption. See Table 12.7.

R=Revised. NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption. See "Section 12 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 12.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> for all available data beginning in 1973.

Sources: See end of section.

**Table 12.4 Carbon Dioxide Emissions From Energy Consumption: Industrial Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Coal Coke Net Imports	Natural Gas <sup>b</sup>	Petroleum									Retail Elec- tricity <sup>g</sup>	Total <sup>h</sup>
				Distillate Fuel Oil <sup>c</sup>	Kero- sene	LPG <sup>d</sup>	Lubri- cants	Motor Gasoline <sup>e</sup>	Petroleum Coke	Residual Fuel Oil	Other <sup>f</sup>	Total		
1973 Total	371	-1	538	106	11	43	7	18	49	144	100	478	515	1,902
1975 Total	336	2	442	97	9	39	6	16	48	117	97	427	490	1,696
1980 Total	289	-4	431	96	13	61	7	11	45	105	142	480	601	1,797
1985 Total	256	-2	360	81	3	58	6	15	54	57	93	369	583	1,566
1990 Total	258	1	432	84	1	39	7	13	64	31	127	366	638	1,695
1995 Total	233	7	490	82	1	45	7	14	67	24	114	355	659	1,743
1996 Total	227	3	506	86	1	46	6	14	70	24	132	381	678	1,795
1997 Total	224	5	506	88	1	48	7	15	68	21	138	386	694	1,815
1998 Total	219	8	495	88	2	39	7	14	77	16	125	368	706	1,796
1999 Total	208	7	474	86	1	48	7	11	81	14	130	378	704	1,772
2000 Total	211	7	481	87	1	56	7	11	74	17	117	370	719	1,788
2001 Total	204	3	439	95	2	49	6	21	77	14	132	395	667	1,709
2002 Total	188	7	448	88	1	54	6	22	76	13	127	388	654	1,685
2003 Total	190	6	430	83	2	50	6	23	76	15	140	394	672	1,692
2004 Total	191	16	432	88	2	55	6	26	82	17	142	419	675	1,732
2005 Total	183	5	398	92	3	51	6	25	80	20	141	417	673	1,675
2006 Total	179	7	395	92	2	56	6	26	82	16	150	430	650	1,662
2007 Total	175	3	405	92	1	54	6	21	80	13	148	415	662	1,661
2008 Total	168	5	407	93	(s)	42	6	17	76	14	130	377	642	1,599
2009 Total	131	-3	383	80	(s)	46	5	17	73	7	111	339	551	1,401
2010 January	12	(s)	37	6	(s)	6	(s)	2	3	1	9	28	46	122
February	12	(s)	34	6	(s)	5	(s)	1	4	1	9	27	44	118
March	13	(s)	35	9	(s)	4	(s)	2	6	1	11	33	46	127
April	12	(s)	32	8	(s)	3	(s)	2	5	1	11	30	45	120
May	12	(s)	32	6	(s)	3	(s)	2	5	1	10	28	51	123
June	12	(s)	31	5	(s)	3	1	2	5	1	10	27	52	122
July	12	(s)	32	4	(s)	3	1	2	5	1	10	26	54	124
August	13	(s)	32	7	(s)	4	(s)	2	6	1	11	31	55	130
September	13	(s)	32	9	(s)	4	(s)	2	6	1	10	31	48	124
October	12	(s)	33	7	(s)	4	(s)	2	5	1	9	28	47	120
November	13	-1	34	8	(s)	4	(s)	2	6	1	9	30	48	124
December	13	-1	37	9	(s)	6	(s)	2	5	1	10	33	50	133
Total	149	-1	401	86	1	50	6	19	62	8	120	352	587	1,488
2011 January	12	(s)	38	10	(s)	6	(s)	1	5	1	10	33	47	132
February	12	(s)	35	7	(s)	5	(s)	1	3	1	9	26	42	115
March	13	(s)	36	10	(s)	4	1	2	5	1	12	33	45	128
April	11	(s)	34	7	(s)	3	(s)	2	5	1	10	28	45	118
May	12	(s)	34	7	(s)	3	(s)	2	6	1	9	28	48	122
June	12	(s)	32	7	(s)	3	(s)	2	5	1	10	28	50	122
July	11	(s)	33	3	(s)	3	(s)	2	5	(s)	11	25	53	123
August	12	(s)	33	7	(s)	4	(s)	2	7	(s)	10	29	53	128
September	12	(s)	33	7	(s)	4	(s)	2	5	1	9	27	46	119
October	12	(s)	34	8	(s)	4	(s)	2	6	1	8	28	47	121
November	12	(s)	35	9	(s)	4	(s)	1	5	1	10	30	45	122
December	12	(s)	38	6	(s)	5	(s)	2	4	1	10	28	45	123
Total	142	1	417	88	(s)	48	5	18	62	8	116	345	567	1,472
2012 January	11	(s)	39	R 8	(s)	5	(s)	1	5	1	10	31	43	123
February	11	(s)	36	9	(s)	5	(s)	1	4	(s)	10	R 31	42	120
March	12	(s)	36	7	(s)	4	(s)	2	5	1	9	28	41	117
April	12	1	34	R 7	(s)	4	(s)	2	5	1	9	R 27	41	114
May	12	(s)	34	7	(s)	4	(s)	2	6	(s)	9	28	47	120
5-Month Total	58	1	179	37	(s)	21	2	8	25	2	48	144	213	595
2011 5-Month Total	60	1	177	41	(s)	21	2	7	24	4	49	149	227	613
2010 5-Month Total	61	1	170	36	(s)	22	2	8	24	4	50	146	232	610

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Liquefied petroleum gases.

<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.

<sup>f</sup> Aviation gasoline blending components, crude oil, motor gasoline blending components, pentanes plus, petrochemical feedstocks, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products.

<sup>g</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 12.6.

<sup>h</sup> Excludes emissions from biomass energy consumption. See Table 12.7.

R=Revised. (s)=Less than 0.5 million metric tons and greater than -0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption, including the nonfuel use of fossil fuels. See "Section 12 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 12.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> for all available data beginning in 1973.

Sources: See end of section.

**Table 12.5 Carbon Dioxide Emissions From Energy Consumption: Transportation Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum							Retail Elec- tricity <sup>f</sup>	Total <sup>g</sup>	
			Aviation Gasoline	Distillate Fuel Oil <sup>c</sup>	Jet Fuel	LPG <sup>d</sup>	Lubri- cants	Motor Gasoline <sup>e</sup>	Residual Fuel Oil			Total
1973 Total	(s)	39	6	163	152	3	6	886	57	1,273	2	1,315
1975 Total	(s)	32	5	155	145	3	6	889	56	1,258	2	1,292
1980 Total	(h)	34	4	204	155	1	6	881	110	1,363	2	1,400
1985 Total	(h)	28	3	232	178	2	6	908	62	1,391	3	1,421
1990 Total	(h)	36	3	268	223	1	7	967	80	1,548	3	1,588
1995 Total	(h)	38	3	307	222	1	6	1,029	72	1,639	3	1,681
1996 Total	(h)	39	3	327	232	1	6	1,047	67	1,683	3	1,725
1997 Total	(h)	41	3	342	234	1	6	1,057	56	1,699	3	1,744
1998 Total	(h)	35	2	352	238	1	7	1,090	53	1,743	3	1,782
1999 Total	(h)	36	3	366	245	1	7	1,115	52	1,789	3	1,828
2000 Total	(h)	36	3	378	254	1	7	1,121	70	1,833	4	1,872
2001 Total	(h)	35	2	387	243	1	6	1,127	46	1,813	4	1,852
2002 Total	(h)	37	2	394	237	1	6	1,158	53	1,851	4	1,892
2003 Total	(h)	33	2	414	231	1	6	1,161	45	1,861	5	1,899
2004 Total	(h)	32	2	434	240	1	6	1,185	58	1,926	5	1,962
2005 Total	(h)	33	2	444	246	2	6	1,186	66	1,953	5	1,991
2006 Total	(h)	33	2	469	240	2	5	1,194	71	1,984	5	2,022
2007 Total	(h)	35	2	472	238	1	6	1,201	78	1,999	5	2,040
2008 Total	(h)	37	2	440	226	3	5	1,146	72	1,895	5	1,937
2009 Total	(h)	38	2	404	204	2	5	1,137	64	1,818	5	1,860
2010 January	(h)	4	(s)	31	17	(s)	(s)	91	6	145	(s)	150
February	(h)	4	(s)	30	15	(s)	(s)	82	5	133	(s)	137
March	(h)	3	(s)	35	18	(s)	(s)	94	6	154	(s)	157
April	(h)	3	(s)	35	17	(s)	(s)	94	7	154	(s)	157
May	(h)	3	(s)	37	18	(s)	(s)	97	6	159	(s)	161
June	(h)	3	(s)	36	19	(s)	1	95	5	156	(s)	159
July	(h)	3	(s)	38	19	(s)	(s)	99	6	162	(s)	165
August	(h)	3	(s)	39	19	(s)	(s)	98	5	161	(s)	165
September	(h)	3	(s)	37	18	(s)	(s)	94	6	155	(s)	157
October	(h)	3	(s)	37	18	(s)	(s)	95	6	157	(s)	160
November	(h)	3	(s)	35	17	(s)	(s)	90	6	149	(s)	152
December	(h)	4	(s)	35	17	(s)	(s)	94	5	153	(s)	158
Total	(h)	38	2	425	210	2	5	1,124	69	1,836	5	1,879
2011 January	(h)	5	(s)	33	17	(s)	(s)	89	7	147	(s)	152
February	(h)	4	(s)	30	15	(s)	(s)	83	7	135	(s)	140
March	(h)	4	(s)	36	17	(s)	1	93	6	153	(s)	157
April	(h)	3	(s)	35	17	(s)	(s)	90	7	151	(s)	154
May	(h)	3	(s)	38	18	(s)	(s)	93	6	155	(s)	158
June	(h)	3	(s)	38	19	(s)	(s)	92	5	155	(s)	158
July	(h)	3	(s)	37	18	(s)	(s)	95	3	155	(s)	158
August	(h)	3	(s)	39	19	(s)	(s)	94	3	157	(s)	160
September	(h)	3	(s)	36	17	(s)	(s)	90	5	150	(s)	153
October	(h)	3	(s)	37	17	(s)	(s)	91	5	151	(s)	154
November	(h)	3	(s)	35	17	(s)	(s)	87	4	145	(s)	148
December	(h)	4	(s)	34	17	(s)	(s)	92	6	149	(s)	153
Total	(h)	39	2	430	209	2	5	1,089	65	1,802	4	1,845
2012 January	(h)	4	(s)	32	16	(s)	(s)	87	5	140	(s)	145
February	(h)	4	(s)	31	16	(s)	(s)	85	4	137	(s)	141
March	(h)	3	(s)	34	17	(s)	(s)	91	5	149	(s)	152
April	(h)	3	(s)	35	16	(s)	(s)	90	5	147	(s)	151
May	(h)	3	(s)	37	18	(s)	(s)	95	3	154	(s)	157
5-Month Total	(h)	18	1	170	83	1	2	449	21	727	2	746
2011 5-Month Total	(h)	18	1	172	85	1	2	448	33	741	2	760
2010 5-Month Total	(h)	17	1	168	85	1	2	458	30	744	2	763

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.  
<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.  
<sup>c</sup> Distillate fuel oil, excluding biodiesel.  
<sup>d</sup> Liquefied petroleum gases.  
<sup>e</sup> Finished motor gasoline, excluding fuel ethanol.  
<sup>f</sup> Emissions from energy consumption (for electricity and a small amount of useful thermal output) in the electric power sector are allocated to the end-use sectors in proportion to each sector's share of total electricity retail sales. See Tables 7.6 and 12.6.  
<sup>g</sup> Excludes emissions from biomass energy consumption. See Table 12.7.  
<sup>h</sup> Beginning in 1978, the small amounts of coal consumed for transportation are reported as industrial sector consumption.

R=Revised. (s)=Less than 0.5 million metric tons.  
 Notes: • Data are estimates for carbon dioxide emissions from energy consumption, including the nonfuel use of fossil fuels. See "Section 12 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 12.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.  
 Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> for all available data beginning in 1973.  
 Sources: See end of section.



**Table 12.6 Carbon Dioxide Emissions From Energy Consumption: Electric Power Sector**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	Coal	Natural Gas <sup>b</sup>	Petroleum				Geo-thermal	Non-Biomass Waste <sup>d</sup>	Total <sup>e</sup>
			Distillate Fuel Oil <sup>c</sup>	Petroleum Coke	Residual Fuel Oil	Total			
<b>1973 Total</b> .....	812	199	20	2	254	276	NA	NA	1,286
<b>1975 Total</b> .....	824	172	17	(s)	231	248	NA	NA	1,244
<b>1980 Total</b> .....	1,137	200	12	1	194	207	NA	NA	1,544
<b>1985 Total</b> .....	1,367	166	6	1	79	86	NA	NA	1,619
<b>1990 Total</b> .....	1,548	176	7	3	92	102	(s)	6	1,831
<b>1995 Total</b> .....	1,661	228	8	8	45	61	(s)	10	1,960
<b>1996 Total</b> .....	1,752	205	8	8	50	66	(s)	10	2,033
<b>1997 Total</b> .....	1,797	219	8	10	56	75	(s)	10	2,101
<b>1998 Total</b> .....	1,828	248	10	13	82	105	(s)	10	2,192
<b>1999 Total</b> .....	1,836	260	10	11	76	97	(s)	10	2,204
<b>2000 Total</b> .....	1,927	281	13	10	69	91	(s)	10	2,310
<b>2001 Total</b> .....	1,870	290	12	11	79	102	(s)	11	2,273
<b>2002 Total</b> .....	1,890	306	9	18	52	79	(s)	13	2,288
<b>2003 Total</b> .....	1,931	278	12	18	69	98	(s)	11	2,319
<b>2004 Total</b> .....	1,943	297	8	23	69	100	(s)	11	2,352
<b>2005 Total</b> .....	1,984	319	8	25	69	102	(s)	11	2,417
<b>2006 Total</b> .....	1,954	338	5	22	28	56	(s)	12	2,359
<b>2007 Total</b> .....	1,987	372	7	17	31	55	(s)	11	2,426
<b>2008 Total</b> .....	1,959	362	5	16	19	40	(s)	12	2,374
<b>2009 Total</b> .....	1,741	373	5	14	14	34	(s)	11	2,159
<b>2010</b>									
January .....	170	30	1	1	1	4	(s)	1	204
February .....	150	26	(s)	1	1	2	(s)	1	179
March .....	143	25	(s)	1	1	2	(s)	1	171
April .....	125	25	(s)	1	1	2	(s)	1	154
May .....	142	30	(s)	1	1	3	(s)	1	176
June .....	163	38	1	1	2	4	(s)	1	206
July .....	177	48	1	2	2	4	(s)	1	231
August .....	177	51	(s)	1	2	3	(s)	1	232
September .....	148	38	(s)	1	1	2	(s)	1	189
October .....	132	31	(s)	1	1	2	(s)	1	166
November .....	136	27	(s)	1	1	2	(s)	1	166
December .....	165	31	1	1	1	3	(s)	1	200
<b>Total</b> .....	<b>1,828</b>	<b>399</b>	<b>6</b>	<b>15</b>	<b>12</b>	<b>33</b>	<b>(s)</b>	<b>11</b>	<b>2,271</b>
<b>2011</b>									
January .....	166	29	1	2	1	3	(s)	1	199
February .....	135	26	(s)	1	1	2	(s)	1	164
March .....	133	26	(s)	1	1	2	(s)	1	163
April .....	123	28	(s)	1	1	2	(s)	1	155
May .....	135	31	(s)	1	1	2	(s)	1	169
June .....	155	38	(s)	1	1	2	(s)	1	196
July .....	173	51	(s)	1	1	3	(s)	1	228
August .....	170	50	(s)	1	1	2	(s)	1	223
September .....	141	37	(s)	1	1	2	(s)	1	181
October .....	128	31	(s)	1	(s)	2	(s)	1	162
November .....	123	29	(s)	1	(s)	2	(s)	1	155
December .....	135	33	(s)	1	(s)	2	(s)	1	171
<b>Total</b> .....	<b>1,718</b>	<b>411</b>	<b>5</b>	<b>14</b>	<b>7</b>	<b>25</b>	<b>(s)</b>	<b>11</b>	<b>2,166</b>
<b>2012</b>									
January .....	130	35	(s)	1	1	2	(s)	1	168
February .....	116	35	(s)	1	(s)	2	(s)	1	153
March .....	106	37	(s)	1	(s)	1	(s)	1	145
April .....	95	39	(s)	1	(s)	1	(s)	1	136
May .....	116	44	(s)	1	(s)	1	(s)	1	163
<b>5-Month Total</b> .....	<b>563</b>	<b>190</b>	<b>2</b>	<b>4</b>	<b>2</b>	<b>7</b>	<b>(s)</b>	<b>5</b>	<b>765</b>
<b>2011 5-Month Total</b> .....	<b>693</b>	<b>141</b>	<b>2</b>	<b>6</b>	<b>3</b>	<b>11</b>	<b>(s)</b>	<b>5</b>	<b>850</b>
<b>2010 5-Month Total</b> .....	<b>729</b>	<b>136</b>	<b>2</b>	<b>6</b>	<b>4</b>	<b>13</b>	<b>(s)</b>	<b>5</b>	<b>882</b>

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Natural gas, excluding supplemental gaseous fuels.

<sup>c</sup> Distillate fuel oil, excluding biodiesel.

<sup>d</sup> Municipal solid waste from non-biogenic sources, and tire-derived fuels.

<sup>e</sup> Excludes emissions from biomass energy consumption. See Table 12.7.

NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Data are estimates for carbon dioxide emissions from energy consumption. See "Section 12 Methodology and Sources" at end of section.

• See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Data exclude emissions from biomass energy consumption. See Table 12.7 and Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> for all available data beginning in 1973.

Sources: See end of section.

**Table 12.7 Carbon Dioxide Emissions From Biomass Energy Consumption**  
(Million Metric Tons of Carbon Dioxide<sup>a</sup>)

	By Source					By Sector					
	Wood <sup>b</sup>	Biomass Waste <sup>c</sup>	Fuel Ethanol <sup>d</sup>	Bio-diesel	Total	Residential	Commercial <sup>e</sup>	Industrial <sup>f</sup>	Transportation	Electric Power <sup>g</sup>	Total
1973 Total .....	143	(s)	NA	NA	143	33	1	109	NA	(s)	143
1975 Total .....	140	(s)	NA	NA	141	40	1	100	NA	(s)	141
1980 Total .....	232	(s)	NA	NA	232	80	2	150	NA	(s)	232
1985 Total .....	252	14	3	NA	270	95	2	168	3	1	270
1990 Total .....	208	24	4	NA	237	54	8	147	4	23	237
1995 Total .....	222	30	8	NA	260	49	9	166	8	28	260
1996 Total .....	229	32	6	NA	266	51	10	170	6	30	266
1997 Total .....	222	30	7	NA	259	40	10	172	7	30	259
1998 Total .....	205	30	8	NA	242	36	9	160	8	30	242
1999 Total .....	208	29	8	NA	245	37	9	161	8	30	245
2000 Total .....	212	27	9	NA	248	39	9	161	9	29	248
2001 Total .....	188	33	10	(s)	231	35	9	147	10	31	231
2002 Total .....	187	36	12	(s)	235	36	9	144	12	35	235
2003 Total .....	188	36	16	(s)	240	38	9	141	16	37	240
2004 Total .....	199	35	20	(s)	255	38	10	151	20	36	255
2005 Total .....	200	37	23	1	261	40	10	150	23	37	261
2006 Total .....	197	36	31	2	266	36	9	151	33	38	266
2007 Total .....	194	37	39	3	274	38	9	146	41	39	274
2008 Total .....	191	40	55	3	289	42	10	140	57	40	289
2009 Total .....	177	41	62	3	284	40	10	128	64	41	284
2010 January .....	16	4	6	(s)	25	3	1	12	6	4	25
February .....	14	3	5	(s)	23	3	1	11	5	3	23
March .....	16	4	6	(s)	25	3	1	12	6	4	25
April .....	15	4	6	(s)	25	3	1	11	6	3	25
May .....	15	4	6	(s)	25	3	1	11	6	3	25
June .....	15	4	6	(s)	25	3	1	11	6	4	25
July .....	16	4	6	(s)	26	3	1	12	6	4	26
August .....	16	4	6	(s)	26	3	1	12	6	4	26
September .....	16	3	6	(s)	25	3	1	12	6	3	25
October .....	16	4	6	(s)	26	3	1	12	6	3	26
November .....	15	4	6	(s)	25	3	1	12	6	4	25
December .....	16	4	6	(s)	27	3	1	12	6	4	27
Total .....	186	43	73	2	304	39	10	139	74	42	304
2011 January .....	16	4	6	(s)	26	3	1	12	6	3	26
February .....	15	3	6	(s)	24	3	1	11	6	3	24
March .....	16	4	6	(s)	26	3	1	12	6	3	26
April .....	15	3	6	1	25	3	1	11	6	3	25
May .....	15	4	6	1	26	3	1	11	7	3	26
June .....	16	4	6	1	26	3	1	12	7	3	26
July .....	16	4	6	1	27	3	1	12	7	4	27
August .....	16	4	7	1	27	3	1	12	7	4	27
September .....	15	4	6	1	26	3	1	12	7	3	26
October .....	15	4	6	1	26	3	1	11	7	3	26
November .....	15	4	6	1	26	3	1	12	7	3	26
December .....	16	4	6	1	27	3	1	12	7	4	27
Total .....	186	43	73	8	311	40	10	140	80	41	311
2012 January .....	16	4	6	<sup>R</sup> (s)	26	3	1	12	6	4	26
February .....	15	3	6	1	25	3	1	11	6	3	25
March .....	15	4	6	1	26	3	1	11	7	3	26
April .....	14	4	6	1	25	3	1	11	7	3	25
May .....	15	4	6	1	27	3	1	12	7	3	27
5-Month Total .....	76	18	30	4	127	17	4	57	33	17	127
2011 5-Month Total .....	76	18	30	2	126	17	4	57	31	16	126
2010 5-Month Total .....	76	17	29	1	123	16	4	57	29	17	123

<sup>a</sup> Metric tons of carbon dioxide can be converted to metric tons of carbon equivalent by multiplying by 12/44.

<sup>b</sup> Wood and wood-derived fuels.

<sup>c</sup> Municipal solid waste from biogenic sources, landfill gas, sludge waste, agricultural byproducts, and other biomass.

<sup>d</sup> Fuel ethanol minus denaturant.

<sup>e</sup> Commercial sector, including commercial combined-heat-and-power (CHP) and commercial electricity-only plants.

<sup>f</sup> Industrial sector, including industrial combined-heat-and-power (CHP) and industrial electricity-only plants.

<sup>g</sup> The electric power sector comprises electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public.

R=Revised. NA=Not available. (s)=Less than 0.5 million metric tons.

Notes: • Carbon dioxide emissions from biomass energy consumption are excluded from the energy-related carbon dioxide emissions reported in Tables 12.1–12.6. See Note 2, "Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion," at end of section. • Data are estimates. See "Section 12 Methodology and Sources" at end of section. • See "Carbon Dioxide" in Glossary. • See Note 1, "Emissions of Carbon Dioxide and Other Greenhouse Gases," at end of section. • Totals may not equal sum of components due to independent rounding. • Geographic coverage is the 50 States and the District of Columbia.

Web Page: See <http://www.eia.gov/totalenergy/data/monthly/#environment> for all available data beginning in 1973.

Sources: See end of section.

## Environment

**Note 1. Emissions of Carbon Dioxide and Other Greenhouse Gases.** Greenhouse gases are those gases—such as water vapor, carbon dioxide (CO<sub>2</sub>), methane, nitrous oxide, hydrofluorocarbons (HFCs), perfluorocarbons (PFCs), and sulfur hexafluoride—that are transparent to solar (short-wave) radiation but opaque to long-wave (infrared) radiation, thus preventing long-wave radiant energy from leaving Earth's atmosphere. The net effect is a trapping of absorbed radiation and a tendency to warm the planet's surface.

Energy-related carbon dioxide emissions account for about 98 percent of U.S. CO<sub>2</sub> emissions. The vast majority of CO<sub>2</sub> emissions come from fossil fuel combustion, with smaller amounts from the nonfuel use of fossil fuels, as well as from electricity generation using geothermal energy and non-biomass waste. Other sources of CO<sub>2</sub> emissions include industrial processes, such as cement and limestone production. Data in the U.S. Energy Information Administration's (EIA) *Monthly Energy Review (MER)* Tables 12.1–12.6 are estimates for U.S. CO<sub>2</sub> emissions from energy consumption, including the nonfuel use of fossil fuels (excluded are estimates for CO<sub>2</sub> emissions from biomass energy consumption, which appear in Table 12.7).

For annual U.S. estimates for emissions of CO<sub>2</sub> from all sources, as well as for emissions of other greenhouse gases, see EIA's *Emissions of Greenhouse Gases Report* at [http://www.eia.gov/environment/emissions/ghg\\_report/](http://www.eia.gov/environment/emissions/ghg_report/).

**Note 2. Accounting for Carbon Dioxide Emissions From Biomass Energy Combustion.** Carbon dioxide (CO<sub>2</sub>) emissions from the combustion of biomass to produce energy are excluded from the energy-related CO<sub>2</sub> emissions reported in MER Tables 12.1–12.6, but appear in Table 12.7. According to current international convention (see the Intergovernmental Panel on Climate Change's "2006 IPCC Guidelines for National Greenhouse Gas Inventories"), carbon released through biomass combustion is excluded from reported energy-related emissions. The release of carbon from biomass combustion is assumed to be balanced by the uptake of carbon when the feedstock is grown, resulting in zero net emissions over some period of time. (This is not to say that biomass energy is carbon-neutral. Energy inputs are required in order to grow, fertilize, and harvest the feedstock and to produce and process the biomass into fuels.)

However, analysts have debated whether increased use of biomass energy may result in a decline in terrestrial carbon stocks, leading to a net positive release of carbon rather than the zero net release assumed by its exclusion from reported energy-related emissions. For example, the clearing of forests for biofuel crops could result in an initial release of carbon that is not fully recaptured in subsequent use of the land for agriculture.

To reflect the potential net emissions, the international convention for greenhouse gas inventories is to report

biomass emissions in the category "agriculture, forestry, and other land use," usually based on estimates of net changes in carbon stocks over time.

This indirect accounting of CO<sub>2</sub> emissions from biomass can potentially lead to confusion in accounting for and understanding the flow of CO<sub>2</sub> emissions within energy and non-energy systems. In recognition of this issue, reporting of CO<sub>2</sub> emissions from biomass combustion alongside other energy-related CO<sub>2</sub> emissions offers an alternative accounting treatment. It is important, however, to avoid misinterpreting emissions from fossil energy and biomass energy sources as necessarily additive. Instead, the combined total of direct CO<sub>2</sub> emissions from biomass and energy-related CO<sub>2</sub> emissions implicitly assumes that none of the carbon emitted was previously or subsequently reabsorbed in terrestrial sinks or that other emissions sources offset any such sequestration.

## Section 12 Methodology and Sources

To estimate carbon dioxide emissions from energy consumption for the *Monthly Energy Review (MER)*, Tables 12.1–12.7, the U.S. Energy Information Administration (EIA) uses the following methodology and sources:

### Step 1. Determine Fuel Consumption

Coal—Coal sectoral (residential, commercial, coke plants, other industrial, transportation, electric power) consumption data in thousand short tons are from MER Table 6.2. Coal sectoral consumption data are converted to trillion Btu by multiplying by the coal heat content factors in MER Table A5.

Coal Coke Net Imports—Coal coke net imports data in trillion Btu are derived from coal coke imports and exports data in MER Tables 1.4a and 1.4b.

Natural Gas (excluding supplemental gaseous fuels)—Natural gas sectoral consumption data in trillion Btu are from MER Tables 2.2–2.6.

Petroleum—Total and sectoral consumption (product supplied) data in thousand barrels per day for asphalt and road oil, aviation gasoline, distillate fuel oil, jet fuel, kerosene, liquefied petroleum gases (LPG), lubricants, motor gasoline, petroleum coke, and residual fuel oil are from MER Tables 3.5 and 3.7a–3.7c. For the component products of LPG (ethane/ethylene, propane/propylene, normal butane/butylene, and isobutane/isobutylene) and "other petroleum" (aviation gasoline blending components, crude oil, motor gasoline blending components, naphthas for petrochemical feedstock use, other oils for petrochemical feedstock use, pentanes plus, special naphthas, still gas, unfinished oils, waxes, and miscellaneous petroleum products), consumption (product supplied) data in thousand barrels per day are from EIA's *Petroleum Supply Annual (PSA)*, *Petroleum Supply Monthly (PSM)*, and earlier

publications (see sources for MER Table 3.5). Petroleum consumption data by product are converted to trillion Btu by multiplying by the petroleum heat content factors in MER Table A1 (Table A3 for motor gasoline).

Biomass—Sectoral consumption data in trillion Btu for wood, biomass waste, fuel ethanol (minus denaturant), and biodiesel are from MER Tables 10.2a–10.2c.

## Step 2. Remove Biofuels From Petroleum

Distillate Fuel Oil—Beginning in 2009, the distillate fuel oil data (for total and transportation sector) in Step 1 include biodiesel, a non-fossil renewable fuel. To remove the biodiesel portion from distillate fuel oil, data in thousand barrels per day for refinery and blender net inputs of renewable diesel fuel (from the PSA/PSM) are converted to trillion Btu by multiplying by the biodiesel heat content factor in MER Table A3, and then subtracted from the distillate fuel oil consumption values.

Motor Gasoline—Beginning in 1993, the motor gasoline data (for total, commercial sector, industrial sector, and transportation sector) in Step 1 include fuel ethanol, a non-fossil renewable fuel. To remove the fuel ethanol portion from motor gasoline, data in trillion Btu for fuel ethanol consumption (from MER Tables 10.2a, 10.2b, and 10.3) are subtracted from the motor gasoline consumption values. (Note that about 2 percent of fuel ethanol is fossil-based petroleum denaturant, to make the fuel ethanol undrinkable. For 1993–2008, petroleum denaturant is double counted in the PSA product supplied statistics, in both the original product category—e.g., pentanes plus—and also in the finished motor gasoline category; for this time period for MER Section 12, petroleum denaturant is removed along with the fuel ethanol from motor gasoline, but left in the original product. Beginning in 2009, petroleum denaturant is counted only in the PSA/PSM product supplied statistics for motor gasoline; for this time period for MER Section 12, petroleum denaturant is left in motor gasoline.)

## Step 3. Remove Carbon Sequestered by Nonfuel Use

The following fuels have industrial nonfuel uses as chemical feedstocks and other products: coal, natural gas, asphalt and road oil, distillate fuel oil, liquefied petroleum gases (ethane/ethylene, propane/propylene, normal butane/butylene, and isobutane/isobutylene), lubricants (which have industrial and transportation nonfuel uses), naphthas for petrochemical feedstock use, other oils for petrochemical feedstock use, pentanes plus, petroleum coke, residual fuel oil, special naphthas, still gas, waxes, and miscellaneous petroleum products. In the nonfuel use of these fuels, some of the carbon is sequestered, and is thus subtracted from the fuel consumption values in Steps 1 and 2.

Estimates of annual nonfuel use and associated carbon sequestration are developed by EIA using the methodology

detailed in “Documentation for *Emissions of Greenhouse Gases in the United States 2008*” at [http://www.eia.gov/oiaf/1605/ggprt/documentation/pdf/0638\(2006\).pdf](http://www.eia.gov/oiaf/1605/ggprt/documentation/pdf/0638(2006).pdf).

To obtain monthly estimates of nonfuel use and associated carbon sequestration, monthly patterns for industrial consumption and product supplied data series are used. For coal nonfuel use, the monthly pattern for coke plants coal consumption from MER Table 6.2 is used. For natural gas, the monthly pattern for other industrial non-CHP natural gas consumption from MER Table 4.3 is used. For distillate fuel oil, petroleum coke, and residual fuel oil, the monthly patterns for industrial consumption from MER Table 3.7b are used. For the other petroleum products, the monthly patterns for product supplied from the PSA and PSM are used.

## Step 4. Determine Carbon Dioxide Emissions From Energy Consumption

Carbon dioxide (CO<sub>2</sub>) emissions data in million metric tons are calculated by multiplying consumption values in trillion Btu from Steps 1 and 2 (minus the carbon sequestered in nonfuel use in Step 3) by the CO<sub>2</sub> emissions factors at [http://www.eia.gov/oiaf/1605/ggprt/excel/CO2\\_coefs\\_09\\_v2.xls](http://www.eia.gov/oiaf/1605/ggprt/excel/CO2_coefs_09_v2.xls). Beginning in 2010, the 2009 factors are used.

Coal—CO<sub>2</sub> emissions for coal are calculated for each sector (residential, commercial, coke plants, other industrial, transportation, electric power). Total coal emissions are the sum of the sectoral coal emissions.

Coal Coke Net Imports—CO<sub>2</sub> emissions for coal coke net imports are calculated.

Natural Gas—CO<sub>2</sub> emissions for natural gas are calculated for each sector (residential, commercial, industrial, transportation, electric power). Total natural gas emissions are the sum of the sectoral natural gas emissions.

Petroleum—CO<sub>2</sub> emissions are calculated for each petroleum product. Total petroleum emissions are the sum of the product emissions. Total LPG emissions are the sum of the emissions for the component products (ethane/ethylene, propane/propylene, normal butane/butylene, and isobutane/isobutylene); residential, commercial, and transportation sector LPG emissions are estimated by multiplying consumption values in trillion Btu from MER Tables 3.8a and 3.8c by the propane emissions factor; industrial sector LPG emissions are estimated as total LPG emissions minus emissions by the other sectors.

Geothermal and Non-Biomass Waste—Annual CO<sub>2</sub> emissions data for geothermal and non-biomass waste are EIA estimates based on Form EIA-923, “Power Plant Operations Report” (and predecessor forms). Monthly estimates are created by dividing the annual data by the number of days in the year and then multiplying by the number of days in the month. (Annual estimates for the current year are set equal to those of the previous year.)

Biomass—CO<sub>2</sub> emissions for wood, biomass waste, fuel ethanol (minus denaturant), and biodiesel are calculated for each sector. Total emissions for each biomass fuel are the sum of the sectoral emissions. The following factors, in million metric tons CO<sub>2</sub> per quadrillion Btu, are used: wood—93.80; biomass waste—90.70; fuel ethanol—68.44; and biodiesel—73.84. For 1973–1988, the biomass portion

of waste in MER Tables 10.2a–10.2c is estimated as 67 percent; for 1989–2000, the biomass portion of waste is estimated as 67 percent in 1989 to 58 percent in 2000, based on the biogenic shares of total municipal solid waste shown in EIA’s “Methodology for Allocating Municipal Solid Waste to Biogenic and Non-Biogenic Energy,” Table 1 at <http://www.eia.gov/cneaf/solar.renewables/page/mswaste/msw.pdf>.

THIS PAGE INTENTIONALLY LEFT BLANK

# Appendix A

## British Thermal Unit Conversion Factors

The thermal conversion factors presented in the following tables can be used to estimate the heat content in British thermal units (Btu) of a given amount of energy measured in physical units, such as barrels or cubic feet. For example, 10 barrels of asphalt has a heat content of approximately 66.36 million Btu (10 barrels x 6.636 million Btu per barrel = 66.36 million Btu).

The heat content rates (i.e., thermal conversion factors) provided in this section represent the gross (or higher or upper) energy content of the fuels. Gross heat content rates are applied in all Btu calculations for the *Monthly Energy Review* and are commonly used in energy calculations in the United States; net (or lower) heat content rates are typically used in European energy calculations. The difference between the two rates is the amount of energy that is consumed to vaporize water that is created during the combustion process. Generally, the difference ranges from 2 percent to 10 percent, depending on the specific fuel and its hydrogen content. Some fuels, such as unseasoned wood, can be more than 40 percent different in their gross

and net heat content rates. See “Heat Content” and “British Thermal Unit (Btu)” in the Glossary for more information.

Thermal conversion factors for hydrocarbon mixes (Table A1) are weighted averages of the thermal conversion factors for each hydrocarbon included in the mix. For example, in calculating the thermal conversion factor for a 60-40 butane-propane mixture, the thermal conversion factor for butane is weighted 1.5 times the thermal conversion factor for propane.

In general, the annual thermal conversion factors presented in Tables A2 through A6 are computed from final annual data or from the best available data and labeled “preliminary.” Often, the previous year’s factor is used as a preliminary value until data become available to calculate the factor appropriate to the year. The source of each factor is described in the section entitled “Thermal Conversion Factor Source Documentation,” which follows Table A6 in this appendix.

**Table A1. Approximate Heat Content of Petroleum Products (Million Btu per Barrel)**

Petroleum Product	Heat Content	Petroleum Product	Heat Content
Asphalt	6.636	Pentanes Plus	4.620
Aviation Gasoline	5.048	Petrochemical Feedstocks	
Butane	4.326	Naptha Less Than 401°F	5.248
Butane-Propane Mixture <sup>a</sup>	4.130	Other Oils Equal to or Greater Than 401°F	5.825
Distillate Fuel Oil <sup>b</sup>	5.825	Still Gas	6.000
Ethane	3.082	Petroleum Coke	6.024
Ethane-Propane Mixture <sup>c</sup>	3.308	Plant Condensate	5.418
Isobutane	3.974	Propane	3.836
Jet Fuel, Kerosene Type	5.670	Residual Fuel Oil	6.287
Jet Fuel, Naphtha Type	5.355	Road Oil	6.636
Kerosene	5.670	Special Naphthas	5.248
Lubricants	6.065	Still Gas	6.000
Motor Gasoline <sup>d</sup>		Unfinished Oils	5.825
Conventional	5.253	Unfractionated Stream	5.418
Reformulated	5.150	Waxes	5.537
Oxygenated	5.150	Miscellaneous	5.796
Natural Gasoline and Isopentane	4.620		

<sup>a</sup> 60 percent butane and 40 percent propane.

<sup>b</sup> Does not include biodiesel. See Table A3 for biodiesel heat contents.

<sup>c</sup> 70 percent ethane and 30 percent propane.

<sup>d</sup> See Table A3 for motor gasoline weighted heat contents beginning in 1994, and for fuel ethanol heat contents.

Note: The values in this table are for gross heat contents. See “Heat Content” in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: See “Thermal Conversion Factor Source Documentation,” which follows Table A6.

**Table A2. Approximate Heat Content of Petroleum Production, Imports, and Exports**  
(Million Btu per Barrel)

	Production		Imports			Exports		
	Crude Oil <sup>a</sup>	Natural Gas Plant Liquids	Crude Oil <sup>a</sup>	Petroleum Products	Total	Crude Oil <sup>a</sup>	Petroleum Products	Total
1973 .....	5.800	4.049	5.817	5.983	5.897	5.800	5.752	5.752
1974 .....	5.800	4.011	5.827	5.959	5.884	5.800	5.773	5.774
1975 .....	5.800	3.984	5.821	5.935	5.858	5.800	5.747	5.748
1976 .....	5.800	3.964	5.808	5.980	5.856	5.800	5.743	5.745
1977 .....	5.800	3.941	5.810	5.908	5.834	5.800	5.796	5.797
1978 .....	5.800	3.925	5.802	5.955	5.839	5.800	5.814	5.808
1979 .....	5.800	3.955	5.810	5.811	5.810	5.800	5.864	5.832
1980 .....	5.800	3.914	5.812	5.748	5.796	5.800	5.841	5.820
1981 .....	5.800	3.930	5.818	5.659	5.775	5.800	5.837	5.821
1982 .....	5.800	3.872	5.826	5.664	5.775	5.800	5.829	5.820
1983 .....	5.800	3.839	5.825	5.677	5.774	5.800	5.800	5.800
1984 .....	5.800	3.812	5.823	5.613	5.745	5.800	5.867	5.850
1985 .....	5.800	3.815	5.832	5.572	5.736	5.800	5.819	5.814
1986 .....	5.800	3.797	5.903	5.624	5.808	5.800	5.839	5.832
1987 .....	5.800	3.804	5.901	5.599	5.820	5.800	5.860	5.858
1988 .....	5.800	3.800	5.900	5.618	5.820	5.800	5.842	5.840
1989 .....	5.800	3.826	5.906	5.641	5.833	5.800	5.869	5.857
1990 .....	5.800	3.822	5.934	5.614	5.849	5.800	5.838	5.833
1991 .....	5.800	3.807	5.948	5.636	5.873	5.800	5.827	5.823
1992 .....	5.800	3.804	5.953	5.623	5.877	5.800	5.774	5.777
1993 .....	5.800	3.801	5.954	5.620	5.883	5.800	5.777	5.779
1994 .....	5.800	3.794	5.950	5.534	5.861	5.800	5.777	5.779
1995 .....	5.800	3.796	5.938	5.483	5.855	5.800	5.740	5.746
1996 .....	5.800	3.777	5.947	5.468	5.847	5.800	5.728	5.736
1997 .....	5.800	3.762	5.954	5.469	5.862	5.800	5.726	5.734
1998 .....	5.800	3.769	5.953	5.462	5.861	5.800	5.710	5.720
1999 .....	5.800	3.744	5.942	5.421	5.840	5.800	5.684	5.699
2000 .....	5.800	3.733	5.959	5.432	5.849	5.800	5.651	5.658
2001 .....	5.800	3.735	5.976	5.443	5.862	5.800	5.751	5.752
2002 .....	5.800	3.729	5.971	5.451	5.863	5.800	5.687	5.688
2003 .....	5.800	3.739	5.970	5.438	5.857	5.800	5.739	5.740
2004 .....	5.800	3.724	5.981	5.475	5.863	5.800	5.753	5.754
2005 .....	5.800	3.724	5.977	5.474	5.845	5.800	5.741	5.743
2006 .....	5.800	3.712	5.980	5.454	5.842	5.800	5.723	5.724
2007 .....	5.800	3.701	5.985	5.503	5.862	5.800	5.749	5.750
2008 .....	5.800	3.706	5.990	5.479	5.866	5.800	5.762	5.762
2009 .....	5.800	3.692	5.988	5.525	5.882	5.800	5.737	5.738
2010 .....	5.800	3.674	5.989	5.557	5.894	5.800	5.670	5.672
2011 <sup>P</sup> .....	5.800	3.675	6.007	5.555	5.910	5.800	5.619	5.622
2012 <sup>E</sup> .....	5.800	3.675	6.007	5.555	5.910	5.800	5.619	5.622

<sup>a</sup> Includes lease condensate.

P=Preliminary, E=Estimate.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.



**Table A3. Approximate Heat Content of Petroleum Consumption and Biofuels Production**  
(Million Btu per Barrel)

	Total Petroleum <sup>a</sup> Consumption by Sector						Liquefied Petroleum Gases Consumption <sup>f</sup>	Motor Gasoline Consumption <sup>g</sup>	Fuel Ethanol <sup>h</sup>	Fuel Ethanol Feed-stock Factor <sup>i</sup>	Biodiesel	Biodiesel Feed-stock Factor <sup>j</sup>
	Residential	Commercial <sup>b</sup>	Industrial <sup>b</sup>	Transportation <sup>b,c</sup>	Electric Power <sup>d,e</sup>	Total <sup>b,c</sup>						
1973	5.258	5.689	5.557	5.396	6.245	5.515	3.746	5.253	NA	NA	NA	NA
1974	5.253	5.683	5.525	5.394	6.238	5.504	3.730	5.253	NA	NA	NA	NA
1975	5.253	5.649	5.513	5.392	6.250	5.494	3.715	5.253	NA	NA	NA	NA
1976	5.277	5.672	5.523	5.396	6.251	5.504	3.711	5.253	NA	NA	NA	NA
1977	5.285	5.682	5.539	5.401	6.249	5.518	3.677	5.253	NA	NA	NA	NA
1978	5.287	5.665	5.536	5.405	6.251	5.519	3.669	5.253	NA	NA	NA	NA
1979	5.365	5.717	5.409	5.429	6.258	5.494	3.680	5.253	NA	NA	NA	NA
1980	5.321	5.751	5.366	5.441	6.254	5.479	3.674	5.253	3.563	6.586	NA	NA
1981	5.283	5.693	5.299	5.433	6.258	5.448	3.643	5.253	3.563	6.562	NA	NA
1982	5.266	5.698	5.247	5.423	6.258	5.415	3.615	5.253	3.563	6.539	NA	NA
1983	5.140	5.591	5.254	5.416	6.255	5.406	3.614	5.253	3.563	6.515	NA	NA
1984	5.307	5.657	5.207	5.418	6.251	5.395	3.599	5.253	3.563	6.492	NA	NA
1985	5.263	5.598	5.199	5.423	6.247	5.387	3.603	5.253	3.563	6.469	NA	NA
1986	5.268	5.632	5.269	5.426	6.257	5.418	3.640	5.253	3.563	6.446	NA	NA
1987	5.239	5.594	5.233	5.429	6.249	5.403	3.659	5.253	3.563	6.423	NA	NA
1988	5.257	5.597	5.228	5.433	6.250	5.410	3.652	5.253	3.563	6.400	NA	NA
1989	5.194	5.549	5.219	5.438	<sup>d</sup> 6.240	5.410	3.683	5.253	3.563	6.377	NA	NA
1990	5.145	5.553	5.253	5.442	6.244	5.411	3.625	5.253	3.563	6.355	NA	NA
1991	5.094	5.528	5.167	5.441	6.246	5.384	3.614	5.253	3.563	6.332	NA	NA
1992	5.124	5.513	5.168	5.443	6.238	5.378	3.624	5.253	3.563	6.309	NA	NA
1993	5.102	<sup>b</sup> 5.505	<sup>b</sup> 5.178	<sup>b</sup> 5.436	6.230	<sup>b</sup> 5.379	3.606	5.253	3.563	6.287	NA	NA
1994	5.098	5.515	5.150	5.424	6.213	5.361	3.635	5.230	3.563	6.264	NA	NA
1995	5.063	5.478	5.121	5.417	6.188	5.341	3.623	5.215	3.563	6.242	NA	NA
1996	4.998	5.433	5.114	5.420	6.195	5.336	3.613	5.216	3.563	6.220	NA	NA
1997	4.989	5.391	5.120	5.416	6.199	5.336	3.616	5.213	3.563	6.198	NA	NA
1998	4.975	5.365	5.137	5.413	6.210	5.349	3.614	5.212	3.563	6.176	NA	NA
1999	4.902	5.291	5.092	5.413	6.205	5.328	3.616	5.211	3.563	6.167	NA	NA
2000	4.908	5.316	5.057	5.422	6.189	5.326	3.607	5.210	3.563	6.159	NA	NA
2001	4.937	5.325	5.142	5.412	6.199	5.345	3.614	5.210	3.563	6.151	5.359	5.433
2002	4.886	5.293	5.093	5.411	6.173	5.324	3.613	5.208	3.563	6.143	5.359	5.433
2003	4.907	5.307	5.142	5.409	6.182	5.340	3.629	5.207	3.563	6.116	5.359	5.433
2004	4.953	5.328	5.144	5.421	6.192	5.350	3.618	5.215	3.563	6.089	5.359	5.433
2005	4.916	5.364	5.178	5.427	6.188	5.365	3.620	5.218	3.563	6.063	5.359	5.433
2006	4.894	5.310	5.160	5.431	6.143	5.353	3.605	5.218	3.563	6.036	5.359	5.433
2007	4.850	5.298	5.127	5.434	6.151	5.346	3.591	5.219	3.563	6.009	5.359	5.433
2008	4.732	5.175	5.149	5.426	6.123	5.339	3.600	5.218	3.563	5.983	5.359	5.433
2009	4.691	5.266	5.018	<sup>b</sup> 5.414	6.105	<sup>b</sup> 5.301	3.558	5.218	3.563	5.957	5.359	5.433
2010	4.692	5.263	4.988	5.421	6.084	5.297	3.557	5.218	3.561	5.931	5.359	5.433
2011	<sup>E</sup> 4.692	<sup>E</sup> 5.261	<sup>E</sup> 4.964	<sup>E</sup> 5.425	<sup>P</sup> 6.062	<sup>P</sup> 5.291	<sup>P</sup> 3.529	<sup>P</sup> 5.218	<sup>P</sup> 3.560	<sup>P</sup> 5.905	5.359	5.433
2012	<sup>E</sup> 4.692	<sup>E</sup> 5.261	<sup>E</sup> 4.964	<sup>E</sup> 5.425	<sup>E</sup> 6.062	<sup>E</sup> 5.291	<sup>E</sup> 3.529	<sup>E</sup> 5.218	<sup>E</sup> 3.560	<sup>E</sup> 5.880	5.359	5.433

<sup>a</sup> Petroleum products supplied, including natural gas plant liquids and crude oil burned directly as fuel. Quantity-weighted averages of the petroleum products included in each category are calculated by using heat content values shown in Table A1.

<sup>b</sup> Beginning in 1993, includes fuel ethanol blended into motor gasoline.

<sup>c</sup> Beginning in 1993, includes renewable diesel fuel (including biodiesel) blended into distillate fuel oil.

<sup>d</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>e</sup> Electric power sector factors are weighted average heat contents for distillate fuel oil, petroleum coke, and residual fuel oil; they exclude other liquids.

<sup>f</sup> Quantity-weighted averages of the major components of liquefied petroleum gases are calculated by using heat content values shown in Table A1.

<sup>g</sup> There is a discontinuity in this time series between 1993 and 1994; beginning in 1994, the single constant factor is replaced by a quantity-weighted

factor—quantity-weighted averages of the major components of motor gasoline, including fuel ethanol, are calculated by using heat content values shown in Table A1.

<sup>h</sup> Includes denaturant (petroleum added to ethanol to make it undrinkable). Fuel ethanol factors are weighted average heat contents for undenatured ethanol (3.539 million Btu per barrel), pentanes plus used as denaturant (4.620 million Btu per barrel), and conventional motor gasoline and motor gasoline blending components used as denaturant (5.253 million Btu per barrel). The factor for 2009 is used as the estimated factor for 1980-2008.

<sup>i</sup> Corn input to the production of undenatured ethanol (million Btu corn per barrel undenatured ethanol), used as the factor to estimate total biomass inputs to the production of undenatured ethanol. Observed ethanol yields (gallons undenatured ethanol per bushel of corn) are 2.5 in 1980, 2.666 in 1998, 2.68 in 2002, and 2.764 in 2009; yields in other years are estimated. Corn is assumed to have a gross heat content of 0.392 million Btu per bushel. Undenatured ethanol is assumed to have a gross heat content of 3.539 million Btu per barrel.

<sup>j</sup> Soybean oil input to the production of biodiesel (million Btu soybean oil per barrel biodiesel), used as the factor to estimate total biomass inputs to the production of biodiesel. It is assumed that 7.65 pounds of soybean oil are needed to produce one gallon of biodiesel, and 5.433 million Btu of soybean oil are needed to produce one barrel of biodiesel. Soybean oil is assumed to have a gross heat content of 16,909 Btu per pound, or 5.483 million Btu per barrel. Biodiesel is assumed to have a gross heat content of 17,253 Btu per pound, or 5.359 million Btu per barrel.

<sup>P</sup>=Preliminary. <sup>E</sup>=Estimate. NA=Not available.

Note: The heat content values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A4. Approximate Heat Content of Natural Gas**  
(Btu per Cubic Foot)

	Production		Consumption <sup>a</sup>			Imports	Exports
	Marketed	Dry	End-Use Sectors <sup>b</sup>	Electric Power Sector <sup>c</sup>	Total		
1973 .....	1,093	1,021	1,020	1,024	1,021	1,026	1,023
1974 .....	1,097	1,024	1,024	1,022	1,024	1,027	1,016
1975 .....	1,095	1,021	1,020	1,026	1,021	1,026	1,014
1976 .....	1,093	1,020	1,019	1,023	1,020	1,025	1,013
1977 .....	1,093	1,021	1,019	1,029	1,021	1,026	1,013
1978 .....	1,088	1,019	1,016	1,034	1,019	1,030	1,013
1979 .....	1,092	1,021	1,018	1,035	1,021	1,037	1,013
1980 .....	1,098	1,026	1,024	1,035	1,026	1,022	1,013
1981 .....	1,103	1,027	1,025	1,035	1,027	1,014	1,011
1982 .....	1,107	1,028	1,026	1,036	1,028	1,018	1,011
1983 .....	1,115	1,031	1,031	1,030	1,031	1,024	1,010
1984 .....	1,109	1,031	1,030	1,035	1,031	1,005	1,010
1985 .....	1,112	1,032	1,031	1,038	1,032	1,002	1,011
1986 .....	1,110	1,030	1,029	1,034	1,030	997	1,008
1987 .....	1,112	1,031	1,031	1,032	1,031	999	1,011
1988 .....	1,109	1,029	1,029	1,028	1,029	1,002	1,018
1989 .....	1,107	1,031	1,031	<sup>c</sup> 1,028	1,031	1,004	1,019
1990 .....	1,105	1,029	1,030	1,027	1,029	1,012	1,018
1991 .....	1,108	1,030	1,031	1,025	1,030	1,014	1,022
1992 .....	1,110	1,030	1,031	1,025	1,030	1,011	1,018
1993 .....	1,106	1,027	1,028	1,025	1,027	1,020	1,016
1994 .....	1,105	1,028	1,029	1,025	1,028	1,022	1,011
1995 .....	1,106	1,026	1,027	1,021	1,026	1,021	1,011
1996 .....	1,109	1,026	1,027	1,020	1,026	1,022	1,011
1997 .....	1,107	1,026	1,027	1,020	1,026	1,023	1,011
1998 .....	1,109	1,031	1,033	1,024	1,031	1,023	1,011
1999 .....	1,107	1,027	1,028	1,022	1,027	1,022	1,006
2000 .....	1,107	1,025	1,026	1,021	1,025	1,023	1,006
2001 .....	1,105	1,028	1,029	1,026	1,028	1,023	1,010
2002 .....	1,103	1,024	1,025	1,020	1,024	1,022	1,008
2003 .....	1,103	1,028	1,029	1,025	1,028	1,025	1,009
2004 .....	1,104	1,026	1,026	1,027	1,026	1,025	1,009
2005 .....	1,104	1,028	1,028	1,028	1,028	1,025	1,009
2006 .....	1,103	1,028	1,028	1,028	1,028	1,025	1,009
2007 .....	1,102	1,027	1,027	1,027	1,027	1,025	1,009
2008 .....	1,100	1,027	1,027	1,027	1,027	1,025	1,009
2009 .....	1,101	1,025	1,025	1,025	1,025	1,025	1,009
2010 .....	1,097	1,023	1,023	1,022	1,023	1,025	1,009
2011 .....	<sup>E</sup> 1,097	<sup>E</sup> 1,022	<sup>E</sup> 1,023	<sup>P</sup> 1,021	<sup>E</sup> 1,022	<sup>E</sup> 1,025	<sup>E</sup> 1,009
2012 .....	<sup>E</sup> 1,097	<sup>E</sup> 1,022	<sup>E</sup> 1,023	<sup>E</sup> 1,021	<sup>E</sup> 1,022	<sup>E</sup> 1,025	<sup>E</sup> 1,009

<sup>a</sup> Consumption factors are for natural gas, plus a small amount of supplemental gaseous fuels.

<sup>b</sup> Residential, commercial, industrial, and transportation sectors.

<sup>c</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

P=Preliminary. E=Estimate.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A5. Approximate Heat Content of Coal and Coal Coke**  
(Million Btu per Short Ton)

	Coal								Coal Coke	
	Production <sup>a</sup>	Waste Coal Supplied <sup>b</sup>	Consumption					Imports		Exports
			Residential and Commercial Sectors	Industrial Sector		Electric Power Sector <sup>d,e</sup>	Total			
				Coke Plants	Other <sup>c</sup>					
1973	23.376	NA	22.831	26.780	22.586	22.246	23.057	25.000	26.596	24.800
1974	23.072	NA	22.479	26.778	22.419	21.781	22.677	25.000	26.700	24.800
1975	22.897	NA	22.261	26.782	22.436	21.642	22.506	25.000	26.562	24.800
1976	22.855	NA	22.774	26.781	22.530	21.679	22.498	25.000	26.601	24.800
1977	22.597	NA	22.919	26.787	22.322	21.508	22.265	25.000	26.548	24.800
1978	22.248	NA	22.466	26.789	22.207	21.275	22.017	25.000	26.478	24.800
1979	22.454	NA	22.242	26.788	22.452	21.364	22.100	25.000	26.548	24.800
1980	22.415	NA	22.543	26.790	22.690	21.295	21.947	25.000	26.384	24.800
1981	22.308	NA	22.474	26.794	22.585	21.085	21.713	25.000	26.160	24.800
1982	22.239	NA	22.695	26.797	22.712	21.194	21.674	25.000	26.223	24.800
1983	22.052	NA	22.775	26.798	22.691	21.133	21.576	25.000	26.291	24.800
1984	22.010	NA	22.844	26.799	22.543	21.101	21.573	25.000	26.402	24.800
1985	21.870	NA	22.646	26.798	22.020	20.959	21.366	25.000	26.307	24.800
1986	21.913	NA	22.947	26.798	22.198	21.084	21.462	25.000	26.292	24.800
1987	21.922	NA	23.404	26.799	22.381	21.136	21.517	25.000	26.291	24.800
1988	21.823	NA	23.571	26.799	22.360	20.900	21.328	25.000	26.299	24.800
1989	21.765	<sup>b</sup> 10.391	23.650	26.800	22.347	<sup>d</sup> 20.898	21.307	25.000	26.160	24.800
1990	21.822	9.303	23.137	26.799	22.457	20.779	21.197	25.000	26.202	24.800
1991	21.681	10.758	23.114	26.799	22.460	20.730	21.120	25.000	26.188	24.800
1992	21.682	10.396	23.105	26.799	22.250	20.709	21.068	25.000	26.161	24.800
1993	21.418	10.638	22.994	26.800	22.123	20.677	21.010	25.000	26.335	24.800
1994	21.394	11.097	23.112	26.800	22.068	20.589	20.929	25.000	26.329	24.800
1995	21.326	11.722	23.118	26.800	21.950	20.543	20.880	25.000	26.180	24.800
1996	21.322	12.147	23.011	26.800	22.105	20.547	20.870	25.000	26.174	24.800
1997	21.296	12.158	22.494	26.800	22.172	20.518	20.830	25.000	26.251	24.800
1998	21.418	12.639	21.620	27.426	23.164	20.516	20.881	25.000	26.800	24.800
1999	21.070	12.552	23.880	27.426	22.489	20.490	20.818	25.000	26.081	24.800
2000	21.072	12.360	25.020	27.426	22.433	20.511	20.828	25.000	26.117	24.800
2001	<sup>a</sup> 20.772	12.169	24.909	27.426	22.622	20.337	20.671	25.000	25.998	24.800
2002	20.673	12.165	22.962	27.426	22.562	20.238	20.541	25.000	26.062	24.800
2003	20.499	12.360	22.242	27.425	22.468	20.082	20.387	25.000	25.972	24.800
2004	20.424	12.266	22.324	27.426	22.473	19.980	20.290	25.000	26.108	24.800
2005	20.348	12.093	22.342	26.279	22.178	19.988	20.246	25.000	25.494	24.800
2006	20.310	12.080	22.066	26.271	22.050	19.931	20.181	25.000	25.453	24.800
2007	20.340	12.090	22.069	26.329	22.371	19.909	20.168	25.000	25.466	24.800
2008	20.208	12.121	21.887	26.281	22.348	19.713	19.977	25.000	25.399	24.800
2009	19.963	12.076	22.059	26.334	21.893	19.521	19.742	25.000	25.633	24.800
2010	20.173	11.960	21.826	26.296	21.005	19.623	19.832	25.000	25.713	24.800
2011 <sup>P</sup>	20.136	11.604	20.724	26.300	20.588	19.370	19.583	25.000	25.645	24.800
2012 <sup>E</sup>	20.136	11.604	20.724	26.300	20.588	19.370	19.583	25.000	25.645	24.800

<sup>a</sup> Beginning in 2001, includes a small amount of refuse recovery (coal recaptured from a refuse mine, and cleaned to reduce the concentration of noncombustible materials).

<sup>b</sup> Waste coal (including fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste) consumed by the electric power and industrial sectors. Beginning in 1989, waste coal supplied is counted as a supply-side item to balance the same amount of waste coal included in "Consumption."

<sup>c</sup> Includes transportation. Excludes coal synfuel plants.

<sup>d</sup> Electricity-only and combined-heat-and-power (CHP) plants within the NAICS 22 category whose primary business is to sell electricity, or electricity and heat, to the public. Through 1988, data are for electric utilities only; beginning in 1989, data are for electric utilities and independent power producers.

<sup>e</sup> Electric power sector factors are for anthracite, bituminous coal, subbituminous coal, lignite, waste coal, and, beginning in 1998, coal synfuel.

P=Preliminary. E=Estimate. NA=Not available.

Note: The values in this table are for gross heat contents. See "Heat Content" in Glossary.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: See "Thermal Conversion Factor Source Documentation," which follows Table A6.

**Table A6. Approximate Heat Rates for Electricity, and Heat Content of Electricity**  
(Btu per Kilowatthour)

	Approximate Heat Rates <sup>a</sup> for Electricity Net Generation						Heat Content <sup>j</sup> of Electricity <sup>k</sup>
	Fossil Fuels <sup>b</sup>				Nuclear <sup>h</sup>	Noncombustible Renewable Energy <sup>g,i</sup>	
	Coal <sup>c</sup>	Petroleum <sup>d</sup>	Natural Gas <sup>e</sup>	Total Fossil Fuels <sup>f,g</sup>			
1973	NA	NA	NA	10,389	10,903	10,389	3,412
1974	NA	NA	NA	10,442	11,161	10,442	3,412
1975	NA	NA	NA	10,406	11,013	10,406	3,412
1976	NA	NA	NA	10,373	11,047	10,373	3,412
1977	NA	NA	NA	10,435	10,769	10,435	3,412
1978	NA	NA	NA	10,361	10,941	10,361	3,412
1979	NA	NA	NA	10,353	10,879	10,353	3,412
1980	NA	NA	NA	10,388	10,908	10,388	3,412
1981	NA	NA	NA	10,453	11,030	10,453	3,412
1982	NA	NA	NA	10,454	11,073	10,454	3,412
1983	NA	NA	NA	10,520	10,905	10,520	3,412
1984	NA	NA	NA	10,440	10,843	10,440	3,412
1985	NA	NA	NA	10,447	10,622	10,447	3,412
1986	NA	NA	NA	10,446	10,579	10,446	3,412
1987	NA	NA	NA	10,419	10,442	10,419	3,412
1988	NA	NA	NA	10,324	10,602	10,324	3,412
1989	NA	NA	NA	10,432	10,583	10,432	3,412
1990	NA	NA	NA	10,402	10,582	10,402	3,412
1991	NA	NA	NA	10,436	10,484	10,436	3,412
1992	NA	NA	NA	10,342	10,471	10,342	3,412
1993	NA	NA	NA	10,309	10,504	10,309	3,412
1994	NA	NA	NA	10,316	10,452	10,316	3,412
1995	NA	NA	NA	10,312	10,507	10,312	3,412
1996	NA	NA	NA	10,340	10,503	10,340	3,412
1997	NA	NA	NA	10,213	10,494	10,213	3,412
1998	NA	NA	NA	10,197	10,491	10,197	3,412
1999	NA	NA	NA	10,226	10,450	10,226	3,412
2000	NA	NA	NA	10,201	10,429	10,201	3,412
2001	10,378	10,742	10,051	10,333 <sup>b</sup>	10,443	10,333	3,412
2002	10,314	10,641	9,533	10,173	10,442	10,173	3,412
2003	10,297	10,610	9,207	10,241	10,421	10,241	3,412
2004	10,331	10,571	8,647	10,022	10,427	10,022	3,412
2005	10,373	10,631	8,551	9,999	10,436	9,999	3,412
2006	10,351	10,809	8,471	9,919	10,436	9,919	3,412
2007	10,375	10,794	8,403	9,884	10,485	9,884	3,412
2008	10,378	11,015	8,305	9,854	10,453	9,854	3,412
2009	10,414	10,923	8,160	9,760	10,460	9,760	3,412
2010	10,415	10,984	8,185	9,756	10,452	9,756	3,412
2011	E 10,415	E 10,984	E 8,185	E 9,756	E 10,452	E 9,756	3,412
2012	E 10,415	E 10,984	E 8,185	E 9,756	E 10,452	E 9,756	3,412

<sup>a</sup> The values in columns 1-6 of this table are for net heat rates. See "Heat Rate" in Glossary.

<sup>b</sup> Through 2000, heat rates are for fossil-fueled steam-electric plants at electric utilities. Beginning in 2001, heat rates are for all fossil-fueled plants at electric utilities and electricity-only independent power producers.

<sup>c</sup> Includes anthracite, bituminous coal, subbituminous coal, lignite, and, beginning in 2002, waste coal and coal synfuel.

<sup>d</sup> Includes distillate fuel oil, residual fuel oil, jet fuel, kerosene, petroleum coke, and waste oil.

<sup>e</sup> Includes natural gas and supplemental gaseous fuels.

<sup>f</sup> Includes coal, petroleum, natural gas, and, beginning in 2001, other gases (blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels).

<sup>g</sup> The fossil-fuels heat rate is used as the thermal conversion factor for electricity net generation from noncombustible renewable energy (hydro, geothermal, solar thermal, photovoltaic, and wind) to approximate the quantity of fossil fuels replaced by these sources. Through 2000, also used as the thermal conversion factor for wood and waste electricity net generation at electric utilities; beginning in 2001, Btu data for wood and waste at electric utilities are available from surveys.

<sup>h</sup> Used as the thermal conversion factor for nuclear electricity net generation.

<sup>i</sup> Technology-based geothermal heat rates are no longer used in Btu calculations in this report. For technology-based geothermal heat rates for 1960–2010, see the *Annual Energy Review 2010*, Table A6.

<sup>j</sup> See "Heat Content" in Glossary.

<sup>k</sup> The value of 3,412 Btu per kilowatthour is a constant. It is used as the thermal conversion factor for electricity retail sales, and electricity imports and exports.

E=Estimate. NA=Not Available.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: See "Thermal Conversion Factor Source Documentation," which follows this table.

# Thermal Conversion Factor Source Documentation

## Approximate Heat Content of Petro- leum and Natural Gas Plant Liquids

**Asphalt.** The U.S. Energy Information Administration (EIA) adopted the thermal conversion factor of 6.636 million British thermal units (Btu) per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Aviation Gasoline.** EIA adopted the thermal conversion factor of 5.048 million Btu per barrel as adopted by the Bureau of Mines from the Texas Eastern Transmission Corporation publication *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Butane.** EIA adopted the Bureau of Mines thermal conversion factor of 4.326 million Btu per barrel as published in the *California Oil World and Petroleum Industry*, First Issue, April 1942.

**Butane-Propane Mixture.** EIA adopted the Bureau of Mines calculation of 4.130 million Btu per barrel based on an assumed mixture of 60 percent butane and 40 percent propane. See **Butane** and **Propane**.

**Crude Oil Exports.** Assumed by EIA to be 5.800 million Btu per barrel or equal to the thermal conversion factor for crude oil produced in the United States. See **Crude Oil Production**.

**Crude Oil Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each type of crude oil imported weighted by the quantities imported. Thermal conversion factors for each type were calculated on a foreign country basis, by determining the average American Petroleum Institute (API) gravity of crude oil imported from each foreign country from Form ERA-60 in 1977 and converting average API gravity to average Btu content by using National Bureau of Standards, Miscellaneous Publication No. 97, *Thermal Properties of Petroleum Products*, 1933.

**Crude Oil Production.** EIA adopted the thermal conversion factor of 5.800 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Distillate Fuel Oil.** EIA adopted the Bureau of Mines thermal conversion factor of 5.825 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Ethane.** EIA adopted the Bureau of Mines thermal conversion factor of 3.082 million Btu per barrel as published in the *California Oil World and Petroleum Industry*, First Issue, April 1942.

**Ethane-Propane Mixture.** EIA calculation of 3.308 million Btu per barrel based on an assumed mixture of 70 percent ethane and 30 percent propane. See **Ethane** and **Propane**.

**Isobutane.** EIA adopted the Bureau of Mines thermal conversion factor of 3.974 million Btu per barrel as published in the *California Oil World and Petroleum Industry*, First Issue, April 1942.

**Jet Fuel, Kerosene-Type.** EIA adopted the Bureau of Mines thermal conversion factor of 5.670 million Btu per barrel for “Jet Fuel, Commercial” as published by the Texas Eastern Transmission Corporation in the report *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Jet Fuel, Naphtha-Type.** EIA adopted the Bureau of Mines thermal conversion factor of 5.355 million Btu per barrel for “Jet Fuel, Military” as published by the Texas Eastern Transmission Corporation in the report *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics.

**Kerosene.** EIA adopted the Bureau of Mines thermal conversion factor of 5.670 million Btu per barrel as reported in a Bureau of Mines internal memorandum, “Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950.”

**Liquefied Petroleum Gases Consumption.** Calculated annually by EIA as the average of the thermal conversion factors for all liquefied petroleum gases consumed (see Table A1) weighted by the quantities consumed. The component products of liquefied petroleum gases are ethane (including ethylene), propane (including propylene), normal butane (including butylene), butane-propane mixtures, ethane-propane mixtures, and isobutane. For 1973–1980, quantities consumed are from EIA, Energy Data Reports, “Petroleum Statement, Annual,” Table 1. For 1981 forward, quantities consumed are from EIA, *Petroleum Supply Annual*, Table 2.

**Lubricants.** EIA adopted the thermal conversion factor of 6.065 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Miscellaneous Products.** EIA adopted the thermal conversion factor of 5.796 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Motor Gasoline Consumption.** 1973–1993: EIA adopted the Bureau of Mines thermal conversion factor of 5.253 million Btu per barrel for “Gasoline, Motor Fuel” as published by the Texas Eastern Transmission Corporation in Appendix V of *Competition and Growth in American Energy Markets 1947–1985*, a 1968 release of historical and projected statistics. 1994 forward: EIA calculated national annual quantity-weighted average conversion factors for conventional, reformulated, and oxygenated motor gasolines (see Table A3). The factor for conventional motor gasoline is 5.253 million Btu per barrel, as used for

previous years. The factors for reformulated and oxygenated gasolines, both currently 5.150 million Btu per barrel, are based on data published in Environmental Protection Agency, Office of Mobile Sources, National Vehicle and Fuel Emissions Laboratory report EPA 420-F-95-003, "Fuel Economy Impact Analysis of Reformulated Gasoline." See **Fuel Ethanol (Denatured)**.

**Natural Gas Plant Liquids Production.** Calculated annually by EIA as the average of the thermal conversion factors for each natural gas plant liquid produced weighted by the quantities produced.

**Natural Gasoline.** EIA adopted the thermal conversion factor of 4.620 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

**Pentanes Plus.** EIA assumed the thermal conversion factor to be 4.620 million Btu or equal to that for natural gasoline. See **Natural Gasoline**.

**Petrochemical Feedstocks, Naphtha less than 401° F.** Assumed by EIA to be 5.248 million Btu per barrel, equal to the thermal conversion factor for special naphthas. See **Special Naphthas**.

**Petrochemical Feedstocks, Other Oils equal to or greater than 401° F.** Assumed by EIA to be 5.825 million Btu per barrel, equal to the thermal conversion factor for distillate fuel oil. See **Distillate Fuel Oil**.

**Petrochemical Feedstocks, Still Gas.** Assumed by EIA to be 6.000 million Btu per barrel, equal to the thermal conversion factor for still gas. See **Still Gas**.

**Petroleum Coke.** EIA adopted the thermal conversion factor of 6.024 million Btu per barrel as reported in Btu per short ton in the Bureau of Mines internal memorandum, "Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950." The Bureau of Mines calculated this factor by dividing 30.120 million Btu per short ton, as given in the referenced Bureau of Mines internal memorandum, by 5.0 barrels per short ton, as given in the Bureau of Mines Form 6-1300-M and successor EIA forms.

**Petroleum Consumption, Commercial Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the commercial sector weighted by the estimated quantities consumed by the commercial sector. The quantities of petroleum products consumed by the commercial sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/states/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/states/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Electric Power Sector.** Calculated annually by EIA as the average of the thermal

conversion factors for all petroleum products consumed by the electric power sector weighted by the quantities consumed by the electric power sector. Data are from Form EIA-923, "Power Plant Operations Report," and predecessor forms.

**Petroleum Consumption, Industrial Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the industrial sector weighted by the estimated quantities consumed by the industrial sector. The quantities of petroleum products consumed by the industrial sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/states/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/states/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Residential Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the residential sector weighted by the estimated quantities consumed by the residential sector. The quantities of petroleum products consumed by the residential sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/states/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/states/sep_use/notes/use_petrol.pdf).

**Petroleum Consumption, Total.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed weighted by the quantities consumed.

**Petroleum Consumption, Transportation Sector.** Calculated annually by EIA as the average of the thermal conversion factors for all petroleum products consumed by the transportation sector weighted by the estimated quantities consumed by the transportation sector. The quantities of petroleum products consumed by the transportation sector are estimated in the State Energy Data System—see documentation at [http://www.eia.gov/states/sep\\_use/notes/use\\_petrol.pdf](http://www.eia.gov/states/sep_use/notes/use_petrol.pdf).

**Petroleum Products Exports.** Calculated annually by EIA as the average of the thermal conversion factors for each petroleum product exported weighted by the quantities exported.

**Petroleum Products Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each petroleum product imported weighted by the quantities imported.

**Plant Condensate.** Estimated to be 5.418 million Btu per barrel by EIA from data provided by McClanahan Consultants, Inc., Houston, Texas.

**Propane.** EIA adopted the Bureau of Mines thermal conversion factor of 3.836 million Btu per barrel as published in the *California Oil World and Petroleum Industry*, First Issue, April 1942.

**Residual Fuel Oil.** EIA adopted the thermal conversion factor of 6.287 million Btu per barrel as reported in the

Bureau of Mines internal memorandum, "Bureau of Mines Standard Average Heating Values of Various Fuels, Adopted January 3, 1950."

**Road Oil.** EIA adopted the Bureau of Mines thermal conversion factor of 6.636 million Btu per barrel, which was assumed to be equal to that of asphalt (see **Asphalt**) and was first published by the Bureau of Mines in the *Petroleum Statement, Annual, 1970*.

**Special Naphthas.** EIA adopted the Bureau of Mines thermal conversion factor of 5.248 million Btu per barrel, which was assumed to be equal to that of the total gasoline (aviation and motor) factor and was first published in the *Petroleum Statement, Annual, 1970*.

**Still Gas.** EIA adopted the Bureau of Mines estimated thermal conversion factor of 6.000 million Btu per barrel, first published in the *Petroleum Statement, Annual, 1970*.

**Total Petroleum Exports.** Calculated annually by EIA as the average of the thermal conversion factors for crude oil and each petroleum product exported weighted by the quantities exported. See **Crude Oil Exports** and **Petroleum Products Exports**.

**Total Petroleum Imports.** Calculated annually by EIA as the average of the thermal conversion factors for each type of crude oil and petroleum product imported weighted by the quantities imported. See **Crude Oil Imports** and **Petroleum Products Imports**.

**Unfinished Oils.** EIA assumed the thermal conversion factor to be 5.825 million Btu per barrel or equal to that for distillate fuel oil (see **Distillate Fuel Oil**) and first published it in EIA's *Annual Report to Congress, Volume 3, 1977*.

**Unfractionated Stream.** EIA assumed the thermal conversion factor to be 5.418 million Btu per barrel or equal to that for plant condensate (see **Plant Condensate**) and first published it in EIA's *Annual Report to Congress, Volume 2, 1981*.

**Waxes.** EIA adopted the thermal conversion factor of 5.537 million Btu per barrel as estimated by the Bureau of Mines and first published in the *Petroleum Statement, Annual, 1956*.

## Approximate Heat Content of Biofuels

**Biodiesel.** EIA estimated the thermal conversion factor for biodiesel to be 5.359 million Btu per barrel, or 17,253 Btu per pound.

**Biodiesel Feedstock.** EIA used soybean oil input to the production of biodiesel (million Btu soybean oil per barrel biodiesel) as the factor to estimate total biomass inputs to the production of biodiesel. EIA assumed that 7.65 pounds

of soybean oil are needed to produce one gallon of biodiesel, and 5.433 million Btu of soybean oil are needed to produce one barrel of biodiesel. EIA also assumed that soybean oil has a gross heat content of 16,909 Btu per pound, or 5.483 million Btu per barrel.

**Ethanol (Undenatured).** EIA adopted the thermal conversion factor of 3.539 million Btu per barrel published in "Oxygenate Flexibility for Future Fuels," a paper presented by William J. Piel of the ARCO Chemical Company at the National Conference on Reformulated Gasolines and Clean Air Act Implementation, Washington, D.C., October 1991.

**Fuel Ethanol (Denatured).** 1981–2008: EIA used the 2009 factor. 2009 forward: Calculated by EIA as the annual quantity-weighted average of the thermal conversion factors for undenatured ethanol (3.539 million Btu per barrel), pentanes plus used as denaturant (4.620 million Btu per barrel), and conventional motor gasoline and motor gasoline blending components used as denaturant (5.253 million Btu per barrel). The quantity of ethanol consumed is from EIA's *Petroleum Supply Annual (PSA)* and *Petroleum Supply Monthly (PSM)*, Table 1, data for renewable fuels and oxygenate plant net production of fuel ethanol. The quantity of pentanes plus used as denaturant is from PSA/PSM, Table 1, data for renewable fuels and oxygenate plant net production of pentanes plus, multiplied by -1. The quantity of conventional motor gasoline and motor gasoline blending components used as denaturant is from PSA/PSM, Table 1, data for renewable fuels and oxygenate plant net production of conventional motor gasoline and motor gasoline blending components, multiplied by -1.

**Fuel Ethanol Feedstock.** EIA used corn input to the production of undenatured ethanol (million Btu corn per barrel undenatured ethanol) as the annual factor to estimate total biomass inputs to the production of undenatured ethanol. U.S. Department of Agriculture observed ethanol yields (gallons undenatured ethanol per bushel of corn) were 2.5 in 1980, 2.666 in 1998, 2.68 in 2002, and 2.764 in 2009; EIA estimated the ethanol yields in other years. EIA also assumed that corn has a gross heat content of 0.392 million Btu per bushel.

## Approximate Heat Content of Natural Gas

**Natural Gas Consumption, Electric Power Sector.** Calculated annually by EIA by dividing the heat content of natural gas consumed by the electric power sector by the quantity consumed. Data are from Form EIA-923, "Power Plant Operations Report," and predecessor forms.

**Natural Gas Consumption, End-Use Sectors.** Calculated annually by EIA by dividing the heat content of natural gas consumed by the end-use sectors (residential, commercial,

industrial, and transportation) by the quantity consumed. Data are from Form EIA-176, “Annual Report of Natural and Supplemental Gas Supply and Disposition.”

**Natural Gas Consumption, Total.** 1973–1979: EIA adopted the thermal conversion factor calculated annually by the American Gas Association (AGA) and published in *Gas Facts*, an AGA annual publication. 1980 forward: Calculated annually by EIA by dividing the total heat content of natural gas consumed by the total quantity consumed.

**Natural Gas Exports.** Calculated annually by EIA by dividing the heat content of natural gas exported by the quantity exported. For 1973–1995, data are from Form FPC-14, “Annual Report for Importers and Exporters of Natural Gas.” Beginning in 1996, data are from U.S. Department of Energy, Office of Fossil Energy, *Natural Gas Imports and Exports*.

**Natural Gas Imports.** Calculated annually by EIA by dividing the heat content of natural gas imported by the quantity imported. For 1973–1995, data are from Form FPC-14, “Annual Report for Importers and Exporters of Natural Gas.” Beginning in 1996, data are from U.S. Department of Energy, Office of Fossil Energy, *Natural Gas Imports and Exports*.

**Natural Gas Production, Dry.** Assumed by EIA to be equal to the thermal conversion factor for dry natural gas consumed. See **Natural Gas Consumption, Total**.

**Natural Gas Production, Marketed.** Calculated annually by EIA by dividing the heat content of dry natural gas produced (see **Natural Gas Production, Dry**) and natural gas plant liquids produced (see **Natural Gas Plant Liquids Production**) by the total quantity of marketed natural gas produced.

## Approximate Heat Content of Coal and Coal Coke

**Coal Coke Imports and Exports.** EIA adopted the Bureau of Mines estimate of 24.800 million Btu per short ton.

**Coal Consumption, Electric Power Sector.** Calculated annually by EIA by dividing the heat content of coal consumed by the electric power sector by the quantity consumed. Data are from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Coal Consumption, Industrial Sector, Coke Plants.** Calculated annually by EIA by dividing the heat content of coal consumed by coke plants by the quantity consumed. Data are from Form EIA-5, “Quarterly Coal Consumption and Quality Report—Coke Plants.”

**Coal Consumption, Industrial Sector, Other.** Calculated annually by EIA by dividing the heat content of coal

consumed by manufacturing plants by the quantity consumed. Data are from Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants.”

**Coal Consumption, Residential and Commercial Sectors.** Calculated annually by EIA by dividing the heat content of coal consumed by the residential and commercial sectors by the quantity consumed. Through 1999, data are from Form EIA-6, “Coal Distribution Report.” Beginning in 2000, data are for commercial combined-heat-and-power (CHP) plants from Form EIA-923, “Power Plant Operations Report,” and predecessor forms.

**Coal Consumption, Total.** Calculated annually by EIA by dividing the total heat content of coal consumed by all sectors by the total quantity consumed.

**Coal Exports.** Calculated annually by EIA by dividing the heat content of steam coal and metallurgical coal exported by the quantity exported. Data are from U.S. Department of Commerce, Bureau of the Census, “Monthly Report EM 545.”

**Coal Imports.** Assumed by EIA to be 25.000 million Btu per short ton.

**Coal Production.** Calculated annually by EIA to balance the heat content of coal supply (production and imports) and the heat content of coal disposition (exports, stock change, and consumption).

**Waste Coal Supplied.** Calculated annually by EIA by dividing the total heat content of waste coal supplied by the quantity supplied. For 1989–1997, data are from Form EIA-867, “Annual Nonutility Power Producer Report.” For 1998–2000, data are from Form EIA-860B, “Annual Electric Generator Report—Nonutility.” For 2001 forward, data are from Form EIA-3, “Quarterly Coal Consumption and Quality Report—Manufacturing Plants”; Form EIA-923, “Power Plant Operations Report”; and predecessor forms.

## Approximate Heat Rates for Electricity

**Electricity Net Generation, Coal.** 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for electric utilities and electricity-only independent power producers using anthracite, bituminous coal, subbituminous coal, lignite, and beginning in 2002, waste coal and coal synfuel.

**Electricity Net Generation, Natural Gas.** 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for electric utilities and electricity-only independent power producers using natural gas and supplemental gaseous fuels.



**Electricity Net Generation, Noncombustible Renewable Energy.** There is no generally accepted practice for measuring the thermal conversion rates for power plants that generate electricity from hydro, geothermal, solar thermal, photovoltaic, and wind energy sources. Therefore, EIA calculates a rate factor that is equal to the annual average heat rate factor for fossil-fueled power plants in the United States (see “Electricity Net Generation, Total Fossil Fuels”). By using that factor it is possible to evaluate fossil fuel requirements for replacing those sources during periods of interruption, such as droughts.

**Electricity Net Generation, Nuclear.** 1973–1984: Calculated annually by dividing the total heat content consumed in nuclear generating units by the total (net) electricity generated by nuclear generating units. The heat content and electricity generation were reported on Form FERC-1, “Annual Report of Major Electric Utilities, Licensees, and Others”; Form EIA-412, “Annual Report of Public Electric Utilities”; and predecessor forms. For 1982, the factors were published in EIA, *Historical Plant Cost and Annual Production Expenses for Selected Electric Plants 1982*, page 215. For 1983 and 1984, the factors were published in EIA, *Electric Plant Cost and Power Production Expenses 1991*, Table 13. 1985 forward: Calculated annually by EIA by using the heat rate data reported on Form EIA-860, “Annual Electric Generator Report” (and predecessor forms).

**Electricity Net Generation, Petroleum.** 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for electric utilities and electricity-only independent power producers using distillate fuel oil, residual fuel oil, jet fuel, kerosene, petroleum coke, and waste oil.

**Electricity Net Generation, Total Fossil Fuels.** 1973–1988: The weighted annual average heat rate for fossil-fueled steam-electric power plants in the United States, as published in EIA, *Electric Plant Cost and Power Production Expenses 1991*, Table 9. 1989–2000: Calculated annually by EIA by using the heat rate data reported on Form EIA-860, “Annual Electric Generator Report” (and predecessor forms); and net generation data reported on Form EIA-759, “Monthly Power Plant Report.” The computation includes data for all electric utility steam-electric plants using fossil fuels. 2001 forward: Calculated annually by EIA by using fuel consumption and net generation data reported on Form EIA-923, “Power Plant Operations Report,” and predecessor forms. The computation includes data for electric utilities and electricity-only independent power producers using coal, petroleum, natural gas, and other gases (blast furnace gas, propane gas, and other manufactured and waste gases derived from fossil fuels).

THIS PAGE INTENTIONALLY LEFT BLANK

# Appendix B

## Metric Conversion Factors, Metric Prefixes, and Other Physical Conversion Factors

---

Data presented in the *Monthly Energy Review* and in other U.S. Energy Information Administration publications are expressed predominately in units that historically have been used in the United States, such as British thermal units, barrels, cubic feet, and short tons. The metric conversion factors presented in Table B1 can be used to calculate the metric-unit equivalents of values expressed in U.S. Customary units. For example, 500 short tons are the equivalent of 453.6 metric tons (500 short tons x 0.9071847 metric tons/short ton = 453.6 metric tons).

In the metric system of weights and measures, the names of multiples and subdivisions of any unit may be derived

by combining the name of the unit with prefixes, such as deka, hecto, and kilo, meaning, respectively, 10, 100, 1,000, and deci, centi, and milli, meaning, respectively, one-tenth, one-hundredth, and one-thousandth. Common metric prefixes can be found in Table B2.

The conversion factors presented in Table B3 can be used to calculate equivalents in various physical units commonly used in energy analyses. For example, 10 barrels are the equivalent of 420 U.S. gallons (10 barrels x 42 gallons/barrel = 420 gallons).

**Table B1. Metric Conversion Factors**

Type of Unit	U.S. Unit		Equivalent in	Metric Units
<b>Mass</b>	1 short ton (2,000 lb)	=	0.907 184 7	metric tons (t)
	1 long ton	=	1.016 047	metric tons (t)
	1 pound (lb)	=	0.453 592 37 <sup>a</sup>	kilograms (kg)
	1 pound uranium oxide (lb U <sub>3</sub> O <sub>8</sub> )	=	0.384 647 <sup>b</sup>	kilograms uranium (kgU)
	1 ounce, avoirdupois (avdp oz)	=	28.349 52	grams (g)
<b>Volume</b>	1 barrel of oil (bbl)	=	0.158 987 3	cubic meters (m <sup>3</sup> )
	1 cubic yard (yd <sup>3</sup> )	=	0.764 555	cubic meters (m <sup>3</sup> )
	1 cubic foot (ft <sup>3</sup> )	=	0.028 316 85	cubic meters (m <sup>3</sup> )
	1 U.S. gallon (gal)	=	3.785 412	liters (L)
	1 ounce, fluid (fl oz)	=	29.573 53	milliliters (mL)
	1 cubic inch (in <sup>3</sup> )	=	16.387 06	milliliters (mL)
<b>Length</b>	1 mile (mi)	=	1.609 344 <sup>a</sup>	kilometers (km)
	1 yard (yd)	=	0.914 4 <sup>a</sup>	meters (m)
	1 foot (ft)	=	0.304 8 <sup>a</sup>	meters (m)
	1 inch (in)	=	2.54 <sup>a</sup>	centimeters (cm)
<b>Area</b>	1 acre	=	0.404 69	hectares (ha)
	1 square mile (mi <sup>2</sup> )	=	2.589 988	square kilometers (km <sup>2</sup> )
	1 square yard (yd <sup>2</sup> )	=	0.836 127 4	square meters (m <sup>2</sup> )
	1 square foot (ft <sup>2</sup> )	=	0.092 903 04 <sup>a</sup>	square meters (m <sup>2</sup> )
	1 square inch (in <sup>2</sup> )	=	6.451 6 <sup>a</sup>	square centimeters (cm <sup>2</sup> )
<b>Energy</b>	1 British thermal unit (Btu) <sup>c</sup>	=	1,055.055 852 62 <sup>a</sup>	joules (J)
	1 calorie (cal)	=	4.186 8 <sup>a</sup>	joules (J)
	1 kilowatthour (kWh)	=	3.6 <sup>a</sup>	megajoules (MJ)
<b>Temperature<sup>d</sup></b>	32 degrees Fahrenheit (°F)	=	0 <sup>a</sup>	degrees Celsius (°C)
	212 degrees Fahrenheit (°F)	=	100 <sup>a</sup>	degrees Celsius (°C)

<sup>a</sup>Exact conversion.

<sup>b</sup>Calculated by the U.S. Energy Information Administration.

<sup>c</sup>The Btu used in this table is the International Table Btu adopted by the Fifth International Conference on Properties of Steam, London, 1956.

<sup>d</sup>To convert degrees Fahrenheit (°F) to degrees Celsius (°C) exactly, subtract 32, then multiply by 5/9.

Notes: • Spaces have been inserted after every third digit to the right of the decimal for ease of reading. • Most metric units belong to the International System of Units (SI), and the liter, hectare, and metric ton are accepted for use with the SI units. For more information about the SI units, see <http://physics.nist.gov/cuu/Units/index.html>.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Sources: • General Services Administration, Federal Standard 376B, *Preferred Metric Units for General Use by the Federal Government* (Washington, DC, January 1993), pp. 9-11, 13, and 16. • U.S. Department of Commerce, National Institute of Standards and Technology, Special Publications 330, 811, and 814. • American National Standards Institute/Institute of Electrical and Electronic Engineers, ANSI/IEEE Std 268-1992, pp. 28 and 29.

**Table B2. Metric Prefixes**

Unit Multiple	Prefix	Symbol	Unit Subdivision	Prefix	Symbol
10 <sup>1</sup>	deka	da	10 <sup>-1</sup>	deci	d
10 <sup>2</sup>	hecto	h	10 <sup>-2</sup>	centi	c
10 <sup>3</sup>	kilo	k	10 <sup>-3</sup>	milli	m
10 <sup>6</sup>	mega	M	10 <sup>-6</sup>	micro	μ
10 <sup>9</sup>	giga	G	10 <sup>-9</sup>	nano	n
10 <sup>12</sup>	tera	T	10 <sup>-12</sup>	pico	p
10 <sup>15</sup>	peta	P	10 <sup>-15</sup>	femto	f
10 <sup>18</sup>	exa	E	10 <sup>-18</sup>	atto	a
10 <sup>21</sup>	zetta	Z	10 <sup>-21</sup>	zepto	z
10 <sup>24</sup>	yotta	Y	10 <sup>-24</sup>	yocto	y

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Source: U.S. Department of Commerce, National Institute of Standards and Technology, *The International System of Units (SI)*, NIST Special Publication 330, 1991 Edition (Washington, DC, August 1991), p.10.

**Table B3. Other Physical Conversion Factors**

Energy Source	Original Unit		Equivalent in Final Units
<b>Petroleum</b>	1 barrel (bbl)	=	42 <sup>a</sup> U.S. gallons (gal)
<b>Coal</b>	1 short ton	=	2,000 <sup>a</sup> pounds (lb)
	1 long ton	=	2,240 <sup>a</sup> pounds (lb)
	1 metric ton (t)	=	1,000 <sup>a</sup> kilograms (kg)
<b>Wood</b>	1 cord (cd)	=	1.25 <sup>b</sup> shorts tons
	1 cord (cd)	=	128 <sup>a</sup> cubic feet (ft <sup>3</sup> )

<sup>a</sup>Exact conversion.

<sup>b</sup>Calculated by the U.S. Energy Information Administration.

Web Page: <http://www.eia.gov/totalenergy/data/monthly/#appendices>.

Source: U.S. Department of Commerce, National Institute of Standards and Technology, *Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices*, NIST Handbook 44, 1994 Edition (Washington, DC, October 1993), pp. B-10, C-17 and C-21.

THIS PAGE INTENTIONALLY LEFT BLANK

# Glossary

**Alcohol:** The family name of a group of organic chemical compounds composed of carbon, hydrogen, and oxygen. The series of molecules vary in chain length and are composed of a **hydrocarbon** plus a hydroxyl group;  $\text{CH}_3\text{-(CH}_2)_n\text{-OH}$  (e.g., **methanol**, **ethanol**, and tertiary butyl alcohol). See **Fuel Ethanol**.

**Alternative Fuel:** Alternative fuels, for transportation applications, include the following: **methanol**; denatured **ethanol**, and other **alcohols**; fuel mixtures containing 85 percent or more by volume of methanol, denatured ethanol, and other alcohols with **motor gasoline** or other fuels; **natural gas**; **liquefied petroleum gas (propane)**; **hydrogen**; **coal-derived liquid fuels**; fuels (other than alcohol) derived from biological materials (**biofuels** such as soy **diesel fuel**); **electricity** (including electricity from **solar energy**); and "... any other fuel the Secretary determines, by rule, is substantially not **petroleum** and would yield substantial energy security benefits and substantial environmental benefits." The term "alternative fuel" does not include alcohol or other blended portions of primarily petroleum-based fuels used as **oxygenates** or extenders, i.e., **MTBE**, **ETBE**, other ethers, and the 10-percent ethanol portion of **gasohol**.

**Alternative-Fuel Vehicle (AFV):** A vehicle designed to operate on an **alternative fuel** (e.g., compressed **natural gas**, **methane** blend, or **electricity**). The vehicle could be either a dedicated vehicle designed to operate exclusively on alternative fuel or a nondedicated vehicle designed to operate on alternative fuel and/or a traditional fuel.

**Anthracite:** The highest rank of **coal**; used primarily for residential and commercial space heating. It is a hard, brittle, and black lustrous coal, often referred to as hard coal, containing a high percentage of fixed carbon and a low percentage of volatile matter. The moisture content of fresh-mined anthracite generally is less than 15 percent. The heat content of anthracite ranges from 22 to 28 million **Btu per short ton** on a moist, mineral-matter-free basis. The heat content of anthracite coal consumed in the United States averages 25 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter). *Note:* Since the 1980's, anthracite refuse or mine waste has been used for steam-electric power generation. This fuel typically has a heat content of 15 million Btu per ton or less.

**Anthropogenic:** Made or generated by a human or caused by human activity. The term is used in the context of global **climate change** to refer to gaseous emissions that are the result of human activities, as well as other potentially climate-altering activities, such as deforestation.

**Asphalt:** A dark-brown-to-black cement-like material containing bitumens as the predominant constituents obtained by petroleum processing. The definition includes crude asphalt as well as the following finished products: cements, fluxes, the asphalt content of emulsions (exclusive of water), and petroleum distillates blended with asphalt to make cutback asphalts.

**ASTM:** The American Society for Testing and Materials.

**Aviation Gasoline Blending Components:** Naphthas that will be used for blending or compounding into finished aviation gasoline (e.g., straight run gasoline, alkylate, reformate, benzene, toluene, and xylene). Excludes oxygenates (alcohols, ethers), butane, and pentanes plus.

**Aviation Gasoline, Finished:** A complex mixture of relatively volatile hydrocarbons with or without small quantities of additives, blended to form a fuel suitable for use in aviation reciprocating engines. Fuel specifications are provided in ASTM Specification D 910 and Military Specification MIL-G-5572. *Note:* Data on blending components are not counted in data on finished aviation gasoline.

**Barrel (Petroleum):** A unit of volume equal to 42 U.S. Gallons.

**Base Gas:** The volume of gas needed as a permanent inventory to maintain adequate underground storage reservoir pressures and deliverability rates throughout the withdrawal season. All native gas is included in the base gas volume.

**Biodiesel:** A fuel typically made from soybean, canola, or other vegetable oils; animal fats; and recycled grease. It can serve as a substitute for **petroleum-derived diesel fuel** or **distillate fuel oil**. For U.S. Energy Information Administration reporting, it is a fuel composed of mono-alkyl esters of long chain fatty acids derived from vegetable oils or animal fats, designated B100, and meeting the requirements of ASTM (American Society for Testing & Materials) D 6751.

**Biofuels:** Liquid fuels and blending components produced from **biomass** (plant) feedstocks, used primarily for transportation. See **Biodiesel** and **Fuel Ethanol**.

**Biogenic:** Produced by biological processes of living organisms. *Note:* EIA uses the term "biogenic" to refer only to organic nonfossil material of biological origin.

**Biomass:** Organic non-fossil material of biological origin constituting a **renewable energy** source. See **Biodiesel**,

## **Biofuels, Biomass Waste, Fuel Ethanol, and Wood and Wood-Derived Fuels.**

**Biomass Waste:** Organic non-fossil material of biological origin that is a byproduct or a discarded product. "Biomass waste" includes municipal solid waste from **biogenic** sources, landfill gas, sludge waste, agricultural crop byproducts, straw, and other **biomass** solids, liquids, and gases; but excludes **wood and wood-derived fuels** (including **black liquor**), **biofuels** feedstock, **biodiesel**, and **fuel ethanol**. **Note:** EIA "biomass waste" data also include energy crops grown specifically for energy production, which would not normally constitute waste.

**Bituminous Coal:** A dense **coal**, usually black, sometimes dark brown, often with well-defined bands of bright and dull material, used primarily as fuel in steam-electric power generation, with substantial quantities also used for heat and power applications in manufacturing and to make **coke**. Bituminous coal is the most abundant coal in active U.S. mining regions. Its moisture content usually is less than 20 percent. The heat content of bituminous coal ranges from 21 to 30 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of bituminous coal consumed in the United States averages 24 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Black Liquor:** A byproduct of the paper production process, alkaline spent liquor, that can be used as a source of energy. Alkaline spent liquor is removed from the digesters in the process of chemically pulping wood. After evaporation, the residual "black" liquor is burned as a fuel in a recovery furnace that permits the recovery of certain basic chemicals.

**British Thermal Unit (Btu):** The quantity of heat required to raise the temperature of 1 pound of liquid water by 1 degree Fahrenheit at the temperature at which water has its greatest density (approximately 39 degrees Fahrenheit). See **Heat Content**.

**Btu:** See **British Thermal Unit**.

**Btu Conversion Factor:** A factor for converting energy data between one unit of measurement and **British thermal units (Btu)**. Btu conversion factors are generally used to convert energy data from physical units of measure (such as **barrels**, **cubic feet**, or **short tons**) into the energy-equivalent measure of Btu. (See <http://www.eia.gov/totalenergy/data/monthly/#appendices> for further information on Btu conversion factors.)

**Butane:** A normally gaseous straight-chain or branched-chain hydrocarbon (C<sub>4</sub>H<sub>10</sub>). It is extracted from natural gas or refinery gas streams. It includes isobutane and normal butane and is designated in ASTM Specification D1835 and Gas Processors Association Specifications for commercial butane.

*Isobutane:* A normally gaseous branched-chain hydrocarbon. It is a colorless paraffinic gas that boils at a temperature of 10.9° F. It is extracted from natural gas or refinery gas streams.

*Normal Butane:* A normally gaseous straight-chain hydrocarbon. It is a colorless paraffinic gas that boils at a temperature of 31.1° F. It is extracted from natural gas or refinery gas streams.

**Butylene:** An olefinic hydrocarbon (C<sub>4</sub>H<sub>8</sub>) recovered from refinery processes.

**Capacity Factor:** The ratio of the electrical energy produced by a generating unit for a given period of time to the electrical energy that could have been produced at continuous full-power operation during the same period.

**Carbon Dioxide (CO<sub>2</sub>):** A colorless, odorless, non-poisonous gas that is a normal part of Earth's atmosphere. Carbon dioxide is a product of **fossil-fuel** combustion as well as other processes. It is considered a **greenhouse gas** as it traps heat (infrared energy) radiated by the Earth into the atmosphere and thereby contributes to the potential for **global warming**. The **global warming potential (GWP)** of other greenhouse gases is measured in relation to that of carbon dioxide, which by international scientific convention is assigned a value of one (1).

**Chained Dollars:** A measure used to express **real prices**. Real prices are those that have been adjusted to remove the effect of changes in the purchasing power of the dollar; they usually reflect buying power relative to a reference year. Prior to 1996, real prices were expressed in constant dollars, a measure based on the weights of goods and services in a single year, usually a recent year. In 1996, the U.S. Department of Commerce introduced the chained-dollar measure. The new measure is based on the average weights of goods and services in successive pairs of years. It is "chained" because the second year in each pair, with its weights, becomes the first year of the next pair. The advantage of using the chained-dollar measure is that it is more closely related to any given period and is therefore subject to less distortion over time.

**CIF:** See **Cost, Insurance, Freight**.

**Citygate:** A point or measuring station at which a distribution gas utility receives gas from a natural gas pipeline company or transmission system.

**Climate Change:** A term used to refer to all forms of climatic inconsistency, but especially to significant change from one prevailing climatic condition to another. In some cases, "climate change" has been used synonymously with the term "**global warming**"; scientists, however, tend to use the term in a wider sense inclusive of natural changes in climate, including climatic cooling.



**Coal:** A readily combustible black or brownish-black rock whose composition, including inherent moisture, consists of more than 50 percent by weight and more than 70 percent by volume of carbonaceous material. It is formed from plant remains that have been compacted, hardened, chemically altered, and metamorphosed by heat and pressure over geologic time. See **Anthracite**, **Bituminous Coal**, **Lignite**, **Subbituminous Coal**, **Waste Coal**, and **Coal Synfuel**.

**Coal Coke:** See **Coke**, **Coal**.

**Coal Stocks:** Coal quantities that are held in storage for future use and disposition. Note: When coal data are collected for a particular reporting period (month, quarter, or year), coal stocks are commonly measured as of the last day of the period.

**Coal Synfuel:** Coal-based solid fuel that has been processed by a **coal synfuel plant**; and coal-based fuels such as briquettes, pellets, or extrusions, which are formed from fresh or recycled coal and binding materials.

**Coal Synfuel Plant:** A plant engaged in the chemical transformation of coal into **coal synfuel**.

**Coke, Coal:** A solid carbonaceous residue derived from low-ash, low-sulfur bituminous coal from which the volatile constituents are driven off by baking in an oven at temperatures as high as 2,000° F so that the fixed carbon and residual ash are fused together. Coke is used as a fuel and as a reducing agent in smelting iron ore in a blast furnace. Coke (coal) has a heating value of 24.8 million Btu per ton.

**Coke, Petroleum:** A residue high in carbon content and low in hydrogen that is the final product of thermal decomposition in the condensation process in cracking. This product is reported as marketable coke or catalyst coke. The conversion is 5 barrels (42 U.S. gallons each) per short ton. Coke (petroleum) has a heating value of 6.024 million Btu per barrel.

**Coking Coal:** Bituminous coal suitable for making coke. See **Coke**, **Coal**.

**Combined-Heat-and-Power (CHP) Plant:** A plant designed to produce both heat and electricity from a single heat source. Note: This term is being used in place of the term "cogenerator" that was used by EIA in the past. CHP better describes the facilities because some of the plants included do not produce heat and power in a sequential fashion and, as a result, do not meet the legal definition of cogeneration specified in the Public Utility Regulatory Policies Act (PURPA).

**Commercial Sector:** An energy-consuming sector that consists of service-providing facilities and equipment of: businesses; Federal, State, and local governments; and other private and public organizations, such as religious,

social, or fraternal groups. The commercial sector includes institutional living quarters. It also includes sewage treatment facilities. Common uses of energy associated with this sector include space heating, water heating, air conditioning, lighting, refrigeration, cooking, and running a wide variety of other equipment. Note: This sector includes generators that produce electricity and/or useful thermal output primarily to support the activities of the above-mentioned commercial establishments. Various EIA programs differ in sectoral coverage-for more information see <http://www.eia.gov/neic/datadefinitions/Guideforwebcom.htm>. See **End-Use Sectors** and **Energy-Use Sectors**.

**Completion:** The installation of permanent equipment for the production of oil or gas. If a well is equipped to produce only oil or gas from one zone or reservoir, the definition of a well (classified as an oil well or gas well) and the definition of a completion are identical. However, if a well is equipped to produce oil and/or gas separately from more than one reservoir, a well is not synonymous with a completion.

**Conventional Gasoline:** Finished motor gasoline not included in the oxygenated or reformulated gasoline categories. Note: This category excludes reformulated gasoline blendstock for oxygenate blending (RBOB) as well as other blendstock.

**Conventional Hydroelectric Power:** Hydroelectric power generated from flowing water that is not created by **hydroelectric pumped storage**.

**Conversion Factor:** A factor for converting data between one unit of measurement and another (such as between **short tons** and **British thermal units**, or between **barrels** and gallons). (See <http://www.eia.gov/totalenergy/data/monthly/#appendices> and <http://www.eia.gov/totalenergy/data/monthly/#appendices> for further information on conversion factors.) See **Btu Conversion Factor** and **Thermal Conversion Factor**.

**Cost, Insurance, Freight (CIF):** A sales transaction in which the seller pays for the transportation and insurance of the goods to the port of destination specified by the buyer.

**Crude Oil:** A mixture of hydrocarbons that exists in liquid phase in natural underground reservoirs and remains liquid at atmospheric pressure after passing through surface separating facilities. Depending upon the characteristics of the crude stream, it may also include: 1) small amounts of hydrocarbons that exist in gaseous phase in natural underground reservoirs but are liquid at atmospheric pressure after being recovered from oil well (casinghead) gas in lease separators and are subsequently commingled with the crude stream without being separately measured. Lease condensate recovered as a liquid from natural gas wells in lease or field separation facilities and later mixed into the crude stream is also included; 2) small amounts of nonhydrocarbons produced with the oil, such as sulfur and

various metals; and 3) drip gases, and liquid hydrocarbons produced from tar sands, oil sands, gilsonite, and oil shale.

Liquids produced at natural gas processing plants are excluded. Crude oil is refined to produce a wide array of petroleum products, including heating oils; gasoline, diesel and jet fuels; lubricants; asphalt; ethane, propane, and butane; and many other products used for their energy or chemical content.

**Crude Oil F.O.B. Price:** The crude oil price actually charged at the oil-producing country's port of loading. Includes deductions for any rebates and discounts or additions of premiums, where applicable. It is the actual price paid with no adjustment for credit terms.

**Crude Oil (Including Lease Condensate):** A mixture of hydrocarbons that exists in liquid phase in underground reservoirs and remains liquid at atmospheric pressure after passing through surface separating facilities. Included are lease condensate and liquid hydrocarbons produced from tar sands, gilsonite, and oil shale. Drip gases are also included, but topped crude oil (residual oil) and other unfinished oils are excluded. Where identifiable, liquids produced at natural gas processing plants and mixed with crude oil are likewise excluded.

**Crude Oil Landed Cost:** The price of crude oil at the port of discharge, including charges associated with the purchase, transporting, and insuring of a cargo from the purchase point to the port of discharge. The cost does not include charges incurred at the discharge port (e.g., import tariffs or fees, wharfage charges, and demurrage).

**Crude Oil Refinery Input:** The total crude oil put into processing units at refineries.

**Crude Oil Stocks:** Stocks of crude oil and lease condensate held at refineries, in pipelines, at pipeline terminals, and on leases.

**Crude Oil Used Directly:** Crude oil consumed as fuel by crude oil pipelines and on crude oil leases.

**Crude Oil Well:** A well completed for the production of crude oil from one or more oil zones or reservoirs. Wells producing both crude oil and natural gas are classified as oil wells.

**Cubic Foot (Natural Gas):** A unit of volume equal to 1 cubic foot at a pressure base of 14.73 pounds standard per square inch absolute and a temperature base of 60° F.

**Degree-Day Normals:** Simple arithmetic averages of monthly or annual degree-days over a long period of time (usually the 30-year period 1961-1990). The averages may be simple degree-day normals or population-weighted degree-day normals.

**Degree-Days, Cooling (CDD):** A measure of how warm a location is over a period of time relative to a base temperature, most commonly specified as 65 degrees Fahrenheit. The measure is computed for each day by subtracting the base temperature (65 degrees) from the average of the day's high and low temperatures, with negative values set equal to zero. Each day's cooling degree-days are summed to create a cooling degree-day measure for a specified reference period. Cooling degree-days are used in energy analysis as an indicator of air conditioning energy requirements or use.

**Degree-Days, Heating (HDD):** A measure of how cold a location is over a period of time relative to a base temperature, most commonly specified as 65 degrees Fahrenheit. The measure is computed for each day by subtracting the average of the day's high and low temperatures from the base temperature (65 degrees), with negative values set equal to zero. Each day's heating degree-days are summed to create a heating degree-day measure for a specified reference period. Heating degree-days are used in energy analysis as an indicator of space heating energy requirements or use.

**Degree-Days, Population-Weighted:** Heating or cooling degree-days weighted by the population of the area in which the degree-days are recorded. To compute State population-weighted degree-days, each State is divided into from one to nine climatically homogeneous divisions, which are assigned weights based on the ratio of the population of the division to the total population of the State. Degree-day readings for each division are multiplied by the corresponding population weight for each division and those products are then summed to arrive at the State population-weighted degree-day figure. To compute national population-weighted degree-days, the Nation is divided into nine Census regions, each comprising from three to eight States, which are assigned weights based on the ratio of the population of the region to the total population of the Nation. Degree-day readings for each region are multiplied by the corresponding population weight for each region and those products are then summed to arrive at the national population-weighted degree-day figure.

**Denaturant: Petroleum,** typically **pentanes plus** or **conventional motor gasoline**, added to **fuel ethanol** to make it unfit for human consumption. Fuel ethanol is denatured, usually prior to transport from the ethanol production facility, by adding 2 to 5 volume percent denaturant. See **Fuel Ethanol** and **Fuel Ethanol Minus Denaturant**.

**Design Electrical Rating, Net:** The nominal net electrical output of a nuclear unit as specified by the electric utility for the purpose of plant design.

**Development Well:** A well drilled within the proved area of an oil or gas reservoir to the depth of a stratigraphic horizon known to be productive.

**Diesel Fuel:** A fuel composed of **distillate fuel oils** obtained in petroleum refining operation or blends of such distillate fuel oils with **residual fuel oil** used in motor vehicles. The boiling point and specific gravity are higher for diesel fuels than for gasoline.

**Direct Use:** Use of electricity that 1) is self-generated, 2) is produced by either the same entity that consumes the power or an affiliate, and 3) is used in direct support of a service or industrial process located within the same facility or group of facilities that house the generating equipment. Direct use is exclusive of **station use**.

**Distillate Fuel Oil:** A general classification for one of the **petroleum** fractions produced in conventional distillation operations. It includes **diesel fuels** and fuel oils. Products known as No. 1, No. 2, and No. 4 diesel fuel are used in on-highway diesel engines, such as those in trucks and automobiles, as well as off-highway engines, such as those in railroad locomotives and agricultural machinery. Products known as No. 1, No. 2, and No. 4 fuel oils are used primarily for space heating and **electricity generation**.

**Dry Hole:** An exploratory or development well found to be incapable of producing either oil or gas in sufficient quantities to justify completion as an oil or gas well.

**Dry Natural Gas Production:** See **Natural Gas (Dry) Production**.

**E85:** A fuel containing a mixture of 85 percent **ethanol** and 15 percent **motor gasoline**.

**Electric Power Plant:** A station containing prime movers, electric generators, and auxiliary equipment for converting mechanical, chemical, and/or fission energy into electric energy.

**Electric Power Sector:** An energy-consuming sector that consists of electricity-only and combined-heat-and-power (CHP) plants whose primary business is to sell electricity, or electricity and heat, to the public-i.e., North American Industry Classification System 22 plants. See also **Combined-Heat-and-Power (CHP) Plant**, **Electricity-Only Plant**, **Electric Utility**, and **Independent Power Producer**.

**Electric Utility:** Any entity that generates, transmits, or distributes **electricity** and recovers the cost of its generation, transmission or distribution assets and operations, either directly or indirectly, through cost-based rates set by a separate regulatory authority (e.g., State Public Service Commission), or is owned by a governmental unit or the consumers that the entity serves. Examples of these entities include: investor-owned entities, public power districts, public utility districts, municipalities, rural electric cooperatives, and State and Federal agencies. Electric utilities may have Federal Energy Regulatory Commission approval for interconnection agreements and wholesale trade tariffs covering either cost-of-service and/or market-based rates

under the authority of the Federal Power Act. See **Electric Power Sector**.

**Electrical System Energy Losses:** The amount of energy lost during generation, transmission, and distribution of electricity, including plant and unaccounted-for uses.

**Electricity:** A form of energy characterized by the presence and motion of elementary charged particles generated by friction, induction, or chemical change.

**Electricity Generation:** The process of producing electric energy, or the amount of electric energy produced by transforming other forms of energy, commonly expressed in **kilowatthours** (kWh) or megawatthours (Mwh).

**Electricity Generation, Gross:** The total amount of electric energy produced by generating units and measured at the generating terminal in **kilowatthours** (kWh) or megawatthours (MWh).

**Electricity Generation, Net:** The amount of **gross electricity generation** less **station use** (the **electric energy** consumed at the generating station(s) for station service or auxiliaries). *Note:* Electricity required for pumping at **hydroelectric pumped-storage** plants is regarded as electricity for station service and is deducted from gross generation.

**Electricity-Only Plant:** A plant designed to produce electricity only. See also **Combined-Heat-and-Power (CHP) Plant**.

**Electricity Retail Sales:** The amount of electricity sold to customers purchasing electricity for their own use and not for resale.

**End-Use Sectors:** The **residential**, **commercial**, **industrial**, and **transportation** sectors of the economy.

**Energy:** The capacity for doing work as measured by the capability of doing work (potential energy) or the conversion of this capability to motion (kinetic energy). Energy has several forms, some of which are easily convertible and can be changed to another form useful for work. Most of the world's convertible energy comes from fossil fuels that are burned to produce heat that is then used as a transfer medium to mechanical or other means in order to accomplish tasks. Electrical energy is usually measured in kilowatthours, while heat energy is usually measured in British thermal units.

**Energy Consumption:** The use of energy as a source of heat or power or as an input in the manufacturing process.

**Energy Service Provider:** An energy entity that provides service to a retail or end-use customer.

**Energy-Use Sectors:** A group of major energy-consuming components of U.S. society developed to measure and

analyze energy use. The sectors most commonly referred to in EIA are: **residential, commercial, industrial, transportation, and electric power.**

**Ethane:** A normally gaseous straight-chain hydrocarbon (C<sub>2</sub>H<sub>6</sub>). It is a colorless, paraffinic gas that boils at a temperature of -127.48° F. It is extracted from natural gas and refinery gas streams.

**Ethanol (C<sub>2</sub>H<sub>5</sub>OH):** A clear, colorless, flammable **alcohol**. Ethanol is typically produced biologically from **biomass** feedstocks such as agricultural crops and cellulosic residues from agricultural crops or wood. Ethanol can also be produced chemically from **ethylene**. See **Biomass, Fuel Ethanol, and Fuel Ethanol Minus Denaturant.**

**Ethylene:** An olefinic hydrocarbon (C<sub>2</sub>H<sub>4</sub>) recovered from refinery processes or petrochemical processes.

**Exploratory Well:** A well drilled to find and produce oil or gas in an area previously considered an unproductive area, to find a new reservoir in a known field (i.e., one previously found to be producing oil or gas in another reservoir), or to extend the limit of a known oil or gas reservoir.

**Exports:** Shipments of goods from within the 50 States and the District of Columbia to U.S. possessions and territories or to foreign countries.

**Extraction Loss:** The reduction in volume of natural gas due to the removal of natural gas liquid constituents, such as ethane, propane, and butane, at natural gas processing plants.

**Federal Energy Administration (FEA):** A predecessor of the U.S. Energy Information Administration.

**Federal Energy Regulatory Commission (FERC):** The Federal agency with jurisdiction over interstate electricity sales, wholesale electric rates, hydroelectric licensing, natural gas pricing, oil pipeline rates, and gas pipeline certification. FERC is an independent regulatory agency within the U.S. Department of Energy and is the successor to the Federal Power Commission.

**Federal Power Commission (FPC):** The predecessor agency of the Federal Energy Regulatory Commission. The Federal Power Commission was created by an Act of Congress under the Federal Water Power Act on June 10, 1920. It was charged originally with regulating the electric power and natural gas industries. It was abolished on September 30, 1977, when the U.S. Department of Energy was created. Its functions were divided between the U.S. Department of Energy and the Federal Energy Regulatory Commission, an independent regulatory agency.

**First Purchase Price:** The price for domestic crude oil reported by the company that owns the crude oil the first time it is removed from the lease boundary.

**Flared Natural Gas:** Natural gas burned in flares on the base site or at gas processing plants.

**F.O.B. (Free on Board):** A sales transaction in which the seller makes the product available for pick up at a specified port or terminal at a specified price and the buyer pays for the subsequent transportation and insurance.

**Footage Drilled:** Total footage for wells in various categories, as reported for any specified period, includes (1) the deepest total depth (length of well bores) of all wells drilled from the surface, (2) the total of all bypassed footage drilled in connection with reported wells, and (3) all new footage drilled for directional sidetrack wells. Footage reported for directional sidetrack wells does not include footage in the common bore, which is reported as footage for the original well. In the case of old wells drilled deeper, the reported footage is that which was drilled below the total depth of the old well.

**Former U.S.S.R.:** See **Union of Soviet Socialist Republics (U.S.S.R.).**

**Fossil Fuel:** An energy source formed in the Earth's crust from decayed organic material, such as **petroleum, coal, and natural gas.**

**Fossil-Fueled Steam-Electric Power Plant:** An electricity generation plant in which the prime mover is a turbine rotated by high-pressure steam produced in a boiler by heat from burning fossil fuels.

**Fuel Ethanol:** **Ethanol** intended for fuel use. Fuel ethanol in the United States must be anhydrous (less than 1 percent water). Fuel ethanol is denatured (made unfit for human consumption), usually prior to transport from the ethanol production facility, by adding 2 to 5 volume percent petroleum, typically **pentanes plus** or **conventional motor gasoline**. Fuel ethanol is used principally for blending in low concentrations with **motor gasoline** as an **oxygenate** or octane enhancer. In high concentrations, it is used to fuel **alternative-fuel vehicles** specially designed for its use. See **Alternative-Fuel Vehicle, Denaturant, E85, Ethanol, Fuel Ethanol Minus Denaturant, and Oxygenates.**

**Fuel Ethanol Minus Denaturant:** An unobserved quantity of anhydrous, **biomass-derived**, undenatured **ethanol** for fuel use. The quantity is obtained by subtracting the estimated **denaturant** volume from **fuel ethanol** volume. Fuel ethanol minus denaturant is counted as **renewable energy**, while denaturant is counted as **nonrenewable fuel**. See **Denaturant, Ethanol, Fuel Ethanol, Nonrenewable Fuels, Oxygenates, and Renewable Energy.**

**Full-Power Operation:** Operation of a nuclear generating unit at 100 percent of its design capacity. Full-power operation precedes commercial operation.

**Gasohol:** A blend of finished motor gasoline containing alcohol (generally **ethanol** but sometimes methanol) at a concentration between 5.7 percent and 10 percent by volume. See **Motor Gasoline, Oxygenated**.

**Gas Well:** A well completed for the production of natural gas from one or more gas zones or reservoirs. (Wells producing both crude oil and natural gas are classified as oil wells.)

**Geothermal Energy:** Hot water or steam extracted from geothermal reservoirs in the earth's crust and used for geothermal heat pumps, water heating, or electricity generation.

**Global Warming:** An increase in the near-surface temperature of the Earth. Global warming has occurred in the distant past as the result of natural influences, but the term is today most often used to refer to the warming some scientists predict will occur as a result of increased **anthropogenic** emissions of **greenhouse gases**. See **Climate Change**.

**Global Warming Potential (GWP):** An index used to compare the relative radiative forcing of different gases without directly calculating the changes in atmospheric concentrations. GWPs are calculated as the ratio of the radiative forcing that would result from the emission of one kilogram of a **greenhouse gas** to that from the emission of one kilogram of **carbon dioxide** over a fixed period of time, such as 100 years.

**Greenhouse Gases:** Those gases, such as water vapor, **carbon dioxide**, nitrous oxide, **methane**, hydrofluorocarbons (HFCs), perfluorocarbons (PFCs) and sulfur hexafluoride, that are transparent to solar (short-wave) radiation but opaque to long-wave (infrared) radiation, thus preventing long-wave radiant energy from leaving Earth's atmosphere. The net effect is a trapping of absorbed radiation and a tendency to warm the planet's surface.

**Gross Domestic Product (GDP):** The total value of goods and services produced by labor and property located in the United States. As long as the labor and property are located in the United States, the supplier (that is, the workers and, for property, the owners) may be either U.S. residents or residents of foreign countries.

**GT/IC:** Gas turbine and internal combustion plants.

**Heat Content:** The amount of heat energy available to be released by the transformation or use of a specified physical unit of an energy form (e.g., a ton of coal, a barrel of oil, a kilowatthour of electricity, a cubic foot of natural gas, or a pound of steam). The amount of heat energy is commonly expressed in **British thermal units (Btu)**. *Note:* Heat content of combustible energy forms can be expressed in terms of either gross heat content (higher or upper heating value) or net heat content (lower heating value), depending upon whether or not the available heat energy includes or

excludes the energy used to vaporize water (contained in the original energy form or created during the combustion process). The U.S. Energy Information Administration typically uses gross heat content values.

**Heat Rate:** A measure of generating station thermal efficiency commonly stated as **Btu per kilowatthour**. *Note:* Heat rates can be expressed as either gross or net heat rates, depending whether the electricity output is gross or net generation. Heat rates are typically expressed as net heat rates.

**Hydrocarbon:** An organic chemical compound of hydrogen and carbon in the gaseous, liquid, or solid phase. The molecular structure of hydrocarbon compounds varies from the simplest (methane, the primary constituent of natural gas) to the very heavy and very complex.

**Hydroelectric Power:** The production of electricity from the kinetic energy of falling water.

**Hydroelectric Power Plant:** A plant in which the turbine generators are driven by falling water.

**Hydroelectric Pumped Storage:** Hydroelectricity that is generated during peak load periods by using water previously pumped into an elevated storage reservoir during off-peak periods when excess generating capacity is available to do so. When additional generating capacity is needed, the water can be released from the reservoir through a conduit to turbine generators located in a power plant at a lower level.

**Hydrogen (H):** The lightest of all gases, hydrogen occurs chiefly in combination with oxygen in water. It also exists in acids, bases, **alcohols**, **petroleum**, and other **hydrocarbons**.

**Imports:** Receipts of goods into the 50 States and the District of Columbia from U.S. possessions and territories or from foreign countries.

**Independent Power Producer:** A corporation, person, agency, authority, or other legal entity or instrumentality that owns or operates facilities for the generation of electricity for use primarily by the public, and that is not an **electric utility**.

**Industrial Sector:** An **energy-consuming** sector that consists of all facilities and equipment used for producing, processing, or assembling goods. The industrial sector encompasses the following types of activity: manufacturing (**NAICS** codes 31-33); agriculture, forestry, fishing and hunting (**NAICS** code 11); mining, including oil and gas extraction (**NAICS** code 21); and construction (**NAICS** code 23). Overall energy use in this sector is largely for process heat and cooling and powering machinery, with lesser amounts used for facility heating, air conditioning, and lighting. Fossil fuels are also used as raw material inputs to manufactured products. *Note:* This sector includes **generators** that produce **electricity** and/or **useful thermal output** primarily to support the

above-mentioned industrial activities. Various EIA programs differ in sectoral coverage—for more information see

<http://www.eia.gov/neic/datadefinitions/Guideforwebind.htm>. See **End-Use Sectors** and **Energy-Use Sectors**.

**Injections (Natural Gas):** Natural gas injected into storage reservoirs.

**Isobutane:** A normally gaseous branch-chain hydrocarbon. It is a colorless paraffinic gas that boils at a temperature of 10.9° F. It is extracted from natural gas or refinery gas streams. See **Butane**.

**Isobutylene:** An olefinic hydrocarbon recovered from refinery processes or petrochemical processes.

**Isopentane:** A saturated branched-chain hydrocarbon obtained by fractionation of natural gasoline or isomerization of normal pentane.

**Jet Fuel:** A refined petroleum product used in jet aircraft engines. It includes kerosene-type jet fuel and naphtha-type jet fuel.

**Jet Fuel, Kerosene-Type:** A kerosene-based product with a maximum distillation temperature of 400° F at the 10-percent recovery point and a final maximum boiling point of 572° F. Fuel specifications are provided in ASTM Specification D 1655 and Military Specifications MIL-T-5624P and MIL-T-83133D (Grades JP-5 and JP-8). It is used primarily for commercial turbojet and turboprop aircraft engines.

**Jet Fuel, Naphtha-Type:** A fuel in the heavy naphtha boiling range, with an average gravity of 52.8 degrees API, 20 to 90 percent distillation temperatures of 290° to 470° F and meeting Military Specification MIL-T-5624L (Grade JP-4). It is used by the military for turbojet and turboprop engines.

**Kerosene:** A petroleum distillate having a maximum distillation temperature of 401° F at the 10-percent recovery point, a final boiling point of 572° F, and a minimum flash point of 100° F. Included are the two grades designated in ASTM D3699 (No. 1-K and No. 2-K) and all grades of kerosene called range or stove oil. Kerosene is used in space heaters, cook stoves, and water heaters; it is suitable for use as an illuminant when burned in wick lamps.

**Kilowatt:** A unit of electrical power equal to 1,000 watts.

**Kilowatthour (kWh):** A measure of electricity defined as a unit of work or energy, measured as 1 kilowatt (1,000 watts) of power expended for 1 hour. One kilowatthour is equivalent to 3,412 Btu. See **Watthour**.

**Landed Costs:** The dollar-per-barrel price of crude oil at the port of discharge. Included are the charges associated

with the purchase, transporting, and insuring of a cargo from the purchase point to the port of discharge. Not included are charges incurred at the discharge port (e.g., import tariffs or fees, wharfage charges, and demurrage charges).

**Lease and Plant Fuel:** Natural gas used in well, field, and lease operations (such as gas used in drilling operations, heaters, dehydrators, and field compressors) and used as fuel in natural gas processing plants.

**Lease Condensate:** A mixture consisting primarily of pentanes and heavier hydrocarbons, which is recovered as a liquid from natural gas in lease or field separation facilities. Note: This category excludes natural gas liquids, such as butane and propane, which are recovered at natural gas processing plants or facilities.

**Lignite:** The lowest rank of coal, often referred to as brown coal, used almost exclusively as fuel for steam-electric power generation. It is brownish-black and has a high inherent moisture content, sometimes as high as 45 percent. The heat content of lignite ranges from 9 to 17 million Btu per short ton on a moist, mineral-matter-free basis. The heat content of lignite consumed in the United States averages 13 million Btu per short ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Liquefied Natural Gas (LNG):** Natural gas (primarily methane) that has been liquefied by reducing its temperature to -260° F at atmospheric pressure.

**Liquefied Petroleum Gases (LPG):** Ethane, ethylene, propane, propylene, normal butane, butylene, and isobutane produced at refineries or natural gas processing plants, including plants that fractionate new natural gas plant liquids.

**Low-Power Testing:** The period of time between a nuclear generating unit's initial fuel loading date and the issuance of its operating (full-power) license. The maximum level of operation during that period is 5 percent of the unit's design thermal rating.

**Lubricants:** Substances used to reduce friction between bearing surfaces or as process materials either incorporated into other materials used as processing aids in the manufacturing of other products or as carriers of other materials. Petroleum lubricants may be produced either from distillates or residues. Other substances may be added to impart or improve certain required properties. Excluded are byproducts of lubricating oil refining, such as aromatic extracts derived from solvent extraction or tars derived from deasphalting. Included are all grades of lubricating oils from spindle oil to cylinder oil and those used in greases. Lubricant categories are paraffinic and naphthenic.

**Marketed Production (Natural Gas):** Gross withdrawals less gas used for repressuring, quantities vented and

flared, and nonhydrocarbon gases removed in treating or processing operations. Includes all quantities of gas used in field and processing operations.

**Methane:** A colorless, flammable, odorless, hydrocarbon gas (CH<sub>4</sub>) that is the principal constituent of natural gas. It is also an important source of hydrogen in various industrial processes.

**Methyl Tertiary Butyl Ether (MTBE):** An ether, (CH<sub>3</sub>)<sub>3</sub>COCH<sub>3</sub>, intended for motor gasoline blending. See **Oxygenates**.

**Methanol:** A light, volatile alcohol (CH<sub>3</sub>OH) eligible for motor gasoline blending. See **Oxygenates**.

**Miscellaneous Petroleum Products:** All finished petroleum products not classified elsewhere—for example, petrolatum, lube refining byproducts (aromatic extracts and tars), absorption oils, ram-jet fuel, petroleum rocket fuels, synthetic natural gas feedstocks, and specialty oils.

**Motor Gasoline Blending:** Mechanical mixing of **motor gasoline blending components** and **oxygenates** as required, to produce finished motor gasoline. Finished motor gasoline may be further mixed with other motor gasoline blending components or oxygenates, resulting in increased volumes of finished motor gasoline and/or changes in the formulation of finished motor gasoline (e.g., conventional motor gasoline mixed with MTBE to produce oxygenated motor gasoline).

**Motor Gasoline Blending Components:** Naphtha (e.g., straight-run gasoline, alkylate, reformate, benzene, toluene, xylene) used for blending or compounding into finished motor gasoline. These components include reformulated gasoline blendstock (RBOB) but exclude oxygenates (alcohols, ethers), butane, and pentanes plus. *Note:* oxygenates are reported as individual components and are included in the total for other hydrocarbons, hydrogens, and oxygenates.

**Motor Gasoline, Finished:** A complex mixture of relatively volatile hydrocarbons with or without small quantities of additives, blended to form a fuel suitable for use in spark-ignition. Motor gasoline, as defined in ASTM Specification D-4814 or Federal Specification VV-G-1690C, is characterized as having a boiling range of 122°F to 158°F at the 10-percent recovery point to 365°F to 374°F at the 90-percent recovery point. “Motor gasoline” includes conventional gasoline, all types of oxygenated gasoline including gasohol, and reformulated gasoline, but excludes aviation gasoline. *Note:* Volumetric data on blending components, as well as oxygenates, are not counted in data on finished motor gasoline until the blending components are blended into the gasoline.

**Motor Gasoline Grades:** The classification of gasoline by octane ratings. Each type of gasoline (conventional, oxygenated, and reformulated) is classified by three

grades: regular, midgrade, and premium. *Note:* Gasoline sales are reported by grade in accordance with their classification at the time of sale. In general, automotive octane requirements are lower at high altitudes. Therefore, in some areas of the United States, such as the Rocky Mountain States, the octane ratings for the gasoline grades may be 2 or more octane points lower.

**Regular Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than or equal to 85 and less than 88. *Note:* Octane requirements may vary by altitude. See **Motor Gasoline Grades**.

**Midgrade Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than or equal to 88 and less than or equal to 90. *Note:* Octane requirements may vary by altitude. See **Motor Gasoline Grades**.

**Premium Gasoline:** Gasoline having an antiknock index, i.e., octane rating, greater than 90. *Note:* Octane requirements may vary by altitude. See **Motor Gasoline Grades**.

**Motor Gasoline, Oxygenated:** Finished motor gasoline, other than reformulated gasoline, having an oxygen content of 2.7 percent or higher by weight and required by the U.S. Environmental Protection Agency (EPA) to be sold in areas designated by EPA as carbon monoxide (CO) nonattainment areas. *Note:* Oxygenated gasoline excludes oxygenated fuels program reformulated gasoline (OPRG) and reformulated gasoline blendstock for oxygenate blending (RBOB). Data on gasohol that has at least 2.7 percent oxygen, by weight, and is intended for sale inside CO nonattainment areas are included in data on oxygenated gasoline. Other data on gasohol are included in data on conventional gasoline.

**Motor Gasoline, Reformulated:** Finished motor gasoline formulated for use in motor vehicles, the composition and properties of which meet the requirements of the reformulated gasoline regulations promulgated by the U.S. Environmental Protection Agency under Section 211(k) of the Clean Air Act. *Note:* This category includes oxygenated fuels program reformulated gasoline (OPRG) but excludes reformulated gasoline blendstock for oxygenate blending (RBOB).

**Motor Gasoline Retail Prices:** Motor gasoline prices calculated each month by the Bureau of Labor Statistics (BLS) in conjunction with the construction of the Consumer Price Index (CPI). Those prices are collected in 85 urban areas selected to represent all urban consumers—about 80 percent of the total U.S. population. The service stations are selected initially, and on a replacement basis, in such a way that they represent the purchasing habits of the CPI population. Service stations in the current sample include those providing all types of service (i.e., full-, mini-, and self-service).

**Motor Gasoline (Total):** For stock level data, a sum including finished motor gasoline stocks plus stocks of

motor gasoline blending components but excluding stocks of oxygenates.

**MTBE:** See **Methyl Tertiary Butyl Ether**.

**NAICS (North American Industry Classification System):** A coding system developed jointly by the United States, Canada, and Mexico to classify businesses and industries according to the type of economic activity in which they are engaged. NAICS replaces the Standard Industrial Classification (SIC) codes. For additional information on NAICS, go to <http://www.census.gov/eos/www/naics/>.

**Naphtha:** A generic term applied to a petroleum fraction with an approximate boiling range between 122 and 400° F.

**Natural Gas:** A gaseous mixture of hydrocarbon compounds, primarily methane, used as a fuel for electricity generation and in a variety of ways in buildings, and as raw material input and fuel for industrial processes.

**Natural Gas, Dry:** Natural gas which remains after: 1) the liquefiable hydrocarbon portion has been removed from the gas stream (i.e., gas after lease, field, and/or plant separation); and 2) any volumes of nonhydrocarbon gases have been removed where they occur in sufficient quantity to render the gas unmarketable. *Note:* Dry natural gas is also known as consumer-grade natural gas. The parameters for measurement are cubic feet at 60 degrees Fahrenheit and 14.73 pounds per square inch absolute.

**Natural Gas (Dry) Production:** The process of producing consumer-grade natural gas. Natural gas withdrawn from reservoirs is reduced by volumes used at the production (lease) site and by processing losses. Volumes used at the production site include 1) the volume returned to reservoirs in cycling, repressuring of oil reservoirs, and conservation operations; and 2) gas vented and flared. Processing losses include 1) nonhydrocarbon gases (e.g., water vapor, carbon dioxide, helium, hydrogen sulfide, and nitrogen) removed from the gas stream; and 2) gas converted to liquid form, such as lease condensate and plant liquids. Volumes of dry gas withdrawn from gas storage reservoirs are not considered part of production. Dry natural gas production equals marketed production less extraction loss.

**Natural Gas Marketed Production:** Gross withdrawals of natural gas from production reservoirs, less gas used for reservoir repressuring; nonhydrocarbon gases removed in treating and processing operations; and quantities vented and flared.

**Natural Gas Plant Liquids (NGPL):** Natural gas liquids recovered from natural gas in processing plants and, in some situations, from natural gas field facilities, as well as those extracted by fractionators. Natural gas plant

liquids are defined according to the published specifications of the Gas Processors Association and the American Society for Testing and Material as follows: ethane, propane, normal butane, isobutane, pentanes plus, and other products from natural gas processing plants (i.e., products meeting the standards for finished petroleum products produced at natural gas processing plants, such as finished motor gasoline, finished aviation gasoline, special naphthas, kerosene, distillate fuel oil, and miscellaneous products).

**Natural Gas Wellhead Price:** The wellhead price of natural gas is calculated by dividing the total reported value at the wellhead by the total quantity produced as reported by the appropriate agencies of individual producing States and the U.S. Minerals Management Service. The price includes all costs prior to shipment from the lease, including gathering and compression costs, in addition to State production, severance, and similar charges.

**Natural Gasoline:** A mixture of hydrocarbons (mostly pentanes and heavier) extracted from natural gas that meets vapor pressure, end-point, and other specifications for natural gasoline set by the Gas Processors Association. Includes isopentane, which is a saturated branch-chain hydrocarbon obtained by fractionation of natural gasoline or isomerization of normal pentane.

**Net Summer Capacity:** The maximum output, commonly expressed in **kilowatts** (kW) or **megawatts** (MW), that generating equipment can supply to system load, as demonstrated by a multi-hour test, at the time of summer peak demand (period of June 1 through September 30). This output reflects a reduction in capacity due to electricity use for station service or auxiliaries.

**Neutral Zone:** A 6,200 square-mile area shared equally between Kuwait and Saudi Arabia under a 1992 agreement. The Neutral Zone contains an estimated 5 billion barrels of oil and 8 trillion cubic feet of natural gas.

**Nominal Dollars:** A measure used to express **nominal price**.

**Nominal Price:** The price paid for a product or service at the time of the transaction. Nominal prices are those that have not been adjusted to remove the effect of changes in the purchasing power of the dollar; they reflect buying power in the year in which the transaction occurred.

**Non-Biomass Waste:** Material of non-biological origin that is a byproduct or a discarded product. "Non-biomass waste" includes municipal solid waste from non-biogenic sources, such as plastics, and tire-derived fuels.

**Nonhydrocarbon Gases:** Typical nonhydrocarbon gases that may be present in reservoir natural gas are carbon dioxide, helium, hydrogen sulfide, and nitrogen.



**Nonrenewable Fuels:** Fuels that cannot be easily made or "renewed," such as **crude oil**, **natural gas**, and **coal**.

**Nuclear Electric Power (Nuclear Power):** Electricity generated by the use of the thermal energy released from the fission of nuclear fuel in a reactor.

**Nuclear Electric Power Plant:** A single-unit or multiunit facility in which heat produced in one or more reactors by the fissioning of nuclear fuel is used to drive one or more steam turbines.

**Nuclear Reactor:** An apparatus in which a nuclear fission chain reaction can be initiated, controlled, and sustained at a specific rate. A reactor includes fuel (fissionable material), moderating material to control the rate of fission, a heavy-walled pressure vessel to house reactor components, shielding to protect personnel, a system to conduct heat away from the reactor, and instrumentation for monitoring and controlling the reactor's systems.

**OECD:** See **Organization for Economic Cooperation and Development**.

**Offshore:** That geographic area that lies seaward of the coastline. In general, the coastline is the line of ordinary low water along with that portion of the coast that is in direct contact with the open sea or the line marking the seaward limit of inland water.

**Oil:** See **Crude Oil**.

**OPEC:** See **Organization of the Petroleum Exporting Countries**.

**Operable Unit (Nuclear):** In the United States, a nuclear generating unit that has completed low-power testing and been issued a full-power operating license by the Nuclear Regulatory Commission, or equivalent permission to operate.

**Organization for Economic Cooperation and Development (OECD):** An international organization helping governments tackle the economic, social and governance challenges of a globalized economy. Its membership comprises about 30 member countries. With active relationships with some 70 other countries, non-governmental organizations (NGOs) and civil society, it has a global reach. For details about the organization, see <http://www.oecd.org>.

**Organization of the Petroleum Exporting Countries (OPEC):** An intergovernmental organization whose stated objective is to "coordinate and unify the petroleum policies of member countries." It was created at the Baghdad Conference on September 10–14, 1960. Current members (with years of membership) include Algeria (1969–present), Angola (2007–present), Ecuador (1973–1992 and 2007–present), Iran (1960–present), Iraq (1960–present), Kuwait (1960–present), Libya (1962–present), Nigeria

(1971–present), Qatar (1961–present), Saudi Arabia (1960–present), United Arab Emirates (1967–present), and Venezuela (1960–present). Countries no longer members of OPEC include Gabon (1975–1994) and Indonesia (1962–2008).

**Oxygenates:** Substances which, when added to gasoline, increase the amount of oxygen in that gasoline blend. **Ethanol**, **Methyl Tertiary Butyl Ether (MTBE)**, **Ethyl Tertiary Butyl Ether (ETBE)**, and **methanol** are common oxygenates.

**PAD Districts:** Petroleum Administration for Defense Districts. Geographic aggregations of the 50 States and the District of Columbia into five districts for the Petroleum Administration for Defense in 1950. The districts were originally instituted for economic and geographic reasons as Petroleum Administration for War (PAW) Districts, which were established in 1942.

**Pentanes Plus:** A mixture of hydrocarbons, mostly pentanes and heavier, extracted from natural gas. Includes isopentane, natural gasoline, and plant condensate.

**Petrochemical Feedstocks:** Chemical feedstocks derived from petroleum principally for the manufacture of chemicals, synthetic rubber, and a variety of plastics.

**Petroleum:** A broadly defined class of liquid hydrocarbon mixtures. Included are crude oil, lease condensate, unfinished oils, refined products obtained from the processing of crude oil, and natural gas plant liquids. Note: Volumes of finished petroleum products include nonhydrocarbon compounds, such as additives and detergents, after they have been blended into the products.

**Petroleum Coke:** See **Coke**, **Petroleum**.

**Petroleum Consumption:** See **Products Supplied (Petroleum)**.

**Petroleum Imports:** Imports of petroleum into the 50 States and the District of Columbia from foreign countries and from Puerto Rico, the Virgin Islands, and other U.S. territories and possessions. Included are imports for the Strategic Petroleum Reserve and withdrawals from bonded warehouses for onshore consumption, offshore bunker use, and military use. Excluded are receipts of foreign petroleum into bonded warehouses and into U.S. territories and U.S. Foreign Trade Zones.

**Petroleum Products:** Products obtained from the processing of crude oil (including lease condensate), natural gas, and other hydrocarbon compounds. Petroleum products include unfinished oils, liquefied petroleum gases, pentanes plus, aviation gasoline, motor gasoline, naphtha-type jet fuel, kerosene-type jet fuel, kerosene, distillate fuel oil, residual fuel oil, petrochemical feedstocks, special naphthas,

lubricants, waxes, petroleum coke, asphalt, road oil, still gas, and miscellaneous products.

**Petroleum Stocks, Primary:** For individual products, quantities that are held at refineries, in pipelines, and at bulk terminals that have a capacity of 50,000 barrels or more, or that are in transit thereto. Stocks held by product retailers and resellers, as well as tertiary stocks held at the point of consumption, are excluded. Stocks of individual products held at gas processing plants are excluded from individual product estimates but are included in other oils estimates and total.

**Photovoltaic Energy:** Direct-current electricity generated from sunlight through solid-state semiconductor devices that have no moving parts.

**Pipeline Fuel:** Gas consumed in the operation of pipelines, primarily in compressors.

**Plant Condensate:** One of the natural gas liquids, mostly pentanes and heavier hydrocarbons, recovered and separated as liquid at gas inlet separators or scrubbers in processing plants.

**Primary Energy:** Energy in the form that it is first accounted for in a statistical energy balance, before any transformation to secondary or tertiary forms of energy. For example, coal can be converted to synthetic gas, which can be converted to electricity; in this example, coal is primary energy, synthetic gas is secondary energy, and electricity is tertiary energy. See **Primary Energy Production** and **Primary Energy Consumption**.

**Primary Energy Consumption:** Consumption of primary energy. (Energy sources that are produced from other energy sources—e.g., coal coke from coal—are included in primary energy consumption only if their energy content has not already been included as part of the original energy source. Thus, U.S. primary energy consumption does include net imports of coal coke, but not the coal coke produced from domestic coal.) The U.S. Energy Information Administration includes the following in U.S. primary energy consumption: coal consumption; coal coke net imports; **petroleum consumption (petroleum products supplied)**, including **natural gas plant liquids** and **crude oil** burned as fuel); **dry natural gas**—excluding **supplemental gaseous fuels**—consumption; **nuclear electricity net generation** (converted to Btu using the nuclear plants **heat rate**); **conventional hydroelectricity** net generation (converted to Btu using the fossil-fueled plants heat rate); **geothermal** electricity net generation (converted to Btu using the fossil-fueled plants heat rate), and geothermal heat pump energy and geothermal direct use energy; **solar thermal** and **photovoltaic** electricity net generation (converted to Btu using the fossil-fueled plants heat rate), and solar thermal direct use energy; **wind** electricity net generation (converted to Btu using

the fossil-fueled plants heat rate); **wood and wood-derived fuels** consumption; **biomass waste** consumption; **fuel ethanol** and **biodiesel** consumption; losses and co-products from the production of fuel ethanol and biodiesel; and electricity net imports (converted to Btu using the electricity heat content of 3,412 Btu per kilowatt-hour). See **Total Energy Consumption**.

**Primary Energy Production:** Production of primary energy. The U.S. Energy Information Administration includes the following in U.S. primary energy production: **coal** production, **waste coal** supplied, and coal refuse recovery; **crude oil** and **lease condensate** production; **natural gas plant liquids** production; **dry natural gas**—excluding **supplemental gaseous fuels**—production; **nuclear electricity net generation** (converted to Btu using the nuclear plants **heat rate**); **conventional hydroelectricity** net generation (converted to Btu using the fossil-fueled plants heat rate); **geothermal** electricity net generation (converted to Btu using the fossil-fueled plants heat rate), and geothermal heat pump energy and geothermal direct use energy; **solar thermal** and **photovoltaic** electricity net generation (converted to Btu using the fossil-fueled plants heat rate), and solar thermal direct use energy; **wind** electricity net generation (converted to Btu using the fossil-fueled plants heat rate); **wood and wood-derived fuels** consumption; **biomass waste** consumption; and **biofuels** feedstock.

**Prime Mover:** The engine, turbine, water wheel, or similar machine that drives an electric generator; or, for reporting purposes, a device that converts energy to electricity directly.

**Products Supplied (Petroleum):** Approximately represents consumption of petroleum products because it measures the disappearance of these products from primary sources, i.e., refineries, natural gas-processing plants, blending plants, pipelines, and bulk terminals. In general, product supplied of each product in any given period is computed as follows: field production, plus refinery production, plus imports, plus unaccounted-for crude oil (plus net receipts when calculated on a PAD District basis) minus stock change, minus crude oil losses, minus refinery inputs, and minus exports.

**Propane:** A normally gaseous straight-chain hydrocarbon (C<sub>3</sub>H<sub>8</sub>). It is a colorless paraffinic gas that boils at a temperature of -43.67° F. It is extracted from natural gas or refinery gas streams. It includes all products designated in ASTM Specification D1835 and Gas Processors Association Specifications for commercial propane and HD-5 propane.

**Propylene:** An olefinic hydrocarbon (C<sub>3</sub>H<sub>6</sub>) recovered from refinery or petrochemical processes.

**Real Dollars:** These are dollars that have been adjusted for inflation. See **Real Price**.

**Real Price:** A price that has been adjusted to remove the effect of changes in the purchasing power of the dollar. Real prices, which are expressed in constant dollars, usually reflect buying power relative to a base year.

**Refiner Acquisition Cost of Crude Oil:** The cost of crude oil to the refiner, including transportation and fees. The composite cost is the weighted average of domestic and imported crude oil costs.

**Refinery and Blender Net Inputs:** Raw materials, **unfinished oils**, and blending components processed at refineries, or blended at refineries or petroleum storage terminals to produce finished **petroleum products**. Included are gross inputs of **crude oil**, **natural gas plant liquids**, other **hydrocarbon** raw materials, **hydrogen**, **oxygenates** (excluding **fuel ethanol**), and renewable fuels (including fuel ethanol). Also included are net inputs of unfinished oils, **motor gasoline blending components**, and **aviation gasoline blending components**. Net inputs are calculated as gross inputs minus gross production. Negative net inputs indicate gross inputs are less than gross production. Examples of negative net inputs include reformulated gasoline blendstock for oxygenate blending (RBOB) produced at refineries for shipment to blending terminals, and unfinished oils produced and added to inventory in advance of scheduled maintenance of a refinery crude oil distillation unit.

**Refinery and Blender Net Production:** Liquefied refinery gases, and finished **petroleum products** produced at a **refinery** or petroleum storage terminal blending facility. Net production equals gross production minus gross inputs. Negative net production indicates gross production is less than gross inputs for a finished petroleum product. Examples of negative net production include reclassification of one finished product to another finished product, or reclassification of a finished product to **unfinished oils** or blending components.

**Refinery (Petroleum):** An installation that manufactures finished petroleum products from crude oil, unfinished oils, natural gas liquids, other hydrocarbons, and alcohol.

**Refuse Mine:** A surface site where **coal** is recovered from previously mined coal. It may also be known as a silt bank, culm bank, refuse bank, slurry dam, or dredge operation.

**Refuse Recovery:** The recapture of **coal** from a **refuse mine** or the coal recaptured by that process. The resulting product has been cleaned to reduce the concentration of noncombustible materials.

**Renewable Energy:** Energy obtained from sources that are essentially inexhaustible (unlike, for example, the **fossil fuels**, of which there is a finite supply). Renewable sources of energy include **conventional hydroelectric power**, **biomass**, **geothermal**, **solar**, and **wind**.

**Repressuring:** The injection of a pressurized fluid (such as air, gas, or water) into oil and gas reservoir formations to effect greater ultimate recovery.

**Residential Sector:** An energy-consuming sector that consists of living quarters for private households. Common uses of energy associated with this sector include space heating, water heating, air conditioning, lighting, refrigeration, cooking, and running a variety of other appliances. The residential sector excludes institutional living quarters. *Note:* Various EIA programs differ in sectoral coverage for more information see

<http://www.eia.gov/neic/datadefinitions/Guideforwebres.htm>. See

**End-Use Sectors** and **Energy-Use Sectors**.

**Residual Fuel Oil:** The heavier oils that remain after the distillate fuel oils and lighter hydrocarbons are distilled away in refinery operations and that conform to ASTM Specifications D396 and 975. Included are No. 5, a residual fuel oil of medium viscosity; Navy Special, for use in steam-powered vessels in government service and in shore power plants; and No. 6, which includes Bunker C fuel oil and is used for commercial and industrial heating, for electricity generation, and to power ships. Imports of residual fuel oil include imported crude oil burned as fuel.

**Road Oil:** Any heavy petroleum oil, including residual asphaltic oil used as a dust palliative and surface treatment on roads and highways. It is generally produced in six grades, from 0, the most liquid, to 5, the most viscous.

**Rotary Rig:** A machine used for drilling wells that employs a rotating tube attached to a bit for boring holes through rock.

**Short Ton (Coal):** A unit of weight equal to 2,000 pounds.

**SIC (Standard Industrial Classification):** A set of codes developed by the U.S. Office of Management and Budget which categorizes industries into groups with similar economic activities. Replaced by **NAICS (North American Industry Classification System)**.

**Solar Energy:** See **Solar Thermal Energy** and **Photovoltaic Energy**.

**Solar Thermal Energy:** The radiant energy of the sun that can be converted into other forms of energy, such as heat or **electricity**.

**Special Naphthas:** All finished products within the naphtha boiling ranges that are used as paint thinner, cleaners or solvents. Those products are refined to a specified flash point. Special naphthas include all commercial hexane and cleaning solvents conforming to ASTM Specifications D1836 and D484, respectively. Naphthas to be blended or marketed as motor gasoline or aviation gasoline, or that are to be used as petrochemical and synthetic natural gas (SNG) feedstocks, are excluded.

**Station Use:** Energy that is used to operate an **electric power plant**. It includes energy consumed for plant lighting, power, and auxiliary facilities, regardless of whether the energy is produced at the plant or comes from another source.

**Steam Coal:** All nonmetallurgical coal.

**Steam-Electric Power Plant:** A plant in which the prime mover is a steam turbine. The steam used to drive the turbine is produced in a boiler where fossil fuels are burned.

**Still Gas (Refinery Gas):** Any form or mixture of gas produced in refineries by distillation, cracking, reforming, and other processes. The principal constituents are methane, ethane, ethylene, normal butane, butylene, propane, and propylene. It is used primarily as refinery fuel and, petrochemical feedstock.

**Stocks:** See **Coal Stocks**, **Crude Oil Stocks**, or **Petroleum Stocks, Primary**.

**Strategic Petroleum Reserve (SPR):** Petroleum stocks maintained by the Federal Government for use during periods of major supply interruption.

**Subbituminous Coal:** A **coal** whose properties range from those of **lignite** to those of **bituminous coal** and used primarily as fuel for steam-electric power generation. It may be dull, dark brown to black, soft and crumbly, at the lower end of the range, to bright, jet black, hard, and relatively strong, at the upper end. Subbituminous coal contains 20 to 30 percent inherent moisture by weight. The heat content of subbituminous coal ranges from 17 to 24 million **Btu** per **short ton** on a moist, mineral-matter-free basis. The heat content of subbituminous coal consumed in the United States averages 17 to 18 million Btu per ton, on the as-received basis (i.e., containing both inherent moisture and mineral matter).

**Supplemental Gaseous Fuels:** Synthetic natural gas, propane-air, coke oven gas, refinery gas, biomass gas, air injected for Btu stabilization, and manufactured gas commingled and distributed with natural gas.

**Synthetic Natural Gas (SNG):** (Also referred to as substitute natural gas) A manufactured product, chemically similar in most respects to **natural gas**, resulting from the conversion or reforming of **hydrocarbons** that may easily be substituted for or interchanged with pipeline-quality natural gas.

**Thermal Conversion Factor:** A factor for converting data between physical units of measure (such as **barrels**, **cubic feet**, or **short tons**) and thermal units of measure (such as **British thermal units**, calories, or joules); or for converting data between different thermal units of measure. See **Btu Conversion Factor**.

**Total Energy Consumption: Primary energy consumption** in the **end-use sectors**, plus **electricity retail sales** and **electrical system energy losses**.

**Transportation Sector:** An energy-consuming sector that consists of all vehicles whose primary purpose is transporting people and/or goods from one physical location to another. Included are automobiles; trucks; buses; motorcycles; trains, subways, and other rail vehicles; aircraft; and ships, barges, and other waterborne vehicles. Vehicles whose primary purpose is not transportation (e.g., construction cranes and bulldozers, farming vehicles, and warehouse tractors and forklifts) are classified in the sector of their primary use. Note: Various EIA programs differ in sectoral coverage—for more information see <http://www.eia.gov/neic/datadefinitions/Guideforwebtrans.htm> See **End-Use Sectors** and **Energy-Use Sectors**.

**Underground Storage:** The storage of natural gas in underground reservoirs at a different location from which it was produced.

**Unfinished Oils:** All oils requiring further refinery processing except those requiring only mechanical blending. Includes naphthas and lighter oils, kerosene and light gas oils, heavy gas oils, and residuum.

**Unfractionated Stream:** Mixtures of unsegregated natural gas liquid components, excluding those in plant condensate. This product is extracted from natural gas.

**Union of Soviet Socialist Republics (U.S.S.R.):** A political entity that consisted of 15 constituent republics: Armenia, Azerbaijan, Belarus, Estonia, Georgia, Kazakhstan, Kyrgyzstan, Latvia, Lithuania, Moldova, Russia, Tajikistan, Turkmenistan, Ukraine, and Uzbekistan. The U.S.S.R. ceased to exist as of December 31, 1991.

**United States:** The 50 States and the District of Columbia. Note: The United States has varying degrees of jurisdiction over a number of territories and other political entities outside the 50 States and the District of Columbia, including Puerto Rico, the U.S. Virgin Islands, Guam, American Samoa, Johnston Atoll, Midway Islands, Wake Island, and the Northern Mariana Islands. EIA data programs may include data from some or all of these areas in U.S. totals. For these programs, data products will contain notes explaining the extent of geographic coverage included under the term "United States."

**Useful Thermal Output:** The thermal energy made available in a combined-heat-and-power system for use in any industrial or commercial process, heating or cooling application, or delivered to other end users, i.e., total thermal energy made available for processes and applications other than electrical generation.

**U.S.S.R.:** See **Union of Soviet Socialist Republics (U.S.S.R.)**.

**Vented Natural Gas:** Gas released into the air on the production site or at processing plants.

**Vessel Bunkering:** Includes sales for the fueling of commercial or private boats, such as pleasure craft, fishing boats, tugboats, and ocean-going vessels, including vessels operated by oil companies. Excluded are volumes sold to the U.S. Armed Forces.

**Waste Coal:** Usable material that is a byproduct of previous coal processing operations. Waste coal is usually composed of mixed coal, soil, and rock (mine waste). Most waste coal is burned as-is in unconventional fluidized-bed combustors. For some uses, waste coal may be partially cleaned by removing some extraneous noncombustible constituents. Examples of waste coal include fine coal, coal obtained from a refuse bank or slurry dam, anthracite culm, bituminous gob, and lignite waste.

**Waste:** See **Biomass Waste** and **Non-Biomass Waste**.

**Watt (W):** The unit of electrical power equal to one ampere under a pressure of one volt. A watt is equal to 1/746 horsepower.

**Watt-hour (Wh):** The electrical energy unit of measure equal to one watt of power supplied to, or taken from, an electric circuit steadily for one hour.

**Waxes:** Solid or semisolid material derived from petroleum distillates or residues. Waxes are light-colored, more or less translucent crystalline masses, slightly greasy to the touch, consisting of a mixture of solid hydrocarbons in which the paraffin series predominates. Included are all marketable waxes, whether crude scale or fully refined. Waxes are used primarily as industrial coating for surface protection.

**Wellhead Price:** The value of crude oil or natural gas at the mouth of the well.

**Wind Energy:** Kinetic energy present in wind motion that can be converted to mechanical energy for driving pumps, mills, and electric power generators.

**Wood and Wood-Derived Fuels:** Wood and products derived from wood that are used as fuel, including round wood (cord wood), limb wood, wood chips, bark, sawdust, forest residues, charcoal, paper pellets, railroad ties, utility poles, **black liquor**, red liquor, sludge wood, spent sulfite liquor, and other wood-based solids and liquids.

**Working Gas:** The volume of gas in a reservoir that is in addition to the base gas. It may or may not be completely withdrawn during any particular withdrawal season. Conditions permitting, the total working capacity could be used more than once during any season.