

Borrow

- Earthen levee construction requires a specific type of clay material which compacts well and prevents seepage. This material needs to contain specific amounts of sand, organic material, etc.
- Before borrow material can be used for levee construction, soil borings, testing, and environmental clearance needs to be completed. Borrow site investigation can take as long as six to nine months to complete.
- Borrow material is normally acquired from a landowner through a real estate transaction. However, the alternative methods of securing borrow, Contractor Furnished or Supply Contract, can be utilized when found to be in the best interest of Government.
- Currently the Corps is aggressively pursuing three methods for acquiring borrow material:
- <u>Government Furnished</u> Utilizing this method, the Corps first identifies the borrow source location, then investigates and approves the borrow material as suitable for use. The acquisition of the real estate interest over the land may be in the name of the non-Federal sponsor.
- <u>Contractor Furnished</u> When using this method, the Corps requires a contractor to provide their own borrow material. The Government may provide the contractor with a list of "Contractor Furnished Sites," but the contractor is ultimately responsible for providing the borrow material for construction. The contractor enters into a contractual agreement with the landowner, not with the Corps, to acquire the borrow material.
- <u>Supply Contract</u> This method allows supply contractors to bid on task orders for the supply of borrow material to be used by the Corps and other contractors for construction of the HSDRRS.





Greater New Orleans Hurricane and Storm Damage Risk Reduction System Borrow Sources

Lake Pontchartrain & Vicinity Project Borrow Needs

o New Orleans East: 8,000,000 cy

o New Orleans Metro: 260,000 cy

o Jefferson/St. Charles: 16,000,000 cy

o St. Bernard Parish: 3,000,000 cy

Westbank & Vicinity Project Borrow Needs

o Belle Chasse: 2,000,000 cy

o Gretna/Algiers: 760,000 cy

Harvey/Westwego/Lake Cataouatche: 15,000,000 cy

Other Projects

o Plaquemines Parish: 30,000,000 cy



Proposed and Approved Borrow Sources

IER 18 – Government Furnished Borrow Approved 2/21/2008

St. Charles Parish

Bonnet Carre North

Jefferson Parish

Churchill Farms

Westbank Site G

Orleans Parish

Maynard

Cummings North

St. Bernard Parish

Dockville

910 Bayou Road

1418/1420 Bayou Road

1572 Bayou Road

4001 Florissant Highway

Plaquemines Parish

Belle Chasse

Triumph

IER 19 – Pre-Approved Contractor Furnished Borrow Approved 2/14/2008

Iberville Parish

St. Gabriel

Jefferson Parish

River Birch Phase 1 and 2

Orleans Parish

Eastover

Hancock County, MS

Pearlington

St. Bernard Parish

Gatien Navv

Sylvia Guillot

DK Aggregates

Plaquemines Parish

Kimble #2

IER 22 – Government Furnished Borrow # 2 Approved 5/30/08

Plaquemines Parish

Brad Buras

Chauvin

Tabony

Westbank N

Jefferson Parish

Westbank F

Westbank I

IER 23 – Pre-Approved Contractor Furnished

Borrow # 2

Approved 5/8/08

St. Bernard Parish 1025 Florissant Hwy.

Acosta

St. Charles Parish

3C Riverside

Plaguemines Parish

Myrtle Grove

Hancock County, MS

Pearlington Dirt Phase 2

IER 25 – Government Furnished Borrow # 3

Public review: 12/8/2008 to 1/7/09

Orleans Parish

Stumpf Phase 1

Stumpf Phase 2

Jefferson Parish

Westbank D

Westbank E Phase 1

Westbank E Phase 2

Plaquemines Parish

Tac Carrere

IER 26 – Pre-Approved Contractor Furnished

Borrow #3

Approved 10/20/08

Jefferson Parish

Willswood

South Kenner Road

Plaquemines Parish

Mever

St. John the Baptist

Willow Bend

Hancock County, MS

Frierson

IER: Individual Environmental Report. NEPA compliance for the GNOHSDRRS takes the form of multiple IERs that examine smaller portions of the proposed GNOHSDRRS. The work will culminate in a Comprehensive Environmental Document that will integrate the findings of all the previously prepared IERs, describe the work being completed as a system, and examine how each project is interrelated to the overall work being done.

Borrow area does not meet Corps geotechnical criteria, and will not be used for the GNOHSDRRS.

Groups of proposed borrow areas are investigated in each IER.



BorrowAll Sites Investigated

















































