

Borrow

- Earthen levee construction requires a specific type of clay material which compacts well and prevents seepage. This material needs to contain specific amounts of sand, organic material, etc.
- Before borrow material can be used for levee construction, soil borings, testing, and environmental clearance needs to be completed. Borrow site investigation can take as long as six to nine months to complete.
- Borrow material is normally acquired from a landowner through a real estate transaction. However, the alternative methods of securing borrow, Contractor Furnished or Supply Contract, can be utilized when found to be in the best interest of Government.
- Currently the Corps is aggressively pursuing three methods for acquiring borrow material:
- <u>Government Furnished</u> Utilizing this method, the Corps first identifies the borrow source location, then investigates and approves the borrow material as suitable for use. The acquisition of the real estate interest over the land may be in the name of the non-Federal sponsor.
- <u>Contractor Furnished</u> When using this method, the Corps requires a contractor to provide their own borrow material. The Government may provide the contractor with a list of "Contractor Furnished Sites," but the contractor is ultimately responsible for providing the borrow material for construction. The contractor enters into a contractual agreement with the landowner, not with the Corps, to acquire the borrow material.
- <u>Supply Contract</u> This method allows supply contractors to bid on task orders for the supply of borrow material to be used by the Corps and other contractors for construction of the HSDRRS.





Greater New Orleans Hurricane and Storm Damage Risk Reduction System Borrow Sources

Lake Pontchartrain & Vicinity Project Borrow Needs

o New Orleans East: 23,100,000 cy

o New Orleans Metro: 260,000 cy

o Jefferson/St. Charles: 16,000,000 cy

o St. Bernard Parish: 28,400,000 cy

Westbank & Vicinity Project Borrow Needs

o Belle Chasse: 5,000,000 cy

o Gretna/Algiers: 3,000,000 cy

Harvey/Westwego/Lake Cataouatche: 13,000,000 cy

Other Projects

o Plaquemines Parish: 30,000,000 cy



Proposed and Approved Borrow Sources

IER 18 - Government Furnished Borrow

Approved 2/21/2008 St. Charles Parish Bonnet Carre North Jefferson Parish Churchill Farms

Westbank Site G

Orleans Parish

Maynard

Cummings North St. Bernard Parish

Dockville

910 Bayou Road

1418/1420 Bayou Road

1572 Bayou Road

4001 Florissant Highway

Plaquemines Parish

Belle Chasse Triumph

IER 19 – Pre-Approved Contractor Furnished Borrow

Approved 2/14/2008

Iberville Parish

St. Gabriel

Jefferson Parish

River Birch Phase 1 and 2

Orleans Parish

Eastover

Hancock County, MS

Pearlington

St. Bernard Parish

Gatien Navy

Sylvia Guillot

DK Aggregates Plaquemines Parish

Kimble #2

IER 22 - Government Furnished Borrow # 2

Public review period ends 4/30/08

Plaquemines Parish

Brad Buras Chauvin Tabony Westbank N Jefferson Parish Westbank F Westbank I

IER 23 – Pre-Approved Contractor Furnished

Borrow # 2

Public review period ends 4/23/08

St. Bernard Parish 1025 Florissant Hwy.

Acosta

St. Charles Parish
3C Riverside

Plaquemines Parish

Myrtle Grove

Hancock County, MS
Pearlington Dirt Phase 2

IER 25 – Government Furnished Borrow # 3

Tentative public review: July 2008

Orleans Parish
Stumpf Phase 1
Jefferson Parish
Westbank D
Westbank E

Plaquemines Parish

Tac Carrere Westbank M

IER 26 – Pre-Approved Contractor Furnished

Borrow #3

Tentative public review: June 2008

<u>Jefferson Parish</u> Willswood

South Kenner Road Plaquemines Parish

Meyer

St. John the Baptist

Willow Bend

Hancock County, MS Harry Frierson

IER: Individual Environmental Report. NEPA compliance for the GNOHSDRRS takes the form of multiple IERs that examine smaller portions of the proposed GNOHSDRRS. The work will culminate in a Comprehensive Environmental Document that will integrate the findings of all the previously prepared IERs, describe the work being completed as a system, and examine how each project is interrelated to the overall work being done.

Borrow area does not meet Corps geotechnical criteria, and will not be used for the GNOHSDRRS.

Groups of proposed borrow areas are investigated in each IER.



Investigated Borrow Sites – System Wide

















































