## Magnet Division All-Hands Meeting

P. Wanderer April 3, 2008

## SAFETY

# CONGRATULATIONS!

2050 days without a lost-time accident continued vigilance is needed moving people and operations around NSLS staff working in 902 Safety tip for this meeting room: Note the location of the doors Don't block the doors


#### Recent technical accomplishments

- · RHIC
- ILC
- LARP
- Superconductor R&D
- KEK/T2K/J-PARC
- NSLS II
- Helping others at BNL (LSST, nano)


#### RHIC

- Completed spare helical magnets, with field measurements during ramp
- Design system to reduce horizontal vibration of RHIC IR quads a factor of 28 below present value, ~ 0.5 μm (1/50 mil).
- Magnetic field measurements of ERL quadrupoles (resistive). Accuracy ~ 10-25 μm, 2-3 X better than RHIC.
- Work in tunnel (summer 07)

### IR quad stabilization



### ERL quadrupole measurements




#### ILC - Beam Delivery System (BDS)

- BDS Magnets:
  - Quadrupoles/sextupoles/octupoles/...
  - Demonstration of basic quadrupole, quad with shield coil, temperature reserve
  - Design and partial construction of tooling for full-length (~ 2m) coils.

#### ILC - Beam Delivery System

- Design work for cryostat, refrigerator
   1.9 K (superfluid helium)
- Measurement, damping of quad vibration
  Want control to ~ 100 nanometers (.1µm)
- BDS interface with experiments
  - Magnets for the experiments, too.


## Upgrade "direct wind" for ILC




## NSLS II

- Shared staff: 12 FTEs over 28 people
- Magnetic measurements:
  - Magnet centerline (using a stretched wire) to an accuracy of ~7  $\mu$ m (total tolerance:  $\pm$  30  $\mu$ m)
  - Magnetic fields (esp. magnets close together)
- Magnet movement, bolting to girder
  - Accuracy of  $\pm$  3 8  $\mu m.$
- Magnetic design  $\rightarrow$  reduced slot length!
- Electrical systems
- Girder stability thermal, vibration (25nm)

## NSLS II magnets & movers




#### Precise wire position measurement



Wire Vibration Sensors

SMD All-Hands

### Precise magnet positioning




## Synergy

- Obvious: magnet design, test
- Work on ILC vibration measurement technology  $\rightarrow$ 
  - RHIC IR quads
  - NSLS II girder
- NSLS II laser tracker  $\rightarrow$  ERL dipole measurements (Hall probe positions)

#### LARP

- Construction, test of 3.6 m racetrack magnet with Nb<sub>3</sub>Sn (with Berkeley)
- Design, construction of tooling for 3.6 m quad coils (with Fermilab)
- Testing of  $Nb_3Sn$  strands
- Management






April 3, 2008

## KEK/T2K/J-PARC

- Four "direct wind" corrector magnets, attached to main bending and focusing magnets for extracted proton beam.
  - Magnets delivered "just in time"
  - Cost less than estimated

#### **BNL** correctors in J-PARC



## $RIA \rightarrow FRIB$

- High temperature superconductor (HTS) used for quadrupole in high radiation area.
  - "tape" conductor, brittle
- Successful test of model made with "First Generation" HTS tape


## What's underway/what's ahead?

- · RHIC
- LARP
- Superconductor R&D
- ILC
- NSLS II
- FRIB


## RHIC technical near term

- Measure motion of RHIC triplet quads during next running period (Jan. 09?)
  - Stabilization system too expensive to build at present
- Separate cryo line from triplet quads
- Locate bad solder joints in tunnel
- Repair, upgrade 902 cryo test facility
- Measure ERL dipoles
- Tunnel help, very soon  $\rightarrow$  end of CY08?

### Separate cryo line ...



#### Measure vibration



## ERL dipole measurements



## RHIC financial near term

- C-AD budget cuts
  - FY08 running reduced: 30 weeks  $\rightarrow$  19
  - Partly financed by cut in support of SMD
  - No layoffs
- Continual financial pressure on C-AD
  - FY08: support = 15 FTE
  - FY09: support = 12 FTE
  - FY10: support = 9 FTE

## RHIC longer term

- A cheaper way to increase luminosity is under development ("stochastic cooling")
- Electron-ion collisions
- More info in Steve's talk

#### LARP

- FY09:
  - Make, assemble(?) Nb<sub>3</sub>Sn quadrupole coils
  - Design, make(?) coil tooling for larger-aperture quadrupoles
- Construction project (LHC upgrade essential)
  - Phase 1: deliver Dec. 2012 or (?)later
    - Deliverables TBD (DX? Large aperture  $Nb_3Sn$  quads)
    - Funding start FY10 likely
  - Phase 2: deliver  $Nb_3Sn$  quads ~ 2015
- Continue  $Nb_3Sn$  materials study several years

## Superconductor R&D


- $Nb_3Sn$  (complementing LARP studies)
- HTS, second generation (YBCO)
  - HTS is also "high field superconductor"
    - That is, higher fields than  $Nb_3Sn$  can tolerate
  - Muon collider needs very high field magnets
    - Fermilab strong interest in Muon Collider

## ILC

- FY08P \$1.6 M  $\rightarrow$  \$0.4 M (SMD)
  - FY08P \$60 M  $\rightarrow$  \$15 M (national)
- FY09P \$30 M, \$1.6 M
  - FY09CR expected, \$0.4 M
  - HEP Particle Physics Project Prioritization Panel (P5) -final meeting today - LARP, ILC, Muon Collider, superconductor R&D
- ILC management: looking at non-U.S. location, will cooperate with CERN

#### NSLS II construction

CD2 CD3 CD4a Early Finish STORAGE RING R&D **Preliminary Design** Final Design Bid & Award Reviews Procurements **Fabrication Assembly and Test** Installation Pentant 1 Installation Pentant 5 Installation Pentant 2 Installation Pentant 3 Installation Pentant 4 Installation Testing Commissioning **INJECTOR (L,B,TL) Preliminary Design** Final Design Bid & Award Reviews Procurements **Fabrication Assembly and Test** Installation Testing Commissioning FLOAT



## FRIB

- DOE has issued draft RFP, will issue final RFP soon, plans to make selection by end of CY  $\rightarrow$  FY10 construction start
- Both competitors (Argonne, Michigan State Univ.) have asked SMD for help with magnets for FRIB (scope TBD)
- BNL will maintain a neutral position with regard to site selection.

## Overall

- FY09 looks tight:
  - ILC a major factor
- Beyond FY09:
  - There are several projects for the three DOE offices (HEP, NP, BES) where SMD can make a significant contribution.
- The high quality work done by SMD staff is an enormous asset.