



**Service/Product Provider**

**Centro Inc.**

321 Hill Avenue  
Nashville, TN 37210

Business: Flow Control Distributor & Representative

Brad Davis

Territory Manager

Phone: 615-255-2220

Email: [bdavis@centromemphis.com](mailto:bdavis@centromemphis.com)

**Industrial Partner**

**Nissan**

983 Nissan Drive  
Smyrna, TN 37167

Business: Automobile Manufacturing

Chris Goddard

Environmental Engineer

Phone: 615-459-1633

Email: [chris.goddard@nissan-usa.com](mailto:chris.goddard@nissan-usa.com)

**Nissan and Centro partner to reduce energy cost 20% through improved metering**

**Project Scope**

Nissan wanted to precisely measure consumption by department in their Smyrna facility. For low pressure natural gas applications, Nissan sought a simple, reliable metering device with no moving parts. Centro determined that the Aaliant Target Flow meter and the Fox Thermal Mass Flow meter would meet Nissan's needs for natural gas applications as well as some water applications. Following a demonstration of the meters that was conducted by Centro, over 100 meters were installed.

**Project Summary**

After installation by Centro of the above mentioned equipment, Nissan's new metering and measurement capability allowed Nissan to identify key areas in the plant with highest annual energy consumption, distribute proper costs to different plant functions to increase awareness and sensitivity, measure performance against budgets, and identify areas for improvement.

- **Energy Savings**  
Installation of these meters contributed to greater than 20% energy savings over the past two years
- **Investment**  
Approximately \$300,000
- **Financial Return**  
Payback in 2.5 years
- **Other Benefits**  
Productivity, maintenance, and reliability

**Monitoring & Verifying Energy Savings**

The installed metering itself verified the savings.

**Distinguishing Value**

While the Aaliant Target Flow meters and Fox Thermal Mass Flow meters used within the air house area of the paint shop was the focus of this project, their success resulted in meters being installed in other departments such as the power house and the paint mix room.