Continuing Authorities Program, Section 205 Feasibility Study City of Carencro, Louisiana


City Council Meeting Project Presentation

April 16, 2012

Presenter: Durund Elzey, Sr. Project Manager



Civil Works Program



Continuing Authorities Program (CAP)

<u>Authority</u>

 Section 205 authorizes the Corps to study, design, and construct small flood risk management projects in cooperation with a local sponsor

Project Sponsor

City of Carencro



City of Carencro CAP 205

 Primary goal is to reduce risk from flooding in Beau Bassin Coulee



Beau Bassin Coulee



Flood Risk Reduction Measures

- Structural measures
 - Enlarging the coulee
 - · Lining the coulee with concrete or gabion
 - Storing flood waters in a retention or detention basin
 - Clearing, grubbing, and dressing (CG&D) to remove accumulated debris and smooth coulee surface
 - Diverting water away from Carencro
- > Nonstructural Measures
 - Acquisition or relocation of high risk structures
 - Elevation of high risk structures




Screening of Alternatives


- Initial Array of Alternatives
 - Initially 11 structural alternatives; screened to 3
 - Initially 6 non-structural alternatives; screened to 1
- Final Array of Alternatives
 - <u>Alternative 3:</u> Gabion and Enlarged Earthen Section
 - <u>Alternative 7:</u> Retention Storage in Central Carencro with Channel Clearing
 - <u>Alternative 8:</u> Retention Storage in Central Carencro with Channel Clearing and Enlarged Earthen Channel
 - <u>Non-structural Alternative:</u> Elevate structures at the 4% chance flood event



Final Array – Structural Alternatives Alternative 3: Combined Gabion and Enlarged Earthen Section




Final Array – Structural Alternatives Alternative 7: Retention Storage in Central Carencro with Channel Clearing



Final Array – Structural Alternatives Alternative 8: Retention Storage in Central Carencro with

Channel Clearing & Enlarged Earthen Channel



Final Array – Non-structural Alternative Elevate Structures



Evaluation of Alternatives – Risk Reduction

Chance- Flood Event	W/O Project	Alternative 3	Alternative 7	Alternative 8	Nonstructural
"2-year"	4	0	0	0	0
"5-year"	30	0	1	0	0
"10-year"	40	1	1	1	10
"25-year"	50	4	8	5	20
"50-year"	81	22	31	20	51
"100-year"	112	37	45	33	82
"250-year"	143	69	78	55	113
"500-year"	154	81	92	77	132

Number of Structures Inundated above First Floor Elevation (FFE)


Evaluation of Alternatives – Economic Benefit/Cost Analysis

	Alternative	Annual Costs	Annual Benefits	Net Benefits	BCR
Alterr	native 3	\$440,200	\$676,700	\$236,500	1.5
Altera	ative 7	\$265,800	\$636,000	\$370,200	2.4
Alterr	native 8	\$357,000	\$687,400	\$330,400	1.9
Nons	tructural	\$191,600	\$277,700	\$86,100	1.4


Tentatively Selected Plan

Alternative 7: Retention Storage in Central Carencro with Channel Clearing

- Provides the greatest net NED benefits
- Would cause the least disruption to the environment



Path Forward



Questions & Discussion



Backup Materials



Chronology

- 2001 Completed Reconnaissance
- 2003 Executed FCSA with City of Carencro
- 2007 Completed initial engineering studies
- 2008 Completed HTRW and cultural resources surveys
- 2008 City requests additional alternatives
- 2010 Completed initial analysis of expanded alternatives; selected final array
- 2011 Updated HTRW and cultural resource surveys; completed feasibility analysis and identified tentatively selected plan; completed quality control reviews.
- 2012 Engineering analysis complete; draft report issued for public review./comment




Geotechnical Sampling



Tentatively Selected Plan (pre-Optimization)

Alternative 7: Retention Storage in Central Carencro with Channel Clearing


- Provides the greatest net NED benefits
- Would cause the least disruption to the environment



Tentatively Selected Plan

Alternative 7: Retention Storage in Central Carencro with Channel Clearing

- 1.67-acre site no longer used for retention
- Adjusted size and shape of remaining retention basin
- Evaluated flow control options at retention basin (none needed)



Path Forward

Complete Feasibility Study

- Complete public review period (20 Apr 12)
- Address public comments/finalize report
- Report Approval (1 Jun 12)
- Execute Project Participation Agreement
 - Matching funds available
 - Cooperative Endeavour Agreement with Parish
- Project Design & Implementation
 - Federal funds are currently available for design (\$300K)
 - Coordination construction activities with Parish

