

FY 2013 MAINTENANCE DREDGING

PROJECT: Gulf Intracoastal Waterway
 SUBPROJECT: Mile 99
 PROJECT MANAGER: Victor Landry
 PHONE: (504) 862-2407
 LOCAL SPONSOR: U.S. Government has sufficient interest

DESCRIPTION OF WORK:

Maintain 12' x 125' channel in the Gulf Intracoastal Waterway (with an additional 3' of advance maintenance)

HISTORICAL DREDGING FREQUENCY: Annually
 LAST DREDGED: 2011
 TYPE OF DREDGE: Leased Cutterhead
 ESTIMATED QUANTITY: 100,000 CY
 ESTIMATED COST: \$600,000

ADVERTISE: Jan 2013
 OPEN BIDS: TBD
 AWARD: TBD
 START WORK: TBD
 DURATION: 7 days

DREDGING REACH: GIWW at Mile 99
 DISPOSAL AREA: Atchafalaya River
 DISPOSAL TYPE: Open Water
 REMARKS: Dredged Material discharged beyond the -32' Depth Contour

GULF INTRACOASTAL WATERWAY MILE 99



PROJECT AUTHORITY: River and Harbor Act of 24 July 1946, Senate Document 242, 79th Congress, 2nd Session, and prior R&H Acts; River and Harbor Act of 23 October 1962, House Document 556, 87th Congress, 2nd Session.

| NEPA DOCUMENTATION | FONSI | PUBLIC NOTICE | WATER QUALITY CERTIFICATION | |
|--|-----------|---------------|-----------------------------|-----------|
| FEIS O&M | 4-Feb-77 | 19-Feb-75 | | 21-Feb-79 |
| SIR#11 Advance Maintenance & Allowable Overdepth | 20-Sep-85 | 28-Oct-86 | | |

* revised Water Quality Certificate

Recent Dredging History Of Gulf Intracoastal Waterway – Mile 99

| Fiscal Year | Disposal Area | Dredging Quantity (CY) |
|-------------|------------------------------|------------------------|
| 2001 | Atchafalaya River Open Water | 60,038 |
| 2002 | Atchafalaya River Open Water | 70,736 |
| 2003 | Atchafalaya River Open Water | 38,056 |
| 2004 | Atchafalaya River Open Water | 67,423 |
| 2005-2006 | NO DREDGING | |
| 2007 | Atchafalaya River Open Water | 73,545 |
| 2008 | Atchafalaya River Open Water | 169,140 |
| 2009 | Atchafalaya River Open Water | 86,523 |
| 2010 | Atchafalaya River Open Water | 55,964 |
| 2011 | Atchafalaya River Open Water | 90,648 |

