Floodwall and Levee Performance Analysis, Physical Modeling









Physical Modeling Team



Michael K. Sharp, PhD, PE
Wipawi Vanadit-Ellis, MS
Wayne Hodo
Henry Blake
David Daily
Dave Carnell



R. Scott Steedman, PhD FREng FICE Kevin Stone, PhD



Prof Tarek H. Abdoun, PhD
Prof Thomas F. Zimmie, PhD, PE
Inthuorn Sasanakul, PhD
Javier Ubilla, MS
Marcelo Gonzalez, MS
Hassan Radwan
Alex Sankovich
Dominic Moffitt



Prof Dr Ir Frans Barends Paul Schaminée , MSc Adam Bezuijen, MSc









Physical Modeling Progress

- Completed 2 models of London North (ERDC & RPI)
- Completed 1 model of 17th Street
- Currently building models of London South (ERDC & RPI)
- Future is 2nd model of 17th Street and model of Orleans Canal









17th Street Model










- One trial model tested at RPI, second model to be tested at ERDC
- Levee: Synthetic clay (match field conditions based on lab test, CPT, etc)
- Swamp/Marsh: Actual field material
- Lacustrine: Synthetic clay (match field conditions)
- Beach: Fine sand such as Nevada Sand











Model Preparation

Clay Placement




















Clay Placement









Shear Strength Estimation of Clay Layer @17th street

Location	Water	Estimate	Estimate
	Content (%)	S _u (kPa)	S _u (psf)
Surface (after Consol.)	75	3-5	70-110
Surface (after Testing)	64	5-7	110-140
Middle (after Testing)	59	9-12	200-250
Bottom (after Testing)	57	12-15	250-310









Swampy/Marsh Placement




















Clay Levee Placement

















Preliminary Results

























Preliminary Observations

- The wall experienced limited tilt and limited increase in the hydrostatic pressure under the downstream levee
- Shear failure occurred in the clay layer comparable to the field observation













Thank You Questions







