CONTRACT DATA REQUIREMENTS LIST
(1 Data Item)

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to the Department of Defense, Executive Services and Communications Directorate (0704-0188). Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. **Please do not return your form to the above organization. Send completed form to the Government Issuing Contracting Officer for the Contract/PR No. listed in Block E.**

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP ____ TM ____ OTHER X
0006	A	

D. SYSTEM/ITEM	E. CONTRACT/PR NO.	F. CONTRACTOR
BRIDGE ERECTION BOAT	W56HZV-12-R-0445	

1. DATA ITEM NO.	2. TITLE OF DATA ITEM	3. SUBTITLE	17. PRICE GROUP
A011	Report, Hazard Tracking System (HTS)	Report	

4. AUTHORITY *(Data Acquisition Document No.)*	5. CONTRACT REFERENCE	6. REQUIRING OFFICE	18. ESTIMATED TOTAL PRICE
	C.5.4	SFAE-CSS-FP-H	

7. DD 250 REQ	9. DIST STATEMENT REQUIRED	10. FREQUENCY	12. DATE OF FIRST SUBMISSION
LT	B	ONE/R	SEE BLK 16

8. APP CODE	11. AS OF DATE	13. DATE OF SUBSEQUENT SUBMISSION
SEE BLK 16	SEE BLK 16	SEE BLK 16

16. REMARKS

In accordance with MIL-STD-882, Task 210.

The HTS shall contain a description of each potential or actual environmental, safety and health hazard of the BEB, the cause and effects of the hazard, when the hazard may be expected to occur under usual and unusual operating or maintenance conditions, and status of each hazard. The contractor shall identify actions to mitigate the risk associated with the hazards and categorize the risk before and after mitigation in accordance with MIL-STD-882. The contractor shall identify if the hazard is software related. Mitigation actions include recommended engineering controls, safety features or devices, warning devices and procedures and training. The HTS shall also include the findings from an Environmental Hazards Analysis (EHA) (MIL-STD-882, Task 210).

Examples of hazards to be identified in the HTS include, but are not limited to: sharp edges, moving parts or rotating parts/assemblies, physical hazards (e.g. extreme temperatures, acoustical energy, ionizing and non-ionizing radiation), chemical hazards, (e.g. flammables, corrosives, carcinogens) toxic fumes (exhaust emissions), electrical hazards, noise, whole body vibration, compliance issues with regulatory organizations, generation of hazardous waste, biological hazards, fire prevention issues and ergonomic hazards.

BLOCK 8: Government has 5 days to review. The contractor shall resubmit 5 days after Government review.

BLOCK 11, 12 and 13: First Report is due 210 days after contract award. After first delivery of report, quarterly reports will be due.

BLOCK 14: E-mail delivery per e-mail addresses on BEB IPT List.

Repro = electronic copy

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES: Draft	Final: Reg	Final: Repro
AMSTA-CSC-Z	1		1
SFAE-CSS-FP-H	1		1
RDTA-EN/ME	1		1
15. TOTAL →	3	0	3

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
SUZANNE ARCHIBALD	09 NOV 12		

Reset