

3/1999 D. Checker 2/1999 Checked by: 2/1999 A. Designer 18-Dec-2007 2:22 Designed by: [orne01ba.xls]Sheet

STATE	PROJECT	SHEET NUMBER
OR	RRP NEBA 100(1)	B.1

SUMMARY OF QUANTITIES

Insert text file generated from Engineer's Estimate program into Summary of Quantities Excel template.

PLAN SHEET SECTION ----->>			SECTION C	SECTION D	SECTION G											ESTIMATED QUANTITIES	
			TYPICAL SECTION	PLAN VIEW	TRAFFIC CONTROL											PLAN	BID SCHEDULE
ITEM	DESCRIPTION	UNIT															
15101-0000	MOBILIZATION	LPSM														ALL	ALL
15201-0000	CONSTRUCTION SURVEY AND STAKING	LPSM														ALL	ALL
15301-0000	CONTRACTOR QUALITY CONTROL	LPSM														ALL	ALL
15401-0000	CONTRACTOR TESTING	LPSM														ALL	ALL
15501-0000	CONSTRUCTION SCHEDULE	LPSM														ALL	ALL
15705-1500	SOIL EROSION CONTROL, SEDIMENT WATTLE	LNFT		500												500	550
15801-0000	WATERING FOR DUST CONTROL	MGAL	43.15													43.15	51.00
20301-1100	REMOVAL OF GATE	EACH		1												1	1
20301-2700	REMOVAL OF STRUCTURE , GATE POST	EACH		2												2	2
20401-0000	ROADWAY EXCAVATION	CUYD	493.0													493.0	493.0
20402-0000	SUBEXCAVATION	CUYD	56.9													56.9	65.0
20701-0700	EARTHWORK GEOTEXTILE, TYPE II-A	SQYD	2785													2785	3,200
21101-2000	ROADWAY OBLITERATION, METHOD 2	SQYD		209												209	250
21201-0000	LINEAR GRADING	STA	2.99													2.99	3.50
30802-1000	ROADWAY AGGREGATE, METHOD 1	TON	3973.63													3973.63	4,500.00
40401-0000	MINOR HOT ASPHALT CONCRETE	TON	1124.77													1124.77	1,200.00
41201-1000	TACK COAT GRADE CSS-1, CSS-1H, SS-1, OR SS-1H	TON	1.19													1.19	1.50
60901-0400	CURB, CONCRETE, 6-INCH DEPTH	LNFT		295.0												295.0	310.0
60907-1000	PAVED DITCH, ASPHALT	LNFT	40.0													40.0	50.0
60915-1000	WHEELSTOP, CONCRETE	EACH		16												16	17
61901-0000	FENCE	LNFT		1687.0												1687.0	1,800.0
61902-0000	GATE , ELECTRIC	EACH		2												2	2
62201-0050	DUMP TRUCK, 5 CUBIC YARD MINIMUM CAPACITY	HOUR															40
62201-0400	BACKHOE LOADER, 2 CUBIC FOOT MINIMUM RATED CAPACITY BUCKET, 12-INCH WIDTH	HOUR															40
62201-2850	MOTOR GRADER, 12 FOOT MINIMUM BLADE	HOUR															40
62301-0000	GENERAL LABOR	HOUR															40
62405-0300	PLACING CONSERVED TOPSOIL, 4-INCH DEPTH	SQYD	460.5													460.5	500.0
63302-0000	SIGN SYSTEM	SQFT			79.1											79.1	90.0

(CO)

(CO) means Contract Quantity