



NOTE
Under Drainage to be 2" Pipes, Size as shown, Bell & Spigot, 4" min. Gravel enveloped, joints filled with Gravel. Gravel fill up to bottom of Floor Slab. Gravel to be 1/8" to 3/8".
All Floor Drains & Pit Drains to have Strainer & Trap. Floor Drains: 1/2" Strainer, 4" Outlet, C.I. 1/16" Secondary Pit. Chlorine Pit Drain: 6" Trap, chemical proof Clay no Strainer.
All C.I. Pipes & Fittings to be Extra heavy C.I. Soil Pipes

DRAWN BY: G.P.S.		CARR & J. E. GREINER CO.—ARCHITECT-ENGINEERS BALTIMORE, MD.	
TRACED BY: G.P.S.		DURHAM, N. C.	
CHECKED BY: F.D.K.		MARINE BARRACKS—NEW FIVER, N. C.	
CHIEF DEPTN: F.D.K.		BUREAU OF YARDS AND DOCKS—NAVY	
IN CHARGE: W.C.M.		DATE: Dec. 20, 1941	
SCALE: AS SHOWN		Y. & D. DRAWING NO.	
162205		ARCHITECT-ENGINEERS SPECIFICATION	
APPROVED: [Signature]		SHEET 4 OF 12	
NOV 24 1941		M.B. PROJ. NO. P-10	
JAN 22 1942		M.B. DWG. NO. 5	

REVISION	DATE	BRIEF	R.O. IN CHARGE	BY
"B"	NOV 24 1941	Relocated Installation Panel Board for Pump Controls, Rec. Gauge, etc. Balcony Floor Trench for Suction Header & Reinf. in Pit. Found'n. added. Drains changed.	[Signature]	L.W.A. G.P.S.
"A"	JAN 22 1942		[Signature]	[Signature]

