

**UT CR2554(4) SEVENMILE-GOOSEBERRY – PHASE 4  
PRE-SHOW  
NOVEMBER 27, 2012**

<b>SCHEDULE</b>	
9:00 am	Sign-in / Review of Schedule / Introductions / Ground Rules
9:15-9:30 am	Pre-Show Objective and Project Overview
9:30 am -11:30 pm	Guided Site Review
11:30-3:00 pm	Unguided Site Review (on your own)
3:00 pm	Plans and Specifications due back to FHWA

<b>PROJECT OVERVIEW</b>
➤ Overview of Central Federal Lands & Federal Lands Access Program(FLAP)
➤ Phase 4 of Multi-Phase Project
➤ 9.5 miles of Reconstruction and Paving. Option for Additional Paving
➤ 1.5 miles of Realignment (southern end)

<b>SPECIAL CONSIDERATIONS</b>
➤ Material Source - Gates Lake (Select Borrow, Riprap, Agg. Base, Permeable Backfill)
➤ Construction Season
➤ Traffic Control
➤ Structural Section
➤ Boulder Fields & Permeable Backfill (Sheet F5)
➤ Wetland Mitigation Site

**UT CR2554(4) SEVENMILE-GOOSEBERRY – PHASE 4  
PRE-SHOW  
NOVEMBER 27, 2012**

**MAJOR ITEMS OF WORK (All quantities approximate)**

- Clearing and Grubbing - 120 acres
- Earthwork - 260K cy of Rdwy Ex, 35K cy Permeable Backfill, 80K cy Waste
- Structural Section -80K cy of Select Borrow, 35K sy of Aggregate Base
- Paving – 35K tons of Superpave
- Drainage - Culverts - 6,000 Inft, Placed Riprap 15K cy
- Placing Conserved Topsoil – 25K cy
- Wetland Mitigation Site ~ 6.2 acres

**ADVERTISEMENT**

- Project is anticipated to be advertised this winter. Notice to Proceed anticipated by April/May, 2013
- What type of information would help in the bidding process (Photos, Electronic Drawings, Reports, etc...)

**IMPORTANT INFORMATION**

- Central Federal Lands website is [www.cflhd.gov](http://www.cflhd.gov) & [www.cflhd.gov/sevenmile](http://www.cflhd.gov/sevenmile)
- Geotech Report is located on CFL Website under Contracting>Construction Procurement>Preshow & Pre-Advertisement Information
- Questions should be e-mailed to [Aaron.Sanford@dot.gov](mailto:Aaron.Sanford@dot.gov) .
- Or mailed to: Acquisition and Contracting  
12300 W Dakota Avenue, Suite 360  
Lakewood, Colorado 80228
- Standard Specifications used is the FP-03 – English Units  
<http://flh.fhwa.dot.gov/resources/pse/specs/>

**UT CR2554(4) SEVENMILE-GOOSEBERRY – PHASE 4  
PRE-SHOW  
NOVEMBER 27, 2012**

<b>STOPPING LOCATIONS</b>		
<i>Stop #</i>	<i>Approx. Station(s)</i>	<i>Significant Feature(s)</i>
1	10+00	<ul style="list-style-type: none"> <li>• Start of Project – Begin Major Realignment Area</li> </ul>
2	75+00	<ul style="list-style-type: none"> <li>• End Major Realignment Area</li> <li>• Parking Areas</li> </ul>
3	150+00	<ul style="list-style-type: none"> <li>• Begin Private Property</li> </ul>
4	348+00	<ul style="list-style-type: none"> <li>• Permeable Backfill for Wet Area</li> </ul>
5	390+00	<ul style="list-style-type: none"> <li>• Cold Springs Road</li> </ul>
6	505+00	<ul style="list-style-type: none"> <li>• End of Project</li> </ul>
7	Material Source	<ul style="list-style-type: none"> <li>• Gates Lake Road Pit</li> </ul>