
# PROJECT MAPS CHARLESTON DISTRICT

## 1991



US ARMY ENGINEER DISTRICT, CHARLESTON US ARMY CORPS OF ENGINEERS




## INDEX TO PROJECT MAPS RIVER AND HARBOR WORKS

U.S. Army Engineer District Corps of Engineers, Charleston Revised to 30 September 1991

LATEST REVISION	
NAVIGATION OF MAPS PG	
Adams Creek, SC (Sep 1990) 2	
* Archers Creek, SC (Sep 1990) 5	-
* Ashley River, SC (Sep 1990)	)
Aquatic Plant Control (Sep 1990) 24	
Atlantic Intracoastal Waterway between Norfolk, Va. and the St. Job	nns
River, FL (Charleston Dist., in 3 sheets)	*1
(Little River to Winyah Bay, SC) (Sep 1990)	a
(Little River to Charleston, SC) (Sep 1990)	b
(Charleston to Port Royal Sound, SC) (Sep 1990)	Lc
Brookgreen Gardens, SC (Nov 1985)	11
Charleston Harbor, SC (Jan 1992)	8
Cooper River, Charleston Harbor, SC - (Sep 1990)	27
Cooper River Seismic Modification, SC (Sep 1990)	51
Edisto River, SC (Sep 1990)	L5
Folly River, SC (Sep 1990)	56
Georgetown Harbor, SC (Sep 1990)	2
* Great Pee Dee River, SC (Sep 1990)	4
Jeremy Creek, SC (Sep 1990)	57
Little River Inlet, NC & SC (Sep 1990)	48
	18
* Mingo Creek, SC (Sep 1990)	5
	49
and the second sec	23
* Salkehatchie River, SC (Sep 1990)	20
* Santee River, SC (Sep 1990)	6
Shipyard River, SC (Sep 1990)	10
Town Creek, SC (Sep 1990)	30
Village Creek, SC (Sep 1990)	26
Waccamaw River, NC & SC (Sep 1990)	3
* Wateree River, SC (Sep 1990)	21
* - Inactive Projects	

- Inactive Projects



## INDEX TO PROJECT MAPS AUTHORIZED BY CONGRESS

U.S. Army Engineer District Corps of Engineers, Charleston Revised to 30 September 1991


FLO	OD CONTROL	LATEST REVISION OF MAPS	PG
*	Edisto River, SC	 (Sep 1990)	12

#### BEACH EROSION

Hunting Island Beach,	SC			(Sep 1990)		25
-----------------------	----	--	--	------------	--	----

#### STREAMBANK EROSION

	Pompion Hill Chapel	-	•	-	÷	-	-	-	2	-	(Sep 1990)	-	-	-	-	-	<b>H</b> 5	-	62	
*	Inactive Projects																			




## INDEX TO PROJECT MAPS CONTINUING AUTHORITY - FLOOD CONTROL

U. S. Army Engineer District Corps of Engineers, Charleston Revised to 30 September 1991

> LATEST REVISION OF MAPS

PG

Buck Creek, NC & SC (Sep 1990)	31
Cow Castle Creek, SC (Sep 1990)	60
Cowpen Swamp, SC (Sep 1990)	33
Crabtree Swamp, SC (Sep 1990)	34
Eagle Creek, SC (Sep 1991)	58
Edisto River, North Fork, SC (Sep 1990)	35
Edisto River, Vicinity	
Canaday's Landing, SC (Sep 1990)	54
Gapway, Swamp, NC & SC (Jun 1972)	36
Kingstree Branch, SC (Sep 1990)	47
Saluda River, SC (Sep 1990)	38
Sawmill Branch, SC (Sep 1990)	39
Scotts Creek, SC (Sep 1990)	53
Shot Pouch Creek, SC (Sep 1990)	40
Todd Swamp, SC (Sep 1990)	44
Turkey Creek, Sumter County, SC (Sep 1990)	45
Wilson Branch, SC (Sep 1990)	59



## CONGRESSIONAL DISTRICTS

#### SENATORS

Strom Thurmond Ernest F. Hollings

#### REPRESENTATIVES

- Arthur Ravenel, Jr.
  Floyd D. Spence
  Butler C. Derrick, Jr.
  Elizabeth V. Patterson
  John Spratt, Jr.
  Robin Tallon

#### GOVERNOR

Carroll Campbell

#### LIEUTENANT GOVERNOR

Nick Theodore

.

### **PROJECTS TRANSFERRED TO WILMINGTON DISTRICT**

RIVER AND HARBOR WORKS <u>Navigation</u> Lumber River, NC & SC

AUTHORIZED BY CONGRESS <u>Flood Control</u> W. Kerr Scott Dam and Reservoir, NC

CONTINUING AUTHORITY - FLOOD CONTROL Little Sugar Creek, NC Old Field Swamp, NC Simmons Bay Creek, NC Waccamaw River and Seven Creeks, NC

#### ATLANTIC INTRACOASTAL WATERWAY BETWEEN NORFOLK, VA. AND THE ST. JOHNS RIVER, FL (CHARLESTON DISTRICT)

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The existing project was authorized by the following River and Harbor Acts: Sept. 19, 1890; June 13, 1902 - H. Doc. 84, 56th Cong., 1st sess.; March 2, 1907 - H. Doc 178, 63d Cong., Ist sess.; March 3, 1925 - H. Doc. 237, 68th Cong., 1st sess.; March 3, 1925 - S. Doc. 178, 68th Cong., 2d sess.; July 3, 1930 - H. Doc. 41, 71st Cong., 1st sess.; Aug 30, 1935 - River and Harbor Committee Doc. 14, 72d Cong., 1st sess.; Aug 30, 1935 - H. Doc. 129, 72d Cong., 1st sess.; Aug 30, 1935 - River and Harbor Committee Doc. 6, 75th Cong., 1st sess.; March 2, 1945 - H. Doc. 327, 76th Cong., 1st session.

**PROJECT:** Provides for a waterway 12 feet deep at mean low water and not less than 90 feet wide from the SC - NC state line at Little River to and including Port Royal Sound with a branch channel of the same dimensions to McClellanville, a total distance of 210 miles; for the construction of 3 bridges crossing the waterway in Horry County, SC; and for an anchorage basin 125 feet wide, 335 feet long, and 12 feet deep near Myrtle Beach, SC.

LOCAL COOPERATION: Requirements fully satisfied.


**PROGRESS:** Project completed in 1940 except an anchorage basin 125 feet wide, 335 feet long, and 12 feet deep near Myrtle Beach, S. C.

#### COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 7,455,378		\$ 7,455,378
Maintenance	53,377,125		53,377,125
Total	60,723,013		60,723,013

**TIDAL RANGE:** At Little River, SC, one mile above the mouth, 5.0 feet; at Combination Bridge, 1.6 feet; Winyah Bay at Georgetown (Pee Dee River Bridge), SC, 3.3 feet; Charleston Harbor (entrance), SC, 5.2 feet; and Port Royal Sound (Battery Creek), SC, 7.2 feet.

Myrtle Beach Anchorage Basin was deauthorized by the Water Resources Development Act of 1986.




1B


OCEAN

10

ETTY

JETTY





#### **GEORGETOWN HARBOR, SC**

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The existing project was authorized by the River and Harbor Act - Aug 5, 1886 - H. Ex. Doc. 258, 48th Cong., 2d sess.; H. Ex. Doc. 117, 50th Cong., 2d sess.; River and Harbor Act - June 25, 1910 - H. Doc. 395, 58th Cong., 2nd sess.; H. Doc. 398, 58th Cong., 2d sess.; River and Harbor Act of March 2, 1945 - H. Doc. 211, 76th Cong., 1st sess.; River and Harbor Act of June 30, 1948 - S. Doc. 21, 81st Cong., 1st session.

**PROJECT:** Provides for a channel 27 feet deep with varying widths of 600 to 400 feet from the Atlantic Ocean to and including a turning basin in Sampit River, with a side channel 2,400 feet long and not less than 200 feet wide leading to a turning basin at the upper end of the built-up portion of the city waterfront, widened at the bends, secured and maintained by two jetties of stone on brush mattresses, springing respectively from North and South Islands, the north jetty 11,139 feet long and the south jetty 21,051 feet long. The project also provides for maintenance to a depth of 18 feet for a width of 400 feet of the bypassed portion of Sampit River opposite the city of Georgetown.


LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: The project was completed in July 1951.

#### COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 7,061,755		\$ 7,061,755
Maintenance	55,600,493	1775	55,600,493
Total	62,662,248		62,662,248

TIDAL RANGE: The mean range of tide at Georgetown (Sampit River) is 3.7 feet, in the inner channel is 5.4 feet, and at the entrance to the bar (Winyah Bay entrance), it is 4.6 feet.



#### WACCAMAW RIVER, NC & SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The existing project was authorized by the following River and Harbor Acts: June 14, 1880 - S. Ex. Doc. 117, 46th Cong., 2d session and Annual Report, 1880, p. 848: July 3, 1930 - H. Doc. 82, 70th Cong., 1st session.

**PROJECT:** Provides for a channel 12 feet deep at mean low water, with 80-foot bottom width, from the mouth to Conway, 41.5 miles; thence 4 feet deep at mean low water and 50 feet wide to Red Bluff, 25.5 miles above Conway; thence a cleared channel to Lake Waccamaw.


LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: The 12-foot channel to Conway (mile 41.5) was completed in 1923, and the 4-foot channel to Red Bluff (mile 67) in 1931.

COST TO DATE:

*	Federal	Non-Federal	Total
New Work	\$ 262,814		\$ 262,814
Maintenance	283,372		283,372
Total	546,186	·	546,186

TIDAL RANGE: The mean range of tide is 3.6 feet at the mouth, 2.0 feet at Enterprise Landing, and 1.2 feet at Conway.



#### GREAT PEE DEE RIVER, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The existing project was authorized by the following River and Harbor Acts: June 14, 1880 - S. Ex. Doc. 117, 46th Cong. 2d sess., and the 1880 Annual Report, p. 844 (For map see Annual Report for 1889, p. 1180); June 13, 1902 - H. Doc. 124, 56th Cong., 2d sess.

**PROJECT:** Provides for a cleared 9-foot channel from Waccamaw River via Bull Creek, to Smiths Mills, and thence a 3½-foot channel to Cheraw at all stages of water.


LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** The existing project was completed in 1909. Project dimensions obtained from the head of Bull Creek at Great Pee Dee River (mile 32.5) to Smiths Mills (mile 55).

#### COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 183,712		\$ 183,712
Maintenance	270,123		270,123
Total	453,835		453,835

**TIDAL RANGE:** The mean range of tide at the Waccamaw entrance is 3.6 and the extreme tide is 4.2 feet.



#### **MINGO CREEK, SC**

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The existing project was authorized by the following River and Harbor Act: July 25, 1912 - H. Doc. 782, 61st Cong., 2d session.


**PROJECT:** Provides for a channel 60 feet wide and 8 feet deep at mean low water from the mouth to Hemingway Bridge, 11 miles, by making four short cutoffs.

LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** The existing project was completed in 1913. The creek was last cleared of obstructions between its mouth at Black River and the Hemingway highway bridge (mile 11), the head of commercial navigation, during January 1945.

COST TO DATE:			
	Federal	Non-Federal	Total
New Work	\$ 29,050		\$ 29,050
Maintenance	7,600		7,600
Total	36,650		36,650

TIDAL RANGE: The mean range of tide is 2 feet and the freshet range is 4.5 feet.



#### SANTEE RIVER, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The existing project was authorized by the following River and Harbor Act: September 19, 1890 - Annual Report for 1889, p. 1184.

PROJECT: Provides for snagging the entire river.


LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: In June 1941, the river was closed to navigation at Wilson Landing (mile 87) by the construction of the Santee Dam of the Santee-Cooper hydroelectric project.

COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 99,750		\$ 99,750
Maintenance	181,494		181,494
Total	281,244		281,244

TIDAL RANGE: The mean range of tide is 4.5 feet at North Santee River Inlet.



## **RESERVED FOR FUTURE USE**

#### CHARLESTON HARBOR, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The existing project was authorized by the following River and Harbor Acts: June 18, 1878; August 8, 1917 - H. Doc. 288, 62d Cong., 2d sess.; July 18, 1918 - H. Doc. 1946, 64th Cong., 2d sess.; January 21, 1927 - H. Doc. 249, 69th Cong., 1st sess.; October 17, 1940 - H. Doc. 259, 76th Cong., 1st sess.; March 2, 1945 - H. Doc. 156, 77th Cong., 1st sess.; September 3, 1954 - S. Doc. 136, 83rd Cong., 2d sess.; July 14, 1960 - H. Doc. 35, 86th Cong., 1st sess.; October 22, 1976 Water Resources Development Act - H. Doc. 94-436 (Section 101), 94th Congress, 2d sess.; and the 1986 Water Resources Development Act dated 17 November 1986 - H. Doc. 99-1013, 99th Cong., 2d sess., and P.L. 99-662.

**PROJECT:** The project, as authorized by the 1986 Water Resources Development Act, provides for deepening of the 35-foot channel to 40 feet (42 feet in the ocean bar and entrance channel) from the 42-foot ocean contour to Goose Creek, a total distance of 26.9 miles, construction of one turning basin, modification of existing turning basins, deepening and modification of the anchorage basin, deepening Shipyard River to 38 feet, maintain the Wando River Channel to 35 feet at federal expense and the deepening of this channel to 40 feet.


LOCAL COOPERATION: The Local Cooperation Agreement was signed on 5 Feb 88. The Wando River supplement was signed on 8 Mar 89. The South Carolina State Ports Authority is the sponsor for this project and has furnished funds and disposal areas in a timely manner.

**PROGRESS:** Previous projects completed except for a portion of the anchorage basin which has been deauthorized and the 40-foot national defense project. Work is currently underway on deepening the harbor to 40 feet with completion scheduled for September 1994.

Federal	Non-Federal <sup>1/</sup>	Total
\$ 35,486,849	\$ 8,189,606	\$ 43,676,455
107,123,018		107,123,018
142,609,867	8,189,606	150,799,473
	\$ 35,486,849 107,123,018	\$ 35,486,849 \$ 8,189,606 107,123,018

<sup>1/</sup> No values are included for disposal area lands or diking costs.

TIDAL RANGE: The mean range of tide is 5.2 feet above mean low water, and extreme tide is 6.1 feet above mean low water.



#### ASHLEY RIVER, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

**AUTHORIZATION:** The existing project was authorized by the following River and Harbor Acts: July 25, 1912 - River and Harbor Committee Doc. 4, 62d Cong., 2d sess.; August 26, 1937 - River and Harbor Committee Doc. 49, 74th Cong., 2d session.

**PROJECT:** Provides for a channel 30 feet deep at mean low water and 300 feet wide from the mouth to the Standard Wharf, 7.4 miles, suitably widened at bends and at the head of the improvement.

LOCAL COOPERATION: Requirements fully satisfied.


PROGRESS: The project was completed in 1940.

COST TO DATE:

	Federal	Non-Federal	Total		
New Work	\$ 260,996		\$	260,996	
Maintenance	552,599		552,599		
Total	813,595			813,595	

TIDAL RANGE: The mean range of tide at the Ashley River, Wappo Creek (highway bridge) is 5.2 feet above mean low water with an extreme tide of 6.1 feet.





#### SHIPYARD RIVER, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

**AUTHORIZATION:** The existing project was authorized by the following River and Harbor Acts: July 25, 1912 - S. Doc. 350, 62d Cong., 2d sess.; March 3, 1925 - H. Doc. 288, 68th Cong., 1st sess.; July 3, 1930 - River and Harbor Committee Doc. 13, 71st Cong., 2d sess.; August 30, 1935 - River and Harbor Committee Doc. 43, 73rd Cong., 2d sess.; August 26, 1937 - River and Harbor Committee Doc. 38, 75th Cong., 1st sess.; March 2, 1945 - H. Doc. 93, 79th Cong., 1st session. The 1986 Water Resources Development Act authorized deepening to 38 feet as part of the Charleston Harbor, S. C Project.

**PROJECT:** Provides for a channel 30 feet deep at mean low water and 200 feet wide, widened to 300 feet at the entrance, from deep water in Cooper River to the vicinity of the plant of the AIRCO Alloys Company, with a turning basin 30 feet deep opposite the Gulf Oil Corporation terminal and a turning basin 30 feet deep at the upper end of the project with flared entrance.


LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** The entrance channel and a portion of the lower turning basin have been deepened to 38 feet.

#### COST TO DATE:

New Work	Federal		Non-Federal	Total		
	\$	491,974	199 <u>9</u>	\$	491,974	
Maintenance	9,753,561			9,753,561		
Total		10,245,535			10,245,535	

**TIDAL RANGE:** The mean range of tide at Shipyard Creek, 0.8 miles above entrance is 5.3 feet above mean low water, and extreme tide is 6.1 feet above mean low water.



#### **BROOKGREEN GARDENS, SC**

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by the River and Harbor Act of 1960, as amended.


**PROJECT:** The project provides for a 3,600 foot canal with a 30 foot bottom width maintained to a depth of four feet mlw.

LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: The project was constructed in August 1990.

#### COST TO DATE:

	Federal		Non-Federal		Total	
New Work	\$	94,700	\$	7,800	\$	102,500
Maintenance						
Total		94,700		7,800		102,500



#### EDISTO RIVER, SC (Flood Control)

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by the Flood Control Act, approved 22 December 1944, S. Doc. 182, 78th Cong., 2d session.

**PROJECT:** Provides for clearing the channel and banks of the lower 18 miles of South Fork, the lower 10 miles of the North Fork, and the upper 15 miles of the Edisto River for flood control.

LOCAL COOPERATION: Requirements fully satisfied.


PROGRESS: Construction of the project has not been started.

COST TO DATE: \$6,379 (100% Federal)

TIDAL RANGE: None

LUKPS UF ENGINEERS

U.S. ARMY



**RESERVED FOR FUTURE USE** 

## EDISTO RIVER, SC (Navigation)

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by the River and Harbor Act of 2 August 1882, H. Doc. No. 23, 46th Cong., 3d session.

**PROJECT:** Provides for the removal of snags and shoals and for channel rectification by cutting off bends and closing lateral channels to provide a clear channel suitable for light draft steamers from the sea to the junction of the North and South Forks, and suitable for rafts and flatboats on South Fork from the junction of the forks to Guignards Landing.


LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: The project was completed in 1896.

## COST TO DATE:

	Federal	Non-Federal	Total	
New Work	\$ 33,103		\$ 33,103	
Maintenance	1,510		1,510	
Total	34.613		34.613	

TIDAL RANGE: The mean range tide at Edisto Marina is 5.9 above mean low water and 1.9 feet above mean low water at Jacksonboro.



CORPS OF ENGINEERS

.

### LYNCHES RIVER AND CLARK CREEK, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The four-feet depth project was authorized by the River and Harbor Act of 1888.

PROJECT: Provides for clearing a channel in Clark Creek to afford an outlet for Lynches River.


LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** Project complete. Abandonment recommended in 1926 (H. Doc. No. 467, 69th Cong. 1st sess.) Reactivated in early FY 80. Local interest requested that channel be snagged and cleared for a 12-mile reach from Hwy. 41 (Mile 12.0) Johnsonville, SC, to its confluence with the Pee Dee River (Mile 0.0). This work was completed April 1981.

## COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 9,500		\$ 9,500
Maintenance	84,620	19 <u>22-</u> 1	84,620
Total	94,120		94,120

TIDAL RANGE: Tidal influence is not felt.



CORPS OF ENGINEERS

#### SALKEHATCHIE RIVER, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by the River and Harbor Act of 1880, H. Doc. No. 23, 46th Cong., 1st session.


**PROJECT:** Provides for the removal of sunken logs, snags, trees and similar obstructions, in such manner as to provide a clear channel for rafts and flatboats, from a point 5 miles above Toby's Bluff down to Hickory Hill.

LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** The project was completed in 1896. Abandonment recommended in 1926 (H. Doc. No. 467, 69th Cong., 1st session).

C	OST TO DATE:			
		Federal	Non-Federal	Total
	New Work	\$ 15,841		\$ 15,841
	Maintenance	780		780
	Total	16,621		16,621

TIDAL RANGE: The mean range of tide is 7.2 feet at the mouth of the river.



#### WATEREE RIVER, SC

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was adopted by the River and Harbor Act of March 3, 1881 - 46th Cong., 2d sess, and the Annual Report for 1880.

**PROJECT:** Provides for a 4-foot navigation channel from the mouth of the river to Camden, South Carolina, a distance of 67 miles.

LOCAL COOPERATION: Requirements fully satisfied.


**PROGRESS:** Project completed in 1939. Abandonment was recommended by House Document No. 805, 64th Cong., 1st session.

COST TO DATE:

	1	Federal	Non-Federal	Total
New Work	\$	60,000		\$ 60,000
Maintenance		152,609		152,609
Total		212,609		212,609

TIDAL RANGE: Tidal influence is not felt.

CURPS OF ENGINEERS



#### PORT ROYAL HARBOR, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The existing project was authorized by the River and Harbor Act approved September 3, 1954, in accordance with plans contained in H. Doc. 469, 81st Cong., 2d session.

**PROJECT:** Provides for a channel from the ocean through Port Royal Sound to Ports Royal, South Carolina, 27 feet deep and 500 feet wide across the ocean bar and in Port Royal Sound for approximately 13.2 miles, thence 24 feet deep and 300 feet wide in Beaufort River and Battery Creek for approximately 7.5 miles to and including a turning basin 27 feet deep and 600 feet wide opposite the wharf of the South Carolina State Port Authority.

LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** That part of the project providing for a 24-foot channel and a 27-foot turning basin at the head of the project was completed in June 1956. The project was completed in May 1959.


#### COST TO DATE:

	Federal		Non-Federal	Total		
New Work	\$	1,786,100		\$	1,786,100	
Maintenance		9,353,830			9,353,830	
Total		11,139,930			11,139,930	

TIDAL RANGE: The mean range of tide on the bar (Martin's Industry) is 6.4 feet above mean low water and at Port Royal (Battery Creek), SC, the mean range of tide is 7.4 feet above mean low water.







## AQUATIC PLANT CONTROL

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991


AUTHORIZATION: The project was authorized by the the River and Harbor Act of October 27, 1965, Section 302.

**PROJECT:** Provides for control and progressive eradication of water hyacinth, alligator week, Eruasian water-milfoil, and other noxious aquatic plant growths from navigable waters, tributary streams, connecting channels, and other allied waters of the U.S., in combined interest of navigation, flood control, drainage, agriculture, fish and wildlife conservation, public health and related purposes, including continued research for development of most effective and economic control measures in cooperation with other Federal and state agencies.

LOCAL COOPERATION: Requirements fully satisfied.

#### COST TO DATE:

	Federal	Non-Federal		Total	
New Work	\$ 5,248,326	\$	52,028	\$	5,300,354
Maintenance					
Total	5,248,326		52,028		5,300,354



### HUNTING ISLAND BEACH, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by the River and Harbor Act of 27 October 1965 (See HD 323/88/2) and the Water Resources Development Act (WRDA) of October 22, 1976 (PL 94-587).

**PROJECT:** This project provides for construction of a terminal groin having a length of 840 feet with stone end protection located some 1,900 feet north of a 10,000-foot feeder beach. It provides, for the authorized 10,000-foot feeder beach, an initial nourishment of 750,000 cubic yards of sand, and expected renourishment at the rate of 250,000 cubic yards a year. WRDA of 1976 extended periodic nourishment from 10 to 15 years.


LOCAL COOPERATION: Requirements fully satisfied. The state contributed 30 percent of construction costs.

**PROGRESS:** Initial placement was completed 15 December 1968 and the terminal groin was completed 12 November 1968 except for additional stone required at its toe for scour protection, placement of which was completed 25 June 1969. First renourishment (761,324 cubic yards) of the feeder beach was begun in May 1971, and was completed on 18 August 1971. The second renourishment (in excess of 477,000 cubic yards) was begun in April 1975 and was completed on 17 June 1975. The third renourishment (in excess of 924,000 cubic yards) was begun in January 1980 and completed on 30 April 1980.

COST TO DATE:

	Federal		Non-Federal		Total	
New Work	\$ 2,872,717	\$	1,249,336	\$	4,122,053	
Maintenance						
Total	2,872,717		1,249,336		4,122,053	

CORPS OF ENGINEERS



### VILLAGE CREEK, SC

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by Section 107 of the 1960 River and Harbor Act, as amended on 24 November 1965 by Chief of Engineers under the Authorization of Section 107 of River and Harbor Act of 1960, as amended.

**PROJECT:** Provides for a channel 8 feet deep and 80 feet wide from that depth in the Morgan River to the Porpoise Fish Company terminal, a distance of 2.2 miles.

LOCAL COOPERATION: Requirements fully satisfied.


PROGRESS: The project was completed in April 1966.

COST TO DATE:

1

	Federal	Non-Federal	Total
New Work	\$ 26,500		\$ 26,500
Maintenance	110,339	( <del></del> )	110,339
Total	136,839		136,839

**TIDAL RANGE:** The mean range of tide is 6.5 feet above mean low water, and 6.8 feet above mean low water at the entrance to Village Creek in Morgan River.



## COOPER RIVER, CHARLESTON HARBOR, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized under the River and Harbor Act of 1968, P.L. 90-483, Senate Document 88.

**PROJECT:** This project provides for construction of a diversion canal (approx. 9.5 miles) from Lake Moultrie which returns approximately 70 percent of the freshwater back into the Santee River. Water rediverted to the Santee River generates electrical energy at an 84,000 kwh hydroelectric power plant located midway on the canal.

LOCAL COOPERATION: Requirements fully satisfied.


**PROGRESS:** Preconstruction planning was completed at the end of Fiscal Year 1974. Construction start funds were appropriated in Fiscal Year 1975. Construction was initiated in March 1977. The project was physically completed and placed in operation in the spring of 1985. The administrative aspects of the construction efforts have not been finalized due to several large claims by the Powerhouse contractor and an outstanding letter of credit with the S. C. Highway Department allowing for the four-laning of the U.S. Highway 52 bridge if begun by 28 May 2001.


#### COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 196,873,971		\$ 196,873,971
Maintenance	22,705,421		22,705,421
Total	219,579,392		219,579,392

TIDAL RANGE: Tidal influence is not felt at St. Stephen site; however, project itself covers the Cooper River down into the harbor. The tides do impact project features & flows.







ARMY

in

## ADAMS CREEK, SC

### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized on 24 September 1969 under Section 107 of the 1960 River and Harbor Act, as amended.

**PROJECT:** Provides for a channel 10 feet deep by 80 feet wide, a distance of approximately 1.45 miles long with a turning basin at the upper end.


LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: Construction completed in February 1973.

COST TO DATE:

	Federal	Non Federal	Total
New Work	\$ 125,697		\$ 125,697
Maintenance	27,061	1997	27,061
Total	\$ 152,758		\$ 152,758

TIDAL RANGE: The mean tide range at Rockville, Bohicket Creek is 5.7 feet above mean low water.



## TOWN CREEK, McCLELLANVILLE, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

**AUTHORIZATION:** The existing project was authorized by OCE on 12 February 1974 under Section 107 of the River and Harbor Act of 1960, as amended.

**PROJECT:** The project provides an entrance channel 12 feet deep by 100 feet wide across the ocean bar a distance of 4.0 miles and includes a channel 10 feet deep by 80 feet wide from the mouth of Five Fathom Creek to the AIWW, a distance of 6.2 miles.


LOCAL COOPERATION: Requirements fully satisfied.


PROGRESS: The project was constructed in October 1974.

COST TO DATE:

	Federal	N	on-Federal	Total
New Work	\$ 219,521	\$	8,600	\$ 228,121
Maintenance	4,372,538			4,372,538
Total	4,592,059		8,600	4,600,659

TIDAL RANGE: The mean tide range in the entrance channel (Five Fathom Creek, entrance) is 5.1 feet above mean low water.





#### BUCK CREEK, NC & SC

### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 1 February 1966, under Section 205 of the 1948 Flood Contraol Act, as amended.


**PROJECT:** Provides for excavation and realignment of the existing channels on Buck Creek and its principal tributaries for a total distance of 18.94 miles with bottom widths varying from 1 to 35 feet and a depth of cut from 4 to 6 feet.

LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: Completed 30 July 1969.

COST TO DATE:

	Federal	Non-Federal		Total	
New Work	\$ 298,167	\$	36,000	\$	334,167
Maintenance					
Total	298,167		36,000		334,167



DATE REVISED: SEPTEMBER 1990

SC-6

CORPS OF ENGINEERS

## COWPEN SWAMP, SC

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991


AUTHORIZATION: The project was authorized by OCE on 17 April 1958, under Section 208 of the 1954 Flood Control Act, as amended.

**PROJECT:** Provides for excavation and clearing from its mouth in Simpson Creek near mile 5 to 3 miles upstream.

PROGRESS: Completed 24 September 1959.

COST TO DATE:

	Federal		Non-Federal		Total	
New Work	\$	18,679	\$	18,521	\$	37,200
Maintenance	18					
Total		18,679		18,521		37,200



### CRABTREE SWAMP, SC

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 16 November 1964, under Section 208 of the 1954 Flood Control Act.


**PROJECT:** Provides for clearing a channel 4.5 miles long with bottom widths of 10 to 50 feet wide along Crabtree Swamp and in short reaches of Kingston Lake Swamp and Smith Lake Swamp for a total length of 1 mile by 50 feet wide.

LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: Completed in FY 1966.

COST TO DATE:

	Federal		Non-Federal		Total	
New Work	\$	97,000	\$	42,900	\$ 139,900	
Maintenance				10		
Total		97,000		42,900	139,900	



## EDISTO RIVER, NORTH FORK, SC

### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 1 June 1966, under Section 205 of the 1948 Flood Control Act, as amended.

**PROJECT:** Provides for removal of debris, fallen tress, and alligatorweed from the North Fork between Orangeburg and the confluence with the South Fork of the Edisto River, a distance of 27 miles.


LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: Completed 31 March 1969.

	Federal	No	n-Federal	Total
New Work	\$ 127,660	\$	43,300	\$ 170,960
Maintenance				100
Total	127,660		43,300	170,960

CURTS OF ENGINEERS

U.S. ARMY



## GAPWAY SWAMP, NC & SC

### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991


AUTHORIZATION: The project was authorized by OCE on 18 January 1966, under Section 205 of the 1948 Flood Control Act, as amended.

**PROJECT:** Provides for enlargement and realignment of the channel. The total length of improvement is 14 miles with bottom widths ranging from 32 to 60 feet.

LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: The project was completed in FY 1968.

	Federal	No	n-Federal	Total
New Work	\$ 339,197	\$	111,500	\$ 450,697
Maintenance				
Total	339,197		111,500	450,697



### SALUDA RIVER, SC

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 17 October 1962, under Section 208 of the 1954 Flood Control.


**PROJECT:** Provides for snagging and clearing the channel along the North Fork (15 miles), the South Fork (11 miles) and the Middle Fork (12 miles).

LOCAL COOPERATION: Requirements fully met.

PROGRESS: Completed in August 1963.

	Federal	Nor	n-Federal	Total
New Work	\$ 99,000	\$	500	\$99,500
Maintenance				
Total	99,000		500	99,500

# 



## SAWMILL BRANCH, SC


## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991


AUTHORIZATION: The project was authorized by OCE on 20 June 1968, under Section 205 of the 1948 Flood Control Act, as amended.

**PROJECT:** Provides for excavating a channel of varying sizes ranging from a maximum of 35 feet to 15 feet up Sawmill Branch from a point above its confluence with the Ashley River about 1,400 feet below the SC Route 642 crossing. The project extends through Summerville to a point 9.0 miles from its beginning.

PROGRESS: Completed in April 1971.

Federal	No	n-Federal		Total
\$ 248,605	\$	85,500	\$	334,105
284,605		85,500		334,105
\$	\$ 248,605 	\$ 248,605 \$	\$   248,605      \$   85,500	\$   248,605    \$   85,500   \$ 





### SHOT POUCH CREEK, SC

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991


AUTHORIZATION: Authorized by OCE on 15 August 1968, under Section 208 of the 1954 Flood Control Act, as amended.

**PROJECT:** provides for snagging and clearing a channel 2.15 miles long with bottom widths from 14 to 30 feet wide.

LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: Completed in October 1970.

	Federal	No	n-Federal	lotal
New Work	\$ 77,400	\$	53,000	\$ 130,400
Maintenance				
Total	77,400		53,000	130,400



## TODD SWAMP, SC

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991


AUTHORIZATION: The authorized by OCE on 1 March 1963, under Section 208 of the 1954 Flood Control Act, as amended.

**PROJECT:** Provides for snagging, clearing and channel enlarging with bottom widths varying from 6-10 feet on the lower 3 miles and includes improvements to 800 feet of Frank Branch.

LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: Completed May 1964.

	Federal	Non-Federal	Total
New Work	\$ 29,000	\$ 28,000	\$ 57,000
Maintenance			<del></del>
Total	29,000	28,000	57,000



## TURKEY CREEK, SUMTER COUNTY, SC

### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991


AUTHORIZATION: The project was authorized by OCE on 14 April 1969, under section 205 of the 1948 Flood Control Act, as amended.

**PROJECT:** Provides for enlargement and clearing a channel approximately 4.5 miles long with bottom widths of 18 to 60 feet.

LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** Initial June 1971 contract is complete. A second construction contract awarded in June 1973, has been completed.

	•//	Federal	Non-Federal	Total
New Work	\$	319,669	\$ 73,500	\$ 393,169
Maintenance				
Total		319,669	73,500	393,169



CORPS OF ENGINEERS

U.S. ARMY

### **KINGSTREE BRANCH, SC**

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 16 August 1972 under section 205 of the 1948 Flood Control Act, as amended.

**PROJECT:** Provides for enlarging the channel 24 to 26 feet wide and 7185 feet long from the Black River through the town of Kingstree to Brooks Street crossing.


LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** The contract for project construction was awarded on 30 September 1976. Construction was initiated on 28 October 1976 and was completed on 24 June 1977.

	Federal	Non-Federal	Total
New Work	\$ 247,242		\$ 247,242
Maintenance			
Total	247,242		247,242







#### LITTLE RIVER INLET, NC & SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

**AUTHORIZATION:** The project was authorized by the Senate Public Works Committee and the House Public Works Committee on October 12, 1972, under authority of Section 201, PL 89-298, 1965 Flood Control Act. Section 15 of the Water Resources Act of 1974 authorized interim maintenance to permit free and safe movement of vessels until the authorized project is constructed.

**PROJECT:** The project provides an entrance channel 12 feet wide to the Atlantic Intracoastal Waterway; and ocean jetties 3,284 feet and 3,830 feet long on the upcoast and downcoast sides of the inlet, respectively. Sand dikes tie the jetties to the shore.

LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** Construction was started on upcoast jetty in FY 1981. The project was completed in FY 1984.


## COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 17,037,428	\$ 1,521,920	\$ 18,559,348
Maintenance	2,707,532*		2,707,532*
Total	19,744,960	1,521,920	21,266,880

\*Includes Section 3 of 1945 River and Harbor Act - \$183,124.19 and Section 15 of 1974 Water Resources Development Act - \$1,116,704.00.

**TIDAL RANGE:** The mean tide range one mile above the mouth is 5.0 feet above mean low water and 5.9 feet at extreme tide.

0



CORPS OF ENGINEERS

U.S. ARMY

#### **MURRELLS INLET, SC**

### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

**AUTHORIZATION:** The project was authorized by the House Committee on Public Works on 10 November 1971 and the Senate Committee on Public Works on 18 November 1971, under authority of Section 201, P.L. 89-298, 1965 Flood Control Act. Section 67 of the Water Resources Act of 1974 authorized interim maintenance to permit free and safe movement of vessels until the authorized project was completed.

**PROJECT:** The project provides for an entrance channel twelve by 300 feet across the seaward bar; thence a ten by 90-foot inner channel to a turning basin at the old Army crashboat dock. The entrance channel is stabilized by ocean jetties extending seaward 3,445 feet and 3,319 feet on the north and south sides of the inlet, respectively. The recreational project includes a walkway on the south jetty with access road and parking area.

#### LOCAL COOPERATION: Requirements fully satisfied.

**PROGRESS:** The construction project was initiated in September 1977. The active portion of the project was completed in August 1981. The maximum benefits are achieved with a 10-foot entrance channel and an 8-foot inner channel. The 2-foot depth difference between the authorized depth and the construction depth has been reclassified as "inactive". The entrance channel and the jetties have been shortened to the 10-foot ocean contour rather than the 12-foot contour.


#### COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 15,502,240	\$ 1,536,893	\$ 17,039,133
Maintenance	3,702,307*	(1 <u>444</u> )	3,702,307*
Total	19,204,547	1,536,893	20,741,440

\*Includes Section 3 of 1945 River and Harbor Act - \$145,569.0 and Section 67 of 1974 Water Resources Development Act - \$556,000.0.

TIDAL RANGE: The mean tide range is 4.5 feet above mean low water.





### ARCHERS CREEK, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by the River and Harbor Act of 1912, H. Doc. No. 513, 62nd Cong., 2nd session.

**PROJECT:** Provides for a channel six feet deep at mean low water and 75 feet wide from its intersection with the Beaufort River for a distance of 2 miles.

LOCAL COOPERTION: Requirements fully satisfied.

PROGRESS: The project was completed in 1914.


COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 20,646		\$ 20,646
Maintenance			
Total	20,646	-	20,646

TIDAL RANGE: The mean tidal range is 6.1 feet.

CORPS OF ENGINEERS





#### SCOTTS CREEK, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 14 November 1975 under section 205 of the 1948 Flood Control Act, as amended.

**PROJECT:** The recommended plan of improvement consists of clearing and snagging of the existing North Fork from SC Highway 34 upstream a distance of approximately 0.4 mile to SC 121 (Highway 34 by-pass). Channel enlargement begins at SC 121 and extends upstream approximately 2.2 miles to a point about 900 feet above Glenn Street. Design channel bottom width varies from 20 to 28 feet with an average depth of cut of 7 feet. The County of Newberry withdrew as co-sponsor of the project. As a result, that portion of the project from Newberry city limits to SC highway 34, a distance of 0.56 mile, has been eliminated. The reach above Glenn Street was also eliminated because it involved expensive rock excavation with very little increase in benefits.

LOCAL COOPERATION: Requirements fully satisfied.


**PROGRESS:** Construction was completed and accepted in 1988. The project upgraded about a mile of the creek, from approximately 50 feet downstream of O'Neal Street to about 200 feet upstream of Nance Street. The City of Newberry has accepted the project for maintenance purposes.

### COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 545,000		\$ 545,000
Maintenance	100		
Total	545,000		545,000

đ





## EDISTO RIVER-VICINITY CANADAY'S LANDING, SC (Flood Control)

### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by Section 208 of the 1954 Flood Control Act, Public Law 780, 83rd Congress, 3 September 1954.

**PROJECT:** Provides for clearing the channel and banks of the Edisto River in the vicinity of Canaday's Landing for flood control.

LOCAL COOPERATION: Requirements fully satisfied.


PROGRESS: Project was completed 17 September 1957.

COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 3,160		\$ 3,160
Maintenance			
Total	3,160		3,160

TIDAL RANGE: Tidal influence not felt.

ų,



đ

### FOLLY RIVER, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 23 December 1977, under Section 107 of the 1960 River and Harbor Act, as amended.

PROJECT: Project provides for shallow draft navigation as follows:

a. Stono Inlet Entrance Channel. An entrance channel 11 feet deep by 100 feet wide extending from the 11-foot contour in the Stono River through the shoal lying off the river mouth to the 11-foot contour in the ocean; a distance of approximately one nautical mile.

b. Folly River Channel. A channel within Folly River 9 feet deep and 80 feet wide, extending downstream from Highway 171 to the confluence of Folly and Stono Rivers; a distance of approximately three nautical miles.

c. Folly Creek Channel. A channel within Folly Creek 9 feet deep by 80 feet wide extending downstream from Highway 171 to the confluence with Folly River: a distance of approximately three nautical miles.

LOCAL COOPERATION: Requirements fully satisfied.


PROGRESS: Project construction was physically completed in September 1979.

COST TO DATE:

	Federal	Non-Federal	Total
New Work	\$ 337,736		\$ 337,736
Maintenance	2,879,733		2,879,733
Total	3,217,469		\$ 3,217,469

**TIDAL RANGE:** In the inner channel, the mean range of tide is 5.4 feet above mean low water, and extreme tide is 6.3 feet above mean low water. In the entrance channel, the mean range of tide is 5.2 above low water and the extreme tide is 6.1 above mean low water.

đ



## JEREMY CREEK, SC

## CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by Section 107 of the 1960 River and Harbor Act, as amended, on 11 January 1982.

**PROJECT:** Provides for a turning basin 12 feet deep and 150 feet in diameter at the head of the previously existing Jeremy Creek navigation channel.

LOCAL COOPERATION: Requirements fully satisfied.


PROGRESS: The project was completed in 1982.

#### COST TO DATE:

New Work	Federal	Non-Federal	Total	
	\$ 49,987		\$ 49,987	
Maintenance	84,504		84,504	
Total	134,491		134,491	

TIDAL RANGE: The mean range of tide is 5.1 feet.

2ª



# EAGLE CREEK, SC

# CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 25 January 1982 under authority contained in Section 205 of the 1948 Flood Control Act, as amended.

**PROJECT:** The authorized plan calls for approximately 3.8 miles of channel modifications and includes recommendations to increase the flow capacity of two highway bridges.


LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: Project was physically completed on 14 August 1985 and fiscally completed in December 1985.

### COST TO DATE:

New Work	F	ederal	Non-Federal		Total	
	\$	1,245,063			\$ 1,245,063	
Maintenance						
Total		1,245,063			1,245,063	

đ



CORPS OF ENGINEERS

U.S. ARMY

## WILSON CREEK, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by OCE on 8 September 1982, under authority contained in Section 205 of the 1948 Flood Control Act, as amended.

**PROJECT:** The authorized plan calls for the removal of six flood-prone structures from the 10-year flood plain as a nonstructural solution to the flood problems.


LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: Project was physically completed on 27 December 1984 and fiscally in January, 1985.

### COST TO DATE:

New Work	Federal		Non-Federal		Total	
	\$	277,111	\$	6,906		\$ 284,017
Maintenance						
Total		277,111		6,906		284,017

i



# COW CASTLE CREEK, ORANGEBURG COUNTY, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by Office, Chief of Engineers on 26 August 1983, under authority of Section 208 of the 1954 Flood Control Act, as amended.

**PROJECT:** The project, as constructed, consisted of the clearing and snagging of the existing channel of Cow Castle Creek for a distance of 8085 feet in the vicinity of the South Carolina Highway 210 crossing. Additionally the project included the clearing of all brush and tress smaller than 12 inches in diameter from the right creek bank. The County of Orangeburg cleared Even Branch (tributary to Cow Castle Creek) for a distance of 1.7 miles as part of the total project.

LOCAL COOPERATION: Requirements fully satisfied.


PROGRESS: Construction contract was awarded on 22 September 1983. Construction activities were completed on 2 May 1984.

# COST TO DATE:

New Work	F	Federal		n-Federal	Total	
	\$	250,000	\$	26,000*	\$ 276,000	
Maintenance						
Total		250,000		26,000*	250,000	

\*Includes \$15,000 land acquisition.

á



# COOPER RIVER SEISMIC MODIFICATION, SC

#### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized by Public Law 90-483 and amended by PL 98-63.

**PROJECT:** The project consists of remedial measures to stabilize the existing Pinopolis West Dam in the event an earthquake should occur. The existing structure is founded on seismically unstable materials that could result in total failure, potentially causing millions of dollars in Flood damage to downstream government and private property. Extensive investigation identified three definable reaches totaling about 4,500 linear feet of unstable structure. Basically, a new dam will be constructed immediately downstream of the existing dam.

LOCAL COOPERATION: The Local Cooperation Agreement was signed on 29 March 1988.

**PROGRESS:** The construction contract was awarded in April 1988 and was physically complete on 24 September 1990.


## COST TO DATE:

20	Federal	Non-Federal	Total	
New Work	\$ 29,209,312	\$ 900,000	\$ 30,109,312	
Maintenance			( <b></b> )	
Total	29,209,312	900,000	30,109,312	

di.

61





## COOPER RIVER, POMPION HILL CHAPEL, SC

### CONDITION OF IMPROVEMENT: 30 SEPTEMBER 1991

AUTHORIZATION: The project was authorized on 23 July 1986 under general authority contained in Section 14 of the 1946 Flood Control Act, as amended.

**PROJECT:** The authorized project consists of bank stabilization of approximately 200 feet of bank on the East Branch of the Cooper River. The project is adjacent to the Pompion Hill Chapel.

LOCAL COOPERATION: Requirements fully satisfied.

PROGRESS: The project was completed in January 1987.

COST TO DATE: \$211,100 (100% Federal)

t.

