

RHIC Performance Update

Wolfram Fischer

BNL Collider-Accelerator Department
Machine Advisory Committee Meeting
23 January 2006



Run-5

- **Beam: 11/23/04 to 06/24/05**
- **Cu-Cu**
 - **100 GeV/n** (8 weeks for physics)
 - **31.2 GeV/n** (1 ½ weeks for physics)
 - **11.2 GeV/n** (1 ½ days for physics)
- **p↑-p↑**
 - **100 GeV** (9 ½ weeks for physics)
 - **205 GeV** (2 stores for physics)

Run-5 Cu-Cu Summary

Major accomplishments at 100 GeV:

- 253m of NEG coated beam pipes installed in warm regions
- start-up/ramp-up in 2.5 weeks (1.5 weeks less than planned)
- enough bunch intensity to run at beam-beam limit with 4 IPs
- β^* reduced by 10% to 0.9m at STAR

Major accomplishments at 31.2 GeV:

- 74% of calendar time in store


Major accomplishments at 11.2 GeV:

- 82% of calendar time in store

Run-5 Cu-Cu Summary

RHIC Run 5 Delivered Cu-Cu Luminosity

Run coordinator: F. Pilat



Run-5 p↑-p↑ summary

Major accomplishments at 100 GeV:

- polarized source upgraded with sc solenoid
- 60% polarization at AGS extraction
- first acceleration of polarized protons in AGS with cold snake (10¹¹ protons per bunch, 50% polarization at AGS extraction)
- operation with up to 111 bunches per ring
- increased store polarization by 5%

Major accomplishment at 205 GeV:


- ramp setup for higher energy in 3 days
- first acceleration and storage of polarized protons >100 GeV
- 30% polarization at higher energy

Initial AGS cold snake commissioning


- extraction with 10¹¹ protons/bunch and 50% polarization

Run-5 p[↑]-p[↑] summary

Run5 RHIC Run-5 delivered p[↑]-p[↑] Luminosity




RHIC delivered luminosity




Last update: 7 July 2005

RHIC calendar time in store



Hadron collider luminosity




Note 1: For ion collisions the nucleon-pair luminosity is shown. The nucleon-pair luminosity is defined as $L_{NN} = A_1 A_2 L$, where L is the luminosity, and A_1 and A_2 are the number of nucleons of the ions in the two beam respectively.

Note 2: An upward arrow next to a particle symbol denotes polarized beam.

RHIC Run-6 plans

- 20 cryo weeks (14 1/2 weeks for physics)
- $p\uparrow$ - $p\uparrow$ at 100 GeV, 31.2 GeV, 250 GeV, (11 GeV)
- Major improvements
 - Further AGS cold snake commissioning
 - increase in polarization and bunch intensity
 - Now 430m of NEG coated beam pipes installed
 - reduction of dynamic in warm regions
 - Arc vacuum now 10^{-6} – 10^{-7} Torr before cool-down
 - reduction of dynamic in cold regions
 - 10Hz orbit feedback for IP under construction
 - likely to cause diurnal vertical orbit movements
 - IR4 triplets disconnected from ceiling
 - likely to cause diurnal vertical orbit movements

Run-6 plans



$$N_b : 0.9 \rightarrow 1.3 \times 10^{11}$$

$$n : 106 \rightarrow 111$$

$$P : 47 \rightarrow 60 \%$$

Path to RHIC II

Quantity	Unit	Design 1999	Achieved 2005	Enhanced	
				Design 2008	RHIC II ≥2012
Au⁷⁹⁺ on Au⁷⁹⁺					
Beam energy	GeV/n			— 100 —	
Number of bunches	...	60	45	— 112 —	
Bunch population, initial	10 ⁹	1.0	1.1	— 1.0 —	
β-function at IP	m	2.0	1.0	1.0	0.5
Peak luminosity	10 ²⁶ cm ⁻² s ⁻¹	12	15	32	90
Average store luminosity	10 ²⁶ cm ⁻² s ⁻¹	2	5	8	70
polarized p⁺ on polarized p⁺					
Beam energy	GeV	250	100	— 250 —	
Number of bunches	...	60	106	— 112 —	
Bunch population, initial	10 ¹¹	1.0	0.9	— 2.0 —	
β-function at IP	m	2.0	1.0	1.0	0.5
Peak luminosity	10 ³⁰ cm ⁻² s ⁻¹	15	10	220	750
Average store luminosity	10 ³⁰ cm ⁻² s ⁻¹	10	7	150	500
Average store polarization	%	—	46	70	70

Need e-cooling for these (this MAC)