

Appendix D

Drawing No.	Drawing Title
10W425-81	Existing Conditions 2004, Drawing Index, Legend & General Notes
10W425-82	Dredge Cell Lateral Expansion Site Location Plan
10W425-83	Dredge Cell Dike Restoration Plan Sheet 1
10W425-84	Dredge Cell Dike Restoration Plan Sheet 2
10W425-85	Dredge Cell Dike Restoration Plan Sheet 3
10W425-86	Dredge Cell Dike Restoration Plan Sheet 4
10W425-87	Dredge Cell Dike Restoration Partial Plan Sheet 5
10W425-88	Dredge Cell Dike Restoration Cross Section Sheet 1
10W425-89	Dredge Cell Dike Restoration Cross Section Sheet 2
10W425-90	Dredge Cell Dike Restoration Cross Section & Details Sheet 3
10W425-91	Dredge Cell Dike Restoration Details Sheet 1
10W425-92	Borrow Area Plan

KINGSTON FOSSIL PLANT

DREDGE CELL RESTORATION



STATE OF TENNESSEE
DEPARTMENT OF ENVIRONMENT AND CONSERVATION
KNOXVILLE ENVIRONMENTAL FIELD OFFICE

2700 MIDDLEBROOK PIKE, SUITE 220
KNOXVILLE, TENNESSEE 37921-5602

PHONE (865) 594-6035

STATEWIDE 1-888-891-8332

FAX (865) 594-6105

April 29, 2005

RECEIVED

MAY 12 2005

Mr. Gordon Park
Manager of Permitted Programs
Tennessee Valley Authority
1101 Market Street
Chattanooga, Tennessee 37402-2801

ENVIRONMENTAL
FOSSIL POWER GROUP

RE: Proposed modification to approved construction and operation plans - New leachate breakout remediation, collection, and transfer system for the lower west and south slopes of the Kingston Power Plant Coal Ash Fill, IDL 73-0094

Dear Mr. Park:

The revised plan for TVA Kingston Power Plant Coal Ash Fill, submitted to our office by TVA Fossil Engineering Services on April 27, 2005, has been reviewed in accordance with Rule Chapter 1200-1-7, Solid Waste Processing and Disposal. This modification consists of leachate collection trench drains at the 775, 781, and 595 elevation bench levels around the west and south sides; a toe drain and improved drainage ditch around the toe of the fill on the west side; and a new collection/retention pond with force main to a channel leading to the ash pond. The plan also calls for geonet to be installed at the toe in the vicinity of the original breakout. We find that the revised plan meets the regulatory requirements, and this design is an improvement over the temporary collection/transfer system that was installed to correct the existing problem. We agree that this revision should be considered a minor modification, and we are therefore approving the plan as submitted. In all aspects of construction and operation affected by the modification, this plan will replace and supercede the original plan.

Mr. Gordon Park
April 29, 2005
Page 2


Work may begin to install the features included with this modification at any time when the weather is suitable and the necessary equipment and materials can be mobilized to the site, but work must begin no later than June 1, 2005, in accordance with your suggested schedule. Installation of the system shall be completed not later than August 31, 2005.

An approved copy of the modified plan is enclosed for your use. If you have any questions concerning this matter, do not hesitate to contact me.

Yours truly,



Rick Brown
Environmental Engineer
Division of Solid Waste Management



Larry F. Cook
Knoxville Field Office Manager

cc: DSWM, Nashville Central Office

RSB /tvaknglcsmda.doc

minrmod

12

11

10

9

8

7

6

5

4

3

2

1

7

6

5


4

3

2

1

TEMPORARY SEDIMENT POND
(TO BE CONVERTED TO PERMANENT POND)



SWAN POND ROAD

REGRADE AND IMPROVE TOE DITCH
INSTALL UNDERDRAINS
IN SLOPE AND TOE

PLANT
ENTRANCE

TEMPORARY
SEDIMENT TRAP

REGRADE AND IMPROVE TOE DITCH

♣ NORTH DIKE
(APPROXIMATE LOCATION)
(SEE TOWNSHIP)

EXISTING ASH POND

STILLING BASIN

DRAWING INDEX

DRAWING NO.	DRAWING TITLE
10M425-81	EXISTING CONDITIONS, DRAWING INDEX, LEGEND & GENERAL NOTES
10M425-82	DREDGE CELL LATERAL EXPANSION SITE LOCATION PLAN
10M425-83	DREDGE CELL DIKE RESTORATION PLAN SHEET 1
10M425-84	DREDGE CELL DIKE RESTORATION PLAN SHEET 2
10M425-85	DREDGE CELL DIKE RESTORATION PLAN SHEET 3
10M425-86	DREDGE CELL DIKE RESTORATION PLAN SHEET 4
10M425-87	DREDGE CELL DIKE RESTORATION PLAN & SECTION SHEET 5
10M425-88	DREDGE CELL DIKE RESTORATION SECTION & DETAIL SHEET 1
10M425-89	DREDGE CELL DIKE RESTORATION SECTION & DETAIL SHEET 2
10M425-90	DREDGE CELL DIKE RESTORATION SECTION & DETAIL SHEET 3
10M425-91	DREDGE CELL DIKE RESTORATION DETAILS SHEET 1
10M425-92	DREDGE CELL DIKE RESTORATION DITCH PROFILES
10M425-93	DREDGE CELL DIKE RESTORATION BORROW AREA

NOTES

- FOR LATERAL EXPANSION DRAWING INDEX AND LEGEND, SEE DRAWING 10M425-20.
- DRAWINGS 10M425-22 AND -23 DEPICT PHASING OF EXPANSION CONSTRUCTION. CONSTRUCTION DRAWINGS BEGIN WITH 10M425-26.
- DCA DRAWINGS 10M425-81 THRU -94 ARE FOR A MINOR MODIFICATION TO THE PERMIT.

LEGEND

EXISTING	NEW
	NA
	580
	NA
	NA
	NA
	SD-15'
	UD-8'
	FM-6'
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	430.5
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA
	NA

COMPARISON DRAWINGS
15B007, 15B008

DATE	DESCRIPTION
10/01/08	ISSUED FOR PERMIT
10/01/08	ISSUED FOR PERMIT
10/01/08	ISSUED FOR PERMIT
10/01/08	ISSUED FOR PERMIT
10/01/08	ISSUED FOR PERMIT

12
11
10
9
8
7
6
5
4
3
2

A

B

C

D

E

F

NO. 0	DATE	DESCRIPTION
0	10/15/68	INITIAL PLAN
1	11/15/68	REVISED PLAN
2	12/15/68	REVISED PLAN
3	1/15/69	REVISED PLAN
4	2/15/69	REVISED PLAN
5	3/15/69	REVISED PLAN
6	4/15/69	REVISED PLAN
7	5/15/69	REVISED PLAN
8	6/15/69	REVISED PLAN
9	7/15/69	REVISED PLAN
10	8/15/69	REVISED PLAN
11	9/15/69	REVISED PLAN
12	10/15/69	REVISED PLAN

PROJECT TITLE		DRUDGE CELL LATERAL EXPANSION
SITE LOCATION		KINGSTON FOSSIL PLANT
NO.	DATE	DESCRIPTION
0	10/15/68	INITIAL PLAN
1	11/15/68	REVISED PLAN
2	12/15/68	REVISED PLAN
3	1/15/69	REVISED PLAN
4	2/15/69	REVISED PLAN
5	3/15/69	REVISED PLAN
6	4/15/69	REVISED PLAN
7	5/15/69	REVISED PLAN
8	6/15/69	REVISED PLAN
9	7/15/69	REVISED PLAN
10	8/15/69	REVISED PLAN
11	9/15/69	REVISED PLAN
12	10/15/69	REVISED PLAN

DESIGNED BY	DATE	DESCRIPTION
W. J. BERRY	10/15/68	INITIAL PLAN
CHECKED BY	DATE	DESCRIPTION
J. W. BERRY	11/15/68	REVISED PLAN
APPROVED BY	DATE	DESCRIPTION
W. J. BERRY	12/15/68	REVISED PLAN
SCALE	DATE	DESCRIPTION
AS SHOWN	10/15/68	INITIAL PLAN

NO.	DATE	DESCRIPTION
0	10/15/68	INITIAL PLAN
1	11/15/68	REVISED PLAN
2	12/15/68	REVISED PLAN
3	1/15/69	REVISED PLAN
4	2/15/69	REVISED PLAN
5	3/15/69	REVISED PLAN
6	4/15/69	REVISED PLAN
7	5/15/69	REVISED PLAN
8	6/15/69	REVISED PLAN
9	7/15/69	REVISED PLAN
10	8/15/69	REVISED PLAN
11	9/15/69	REVISED PLAN
12	10/15/69	REVISED PLAN

NO.	DATE	DESCRIPTION
0	10/15/68	INITIAL PLAN
1	11/15/68	REVISED PLAN
2	12/15/68	REVISED PLAN
3	1/15/69	REVISED PLAN
4	2/15/69	REVISED PLAN
5	3/15/69	REVISED PLAN
6	4/15/69	REVISED PLAN
7	5/15/69	REVISED PLAN
8	6/15/69	REVISED PLAN
9	7/15/69	REVISED PLAN
10	8/15/69	REVISED PLAN
11	9/15/69	REVISED PLAN
12	10/15/69	REVISED PLAN


NO.	DATE	DESCRIPTION
0	10/15/68	INITIAL PLAN
1	11/15/68	REVISED PLAN
2	12/15/68	REVISED PLAN
3	1/15/69	REVISED PLAN
4	2/15/69	REVISED PLAN
5	3/15/69	REVISED PLAN
6	4/15/69	REVISED PLAN
7	5/15/69	REVISED PLAN
8	6/15/69	REVISED PLAN
9	7/15/69	REVISED PLAN
10	8/15/69	REVISED PLAN
11	9/15/69	REVISED PLAN
12	10/15/69	REVISED PLAN

NO.	DATE	DESCRIPTION
0	10/15/68	INITIAL PLAN
1	11/15/68	REVISED PLAN
2	12/15/68	REVISED PLAN
3	1/15/69	REVISED PLAN
4	2/15/69	REVISED PLAN
5	3/15/69	REVISED PLAN
6	4/15/69	REVISED PLAN
7	5/15/69	REVISED PLAN
8	6/15/69	REVISED PLAN
9	7/15/69	REVISED PLAN
10	8/15/69	REVISED PLAN
11	9/15/69	REVISED PLAN
12	10/15/69	REVISED PLAN

NO.	DATE	DESCRIPTION
0	10/15/68	INITIAL PLAN
1	11/15/68	REVISED PLAN
2	12/15/68	REVISED PLAN
3	1/15/69	REVISED PLAN
4	2/15/69	REVISED PLAN
5	3/15/69	REVISED PLAN
6	4/15/69	REVISED PLAN
7	5/15/69	REVISED PLAN
8	6/15/69	REVISED PLAN
9	7/15/69	REVISED PLAN
10	8/15/69	REVISED PLAN
11	9/15/69	REVISED PLAN
12	10/15/69	REVISED PLAN

TOPOGRAPHY TRACED BY M.P. TERMON / 05/1981

SITE PLAN- KINGSTON FOSSIL PLANT



12
11
10
9
8
7
6
5
4
3
2
1

A

B

C

D

E


F

G


H

12
11
10
9
8
7
6
5
4
3
2
A B C D E F G H

- NOTES:
1. FOR PERMIT MINOR MODIFICATION DRAWING INDEX AND LEGEND, SEE DRAWING 10W425-81. FOR GENERAL NOTES, SEE 10W425-20.
 2. ALL WORK SHALL COMPLY WITH THE APPROVED STORMWATER POLLUTION PREVENTION PLAN & CONSTRUCTION STORMWATER PERMIT.
 3. WELLS SHALL BE INSTALLED AFTER UNDERDRAINS, AND PRIOR TO DREDGING ACTIVITIES. VERIFY THAT WELL LOCATIONS DO NOT INTERFERE WITH UNDERDRAINS AND LATERALS.
 4. NOT USED.
 5. REPORT IMMEDIATELY TO TVA FES ANY SIGNS OF SEEPAGE THRU THE DIKE, OR IF SATURATED GROUND CONDITIONS SUDDENLY EXIST.
 6. NOTIFY TENNESSEE ONE CALL (800) 351-1111 PRIOR TO PERFORMING ANY EXCAVATION ADJACENT TO SWAN POND ROAD.
 7. EXISTING CONTOURS ON SLOPE OF EXISTING DREDGE CELL (BELOW EL. 810) HAVE AN EXISTING 1' SOIL COVER LAYER.
 8. USE CAUTION DURING DITCH CONSTRUCTION AROUND MONITORING WELLS 4A, 4B, 5A AND 5B.





DATE	08/27/2008	BY	JONATHAN D. BROWN
PROJECT	BRANWINE SW BRANWINE SK BRANWINE-85	DESIGNED BY	JONATHAN D. BROWN
CLIENT	TVA	CHECKED BY	JONATHAN D. BROWN
SCALE	AS SHOWN	DATE	08/27/2008
PROJECT NO.	10W425-81	PROJECT TITLE	DREDGE CELL DIKE RESTORATION
DRAWING NO.	10W425-81	DRAWING TITLE	PLAN SHEET 1
SCALE	AS SHOWN	DATE	08/27/2008
PROJECT	BRANWINE SW BRANWINE SK BRANWINE-85	DESIGNED BY	JONATHAN D. BROWN
CLIENT	TVA	CHECKED BY	JONATHAN D. BROWN
SCALE	AS SHOWN	DATE	08/27/2008
PROJECT NO.	10W425-81	PROJECT TITLE	DREDGE CELL DIKE RESTORATION
DRAWING NO.	10W425-81	DRAWING TITLE	PLAN SHEET 1



1
2
3
4
5
6
7
8
9
10
11
12

12
11
10
9
8
7
6
5
4
3
2
1

A B C D E F



- GRADING NOTES:
1. FOR PERMIT MINOR MODIFICATION DRAWING INDEX AND LEGEND, SEE DRAWING 10W425-81. FOR CONSTRUCTION NOTES, SEE 10W425-83.
 2. INSTALL SILT FENCE IMMEDIATELY BEHIND GUARDRAILS ON SWAN POND ROAD.
 3. PRECAST LIFT STATION TO BE INSTALLED DURING POND CONSTRUCTION. RELOCATE EXISTING SUBMERSIBLE PUMPS TO THE PERMANENT LIFT STATION. (INCLUDING TEMPORARY AND PERMANENT STRUCTURES).
 4. PROVIDE RIPRAP AT END OF FORCE MAIN FOR EROSION PROTECTION. SIZE: D₅₀ = 6 INCHES. THICKNESS = 1 FT.
 5. CONSTRUCT THE NEW POND PRIOR TO DISTURBING OR REMOVING EXISTING UNDERDRAINS & ELECTRICAL SERVICE. THE POND SHALL FUNCTION AS A TEMPORARY SEDIMENT BASIN DURING CONSTRUCTION, AND WILL BE CONVERTED TO A PERMANENT POND AT THE COMPLETION OF CONSTRUCTION.
 6. THE EXISTING CONCRETE SUMP SHALL BE REMOVED.

PROJECT NO.	10W425-84
DATE	10/24/83
PROJECT NAME	DREDGE CELL DIKE RESTORATION
PLANNING	10W425-84
DESIGN	10W425-84
CONSTRUCTION	10W425-84
OPERATION	10W425-84
MAINTENANCE	10W425-84
OWNER	US ARMY CORPS OF ENGINEERS
DESIGNED BY	W.A. [unclear]
CHECKED BY	[unclear]
DATE	10/24/83
SCALE	AS SHOWN
UNIT	FEET

DRAWING CHANGE AUTHORIZATION

NEW POND (SEE NOTE 5)

LIMITS OF SOIL STRIPPING

FOR DITCH FINISHED GRADE ELEVATIONS AND SLOPE, SEE PROFILES ON 10W425-82

DITCH D1 (DETAIL 687)

EXISTING CONCRETE GROUP (ABANDON OR REMOVE) REMOVE EXISTING HIPE SD (SEE NOTE 6)

LIMIT OF COMPOSITE GENET

EXISTING UNDERDRAINS (SEE 10W425-2 & 4 FOR ORIGINAL CONSTRUCTION)

DO NOT STRIP SOIL ON DIKES FOR CELL 2

NEW UNDERDRAINS (SEE 10W425-6)

EXISTING UNDERDRAINS @ EL. 795 ± (CELLS 1 & 3) (NOT SHOWN FOR CLARITY) FOR INSTALLATION DETAILS SEE 10W425-6

DREDGE CELL NO 2

DREDGE CELL NO 3



NEW MONITORING WELL (DETAIL 691) (TYPE SEE NOTE 3, 10W425-83)

N 557299.07
E 2440997.32

N 557351.46
E 2441046.81

N 557393.15
E 2441086.21


MATCHLINE A. SEE 10W425-83



KEY PLAN

GENERAL NOTES
 1. FOR PERMIT MINOR MODIFICATION DRAWING INDEX AND LEGEND, SEE DRAWING 10W425-81. FOR CONSTRUCTION NOTES, SEE 10W425-83.


DRAWING CHANGE AUTHORIZATION		PROJECT INFORMATION	
No.	1	Project No.	10W425-86
Date		Contract No.	10W425-86
By		Contract Name	Engineering
Checked		Contract No.	10W425-86
Approved		Contract Name	Engineering
Project	DREDGE CELL RESTORATION	Contract No.	10W425-86
Sheet	PLAN SHEET 4	Contract Name	Engineering
Scale		Contract No.	10W425-86
Author		Contract Name	Engineering
Checker		Contract No.	10W425-86
Designer		Contract Name	Engineering
Engineer		Contract No.	10W425-86
Surveyor		Contract Name	Engineering
Unit	CIVIL	Contract No.	10W425-86
Unit No.	1-2	Contract Name	Engineering




NO.	DATE	DESCRIPTION	BY	CHECKED
1	10/14/25-84	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS
2	10/14/25-84	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS
3	10/14/25-84	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS
4	10/14/25-84	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS
5	10/14/25-84	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS

- NOTES:**
1. AT THE END OF CONSTRUCTION, REMOVE RIPRAP RING.
 2. REMOVE ACCUMULATED SEDIMENT WHEN LEVEL EXCEEDS THE SEDIMENT CLEANOUT LEVEL SHOWN ON DETAIL E91.
 3. REMOVE ACCUMULATED SEDIMENT IN POND AT THE END OF CONSTRUCTION.
 4. PLACE CLAY LINER AND RIPRAP LINING IN POND AT THE END OF CONSTRUCTION.
 5. RIPRAP PLACED ON SLOPE SHALL BE UNDERLAIN WITH GEOTEXTILE AND HAND PLACED, TO PREVENT ROCK FROM BEING PLACED INTO SWAN POND EMBAYMENT.
 6. STRIP OR CUT VEGETATION PRIOR TO INSTALLING EMERGENCY SPILLWAY.
 7. EXISTING UNDERGROUND UTILITIES ARE NOT SHOWN. CONSTRUCTOR SHALL TEMPORARILY RELOCATE UNDERGROUND UTILITIES TO THE EXISTING SWAN POND EMBAYMENT PRIOR TO CONSTRUCTION OF THE EMERGENCY SPILLWAY. (AS REQUIRED) TO CONSTRUCT POND. FOLLOW PROPER LOCKOUT/TAGOUT PROCEDURES.

SEE DRAWING 10W425-84
PARTIAL PLAN 2
SCALE 1"=20'



SECTION A87
SCALE: HORIZONTAL 1"=5'
VERTICAL 1"=10'




PARTIAL PLAN 1
SCALE 1"=50'

NO.	DATE	DESCRIPTION	BY	CHECKED
1	10/14/25-87	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS
2	10/14/25-87	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS
3	10/14/25-87	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS
4	10/14/25-87	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS
5	10/14/25-87	ISSUED FOR CONSTRUCTION	J. L. HARRIS	J. L. HARRIS

DRIVEWAY CELL DIKE RESTORATION
PLAN & SECTION SHEET 5

PROJECT NO. 10W425-87
SHEET NO. 5
DATE 10/14/25-87
UNIT 1-9



12 11 10 9 8 7 6 5 4 3 2 1

A B C D E F G H

900 890 880 870 860 850 840 830 820 810 800 790 780 770 760 750 740 730 720 710 700

1+00 2+00 3+00 4+00 5+00 6+00 7+00 8+00 9+00 10+00 11+00 12+00 13+00 14+00 15+00 16+00 17+00 18+00

EXISTING UNDERDRAINS IN DIKE ABOVE EL 795 FOR CELL 3 NOT SHOWN FOR CLARITY. SEE 10W425-6.

FUTURE PERIMETER DRAIN (TYP)

TOP OF GROUND EL 810.71

MW-3

TOP OF GROUND EL 804.121 (APPROX LOCATION)

MW-5

EXISTING GROUND ELEVATION (2005)

STRIP EXISTING SOIL COVER, PLACE COMPOSITE GEONET & PLACE 1 FT COMPACTED CLAY SOIL ON COMPOSITE GEONET

SECTION A88

SCALE: HORIZONTAL: 1" = 30'

VERTICAL: 1" = 20'

NOTES:

- FOR DRAWINGS LIST AND LEGEND SEE 10W425-81.
- FOR GENERAL NOTES SEE 10W425-26. FOR CONSTRUCTION NOTES, SEE 10W425-83.
- BETWEEN EL 760 & 775, STRIP EXISTING 1'-0" SOIL COVER WITHIN THE LIMITS SHOWN ON DRAWINGS 10W425-83 THRU 10W425-86, PRIOR TO INSTALLING FINAL COVER STOCK PILE SOIL AND REUSE AS RANDOM FILL VEGETATIVE LAYER FOR FINAL COVER.
- DETAIL PERFORM SECTION THROUGH EXISTING DREDGE CELLS ADJACENT TO SWAN POND ROAD. BASE ELEVATION OF DREDGE CELL VARIES.
- UNDERDRAINS ARE NOT REQUIRED FOR EXISTING DIKE CONSTRUCTED FOR DREDGE CELL 2.
- LATERAL OUTLET PIPE SHALL BE NON-PERFORATED POLYETHYLENE CORRUGATED TUBING AS MANUFACTURED BY ADVANCED DRAINAGE SYSTEMS, INC., COLUMBUS, OHIO (614) 457-3051 OR EQUAL.
- LATERAL OUTLET PIPES SHALL BE PLACED EVERY 200 FEET ON CENTER, AT LOW POINTS. FOR PROFILE OF DRAINS, SEE 10W425-94.
- GEOTEXTILE USED FOR UNDERDRAIN SHALL BE A WOVEN MONOFILAMENT WITH AN APPARENT OPENING SIZE (AOS) SELECTED BY VA FES (US STANDARD SIEVE SIZE) WHEN TESTED IN ACCORDANCE WITH ASTM 4753. GEOTEXTILE SHALL BE GEOTEX 10P AS MANUFACTURED BY SYNTHETIC INDUSTRIES OR APPROVED EQUAL.
- WATER LEVELS SHOWN ARE THOSE EXISTING AFTER MW DEVELOPMENT.

SCREENING FOR BORE HOLE CONVERTED TO MW.

DETAIL B88

PERIMETER UNDERDRAIN

SCALE: 1" = 1'-0"

EXISTING GRADE

1081 CRUSHED STONE

8" UNDERDRAIN PIPE


GEOTEXTILE

8" MIN OVERLAP

DATE	10/15/2008	BY	10W425-85
PROJECT	DREDGE CELL DIKE RESTORATION SECTION & DETAIL SHEET 1		
CLIENT	KINGSTON FOSSIL PLANT		
DESIGNER	KINGSTON FOSSIL PLANT		
CHECKED	KINGSTON FOSSIL PLANT		
APPROVED	KINGSTON FOSSIL PLANT		
DATE	10/15/2008	BY	10W425-85
PROJECT	DREDGE CELL DIKE RESTORATION SECTION & DETAIL SHEET 1		
CLIENT	KINGSTON FOSSIL PLANT		
DESIGNER	KINGSTON FOSSIL PLANT		
CHECKED	KINGSTON FOSSIL PLANT		
APPROVED	KINGSTON FOSSIL PLANT		
DATE	10/15/2008	BY	10W425-85
PROJECT	DREDGE CELL DIKE RESTORATION SECTION & DETAIL SHEET 1		
CLIENT	KINGSTON FOSSIL PLANT		
DESIGNER	KINGSTON FOSSIL PLANT		
CHECKED	KINGSTON FOSSIL PLANT		
APPROVED	KINGSTON FOSSIL PLANT		

- NOTES:**
- FOR DRAWINGS LIST AND LEGEND SEE 10W425-81.
 - FOR NOTES SEE 10W425-88.

— SCREENING FOR BORE HOLE CONVERTED TO MIN.




SECTION A89
SCALE: HORIZONTAL: 1" = 30'
VERTICAL: 1" = 20'


DRAWING CHANGE AUTHORIZATION

PROJECT No.		10W425-89	
DATE	BY	DATE	BY
10/15/08	MM	10/15/08	MM
PROJECT No.		10W425-81	
SHEET No.		SECTION SHEET 2	
OWNER		KONISTON FOSSEL PLANT	
DESIGNER		CIVIL	
CHECKED		N/A	
APPROVED		N/A	
DATE		09/15	
SCALE		AS SHOWN	


1 2 3 4 5 6 7 8 9 10 11 12



NOTES:
 1. FOR DRAWINGS LIST AND LEGEND SEE 10W425-81.
 2. FOR NOTES SEE 10W425-88.




BARBED WIRE ARM
N.T.S.









BASE DETAIL
N.T.S.

- CHAIN LINK NOTES:
1. ALL FENCING WORK SHALL BE DONE IN ACCORDANCE WITH STANDARD INDUSTRY PRACTICE.
 2. STRUCTURAL STEEL SHAPES SHALL BE ASTM A 36.
 3. CONCRETE SHALL BE CLASS "B" PER SECTION 400 OF THE GENERAL CONSTRUCTION SPECIFICATION NO. 11.
 4. FENCING TO BE 7-FEET #9 ZINC COATED TYPE 2 CHAIN LINK FENCE FABRIC WITH #7 ZINC COATED BOTTOM TAUGHT WIRE. MATERIAL AND INSTALLATION SHALL BE IN ACCORDANCE WITH CHAIN LINK FENCE MANUFACTURERS INSTITUTE. INDUSTRIAL FENCE FRAMING SHALL COMPLY WITH ASTM F1043. DESIGN GROUP TCF AND INCLUDE POSTS, BRACING, TOP RAILS, STRETCHER BARS, TRUSS RODS, AND TENSION WIRE.
 5. ALL POSTS AND OTHER APPURTENANCES SHALL BE HOT DIP GALVANIZED.
 6. ALL DAMAGED GALVANIZING SHALL BE REPAIRED BY USE OF ZINC PAINT.
 7. FIELD WORK FOR ELECTRICAL GROUNDING: GROUND FENCE AT APPROXIMATELY 125 FEET INTERVALS BY CLAMPING 2/0 GROUND CABLE TO FENCE POSTS AND TERMINATE CABLE TO 5/8" 8'-0" GROUND ROD LOCATED APPROXIMATELY 2'-0" INSIDE FENCE, DRIVEN SO THAT THE TOP OF GROUND ROD IS 8" BELOW GRADE SURFACE; SIMILARLY, GROUND ALL CORNER AND END POSTS.
 8. BARBED WIRE TO BE ALUMINUM COATED STEEL.



DETAIL B90 - CHAIN LINK FENCE
TYPICAL PANELS
N.T.S.

PROJECT NO.	10W425-80
SECTION	SECTION & DETAILS SHEET 3
DATE	10/10/2008
DESIGNED BY	DR. S. J. HUNTER
CHECKED BY	M/A
SCALE	AS SHOWN
DATE	10/10/2008
UNIT	1-9



REVISIONS

NO.	DATE	DESCRIPTION
1	11/17/2008	ISSUED FOR PERMIT
2	01/07/2009	REVISED TO REFLECT PERMIT COMMENTS
3	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
4	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
5	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
6	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
7	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
8	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
9	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
10	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
11	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
12	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS

PROJECT INFORMATION





















NO.	DATE	DESCRIPTION
1	11/17/2008	ISSUED FOR PERMIT
2	01/07/2009	REVISED TO REFLECT PERMIT COMMENTS
3	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
4	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
5	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
6	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
7	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
8	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
9	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
10	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
11	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
12	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS

PROJECT INFORMATION

NO.	DATE	DESCRIPTION
1	11/17/2008	ISSUED FOR PERMIT
2	01/07/2009	REVISED TO REFLECT PERMIT COMMENTS
3	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
4	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
5	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
6	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
7	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
8	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
9	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
10	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
11	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
12	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS

PROJECT INFORMATION

NO.	DATE	DESCRIPTION
1	11/17/2008	ISSUED FOR PERMIT
2	01/07/2009	REVISED TO REFLECT PERMIT COMMENTS
3	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
4	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
5	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
6	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
7	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
8	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
9	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
10	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
11	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS
12	03/02/2009	REVISED TO REFLECT PERMIT COMMENTS



NOTES:

- FOR COMPOSITE GEONET INSTALLATION, SEE SPECIFICATION KIT-02-0822.
- LATERAL DRAIN TO DAYLIGHT SLOPE.

NOTES:

- REMOVE SEDIMENT WHEN SEDIMENT HEIGHT IS ONE-HALF THE HEIGHT OF THE SEDIMENT TRAP.

NOTES:


- ELEVATIONS ARE FOR PERMANENT POND OPERATION.
- CHECK VALVE IS 4" A/C 525C W/ LEVER AND WEIGHT. DUCTILE IRON BODY W/ BRONZE VALVE OR EQUAL.

NOTES:

- INSTALL FENCE POSTS IN SPILLWAY
- INSTALL FENCE UNDERBENEATH FENCE FABRIC


NOTES:

- REMOVE SEDIMENT WHEN SEDIMENT HEIGHT IS ONE-HALF THE HEIGHT OF THE SEDIMENT TRAP.



DRAWING CHANGE AUTHORIZATION


PROFILE DITCH D1 & D1A



PROFILE DITCH D13 & D13A

PROFILE DITCH D1A

PROFILE DITCH D1 & D1A



PROFILE DITCH D17

KINGSTON FOSILL PLANT	
Project No.	10445-92
Contract No.	N/A
Design Reference	N/A
Approved Date	10/17/00
Drawn By	JCH
Checked By	JCH
Scale	AS SHOWN
Sheet No.	13
Unit	FT

12
11
10
9
8
7
6
5
4
3
2
1

A B C D E F

A B C D E F G H



PROJECT NO.	1000
PROJECT NAME	PRELIMINARY EROSION CONTROL RESTORATION BORROW AREA
DATE	10/10/2008
BY	E. L. DOWNS-BS
CHECKED BY	UNISTON FOSSEL PLANT
DESIGNED BY	
PROJECT NO.	N/A
SCALE	N/A
DATE	10/10/2008
BY	
CHECKED BY	
PROJECT NO.	1000
PROJECT NAME	PRELIMINARY EROSION CONTROL RESTORATION BORROW AREA
DATE	10/10/2008
BY	E. L. DOWNS-BS
CHECKED BY	UNISTON FOSSEL PLANT
DESIGNED BY	
PROJECT NO.	N/A
SCALE	N/A
DATE	10/10/2008
BY	
CHECKED BY	

2 442 000
2 443 000
2 444 000

TVA/COO		FORM A - DESIGN CHANGE NOTICE			Page 1 of 2	
1. a. DCN Type <input type="checkbox"/> Base DCN <input checked="" type="checkbox"/> PIC for Base/ Parent DCN No.: KIF-05-1090		b. Class Routine Design Change <input type="checkbox"/> Documentation Only <input type="checkbox"/> Material Equivalency <input type="checkbox"/> c. Advance Authorization <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		2. DCN No. KIF-05-1090 <i>12-99</i>	Rev. 0	3. Plant/TL/SUB/Facility KIF
		3. Unit/TL/SUB No. 1-9		4. System(s) 14,114		

PART I - REQUESTED CHANGE

5. Authorizing Documents	KIF530				
6. Requested Change or Problem Statement	Due to unanticipated design and construction issues, design changes within the PIC criteria is anticipated to track configuration control of the plant. This PIC is initiated as a mechanism for releasing the changes				
7. Initiator's Name (Print)	Gary Melton	Organization	Parsons E&C	Phone	757-9974
				8. Supervisor/Principal Engr	William M. Lytle
					6/3/05

PART II - INITIATION APPROVAL

(Skip blocks 9 and 10 for Advance Authorization Approval)

9. INITIATOR'S DEPARTMENT MANAGER	Reviewed	Date	10. ENGRG/OPERATIONS MANAGER	Approved	Date

PART III - APPROVED CHANGE/DETAILED DESIGN

11. Approved Change Description	<input type="checkbox"/> Planned at Initiation	<input type="checkbox"/> As Issued (If different than planned, line through below and update on continuation sheet.)
The changes included in this DCN involve various field and design changes. See individual AA's for field changes.		
12. Advanced Authorization Approval (If applicable, otherwise mark N/A.)	RE or Manager	Date
	<i>K91.2 PATT FOR REP</i>	6-7-05
13. Does this change contain any assumptions or constraints that require confirmation before RTO?	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
14. Does this change address the full scope of the authorizing document?	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
15. RE	Phone	Date
<i>M. Melton</i>	757-2783	6/2/05
16. Civil Lead		Date
<i>R. E. P...</i>		6/7/05
17. Electrical/I&C Lead		Date
N/A		
18. Mechanical Lead		Date
N/A		
19. Operations		Date
N/A		
20. Maintenance		Date
N/A		
21. System Engineer		Date
N/A		
22. Implementing Organization		Date
N/A		
23. Telecommunications		Date
N/A		
25. Plant/Site Manager		Date
N/A		
24. Engrg or Site Engrg Manager		Date
N/A		
26. ISSUE EDMS #		

PART IV - DCN CLOSURE

27. Facility Manager or Engrg Manager	Date	29. CLOSURE EDMS #
28. RE Signature for DCN Closure	Date	
<i>M. Melton</i>	11/1/05	

Mark "N/A" in any blocks not applicable.

ADVANCE AUTHORIZATION FORM

AA-01	Parent DCN: KIF - 05 - 1090	FTS:	
	Parent PIC: KIF - 05 - 1099	Responsible Design Engineer/ORG/Phone:	Dan Smith /(423)757-8088

Requested Change or Problem:



1. Surveyors requested additional points to locate centerline of ditches at toe of existing ash dike.
2. Revise specification KIF-0-TS-02621 to clarify bottom woven (calendared) geotextile in lieu of non-woven geotextile. The specification was originally written for the permit application and portions of the cover can utilize non-woven on top and bottom of geonet. The specification addressed the calendared geotextile (where shown on drawings). While this statement is applicable for the permit application, the composite geonet for this installation should address only the calendared geotextile on the bottom of the composite geonet.

Suggested Solution (not required):

1. See revised DCA sketches to this AA.
2. See revised specification KIF-0-TS-2621 R1.

Approved Change

See suggested solution.

Resp. Engineer:		6/3/05	Supv.		6/1/05
	Signature	Date		Signature	Date

DANIEL R. SMITH

ADVANCE AUTHORIZATION FORM

AA-02	Parent DCN: KIF - 05 - 1090	FTS:
	Parent PIC: KIF - 05 - 1099	Responsible Design Engineer/ORG/Phone: Dan Smith / (423)757-8088

Requested Change or Problem:



1. Revise spillway as shown. Due to a difference in topography (pre construction vs. post construction), the spillway needs to be lowered to ensure the upstream ditch does not overtop. The pond will not discharge a 25-yr storm event with the pumps running.

Suggested Solution (not required):

1. See revised DCA sketches to this AA.

Approved Change

See suggested solution.

Resp. Engineer:		7/27/05 7/27/05	Supv.		7/27/05
	Signature	Date		Signature	Date

FORM G - ADVANCE AUTHORIZED TRACKING SHEET

AA- 02 PIC# KIF - 05 - 1099 Page _____ of _____

Block 6 - Requested Change

Revise spillway as shown. Due to a difference in topography (pre construction vs. post construction), the spillway needs to be lowered to ensure the upstream ditch does not overtop. The pond will not discharge a 25-yr storm event with the pumps running.

Block 11 - Approved Change


See revised DCA sketches to this AA

Supv/Prin Egrn: _____
Signature Date

RE: *Michael D. Dyer* 7/27/05
Signature Date

NON-NOVEN
GEOFILE

DETAIL J91
DITCH D13
N.T.S.



DETAIL L91
EMERGENCY SPILLWAY
N.T.S.

PIC: KIF-05-1099

AA# 02

KIF 0201 PIC - KIF - 05 - 1099 TO DCN 1090

ADVANCE AUTHORIZATION FORM

AA-03	Parent DCN: KIF - 05 - 1090	FTS:
	Parent PIC: KIF - 05 - 1099	Responsible Design Engineer/ORG/Phone: Dan Smith (423)757-8088

Requested Change or Problem:



1. Revise specification KIF-0-TS-02621 to clarify bottom non-woven geotextile.

Suggested Solution (not required):

1. See revised specification KIF-0-TS-2621 R2.

Approved Change

See suggested solution.

Resp. Engineer:	 Signature	9/17/05 Date	Supv.	 Signature	9/18/05 Date
-----------------	--	-----------------	-------	---	-----------------

**APPENDIX 2 TO FORM C DCN KIF-05-1090
KINGSTON FOSSIL PLANT DREDGE CELL RESTORATION**

SPECIFICATION KIF-0-TS-02621

REVISION 2

FOR

GEOCOMPOSITE DRAINAGE LAYER

SECTION KIF-0-TS-02621
GEOCOMPOSITE DRAINAGE LAYER

TABLE OF CONTENTS

<u>ARTICLE</u>	<u>TITLE</u>	<u>SHEET</u>
1.0	PART 1 – GENERAL	02621-1
1.1	SECTION INCLUDES	02621-1
1.2	CODES AND STANDARDS	02621-1
1.3	SUBMITTALS	02621-2
1.4	PACKAGING AND DELIVERY	02621-2
1.5	HANDLING, STORAGE, AND PROTECTION	02621-2
2.0	PART 2 – PRODUCTS	02621-3
2.1	MATERIALS	02621-3
3.0	PART 3 – EXECUTION	02621-5
3.1	INSTALLER REQUIREMENTS	02621-5
3.2	GEOCOMPOSITE DRAINAGE LAYER INSTALLATION	02621-5
3.3	COVER PLACEMENT	02621-6
3.4	REPAIR	02621-6
3.5	INTERFACE-FRICTION TESTING	02621-8
	TABLE 02621-1 - DATA REQUIREMENTS AND SUBMITTAL SCHEDULE	02621-8
	END	

PART 1 - GENERAL

1.1 SECTION INCLUDES

- A. This Section covers technical requirements for furnishing and installing the geocomposite drainage layer.
- B. This Section includes the following:
 - 1. Geocomposite panel layout.
 - 2. Furnishing and installing geocomposite.
 - 3. Supervision of geocomposite installation by liner manufacturer's representative.
 - 4. Construction of fill to be placed on geocomposite.
 - 5. Submittal of data per Table 02621-1.

1.2 CODES AND STANDARDS

- A. The latest edition and published addenda of the following publications in effect on the date of Contract Award are a part of this Section and, where referred to by title or by basic designation only, are applicable to the extent indicated by the specific reference:
 - 1. American Society for Testing and Materials (ASTM):
 - a. D 1505, "Standard Test Method for Density of Plastics by the Density-Gradient Technique."
 - b. D 1603, "Standard Test Method for Carbon Black in Olefin Plastics."
 - c. D 4355, "Standard Test Method for Deterioration of Geotextiles by Exposure to Light, Moisture and Heat in a Xenon Arc Type Apparatus."
 - d. D 4491, "Standard Test Method for Water Permeability of Geotextiles by Permittivity."
 - e. D 4716, "Standard Test Method for Determining the (In-Plane) Flow Rate Per Unit Width and Hydraulic Transmissivity of a Geosynthetic Using a Constant Head."
 - f. D 4751, "Standard Test Method for Determining Apparent Opening Size of a Geotextile."
 - g. D 4833, "Standard Test Method for Index Puncture Resistance of Geotextiles, Geomembranes and Related Products."
 - h. D 5035, "Standard Test Method for Breaking Force and Elongation of Textile Fabrics (Strip Method)."

GEOCOMPOSITE DRAINAGE LAYER

- i. D 5199, "Standard Test Method for Measuring Nominal Thickness of Geotextiles and Geomembranes."
 - j. D 5261, "Standard Test Method for Measuring the Mass per Unit Area of Geotextiles."
 - k. D 5321, "Standard Test Method for Determining the Coefficient of Soil and Geosynthetic or Geosynthetic and Geosynthetic Friction by the Direct Shear Method."
2. Geosynthetic Research Institute (GRI), GC-7, "Determination of Adhesion and Bond Strength of Geocomposites."
- B. Where the above referenced codes and standards contain recommendations in addition to requirements, the recommendations shall be considered requirements and shall be followed unless stated otherwise by this technical specification Section.
 - C. In the event of any conflict between codes, or Technical Specifications and codes, the more stringent regulation shall apply.

1.3 SUBMITTALS

Submittals shall be as required in Table 02621-1.

1.4 PACKAGING AND DELIVERY

All geocomposites shall be covered during shipment. The geocomposite shall be supplied in rolls, labeled with at least the following information:

Manufacturer's Name

Product Identification

Roll Number

Roll Weight

Roll Dimensions

Date of Manufacture

Geotextile Types

Geotextile Bonding

1.5 HANDLING, STORAGE, AND PROTECTION

- A. The geocomposite rolls shall be stored on pallets in a secured area, away from dirt, dust, water, and extreme heat. The storage space shall be protected from theft, vandalism, animals, passage of vehicles, and be adjacent to the area to be lined. Stack geocomposite drainage layer material to a height not exceeding four (4) rolls high. The Contractor shall

be responsible for unloading and storing the geocomposite in accordance with the manufacturer's recommendations.

- B. Upon arrival at the jobsite, the installer shall conduct a surface inspection of all rolls for defects and damage. This inspection shall be conducted without unrolling or unpacking unless defects or damages are found or suspected. The Contractor shall notify the Owner of any defects or damages.

PART 2 – PRODUCTS

2.1 MATERIALS

A. Manufacturer Requirements

1. The manufacturer of the geocomposite materials shall have had at least 10,000,000 square feet of its material installed for drainage and shall be approved by the Owner.
2. The geocomposite installation shall be performed under the supervision of the manufacturer's field representative or an installer approved by the manufacturer. The method of installation shall be approved by the manufacturer and authorized in writing, and submitted for approval before work begins to ensure that all warranties remain valid.

B. General Requirements

1. Geonet shall be manufactured by extruding two sets of polyethylene strands to form a three dimensional structure to provide planer water flow.
2. The geonet shall contain stabilizers to prevent ultraviolet light degradation.
3. The drainage layer shall be provided as a geocomposite manufactured by heat bonding 6 oz/yd² nonwoven geotextile on the top of the geonet. For bottom geotextile, see paragraph 4 below. The bond shall be continuous with no unbonded areas. No burn through the geotextiles will be permitted. Glue and adhesives shall not be used. Geocomposite shall be FabriNet as manufactured by GSE Lining Technology, Inc. or approved equivalent. The geocomposite shall meet the following properties:

R1

GEOCOMPOSITE DRAINAGE LAYER

Characteristics	Test Method	Units	Criteria (MARV)
<i>Resin</i>			
Polymer Density	ASTM D 1505	g/cm ³	0.94
Melt Flow Index	ASTM D 1238	g/10 min	≤1.0
<i>Geonet Test</i>			
Carbon Black	ASTM D 1603	%	2.0
Tensile Strength, MD	ASTM D 5035	lbs/ ft	45
Density	ASTM D 1505	g/cm ³	0.94
Thickness	ASTM D 5199	mil	200
<i>Non-Woven Geotextile Tests (Upper Geotextile)</i>			
Mass per Unit Area	ASTM D 5261	oz/yd ²	6.0
Grab Tensile	ASTM D 4632	lbs.	170
Puncture	ASTM D 4833	lbs.	90
AOS, US Sieve	ASTM D 4751	mm	70
Water Flow Rate	ASTM D 4491	gpm/ft ²	110
UV Resistance	ASTM D 4355 (after 500 hours)	% retained	70
<i>Woven Geotextile Tests (Lower Geotextile)**</i>			
Mass per Unit Area	ASTM D 5261	oz/yd ²	10
Grab Tensile	ASTM D 4632	lbs.	250
Puncture	ASTM D 4833	lbs.	150
AOS, US Sieve	ASTM D 4751	mm	100
Water Flow Rate	ASTM D 4491	gpm/ft ²	85
<i>Geocomposite Tests</i>			
Ply Adhesion	GRI GC-7	lbs/ in.	1.0
Transmissivity*	ASTM D 4716-00	m ² /sec	1 x 10 ⁻⁴
<i>Interface-Friction Tests</i>			
Geocomposite/ Cover Soil	ASTM D 5321	degrees	22 (Residual)
Geocomposite/Geomemb.	ASTM D 5321	degrees	24 (Residual)

*Water at 20° C with a gradient of 0.1 and a load of 10,000 psf between two steel plates for 15 min.

**Non-Woven needlepunched geotextile shall be Carthage Mills FX-100HS or equivalent. R2

4. The geocomposite drainage layer beneath the compacted soil layer shall consist of the following components placed in order from ash surface upward:
 - a. a non-woven needlepunched geotextile with AOS equal to 100; R2
 - b. the non-woven needlepunched geotextile shall be heat bonded to the geonet; R2
 - c. the upper geotextile shall be a non-woven needlepunched geotextile heat bonded to the geonet.

Manufacturing Quality Control

1. The geocomposite shall be manufactured in accordance with the Manufacturer's Quality Control Plan submitted to and approved by the Owner.
2. The geocomposite shall be tested according to the test methods and frequencies listed below:

Manufacturing Quality Control Test Frequencies			
Characteristics	Test Method		FREQUENCY
<i>Resin</i>			
Polymer Density	ASTM D 1505		Once Per Lot
Melt Flow Index	ASTM D 1238		Once Per Lot
<i>Geonet Test</i>			
Carbon Black	ASTM D 1603		1/50,000 ft ²
Tensile Strength, MD	ASTM D 5035		1/50,000 ft ²
Density	ASTM D 1505		1/50,000 ft ²
Thickness	ASTM D 5199		1/50,000 ft ²
<i>Geotextile Tests</i>			
Mass per Unit Area	ASTM D 5261		1/90,000 ft ²
Grab Tensile	ASTM D 4632		1/90,000 ft ²
Puncture	ASTM D 4833		1/90,000 ft ²
AOS, US Sieve	ASTM D 4751		1/540,000 ft ²
Water Flow Rate	ASTM D 4491		1/540,000 ft ²
UV Resistance	ASTM D 4355 (after 500 hours)		Once per resin formulation
<i>Geocomposite Tests</i>			
Ply Adhesion	GRI GC-7		1/50,000 ft ²
Transmissivity	ASTM D 4716-00		1/540,000 ft ²
<i>Interface-Friction Tests*</i>			
Geocomposite/ Cover Soil	ASTM D 5321		two tests
Geocomposite/Geomemb.	ASTM D 5321		two tests

* See NOTE under Table 02621-1 herein.

PART 3 – EXECUTION

3.1 INSTALLER REQUIREMENTS

- A. An installer that has previously installed a minimum of 2,000,000 square feet of geocomposite shall perform the installation.
- B. The installer's or manufacturer's field representative shall be in attendance full time during the GCL installation.
- C. The GCL installer's or manufacturer's field representative shall certify in writing that all materials and shop drawings regarding panel placement, and construction techniques are

in compliance with the manufacturer's recommendations and other accepted QA/QC procedures.

3.2 GEOCOMPOSITE DRAINAGE LAYER INSTALLATION

A. General Requirements:

1. The Contractor shall be responsible for the design of the geocomposite panel layout. Panels shall be placed with seams running up and down slopes, not horizontally.
2. The fabricator of the geocomposite panels used in the work shall prepare shop drawings with a proposed panel layout to cover the area shown on the Drawings. These drawings shall be submitted for approval prior to fabrication of the geocomposite. The drawings shall be provided in a reproducible hard copy or electronic format.
3. Written specifications for the manufacture, fabrication, installation, and quality assurance/quality control for the geocomposite shall be approved by the Owner prior to start of liner fabrication.

B. Installation Requirements:

1. The geocomposite shall be placed with the long dimension parallel with the slope direction (up and down the slope, not sideways).
2. For long, steep slopes, special care shall be taken so that only full-length rolls are used at the top of the slope.
3. Adjacent roll edges of geocomposite shall be overlapped a minimum of 3-inches. The roll ends of geonets shall be overlapped a minimum of 6-inches.
4. All overlaps shall be joined by tying with plastic fasteners or polymeric braid. Metallic ties or fasteners are not allowed.
5. Tying devices shall be white or yellow, as contrasted to the black geonet, for ease of visual inspection.
6. Tie intervals along the roll edges shall be every 5-feet. Tie intervals along the roll ends shall be every 6-inches.
7. The geocomposite edges shall be seamed in accordance with the above requirements and sewn together. Roll ends shall be seamed in accordance with the above requirements and a geotextile cap shall be heat-bonded over the completed seam. The geotextile cap shall cover the open end of the geonet, the ties, and at least 6 inches of geotextile beyond the ties or geonet end. Heat bonding shall be performed with the utmost of care to prevent damage to any portion of the liner system. No burn through the geotextiles will be permitted.

GEOCOMPOSITE DRAINAGE LAYER

8. The geocomposite shall be protected at all times during construction from contamination resulting from surface runoff. Any geocomposite so contaminated or otherwise damaged shall be removed and replaced.
9. In the presence of wind, all geocomposites shall be weighted down with sandbags or the equivalent. Such sandbags shall be used during placement and remain until replaced with cover material.
10. The geocomposite shall be properly anchored in the anchor trench to resist sliding. Anchor trench compaction equipment shall not come into contact with the geocomposite.
11. Install anchor trench in accordance with Specification 02778, LLDPE Geomembrane Construction Quality Assurance (Attachment 2 to QA/QC Plan).

3.3 COVER PLACEMENT

- A. Cover soils shall be free of angular stones or other foreign matter, which could damage the geocomposite. Cover soils shall be approved by the Owner with respect to particle size, uniformity and chemical compatibility.
- B. Soil cover shall be placed over the geocomposite using construction equipment that minimizes stresses on the geocomposite. A minimum of 1 foot of cover shall be maintained between the equipment tires/tracks and the geocomposite at all times during the covering process. This thickness recommendation does not apply to frequently trafficked areas or roadways, for which a minimum thickness of 2 feet shall be required.
- C. Soil cover shall be placed in a manner that prevents the soil from entering the geocomposite overlap zones. Cover soil shall be pushed up slopes, not down slopes, to minimize tensile forces on the geocomposite.
- D. Although direct vehicular contact with the geocomposite is to be avoided, lightweight, low ground pressure vehicles (such as 4-wheel, all-terrain vehicles) may be used to facilitate the initial placement of cover soil. The geocomposite supplier shall be contacted with specific recommendations on the appropriate procedures in this situation.

3.4 REPAIR

- A. Prior to covering the deployed geocomposite, each roll shall be inspected for damage resulting from construction.
- B. Any rips, tears or damaged areas on the deployed geocomposite shall be removed and patched. The patch shall be secured to the original geonet by tying every 6 inches with the approved tying devices. If the area to be repaired is more than 50 percent of the width of the panel, the damaged area shall be cut out and the two portions of the geocomposite shall be cut out and the two portions of the geocomposite shall be joined together in accordance with Section 3.3.

3.5 INTERFACE-FRICTION TESTING

- A. Laboratory interface friction testing on the geocomposite/cover-soil and geocomposite/geomembrane interfaces shall be performed in accordance with ASTM D5321. Testing shall be performed with representative samples of geocomposite, geomembrane and Random Fill soil that will be compacted to 90% standard Proctor maximum dry density and used for construction of the final cover. For the geocomposite/cover-soil test, the substratum shall be the top surface of the geocomposite and the superstratum shall be the cover soil. For the geocomposite/geomembrane test, the superstratum shall be the geocomposite bottom surface and the substratum shall be the geomembrane top surface. A normal-stress range 0.1 tsf to 1.0 tsf shall be used. The compacted soil sample shall be saturated with water and both the geocomposite and geomembrane surfaces shall be wetted prior to shearing during the test. Both peak and residual shear stresses under each normal stress shall be recorded and friction angle interpreted separately for both peak and residual shear strength.
- B The report for the testing shall consist, at a minimum, of sample size, sample origin, sample lot number, illustration of equipment used, summary of test methods employed, strain rate used during shear, shear stress-versus-displacement, normal stress-versus-peak stress and residual stress, peak and residual strength envelope plots. All stress versus displacement tests and all calculations performed to determine the angles of friction shall be corrected for machine resistance.

TABLE 02621-1 - DATA REQUIREMENTS AND SUBMITTAL SCHEDULE

Paragraph - Submittal Requirements		With Proposal	For Approval		For Record	
			Date	Copies	Date	Copies
All	Alternative Materials or Procedures	Yes	-	-	-	-
2.1 A	Manufacturer & Specification Sheet	Yes	-	-	-	-
2.1 B	Material Certification	No	2 Weeks prior to delivery	3	-	-
2.1 C	Manufacturing QC Testing	No	-	-	With delivery of rolls	3
3.1 A	Geocomposite Manufacturer's Experience	Yes	-	-	-	-
3.2 A	Manufacturer's Representative and Installation Requirements	No	2 Weeks prior to delivery	3	-	-
3.2 A	Shop Drawings for Geocomposite Installation	No	2 Weeks prior to Work	3 Prints	-	-
3.1 C	Final Documentation	No	-	-	Within 2 weeks after Work	3 Prints
3.5	Interface Friction Testing	No	*	-	-	-

* NOTE: Interface-friction testing shall be performed by CQA Consultant and the results will be used for approval prior to procurement. Geocomposite and geomembrane samples shall be provided by the manufacturer(s) and loose soil sample will be provided by TVA.

END