

**CLOSURE/POST CLOSURE PLAN
ASH POND AREA**

TENNESSEE VALLEY AUTHORITY

KINGSTON FOSSIL PLANT

SEPTEMBER 1995



Prepared By:

Tennessee Valley Authority
Site and Environmental Engineering Section

Title: CLOSURE/POST-CLOSURE PLAN ASH POND AREA		Report No: N/A	
		Plant/Unit: KINGSTON FOSSIL PLANT	
Vendor	Contract No.	Key Nouns: Closure Plan, Ash Pond	
Applicable Design Documents	REV	RIMS NUMBER	DESCRIPTION
	R0		Original Submittal
References	R1		Correct for NOD from DSWM
	R2		

TENNESSEE VALLEY AUTHORITY
FOSSIL AND HYDRO POWER
FOSSIL ENGINEERING
SITE AND ENVIRONMENTAL ENGINEERING



4/6/98

	Revision 0	R1	R2
Date	September 29, 1995	4/06/98	
Prepared	B. Keith Elder	<i>BKE</i>	
Checked	Harold L. Petty	<i>HLP</i>	
Reviewed	Kenneth W. Burnett	<i>KWB</i>	

CLOSURE/POST-CLOSURE PLAN
ASH POND AREA
TENNESSEE VALLEY AUTHORITY
KINGSTON FOSSIL PLANT

Table of Contents

<u>I. INTRODUCTION</u>	
A. <u>Facility Description</u>	3
B. <u>Operational History</u>	3
C. <u>Expected Year Of Closure</u>	3
D. <u>Facility Contact</u>	4
<u>II. FACILITY CLOSURE</u>	
A. <u>Partial Closure Steps</u>	5
B. <u>Complete Closure Steps</u>	5
1. <u>Facility Operation</u>	5
2. <u>Drainage System</u>	6
3. <u>Leachate Collection</u>	7
4. <u>Gas Collection</u>	7
5. <u>Final Cover</u>	8
6. <u>Intermediate Cover</u>	8
7. <u>Vegetative Cover</u>	9
8. <u>Groundwater Monitoring</u>	9
(1) <u>Compliance Monitoring Boundary</u>	9
(2) <u>Monitoring System for the Existing Facility</u>	9
(3) <u>Detection Monitoring Program</u>	10
a. <u>Sampling and Analysis Plan</u>	10
b. <u>Record Keeping and Reporting</u>	11
c. <u>Well Plugging</u>	11
9. <u>Closure Schedule</u>	11
10. <u>Notice in Deed to Property</u>	12
11. <u>Post-Closure Care Activities</u>	12
12. <u>Cost Estimate/Financial Assurance</u>	12
13. <u>Dredge Cell Stability</u>	13
<u>III. QUALITY ASSURANCE/QUALITY CONTROL</u>	
A. <u>General</u>	14
B. <u>Cap Requirements</u>	14
<u>Clay Source Verification</u>	15
<u>Cap Construction</u>	15
<u>Clay Construction Certification</u>	16
C. <u>Documentation</u>	17
1. <u>Daily Logs</u>	17
2. <u>Approval Documentation</u>	18

APPENDICES

- A. TVA Vegetation Specifications
- B. TCLP and VOC Testing of KIF Ash
- C. Groundwater Sample Collection Techniques
and Quality Assurance Procedures
- D. Hydrogeologic Evaluation of Ash Pond Area