

Proposal Number :  
 WO/JO Number :  
 Letter Number : PP-6764-PR-C

Scope Change Number : 0A

**TENNESSEE VALLEY AUTHORITY  
 TASK ASSIGNMENT ORDER (TAO)**

CONTRACT NUMBER : 99998970  
 CONTRACTOR : Parsons  
 TASK NUMBER : PR - 0637 - RPT637  
 REVISION NUMBER : 00

LEAD : Lynn Petty  
 TECHNICAL MGR. : Ron Purkey  
 EFFECTIVE BEGIN DATE : 12/13/02  
 CURRENT END DATE : 5/16/03  
 PHASE : 1A

PLANT : Kingston Fossil Plant  
 PROJECT : KIF Scrubber addition gypsum stack  
 TASK DESCRIPTION : Determine feasibility of locating gypsum stack on the KIF reservation.  
 DESCRIPTION OF REVISION: Intial authorization.


FEE TYPE APPLICABLE TO THIS TAO :

Performance Award Fee  
 Fixed Price Fee - Managed ( 6% ) Fixed Percentage Type  
 Fixed-Percentage Fee =====>  Staff Augmentation  Field Support  
 No fee applies to this task

**TASK SUMMARY**

|                              | Previous Revision |          | Net Change      |          | Total task Authorization |
|------------------------------|-------------------|----------|-----------------|----------|--------------------------|
| Negotiated Estimated Cost    | \$0               | +        | \$49,247        | =        | \$49,247                 |
| Fixed Fee                    | \$0               | +        | \$2,659         | =        | \$2,659                  |
| Earned Award Fee To Date     | \$0               | +        | \$0             | =        | \$0                      |
| Available Award Fee          | \$0               | +        | \$0             | =        | \$0                      |
| <b>Total Estimated Price</b> | <b>\$0</b>        | <b>+</b> | <b>\$51,906</b> | <b>=</b> | <b>\$51,906</b>          |

TVA SHORT CODE 001BRG4 PCN \_\_\_\_\_ LOCATION CODE \_\_\_\_\_ PERFORMING UNIT \_\_\_\_\_

APPROVED BY:  Date 1/13/03

TVA Contract Administrator

DISTRIBUTION:  
 Partner (cc) Eng. Support Svs.  
 Lead Eng.

1/8/2003

Letter Number : PP-6764-PR-C

Scope Change Number : 0A

**PROPOSAL INTERNAL REVIEW SHEET**

CONTRACT NUMBER : 99998970  
 CONTRACTOR : Parsons  
 TASK NUMBER : PR - 0637 - RPT637

PROJ ENG/TECH REP : Lynn Petty  
 TECHNICAL MGR. : Ron Purkey  
 EFFECTIVE BEGIN DATE : 12/13/02  
 CURRENT END DATE : 5/16/03

PHASE : 1  
 PLANT : Kingston Fossil Plant  
 PROJECT : KIF Scrubber addition gypsum stack  
 TASK DESCRIPTION : Determine feasibility of locating gypsum stack on the KIF reservation.

Is this in the Spend Plan ? YES

Subcontractor Name :

Budget Amt. \$ ~~5,906~~ 5,906<sup>00</sup>

FEE TYPE APPLICABLE TO THIS TAO :

Performance Award Fee  
 Fixed Price Fee - Managed ( 6% ) Fixed Percentage Type  
 Fixed-Percentage Fee =====>  Staff Augmentation  Field Support  
 No fee applies to this task

DESCRIPTION OF REVISION : **Intial authorization.**

| Net Change                   |                 |
|------------------------------|-----------------|
| Negotiated Estimated Cost    | \$49,247        |
| Fixed Fee                    | \$2,659         |
| Available Award Fee          | \$0             |
|                              |                 |
| <b>Total Estimated Price</b> | <b>\$51,906</b> |

**APPROVAL :**

- \* Please provide or confirm the above TAO information and short code reference listed below.
- \* If the attached proposal is to be approved, please complete, sign and return this review sheet to Larry Harless, LP-2P-C, so that the TAO form to be signed by the appropriate Department Manager can be generated.

*AZ. Purkey* Date 1-14-03

**DISAPPROVAL :**

- \* If the attached proposal is not acceptable, please contact the contractor to prepare a revised proposal.
- \* If the attached proposal is to be cancelled and the work is not to be performed by the Contractor, sign below and return to Larry Harless.

Date \_\_\_\_\_

**Short Code**

| Short Code     | PCN | Loc Code | Perf Unit | Commit \$<br>(Approp. Only) | Comments |
|----------------|-----|----------|-----------|-----------------------------|----------|
| <u>φφ1BRGA</u> |     |          |           |                             |          |

**TENNESSEE VALLEY AUTHORITY  
CONTRACT 99998970  
KINGSTON FOSSIL PLANT  
SCRUBBER ADDITION  
GYPSUM STACK  
PHASE 1A STUDY  
PR- 0637 – PCN**

December 20, 2002  
PP-6764-PR-C  
Scope Change: 0A  
Required Start Date: December 13, 2002  
Requester: L. Petty

Mr. James G. Adair  
Tennessee Valley Authority  
1101 Market Street  
Chattanooga, TN 37402-2801

Dear Mr. Adair:

Parsons E&C is pleased to submit this proposal for preparing a Phase 1A engineering study for a proposed gypsum stack for the proposed scrubber addition at Kingston Fossil Plant.

## **SCOPE**

The scope of this proposal includes determining the feasibility of locating a gypsum stack within the Kingston Fossil Plant Reservation at the location specified by TVA as outlined in the attached Task Work Statement.

## **ORGANIZATION**

All work will be performed under the direction of Mr. Bill Griffith, Manager Chattanooga Operations, who is directly responsible to TVA for the overall quality of the work. Mr. Dan Smith will serve as the Engineering Manager and Lead Engineer, with support provided by the Parsons Chattanooga and Reading offices.

## **SCHEDULE**

Mr. James G. Adair  
PP-6764-PR-C  
December 20, 2002  
Page 2

Based on a December 13, 2002 authorization date, the TAO end date will be May 16, 2003. Parsons will provide preliminary volume calculations to TVA's Environmental Affairs Group by January 14, 2003. The remainder of deliverables specified in the attached Task Work Statement is due to TVA by April 15, 2003.

### PRICING


All work performed will be in accordance with the terms of Contract 99998970. The estimated engineering cost for the additional work included here is \$51,906.

This estimate was prepared assuming that no overtime will be required. However, should emergency conditions or schedule constraints occur, Parsons requests the flexibility to use additional overtime under the original authorization provided the total price is not exceeded.

### SUMMARY

Parsons is pleased with the opportunity to be of service to TVA and we look forward to the successful completion of this task. If you have any questions, please feel free to contact Mr. Dan Smith at (423) 757-8088 or me at (423) 757-8027.

Very truly yours,

  
William D. Griffith, P.E.  
Manager Chattanooga Operations

Attachment: Task Work Statement  
Proposal Pricing Forms

**TENNESSEE VALLEY AUTHORITY  
CONTRACT 99998970  
KINGSTON FOSSIL PLANT  
SCRUBBER ADDITION  
GYPSUM STACK  
PHASE 1A STUDY  
PR- 0637 – PCN**

**TASK WORK STATEMENT**

**1.0 BACKGROUND**

A new gypsum disposal area will be constructed due to the addition of scrubbers to Kingston Fossil Plant (KIF). Current disposal plans involve sluicing of gypsum from KIF (wet stacking). In addition, some by-product from Bull Run Fossil Plant (BRF) may also be transported and disposed at this facility (dry stack). The site is an approximate 90-acre area located on the peninsula area east of the powerhouse adjacent to the Clinch River. The scope includes a determination of the overall volume of gypsum that can be disposed at this location.

**2.0 PURPOSE**

This Task Work Statement describes engineering support activities associated with this project. The purpose of this task is to determine overall feasibility and suitability of this site for location of this facility. Based on current TVA projections, it is assumed for purposes of this study that 300,000 tons of gypsum produced annually at KIF, and 185,000 tons produced annually at BRF will require disposal over a 20 year period. TVA desires that the facility be capable of a disposal volume ranging from 6 million tons to 10 million tons.

**3.0 SCOPE**

Perform a Phase IA study to determine the feasibility of the peninsula area site selection for disposal of gypsum. The scope of work will be as follows:

- Participate in a KIF site walkdown and preliminary meeting with TVA and Tennessee DSWM. Determine the feasibility of attaining waivers on solid waste regulations, including buffer requirements, liner requirements, and design storm events for the sediment pond.
- Calculate preliminary storage volumes (two scenarios) based on standard engineering practices. The volumes should be based on one scenario utilizing the western slough for storage (Scenario 1) and another scenario assuming the western slough will require a buffer (Scenario 2). The eastern slough is assumed to require a buffer for both scenarios.
- Evaluate existing boring logs, geoprobe data, and groundwater levels previously obtained by TVA. Prepare boring location plan and scope of geotechnical field and laboratory work to be performed by MacTech. Coordinate with MacTech and TVA during geotechnical evaluation of the new disposal site area.
- Evaluate geotechnical data and suitability of foundation material for stack development.

- Develop preliminary Autocad drawings for gypsum stacking plan. Develop a phased development footprint and incremental phases of stacking plan to meet stormwater permit requirements. Preliminary design shall also be in accordance with Tennessee DSWM Class II permit requirements (sufficient for a Phase 1 Study) and waivers granted to TVA by TDEC for coal combustion by-products. The design shall also consider the necessity of obtaining additional waivers, based on the site visit with TVA and TDEC. TVA's Fossil Engineering Services Design Criteria contains additional information regarding these waivers.
- Participate in internal scoping meetings with TVA as required.

#### 4.0 CLARIFICATIONS/ASSUMPTIONS

Parsons work scope for this project includes the following clarifications and assumptions:

- Preliminary annual gypsum production volumes are as stated in this Task Work Statement.
- In order to meet stormwater permit requirements, assume development of stack to occur in maximum 50-acre open footprints.
- The study will not determine configurations of this facility for combinations of dry and wet stacking scenarios.
- Detailed calculations using computer programs to determine sediment pond routing and sizing will not be performed during Phase IA. Parsons E&C will determine preliminary sediment/detention pond sizes based on TDEC guidelines, and potential for TDEC solid waste regulation waivers.
- Sufficient geotechnical investigation shall be performed during Phase IA to determine overall suitability for this type of facility at this location. The study will consider the geology to the extent that this site has sufficient bearing capacity for the stack, and will address any potential fatal flaws (i.e., location of Holocene faults within 200 ft, or any distinguishing karst geologic features) that would prevent this site from being permitted as a solid waste disposal facility in Tennessee. Adjacent areas located on the peninsula area outside the facility footprint provided by TVA will be explored as potential borrow areas. However, given the limited time available, the geotechnical investigation cannot address each and every criteria established in Tennessee Rule 1200-1-7.
- Seismic analysis of the proposed stack geometry will not be conducted for this study. The configuration of the stack will assume an earthen starter dike, and a 3:1 slope for the gypsum stack, with 15 foot horizontal terraces placed at 30 foot vertical intervals. The overall stack height for the preliminary volume determination will be determined by the stack geometry. Subsequent engineering design will be required to determine the validity of this assumption.
- Digital copy of Kelsh topography to be provided by TVA.
- Development of quantities for a cost estimate will not be included in Phase 1A scope.
- No allowance is included for DCN preparation.

#### 5.0 DELIVERABLES

Parsons anticipates the following deliverables as part of this task:

- Preliminary volume estimates.
- Autocad drawings:

- Title Sheet with site location and site access (1 sheet)
- Interior grading Scenarios 1 and 2 (2 sheets @ 1 inch = 100 ft)
- Final grading Scenarios 1 and 2 (2 sheets @ 1 inch = 100 ft)
- Borrow area plan sheet (1 sheet @ 1 inch = 200 ft)
- Phased development (1 sheet @ 1 inch = 200 ft)
- Cross-sections (1 sheet)
- Report addressing overall feasibility and data collected.

**PARSONS ENERGY & CHEMICALS GROUP INC.**  
**TVA TASK PROPOSAL FORM - CONTRACT 99998970**  
**KIF Scrubber Addition Gypsum Stack Phase 1 Study**  
**PR - 0637 SC No.: 0A**  
**19-Dec-02**

"LABOR" & "OVERTIME LABOR"

| POSITION/<br>GRADE       | ST Billing Rate<br>(\$/HR) | ST<br>HOURS | ST<br>COST      | OT Billing Rate<br>(\$/HR) | OT<br>HOURS | OT<br>COST(\$) | TOTAL<br>COST(\$) |
|--------------------------|----------------------------|-------------|-----------------|----------------------------|-------------|----------------|-------------------|
| Project Management       | \$103.61                   | 23          | \$2,397         | \$84.71                    | 0           | \$0            | \$2,397           |
| Technical Management     | \$83.88                    | 17          | \$1,456         | \$68.58                    | 0           | \$0            | \$1,456           |
| Project Services         | \$62.23                    | 35          | \$2,160         | \$50.88                    | 0           | \$0            | \$2,160           |
| <b>SUBTOTAL SERVICES</b> |                            | <b>75</b>   | <b>\$ 6,013</b> |                            | <b>0</b>    | <b>\$ -</b>    | <b>\$ 6,013</b>   |

|                                    |         |            |                  |         |          |             |                  |
|------------------------------------|---------|------------|------------------|---------|----------|-------------|------------------|
| Senior Supervising Engineer (E11)  | \$89.08 | 0          | \$0              | \$72.83 | 0        | \$0         | \$0              |
| Supervising Engineer (E10)         | \$80.90 | 366        | \$29,583         | \$66.15 | 0        | \$0         | \$29,583         |
| Principal Engr/Spv Designer (E09)  | \$75.51 | 0          | \$0              | \$61.74 | 0        | \$0         | \$0              |
| Senior Engineer (E08)              | \$66.28 | 0          | \$0              | \$54.19 | 0        | \$0         | \$0              |
| Engineer II (E07)                  | \$61.01 | 0          | \$0              | \$49.88 | 0        | \$0         | \$0              |
| Engineer I (E06)                   | \$53.37 | 0          | \$0              | \$43.63 | 0        | \$0         | \$0              |
| Associate Engineer (E05)           | \$49.17 | 0          | \$0              | \$40.20 | 0        | \$0         | \$0              |
| Principal Designer (N16)           | \$64.69 | 0          | \$0              | \$79.33 | 0        | \$0         | \$0              |
| Senior Designer (N14)              | \$57.91 | 0          | \$0              | \$71.02 | 0        | \$0         | \$0              |
| Designer II (N12)                  | \$42.30 | 0          | \$0              | \$51.87 | 0        | \$0         | \$0              |
| Senior Drafter (N10)               | \$35.26 | 247        | \$8,716          | \$43.24 | 0        | \$0         | \$8,716          |
| Drafter (N08)                      | \$27.84 | 0          | \$0              | \$34.14 | 0        | \$0         | \$0              |
| Associate Drafter (N06)            | \$27.84 | 0          | \$0              | \$34.14 | 0        | \$0         | \$0              |
| Technician (N04)                   | \$18.93 | 0          | \$0              | \$23.21 | 0        | \$0         | \$0              |
| <b>SUBTOTAL ENG'G &amp; DESIGN</b> |         | <b>613</b> | <b>\$ 38,298</b> |         | <b>0</b> | <b>\$ -</b> | <b>\$ 38,298</b> |

SUBTOTAL LABOR \$44,311

TRANSPORTATION & SUBSISTANCE \$940

TEMPORARY ASSIGNMENT LIVING EXPENSES \$0

COMPUTERS, CAD, TELEPHONE, REPRODUCTION \$3,496

REPROGRAPHICS (OUTSIDE SERVICES) \$0

MISCELLANEOUS EXPENSES \$500

SUBCONTRACTED SERVICES \$0

SUBTOTAL EXPENSES \$4,936

SUBTOTAL (Labor & Expenses) \$49,247

FIXED FEE @ 6% (APPLIED TO LABOR ONLY) \$2,659

TOTAL TASK ESTIMATED COST \$51,906

Man-hours by Discipline - Provided for reference only

|                             |    |              |     |
|-----------------------------|----|--------------|-----|
| Project Management          | 23 | Mechanical   | 5   |
| Technical Management        | 17 | Electrical   | 0   |
| Project Scheduling/Controls | 35 | Cntr'l Sytms | 0   |
| Specialist                  | 72 | Civil/Struct | 536 |
| Clerical/Admin Support      | 24 | TOTAL        | 712 |



**PARSONS ENERGY & CHEMICALS GROUP INC.**  
**TVA FHP TASK PROPOSAL FORM - CONTRACT 99998970**  
**KIF Scrubber Addition Gypsum Stack Phase 1 Study**  
**PR - 0637            SC No.: 0A**  
**19-Dec-02**

Project Spend Plan

13-Dec-02 - Project Start  
 16-May-03 - Project Complete  
 5 - Project Duration - Months

|              | Hours      | Cost            |
|--------------|------------|-----------------|
| Month 1      | 91         | \$6,331         |
| Month 2      | 211        | \$14,598        |
| Month 3      | 180        | \$12,471        |
| Month 4      | 176        | \$12,215        |
| Month 5      | 52         | \$3,632         |
| Month 6      | 0          | \$0             |
| Month 7      | 0          | \$0             |
| Month 8      | 0          | \$0             |
| Month 9      | 0          | \$0             |
| Month 10     | 0          | \$0             |
| Month 11     | 0          | \$0             |
| Month 12     | 0          | \$0             |
| Month 13     | 0          | \$0             |
| Month 14     | 0          | \$0             |
| Month 15     | 0          | \$0             |
| Month 16     | 0          | \$0             |
| Month 17     | 0          | \$0             |
| Month 18     | 0          | \$0             |
| Month 19     | 0          | \$0             |
| Month 20     | 0          | \$0             |
| Fee          |            | \$2,659         |
| <b>TOTAL</b> | <b>711</b> | <b>\$51,906</b> |

Resource Loading Reference (Parsons' use)

|    |    |       |   |              |            |
|----|----|-------|---|--------------|------------|
| XE | 12 | ME    | 5 | NE           | 0          |
| XT | 12 | MD/MC | 0 | CE           | 288        |
| XC | 17 | EE    | 0 | CD/CC        | 247        |
| XP | 35 | ED/EC | 0 | <b>TOTAL</b> | <b>712</b> |
| XS | 72 |       |   |              |            |
| XA | 24 |       |   |              |            |